Reynoldsburg
OHIO · 1839

Shanette Strickland, President
Julie Towns, Ward 1
Louis Salvati, Ward 2
Bhuwan Pyakurel, Ward 3
Erin Hill, Ward 4
Barth Cotner, At-Large
Mildred Johnson, At-Large
Stacie A. Baker, At-large

City Council

Special Council Meeting

7232 East Main Street
Reynoldsburg, OH 43068
www.reynoldsburg.gov

Mollie Prasher, Clerk of Council
614-322-6836

Monday, December 15, 2025 | **6:30 PM** | **Council Chambers**

1. CALL TO ORDER

2. PLEDGE OF ALLEGIANCE

3. ROLL CALL

4. APPROVAL OF AGENDA

5. APPROVAL OF MINUTES

a. There are no minutes for the December 8, 2025 meeting.

6. COMMUNITY COMMENTS

The Community Comments portion of the meeting is an opportunity for citizens to address Council. Citizens may wish to bring matters to the attention of City Council or discuss items on the agenda with the exception of legislation scheduled for a public hearing. Comments related to a public hearing may only be made during the Public Hearing portion of the meeting.

Before addressing City Council, members of the public are asked to complete a speaker's form and give it to the Clerk of Council. The Council President will invite speakers to step to the microphone and give their name and address. All remarks should be addressed to Council as a whole and not exceed three minutes.

7. PROCLAMATIONS

a. A Proclamation of Appreciation for Auditor Stephen Cicak

b. A Proclamation of Appreciation for Barth Cotner

c. A Proclamation of Appreciation for Shanette Strickland

8. COMMUNICATIONS

a. 2026 Council Meeting Dates and Submission Deadlines

9. REPORTS

a. <u>There is no Development, Parks & Recreation Committee meeting.</u>

b. <u>There is no Public Safety, Law & Courts Committee meeting.</u>

c. **Public Service & Transportation Committee**

1. An Ordinance Authorizing the Mayor to Grant the Ohio Department of Transportation (ODOT) a Highway Easement (0.470 Acres), and Declaring an Emergency

d. **Finance & Administration Committee**

1. An Ordinance to Make Final Appropriations for Expenses and Other Expenditures for the City of Reynoldsburg, State of Ohio, During the Fiscal Year Ending December 31, 2026, and Declaring an Emergency

2. An Ordinance to Transfer Funds Among Various General Fund Accounts, and Declaring an Emergency

10. CONSENT AGENDA FOR EMERGENCY ADOPTION

a. An Ordinance Authorizing the Mayor to Enter into a Contract with Builderscape, Inc. for the JFK Park Pickleball Improvements Project, Appropriate Funds Therefor, and Declaring an Emergency

b. An Ordinance to Amend Chapter 953 Water Charges, Section 953.01(a) Water Rate Schedule of the Code of Ordinances for the City of Reynoldsburg, Ohio, and Declaring an Emergency

c. An Ordinance to Amend Chapter 945 Sewer Charges, Section 945.02(c) Rate Schedule of the Code of Ordinances for the City of Reynoldsburg, and Declaring an Emergency

d. An Ordinance to Amend Chapter 958 Stormwater Charges, Section 958.06 Equivalent Residential Unit of the Code of Ordinances for the City of Reynoldsburg, and Declaring an Emergency

e. An Ordinance Authorizing the Mayor to Grant the Ohio Department of Transportation (ODOT) a Highway Easement (0.470 Acres), and Declaring an Emergency

f. An Ordinance to Make Final Appropriations for Expenses and Other Expenditures for the City of Reynoldsburg, State of Ohio, During the Fiscal Year Ending December 31, 2026, and Declaring an Emergency

g. An Ordinance to Transfer Funds Among Various General Fund Accounts, and Declaring an Emergency

11. CONSENT AGENDA FOR SECOND READING

a. An Ordinance Providing for the Issuance and Sale of Bonds in the Maximum Principal Amount of $1,300,000, for the Purpose of Paying the Costs of Improving the Municipal Waterworks System, and Declaring an Emergency

12. CONSENT AGENDA FOR THIRD READING

a. An Ordinance to Amend Chapter Eleven — Planning and Zoning Code for the City of Reynoldsburg, Ohio

b. An Ordinance Authorizing the Mayor to Enter into a Contract with Compton Construction for Design and Construction Services

13. OTHER COUNCIL MATTERS

a. Selection of Council President

14. UPCOMING MEETINGS

a. December 24 & 25, 2025 Christmas Holiday City Offices Closed
December 31, 2025 New Year's Eve City Offices Closed
January 1, 2026 New Year's Day City Offices Closed
January 12, 2026 Council (Organizational Meeting)
January15, 2026 Planning & Zoning Board
January 19, 2026 Martin Luther King, Jr. Day City Offices Closed
January 26, 2026 Council

15. ADJOURNMENT

****

ADJOURNMENT

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: A Proclamation of Appreciation for Auditor Stephen Cicak

APPROVALS:

Mollie Prasher

EMERGENCY:

REASON FOR EMERGENCY:

STAFF REPORT:

A Proclamation of Appreciation for Stephen Cicak

Whereas, Stephen Cicak has served the City of Reynoldsburg with merit for the past ten years as Reynoldsburg City Auditor since January, 2018, when he was elected to serve following the retirement of City Auditor Richard Harris; and

Whereas, Stephen was also elected to serve on Council as the Ward 1 Representative in 2016 and 2017 and serving on the Development, Parks & Recreation Committee, Public Safety and Laws Committee, and Public Service and Transportation Committee; and

Whereas, Stephen has served on other various City committees including the Treasury Investment Board and Volunteer Peace Officer's Dependents' Fund Board; and

Whereas, in those many years of service, Stephen has performed his duties with dedication, consistency, and a commitment to the City; and

Whereas, Stephen has been acknowledged by the Auditor of State repeatedly for his department's efforts in overseeing the City's finances; and

Whereas, in recognition of all of Stephen's attributes, City Council wishes to recognize the work he has performed during his tenure as City Auditor.

Now therefore, be it resolved by the City Council of Reynoldsburg:

We hereby offer our gratitude and appreciation to Stephen Cicak for your years of service, dedication and efforts on behalf of the members of the Reynoldsburg community and wish you success in all your future endeavors.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: A Proclamation of Appreciation for Barth Cotner

APPROVALS:

Mollie Prasher

EMERGENCY:

REASON FOR EMERGENCY:

STAFF REPORT:

A Proclamation of Appreciation for Barth Cotner

Whereas, Barth Cotner served as a member of Council for the City of Reynoldsburg beginning from 2009 until the present as a Ward 1 representative and then as an At Large member; and

Whereas, Barth has served on the Community Development Committee, Safety Committee and Service Committee as well as on the Development, Parks & Recreation Committee, Public Safety and Laws Committee, Public Service and Transportation Committee and the Finance and Administrative Committee; and chaired the Public Service and Transportation Committee in 2018 and 2019; and

Whereas, Barth also served as chair of the Finance and Administrative Committee for several years; and

Whereas, Barth served as the City's representative to the Reynoldsburg Visitor's Bureau and on the YMCA Board as well as being active in several community groups and events; and

Whereas, Barth gave of his time and talents to further the interests of the City's residents and represented the City with a high degree of professionalism; and

Whereas, Barth participated in Council's efforts to address development issues, improve roadway and utility infrastructure projects, and always promoted the common welfare of the community; and

Whereas, during Barth's years of service on Council, his hard work and wise use of City resources helped maintain a community standard that is apparent to both residents and visitors of the city.

Now, therefore, be it resolved by the City Council of Reynoldsburg:

We are proud to acknowledge, recognize, and thank Barth Cotner for his sixteen years of service to the City of Reynoldsburg. Your dedication and commitment to the City is gratefully appreciated and applauded.

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: A Proclamation of Appreciation for Shanette Strickland

APPROVALS:

Mollie Prasher

EMERGENCY:

REASON FOR EMERGENCY:

STAFF REPORT:

A Proclamation of Appreciation for Shanette Strickland

Whereas, Shanette Strickland has served as a member of Council for the City of Reynoldsburg from 2020 through 2024 as a Ward 1 representative; and

Whereas, during those years of service, Shanette served as Chair of the Public Service and Transportation Committee; and

Whereas, in 2025 Shanette was appointed by Council to serve as Council President where she has served with dedication and commitment; and

Whereas, during Shanette's tenure as President, she had the responsibility to serve as Acting Mayor of Reynoldsburg on occasion; and

Whereas, under Shanette's leadership while on Council, she proposed legislation and support for the Crown Act, racism as a public health crisis, a grant program for women, military, and minority business owners, a mask mandate during COVID, protections for fair housing, and initiated the Martin Luther King, Jr. breakfast; and

Whereas, Shanette also supported new development in the City such as The Alliance and Central Ohio Primary Care as well as many housing projects to address the housing shortage in central Ohio; and

Whereas, during Shanette's years of service, she has provided concerned, thoughtful and attentive counsel and commentary to Council, the Mayor, City staff, and to the citizenry of the City of Reynoldsburg.

Now, therefore, be it resolved by the City Council of Reynoldsburg:

We are proud to acknowledge, recognize, and thank Shanette Strickland for her six years of service to the community of Reynoldsburg. Your dedication and commitment to the City is gratefully appreciated and acknowledged.

COUNCIL MEETING DATES AND SUBMISSION DEADLINES
2026

Submission Deadline	**Meeting Date**
January 2nd	January 12th
January 15th	January 26th
January 29th	February 9th
February 12th	February 23rd
February 26th	March 9th
March 12th	March 23rd
April 2nd	April 13th
April 16th	April 27th
April 30th	May 11th
May 14th	May 26th **TUESDAY**
May 28th	June 8th
June 11th	June 22nd
July 2nd	July 13th
July 16th	July 27th
August Recess	
September 3rd	September 14th
September 17th	September 28th
October 1st	October 12th
October 15th	October 26th
October 29th	November 9th
November 19th	November 23rd
December 3rd	December 14th
December Second Meeting TBA	

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance Authorizing the Mayor to Grant the Ohio Department of Transportation (ODOT) a Highway Easement (0.470 Acres), and Declaring an Emergency

APPROVALS:

Joe Begeny
Chris Shook
Mollie Prasher

EMERGENCY:

single-read emergency

REASON FOR EMERGENCY:

for the health and safety of the City to facilitate the continuation of the road project

STAFF REPORT:

AN ORDINANCE AUTHORIZING THE MAYOR TO GRANT THE OHIO DEPARTMENT OF TRANSPORTATION (ODOT) A HIGHWAY EASEMENT (0.470 ACRES), AND DECLARING AN EMERGENCY

WHEREAS, ODOT is currently in the construction design phase of the I-70 Improvements Project between Taylor Road and Baltimore-Reynoldsburg Road (310); and

WHEREAS, the current design includes a full interchange at Taylor Road (currently only one exit for eastbound traffic on I-70); and

WHEREAS, this design necessitates the need for several deeds/easements from various property owners including the City of Reynoldsburg; and

WHEREAS, the City is amenable to providing ODOT with the necessary Warranty Deeds for the project, given the overall benefit this work will provide the City and its residents.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That the Mayor be and is hereby authorized to grant ODOT three (3) Warranty Deeds per the attachment for the construction of the I-70 and Taylor Road interchange.


SECTION 2. That an amount to be determined shall be paid to the City of Reynoldsburg for compensation of said Warranty Deed.

SECTION 3. That the following unrecorded Warranty Deed (0.470 acres) from the City of Reynoldsburg, be and is hereby transferred as Exhibit A attached hereto and made a part hereof.

SECTION 4. This Ordinance is declared to be an emergency measure necessary for the immediate preservation of the public

peace, health and safety, and for the further reason that this Ordinance is required to be immediately effective in order to enable the City to timely enter into contracts for the construction of the Improvement; wherefore, this Ordinance shall be in full force and effect immediately upon its passage.

FRANKLIN COUNTY, FAIRFIELD COUNTY, & LICKING COUNTY
VIOLET TOWNSHIP
CITIES OF REYNOLDSBURG & PICKERINGTON
HALF SEC. 27, 28, 33-35, (SEC. 17, 20 & 21)
TWP. 16, RNG. 20
REFUGEE LANDS
(FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)



HORIZONTAL SCALE IN FEET
0 100 200 400

** 83 ITHACA III, LLC
** 84 CHICK-FIL-A, INC.
** 85 TAYLOR SQUARE CRI-OP, LLC
113 FRANK GERACI aka FRANK GERACI III AND TAMY GERACI
114 KRISTA L. CERULLO
** 117 TAYLOR SQUARE CONDOMINIUM ASSOCIATION
118 TERRACEVIEW APARTMENTS, LTD.
119 CAROLYN M. YOUSEY
121 BOARD OF EDUCATION OF REYNOLDSBURG CITY SCHOOL DISTRICT, FAIRFIELD, FRANKLIN AND LICKING COUNTIES, OHIO
123 GREGORY C. OTTING JR AND MYRNA LEE OTTING
124 LYNN A. HINSHAW AND HSIU C. SHIH

STRUCTURE KEY
RESIDENTIAL
COMMERCIAL
OUT-BUILDING

** 27 HARSHMAN INVESTMENT, LLC
** 28 FCPT GARDEN PROPERTIES, LLC
** 29 TAYLOR SQUARE HOTEL GROUP LLC
** 30 TITAN HOSPITALITY, LLC
** 31 P & S HOTEL GROUP, LLC
** 32 NS RETAIL HOLDINGS, LLC
33 AMERICAN MOTORCYCLE ASSOCIATION, d/b/a AMERICAN MOTORCYCLIST ASSOCIATION
34 ONYX REYNOLSDBURG OH LLC
35 FALCON FOUR PROPERTY HOLDING, LLC
36 THE BOARD OF TOWNSHIP TRUSTEES OF VIOLET TOWNSHIP
** 37 REALTY INCOME PROPERTIES 9, LLC
38 *NOT USED*
** 39 WAYNE N. JOHNSON AND CHERYL A. JOHNSON, TRUSTEES, OR THEIR SUCCESSORS IN TRUST, UNDER THE JOHNSON TRUST, DATED OCTOBER 12, 2022, AND ANY AMENDMENTS THERETO
40 CREEKSIDE ACQUISITION COLUMBUS ASSOCIATES II, LLC
40A CITY OF REYNOLDSBURG, OHIO
40B GEORGE A. PAGE AND VIOLET L. PAGE
41 HAAF FARMS HOMEOWNERS ASSOCIATION
42 IGNACIO CARREON ALVAREZ AND ROSARIO MARTINEZ GONZALEZ

REV. BY	DATE	DESCRIPTION

DATE COMPLETED 07/02/2025

PROPERTY MAP
SHEET 3 OF 6

DESIGN AGENCY
STRUCTUREPOINT LLC

DESIGNER	JBY
REVIEWER	MJW 07/02/25
PROJECT ID	96808
SHEET	RW.23
TOTAL	RW.220

FAI/LIC-IR 70-0.00/0.00

MODEL: I70 - Property Map 3 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 8:16:24 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RM003.dgn

FRANKLIN COUNTY, LICKING COUNTY
ETNA TOWNSHIP, VIOLET TOWNSHIP, CITY OF REYNOLDSBURG
HALF SEC. 24-27, 35, & 36, (SEC. 15-17 & 21)
TWP.16, RNG. 20
REFUGEE LANDS
(FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)

S1 HAAF FARM SECTION 6 PART 2
P.C. 2, SLOT 77

S2 DEXTER HEIGHTS
P.B. 8, PG. 9

40 CREEKSIDE ACQUISITION COLUMBUS ASSOCIATES II, LLC

40A CITY OF REYNOLDSBURG, OHIO

41 HAAF FARMS HOMEOWNERS ASSOCIATION

42 IGNACIO CARREON ALVAREZ AND ROSARIO MARTINEZ GONZALEZ

** 43 NETSAI GILBERT TRUSTEE OF THE NETSAI GILBERT TRUST AGREEMENT DATED AUGUST 20, 2021

44 LESLIE K. BAUKNIGHT AND TILLMAN A. BAUKNIGHT, II

45 THOMAS B. PHOMMASATHIT AND BOUNTHANH PHOMMASATHIT

46 DAVID F. BURROUGHS AND DAWN E. BURROUGHS

47A HOMEWOOD CORPORATION

47 FISH BELLY LLC

48 DUANE GOSA

49 DAVID A. POWELL

** 50 WAGNER LOUIS-CHARLES AND ALISHARIM K. LOUIS-CHARLES

** 51 RENE L. TENNANT

** 52 NIKOLCE STOJANOVSKI AND MARINA STOJANOVSKA

** 53 NEAL L. MORTON AND CHRISTINE D. MORTON

** 54 JOE H. JACKSON AND THERESA J. JACKSON

** 55 ETNA TOWNSHIP

** 56 KENTON FAIRCHILD II

** 57 MICHELLE M. WILLIAMS TRUST SHARE OF THE CARLTON IRREVOCABLE TRUST, MICHELLE M. WILLIAMS, JENNIFER R. CARLTON AND AMANDA E. CARLTON, CO-TRUSTEES

** 58 GREGORY FRAZIER AND CIERRA M. FRAZIER

** 62 STATE OF OHIO

67 — 69 NOT USED

** 70 DIANE P. TAYLOR

** 71 JOHN H. VOGEL

115 NOT USED

116 M. ELIZABETH GILL AND JENNIFER T. SAUTER, SUCCESSOR CO-TRUSTEES OF THE ROBERTA A. GILL TRUST DATED JULY 7, 1999

118 TERRACEVIEW APARTMENTS, LTD.

119 CAROLYN M. YOUSEY

120 VEDIC WELFARE SOCIETY OF COLUMBUS

121 BOARD OF EDUCATION OF REYNOLDSBURG CITY SCHOOL DISTRICT, FAIRFIELD, FRANKLIN AND LICKING COUNTIES, OHIO

122 GARY CARTER AND BETTY CARTER

123 GREGORY C. OTTING JR AND MYRNA LEE OTTING

124 LYNN A. HINSHAW AND HSIU C. SHIH

RELOCATED TAYLOR ROAD

END RW ACQUISITION
℄ R/W RELOCATED TAYLOR ROAD
STA. 22+08.44

END RW ACQUISITION
℄ R/W I.R. 70
STA. 139+35.93

PROP. TAYLOR ROAD SW

PROP. TAYLOR ROAD

TAYLOR ROAD SW

INTERSTATE ROUTE 70

RAMP J

BROOKMEADOW PARK NO. 2
P.B. 7, PG. 114

PALMER ROAD

SERVICE ROAD "A"

DEXTER HEIGHTS
P.B. 8, PG. 9

COLONIAL MANOR REPLAT OF LOTS 4, 5, 6 AND 0.973 ACRE
I.N. 200502250005564

THE PRESERVE AT HAAF FARM
I.N. 201609060019053

GEORGIAN DRIVE

COLONIAL MANOR
P.B. 7, PG. 58

CLONCH SUBDIVISION NO. 1
P.B. 13, PG. 373

HAAF FARM
SECTION 6 PART 1
P.C. 2, SLOT 41

HAAF FARM
SECTION 6 PART 2
P.C. 2, SLOT 77

CITY OF REYNOLDSBURG
HALF SECTION 26
HALF SECTION 25
ETNA TOWNSHIP

LICKING COUNTY
(SECTION 16)
HALF SECTION 26
HALF SECTION 35
(SECTION 21)
FAIRFIELD COUNTY

HALF SECTION 26
HALF SECTION 25

HALF SECTION 35
HALF SECTION 36

(SECTION 16)
HALF SECTION 25
HALF SECTION 36
(SECTION 21)

(SECTION 16)
HALF SECTION 25
HALF SECTION 24
(SECTION 15)

MATCH LINE STA. 114+00.00 (SEE SHEET RW.23)

MATCH LINE STA. 164+00.00 (SEE SHEET RW.25)

Ex LA-R/W

Ex R/W

Ex U

STRUCTURE KEY
- RESIDENTIAL
- COMMERCIAL
- OUT-BUILDING

HORIZONTAL SCALE IN FEET
0 100 200 400

PROPERTY MAP
SHEET 4 OF 6

REV. BY	DATE	DESCRIPTION

DATE COMPLETED 07/02/2025

FAI/LIC-IR 70-0.00/0.00

DESIGN AGENCY
STRUCTUREPOINT LLC

DESIGNER JBY

REVIEWER MJW 07/02/25

PROJECT ID 96808

SHEET RW.24 TOTAL RW.220

MODEL: I70 - Property Map 4 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 8:16:39 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RM004.dgn

NET TAKE = GROSS TAKE - PRO IN TAKE

NET RESIDUE = RECORD AREA - TOTAL PRO - NET TAKE

ALL AREAS ARE IN ACRES (UNLESS OTHERWISE STATED)

PARCEL NO.	OWNER	RW SHEET NO.	OWNER'S RECORD	AUDITOR'S PARCEL NO.	RECORD AREA	TOTAL P.R.O.	GROSS TAKE	P.R.O. IN TAKE	NET TAKE	STRUC-TURE	NET RESIDUE LEFT	NET RESIDUE RIGHT	REMARKS
33-WL	AMERICAN MOTORCYCLE ASSOCIATION,	92,93,96,97	OR 675, PG 852	041-06263.00	18.95	0.000	0.158	0.000	0.158			**18.792**	NO TAKE ITEMS
	d/b/a AMERICAN MOTORCYCLIST ASSOCIATION	100,101,104,105											
33-T1		96,97		041-06263.00	18.95	0.000	0.009	0.000	0.009				TO GRADE AND SEED
33-T2		100,101		041-06263.00	18.95	0.000	0.172	0.000	0.172				TO GRADE AND SEED
34-T	ONYX REYNOLDSBURG OH LLC	102,103, 106,107		044-03795.14	1.98	0.000	0.022	0.000	0.022				TO GRADE AND SEED
				045-03793.60	2.09	0.000	0.021	0.000	0.021				
	34-T TOTAL				**4.07**	**0.000**	**0.043**	**0.000**	**0.043**				
35-WL	FALCON FOUR PROPERTY HOLDING, LLC	104,105,108,109 112,113	OR 1648, PG 832	036-00733.00	11.78	0.000	0.120	0.000	0.120			**11.660**	NO TAKE ITEMS
36-WL1	THE BOARD OF TOWNSHIP TRUSTEES OF VIOLET TOWNSHIP	104,105,108,109, 112,113,116,117, 184,185,194-201, 210,211	OR 1769, PG 3357	036-00734.00	62.393	0.000	1.809	0.000	1.809				+1095 SF BRUSH PILE, +76.1 LF CHAINLINK FENCE, +1971.5 LF CHAINLINK FENCE*
36-WL2			OR 1769, PG 3357	036-00734.00	62.393	0.000	0.225	0.000	0.225				+5 TREES, +661.7 FT CHAINLINK FENCE, +147.1 LF CHAINLINK FENCE*
36-SH			OR 1769, PG 3357	036-00734.00	62.393	0.000	0.150	0.000	0.150				+25 TREES, +17.6 FT GATE, +159.1 FT CHAINLINK FENCE, +217.9 FT CHAINLINK FENCE*
	36 TOTAL (36-WL1, 36-WL2 & 36-SH)				**62.393**	**0.000**	**2.184**	**0.000**	**2.184**		**60.209**		NET RESIDUE RIGHT OF IR-70, LEFT OF SR 204, & LEFT OF PROPOSED TAYLOR RD
36-PRW			OR 1769, PG 3357	036-00734.00	62.393	N/A	N/A	N/A	N/A				LOSS OF ACCESS, 20.00 FT (ALL OF EX. 20 FT RESERVATION - OR 684 PG 558)
36-T1			OR 1769, PG 3357	036-00734.00	62.393	0.000	0.105	0.000	0.105				+542.4 LF CHAINLINK FENCE; TO GRADE AND SEED
36-T2			OR 1769, PG 3357	036-00734.00	62.393	0.000	0.149	0.000	0.149				+1 TREE, +339.7 LF CHAINLINK FENCE*, 19.9 LF GATE*; TO RECONSTRUCT ONE DRIVE AND TO GRADE AND SEED (36 MO. TEMP DURATION)
36-T3			OR 1769, PG 3357	036-00734.00	62.393	0.000	0.006	0.000	0.006				TO GRADE AND SEED (36 MO. TEMP DURATION)
36-T4			OR 1769, PG 3357	036-00734.00	62.393	0.000	0.024	0.000	0.024				TO GRADE AND SEED (36 MO. TEMP DURATION)
37	REALTY INCOME PROPERTIES 9, LLC	106,107,110,111	OR 1663, PG 2112	045-03793.20	3.19								NO ADDITIONAL R/W REQUIRED
38	*NOT USED*												
39	WAYNE N. JOHNSON AND CHERYL A. JOHNSON, TRUSTEES, OR THEIR SUCCESSSORS IN TRUST, UNDER THE JOHNSHON TRUST, DATED OCTOBER 12, 2022, AND ANY AMENDMENTS THERETO	110,111	IN 202300008424	045-03793.00	2.29								NO ADDITIONAL R/W REQUIRED
40-WL	CREEKSIDE ACQUISITION COLUMBUS ASSOCIATES II, LLC	110,111,114,115, 118,119,122,123, 126,127,204-207, 214, 215	OR 1745, PG 4507	045-03793.10	23.64	0.000	0.909	0.000	0.909				NO TAKE ITEMS
40-WDV			IN 201708230017770	013-027582-00.001	2.762	0.000	0.194	0.000	0.194				+3 TREES*, +1 BUSH*, +156.5 LF FENCE *TO BE ACQ. IN THE NAME OF "CITY OF REYNOLDSBURG, OHIO"*
	40 TOTAL (40-WDV & 40-WL)				**26.402**	**0.000**	**1.103**	**0.000**	**1.103**		**25.299**		NET RESIDUE LEFT OF IR-70, LEFT OF PROPOSED TAYLOR RD, & RIGHT OF TAYLOR RD SW
40-PRW1			OR 1745, PG 4507	045-03793.10	23.64	N/A	N/A	N/A	N/A				59.88 FT. OF ACCESS ALONG TAYLOR RD IS BEING LIMITED BY CONVERSION OF EX. R/W TO LIMITED ACCESS R/W
40-PRW2			IN 201708230017770	013-027582-00.001	2.762	N/A	N/A	N/A	N/A				37.70 FT. OF ACCESS ALONG TAYLOR RD IS BEING LIMITED BY CONVERSION OF EX. R/W TO LIMITED ACCESS R/W
40-T			IN 201708230017770	013-027582-00.001	2.762	0.000	0.020	0.000	0.020				TO GRADE AND SEED (36 MO. TEMP DURATION)
40A-WL1	CITY OF REYNOLDSBURG, OHIO	126, 127, 204, 205	OR 1121, PG 670	N/A	0.207 (c)	0.207 (c)	0.171	0.171	0.000				+1 TREE*, +3 BUSHES*
40A-WL2		206, 207	IN 200005260016710	N/A	0.263 (c)	0.263 (c)	0.028	0.028	0.000				+1 TREE*, +2 BUSHES*, +312 SQ. FT. PLANTER*
40A-WD		204-207	OR 1121, PG 670	N/A	0.207 (c)	0.207 (c)	0.036	0.036	0.000				+2 TREES*, +7 BUSHES*, +413 SQ. FT. PLANTER*
			IN 200005260016710	N/A	0.263 (c)	0.263 (c)	0.195	0.195	0.000				
	40A-WD TOTAL				**0.470 (c)**	**0.470 (c)**	**0.231**	**0.231**	**0.000**				
	40A TOTAL (40A-WL1, 40A-WL2 & 40A-WD)				**0.470 (c)**	**0.470 (c)**	**0.430**	**0.430**	**0.000**				
40B-WL	GEORGE A. PAGE AND VIOLET L. PAGE	126, 127	DB 223, PG 34	N/A	0.174 (c)	0.174 (c)	0.174	0.174	0.000				*MISSED SPLIT PARCEL LAYING WITHIN STADARD HIGHWAY EASEMENT*
41-WL	HAAF FARMS HOMEOWNERS ASSOCIATION	124,125,128,129	OR 1455, PG 2604	036-05963.00	9.470	0.000	6.273	0.000	6.273				+7 TREES
		186,187,198-203		036-06074.00	0.050	0.000	0.000	0.000	0.000				NET RESIDUE RIGHT OF IR-70 & RIGHT OF PROPOSED TAYLOR RD
	41-WL TOTAL				**9.520**	**0.000**	**6.273**	**0.000**	**6.273**			**3.247**	
41-T		198-201	OR 1455, PG 2604	036-05963.00	9.470	0.000	0.081	0.000	0.081				TO GRADE AND SEED (36 MO. TEMP DURATION)
				036-06074.00	0.050	0.000	0.000	0.000	0.000				
					9.520	**0.000**	**0.081**	**0.000**	**0.081**				

TYPES OF TITLE LEGEND:
WL = FEE SIMPLE WITH LIMITATION OF ACCESS
WD = WARRANTY DEED
WDV = WARRANTY DEED IN THE NAME OF OTHERS
PRW = PROPERTY RIGHT FEE SIMPLE
SH = STANDARD HIGHWAY EASEMENT
T = TEMPORARY EASEMENT
SWV = SEWER EASEMENT IN THE NAME OF OTHERS

\+ DENOTES REMOVAL ITEMS SEE CORRESPONDING RIGHT OF WAY PLAN SHEET FOR DESCRIPTION

** DENOTES RIGHT OF WAY ENCROACHMENT*

(c) = CALCULATED AREA

NOTE: ALL TEMPORARY PARCELS TO BE OF 60 MONTH DURATION UNLESS OTHERWISE NOTED.

NOTE: UNDER NO CIRCUMSTANCES ARE TEMPORARY EASEMENTS TO BE USED FOR STORAGE OF MATERIAL OR EQUIPMENT BY THE CONTRACTOR UNLESS NOTED OTHERWISE.

REV. BY	DATE	DESCRIPTION

FIELD REVIEW BY: R.A. MOSELEY DATE: 05/05/2025

OWNERSHIP VERIFIED BY: M.W. MAYES DATE: 05/19/2025

DATE COMPLETED 07/02/2025

SUMMARY OF ADDITIONAL R/W PARCELS 33 - 41

DESIGN AGENCY
AMERICAN STRUCTUREPOINT INC.

DESIGNER JBY

REVIEWER MJW 07/02/25

PROJECT ID 96808

SHEET RW.28 TOTAL RW.220

FAI/LIC-IR 70-0.00/0.00

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 8:17:27 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RS002.dgn

15 STA. 111+60.43

16 STA. 112+93.76 (℄ R/W I.R. 70) =
STA. 41+15.09 (PROP. ℄ R/W TAYLOR ROAD)

FAIRFIELD COUNTY, VIOLET TOWNSHIP
CITY OF REYNOLDSBURG
HALF SEC. 34 & 35, (SEC. 20 & 21), TWP. 16, RNG. 20
REFUGEE LANDS
(FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)

DATE COMPLETED 07/02/2025		
REV. BY	DATE	DESCRIPTION

HORIZONTAL SCALE IN FEET
0 10 20 40

MATCH LINE STA. 44+00.00 (SEE SHEET RW.205)

40A
CITY OF REYNOLDSBURG, OHIO
OR 1121 PG 670
0.206 ACRES

40 WL
40A WL1
42 WL
40B WL

CITY OF REYNOLDSBURG
VIOLET TOWNSHIP

LA-R/W
Ex. R/W
Ex SH
20166
20140
20149
20038
30168
30131
161125
30167
30130
161123

40
PID: 045-03793.10
CREEKSIDE ACQUISITION COLUMBUS
ASSOCIATES II, LLC
2405-2459 TAYLOR ROAD
COMMERCIAL

40B
PID: N/A
GEORGE A. PAGE JR.
AND
VIOLET L. PAGE
MISS-SPLIT
PARCEL

42
PID: 036-00789.00
IGNACIO CARREÓN ÁLVAREZ AND
ROSARIO MARTINEZ GONZALEZ
13920 TAYLOR ROAD NW
RESIDENTIAL

HALF SECTION 34
HALF SECTION 35
(SECTION 20)
HALF SECTION 34
HALF SECTION 35
(SECTION 21)

WOODS TBR
GRAVEL TBR
ASPH TBR
GRASS
4' STEEL FENCE TBR
OVERHEAD WOOD SIGN & POSTS TBR
GRAVEL DRIVE TBR
RUSTY FRAME HOUSE TBR
PLANTER TBR
BRICK PAVERS TBR
EX. RIPRAP TBR
EX. DITCH TBR
EX. CABLE BARRIER TBR

PROP. GUARDRAIL
PROP. SHOULDER
PROP. EDGE OF PAVEMENT
PROP. ℄ RAMP H
PROP. ℄ RAMP I
PROP. DITCH W/ RIPRAP
PROP. ABUTMENT WALL
PROP. WING WALL
PROP. BRIDGE
PROP. CURB
PROP. PIER
PROP. DITCH
PROP. GUARD RAIL
PROP. STORM

HISTORIC ℄ R/W TAYLOR ROAD
℄ PROP. R/W & CONST. TAYLOR ROAD
N03°39'46"E
N72°29'31"E
℄ R/W & CONST. INTERSTATE ROUTE 70

MATCH LINE STA. 110+50.00 (SEE SHEET RW.122)
MATCH LINE STA. 115+50.00 (SEE SHEET RW.130)

111 112 113 115 41 42 43

RIGHT-OF-WAY TOPO SHEET - IR 70 WB
STA 110+50.00 TO STA 115+50.00

DESIGN AGENCY
WEPFER STRUCTUREPOINT INC.

DESIGNER	JBY
REVIEWER	MJW 07/02/25
PROJECT ID	96808
SHEET	RW.126
TOTAL	RW.220

FAI/LIC-IR 70-0.00/0.00

MODEL: 96808_RT924 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 8:55:58 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RT924.dgn

10' ELECTRIC EASEMENT
COLUMBUS SOUTHERN POWER COMPANY
O.R. 1111, PG. 2369
O.R. 1125, PG. 364
(10' WIDE AS INSTALLED, BUT UNABLE TO DETERMINE LOCATION)
(ACROSS PARCEL 40)

5' TELECOM EASEMENT
OHIO BELL TELEPHONE COMPANY a.k.a. AMERITECH OHIO INC.
O.R. 1108, PG. 115
(5' WIDE AS INSTALLED, BUT UNABLE TO DETERMINE LOCATION)
(ACROSS PARCEL 40)

10' GAS PIPELINE EASEMENT
OHIO ENERGY CONSUMER COOPERATIVE, INC.
O.R. 693, PG. 692
(10' WIDE AS INSTALLED, BUT UNABLE TO DETERMINE LOCATION)
(ACROSS PARCEL 40)

15' CABLE TELEVISION EASEMENT
INSIGHT COMMUNICATIONS OF CENTRAL OHIO, LLC
O.R. 1545, PG. 1546
(15' WIDE AS INSTALLED, BUT UNABLE TO DETERMINE LOCATION)
(ACROSS PARCEL 40)

FAIRFIELD COUNTY, VIOLET TOWNSHIP
CITY OF REYNOLDSBURG
HALF SEC. 34 & 35, (SEC. 20 & 21), TWP. 16, RNG. 20
REFUGEE LANDS
(FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)

DATE COMPLETED 07/02/2025		
REV. BY	DATE	DESCRIPTION

HORIZONTAL SCALE IN FEET
0 10 20 40

MATCH LINE STA. 44+00.00 (SEE SHEET RW.205)
MATCH LINE STA. 110+50.00 (SEE SHEET RW.123)
MATCH LINE STA. 115+50.00 (SEE SHEET RW.131)

40A
CITY OF REYNOLDSBURG, OHIO
OR 1121 PG 670
0.206 ACRES

141.13' LA-R/W N03°49'05"E
194.16' Ex R/W
L1
L2
L3
40A WL1
20149
20038
P1
N.F.
P.O.B.
P.O.C.
1
42 WL
N30°22'45"E
Ex SH
42
PID: 036-00789.00
IGNACIO CARREÓN ÁLVAREZ AND ROSARIO MARTINEZ GONZALEZ
13920 TAYLOR ROAD NW
RESIDENTIAL

STA. 111+25.00
OFF. 290.00' LT.
P.O.S.
N72°29'31"E
94.97'
LA-R/W
N59°37'01"E - 179.51'
STA. 112+19.97
OFF. 290.00' LT.
STA. 43+58.87
OFF. 173.54' LT.
LA-R/W
P.O.S.
20166
S72°30'49"W - 54.17'
Ex SH
86.37'
20140
STA. 111+81.41
OFF. 275.00' LT.
STA. 43+30.95
OFF. 204.09' LT.
40B WL
STA. 112+35.58
OFF. 274.98' LT.
STA. 43+50.50
OFF. 153.57' LT.
(P.O.C. 40-PRW1)
(P.O.B. 40-WL)
STA. 43+31.92
OFF. 108.62' LT.
30168
STA. 112+70.78
OFF. 241.42' LT.

40
PID: 045-03793.10
CREEKSIDE ACQUISITION COLUMBUS ASSOCIATES II, LLC
2405-2459 TAYLOR ROAD
COMMERCIAL
40 WL
2
S17°32'40"E - 118.88'
40B
PID: N/A
GEORGE A. PAGE JR. AND VIOLET L. PAGE
MISS-SPLIT PARCEL
130.70' (40B-WL)
N03°49'05"E - 425.50' (42-WL)
N03°49'05"E

PROP. ℄ RAMP H
PROP. ℄ RAMP I
111
112
113
115
16' ACCESS EASEMENT
D.B. 144, PG. 54
I.N. 202309050016101
42 WL
43

30131
161125
40B WL
42 WL
Ex SH
38.87'
S76°46'53"W - 185.58'
CITY OF REYNOLDSBURG
VIOLET TOWNSHIP
Ex LA-R/W
30167
STA.111+81.48
OFF. 156.12' LT.
STA. 42+20.12
OFF. 161.08' LT.
30130
STA. 42+35.96
OFF. 108.88' LT.
STA. 112+20.24
OFF. 153.21' LT
STA. 42+31.41
OFF. 123.89' LT
S76°46'53"W - 176.67'
Ex LA-R/W
STA. 113+49.35
OFF. 143.53' LT.
161123
STA. 113+96.42
OFF. 140.00' LT.
STA. 42+82.71
OFF. 45.17' RT
S70°17'48"W - 156.63'
Ex LA-R/

HISTORIC ℄ R/W TAYLOR ROAD
(SECTION 20)
HALF SECTION 34
HALF SECTION 35
(SECTION 21)
℄ PROP. R/W & CONST. TAYLOR ROAD
N03°39'46"E
42
41

PARCEL 316-WL
STATE OF OHIO
FAI-70-0.00 LIC-70-0.00
D.B. 357, PG. 683
19.37 ACRES

PARCEL 319-WL
STATE OF OHIO
FAI-70-0.00 LIC-70-0.00
D.B. 345, PG. 352
7.84 ACRES

PARCEL 320-WL
STATE OF OHIO
FAI-70-0.00 LIC-70-0.00
D.B. 360, PG. 624
1.25 ACRES

15
16
111
112
113
114
115
℄ R/W & CONST. INTERSTATE ROUTE 70
N72°29'31"E

15 STA. 111+60.43

16 STA. 112+93.76 (℄ R/W I.R. 70) = STA. 41+15.09 (PROP. ℄ R/W TAYLOR ROAD)

1 FAIRFIELD COUNTY, OHIO
OR 1618 PG 3840
OR 1618 PG 1310
0.338 ACRES

2 STANDARD HIGHWAY EASE.
PARCEL NO. 316
BOARD OF COUNTY COMMISSIONERS OF FAIRFIELD COUNTY, OHIO
D.B. 476. PG. 467
0.173 ACRES

L1 - N03°49'05"E - 254.04' (40A-WL1)
L2 - S03°49'05"W - 294.80'
L3 - S72°30'49"W - 32.20'

STA 43+62.11 OFF 123.53' LT
P1: STA 112+67.78 OFF 274.97' LT
(P.O.B. 40B-WL)

FAI/LIC-IR 70-0.00/0.00

RIGHT-OF-WAY BOUNDARY SHEET - IR 70 WB
STA 110+50.00 TO STA 115+50.00

DESIGN AGENCY
AMERICAN STRUCTUREPOINT INC.
DESIGNER JBY
REVIEWER MJW 07/02/25
PROJECT ID 96808
SHEET RW.127 TOTAL RW.220

MODEL: 96808_RB924 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 8:56:20 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\v401-Engineering_StructurePoint\RW\Sheets\96808_RB924.dgn

HE PC STA. 45+13.53

HF PT STA. 47+19.03

18 STA. 46+56.98

PROP. ℄ R/W TAYLOR ROAD CURVE DATA (C10)
P.I. = STA. 46+16.62
Δ = 11°18'09" LT
Dc = 05°30'00"
R = 1,041.74'
T = 103.08'
L = 205.50'

FAIRFIELD COUNTY, VIOLET TOWNSHIP
LICKING COUNTY, ETNA TOWNSHIP
CITY OF REYNOLDSBURG
HALF SEC. 26, 27, 34 & 35, (SEC. 16, 17, 20, & 21), TWP. 16, RNG. 20
REFUGEE LANDS, (FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)

HORIZONTAL SCALE IN FEET
0 10 20 40

RIGHT-OF-WAY TOPO SHEET - PROP. TAYLOR RD
STA 44+00.00 TO STA 49+50.00

MATCH LINE STA. 44+00.00 (SEE SHEET RW.126)

MATCH LINE STA. 49+50.00 (SEE SHEET RW.206)

PID: 045-03793.10
2405-2459 TAYLOR ROAD
COMMERCIAL

PID: 013-027582-00.001
CREEKSIDE ACQUISITION
COLUMBUS ASSOCIATES II, LLC
TAYLOR ROAD SW
RESIDENTIAL

PID: 036-00789.00
IGNACIO CARREÒN ÁLVAREZ AND
ROSARIO MARTINEZ GONZALEZ
13920 TAYLOR ROAD NW
RESIDENTIAL

PID: 012-027366-00.000
M. ELIZABETH GILL AND JENNIFER T. SAUTER,
SUCCESSOR CO-TRUSTEES OF THE
ROBERTA A. GILL TRUST DATED JULY 7, 1999
10517 TAYLOR ROAD SW
RESIDENTIAL

PROP. RIPRAP
PROP. STORM
PROP. CURB
PROP. EDGE OF PAVEMENT
PROP. BIKE PATH
PROP. DITCH
PROP. WALL
PROP. DITCH W/ RIPRAP
PROP. ℄ R/W & CONST. TAYLOR ROAD
HISTORIC ℄ R/W TAYLOR ROAD
CITY OF REYNOLDSBURG
VIOLET TOWNSHIP (SECTION 20) HALF SECTION 34
ETNA TOWNSHIP (SECTION 17) HALF SECTION 27
HALF SECTION 35 (SECTION 21)
HALF SECTION 26 (SECTION 16)
FAIRFIELD COUNTY (VIOLET TOWNSHIP)
LICKING COUNTY (ETNA TOWNSHIP)
TBRLBO
EX. CONC HEADWALL TBR
1-STY FRAME HOUSE
WOOD DECK
PLANTER
GRAVEL
2 STY VINYL
ASPH
CONC
WOODS
N03°39'46"E
N07°38'23"W
279.52'
3.39'
5.18'
16.6'
(SEE SHEET RW.218)


REV. BY	DATE	DESCRIPTION
DATE COMPLETED	07/02/2025	

DESIGN AGENCY: STRUCTUREPOINT LLC
DESIGNER: JBY
REVIEWER: MJW 07/02/25
PROJECT ID: 96808
SHEET: RW.204 TOTAL: RW.220

FAI/LIC-IR 70-0.00/0.00

MODEL: 96808_RT346 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 9:30:57 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RT346.dgn

FAIRFIELD COUNTY, VIOLET TOWNSHIP
LICKING COUNTY, ETNA TOWNSHIP
CITY OF REYNOLDSBURG
HALF SEC. 26, 27, 34 & 35, (SEC. 16, 17, 20 & 21), TWP. 16, RNG. 20
REFUGEE LANDS, (FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)



REV. BY	DATE	DESCRIPTION

DATE COMPLETED 07/02/2025

DESIGN AGENCY
AMERICAN STRUCTUREPOINT INC.

DESIGNER JBY
REVIEWER MJW 07/02/25
PROJECT ID 96808
SHEET RW.205 TOTAL RW.220

RIGHT-OF-WAY BOUNDARY SHEET - PROP. TAYLOR RD
STA 44+00.00 TO STA 49+50.00

FAI/LIC-IR 70-0.00/0.00

MODEL: 96808_RB346 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 9:31:29 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RB346.dgn

DATE COMPLETED 07/02/2025		
REV. BY	DATE	DESCRIPTION

PROP. ℄ R/W TAYLOR ROAD CURVE DATA (C11)
P.I. = STA. 51+36.59
Δ = 11°28'30" RT
Dc = 05°30'00"
R = 1,041.74'
T = 104.67'
L = 208.64'

℄ R/W TAYLOR ROAD SW CURVE DATA (C13)
P.I. = STA. 16+74.57
Δ = 41°04'07" LT
Dc = 05°43'46"
R = 1,000.00'
T = 374.57'
L = 716.78'

℄ CONST. TAYLOR ROAD SW CURVE DATA (C30)
P.I. = STA. 13+90.69
Δ = 40°13'45" RT
Dc = 15°00'00"
R = 381.97'
T = 139.89'
L = 268.20'

HG PC STA. 50+31.92
HH PT STA. 52+40.56
ZB PT STA. 15+19.00
21 STA. 16+58.75
50 STA. 15+74.78 (℄ CONST. TAYLOR RD SW) = STA. 51+00.00 (PROP. ℄ R/W TAYLOR RD)

LICKING COUNTY, ETNA TOWNSHIP
CITY OF REYNOLDSBURG
HALF SEC. 26 & 27, (SEC. 16 & 17)
TWP. 16, RNG. 20
REFUGEE LANDS
(FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)

HORIZONTAL SCALE IN FEET
0 10 20 40

RIGHT-OF-WAY TOPO SHEET - PROP. TAYLOR RD
STA 49+50.00 TO STA 54+00.00

MATCH LINE (SEE SHEET RW.214)
MATCH LINE STA. 15+50.00 (SEE SHEET RW.214)
MATCH LINE STA. 49+50.00 (SEE SHEET RW.206)
MATCH LINE STA. 54+00.00 (SEE SHEET RW.208)

PID: 013-027582-00.001
CREEKSIDE ACQUISITION COLUMBUS ASSOCIATES II, LLC
TAYLOR ROAD SW
RESIDENTIAL

PID: 013-027582-00.000
TERRACEVIEW APARTMENTS, LTD.
10564 TAYLOR ROAD SW
RESIDENTIAL

PID: 013-029502-00.000
CAROLYN M. YOUSEY
TAYLOR ROAD SW
RESIDENTIAL

PID: 012-027366-00.000
M. ELIZABETH GILL AND JENNIFER T. SAUTER, SUCCESSOR CO-TRUSTEES OF THE ROBERTA A. GILL TRUST DATED JULY 7, 1999
10517 TAYLOR ROAD SW
RESIDENTIAL

PID: 012-027528-00.000
VEDIC WELFARE SOCIETY OF COLUMBUS
10479 TAYLOR ROAD SW
RESIDENTIAL

DEXTER HEIGHTS
P.B. 8, PG. 9

CITY OF REYNOLDSBURG
ETNA TOWNSHIP

℄ R/W TAYLOR ROAD SW
HISTORIC ℄ R/W TAYLOR ROAD
PROP. ℄ R/W & CONST. TAYLOR ROAD
(SECTION 17) HALF SECTION 27 HALF SECTION 26 (SECTION 16)

PROP. BIKE PATH
PROP. CURB
PROP. WALK
PROP. DITCH
PROP. STORM
PROP. RIPRAP
PROP. ℄ CONST. TAYLOR ROAD SW
Ex R/W
Ex SH
TMP R/W
LA-R/W
EX. PARKING LOT
1 STY VINYL
WOODS
GRASS
ASPH
CONC
GRAVEL
LARGE ROCK
EX. WALK
EX. DITCH
TBR
TBRLBO
LOT 5
N07°38'23"W
N86°06'17"E
N03°50'07"E
47.9'
54.91'
18.23'
160.60'
90.19'
91.21'

FAI/LIC-IR 70-0.00/0.00

MODEL: 96808_RT347 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 9:32:01 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RT347.dgn

DESIGN AGENCY: STRUCTUREPOINT
DESIGNER: JBY
REVIEWER: MJW 07/02/25
PROJECT ID: 96808
SHEET: RW.206 TOTAL: RW.220

DATE COMPLETED 07/02/2025		
REV. BY	DATE	DESCRIPTION

HG PC STA. 50+31.92

HH PT STA. 52+40.56

ZB PT STA. 15+19.00

21 STA. 16+58.75

50 STA. 15+74.78 (℄ CONST. TAYLOR RD SW) = STA. 51+00.00 (PROP. ℄ R/W TAYLOR RD)

PROP. ℄ R/W TAYLOR ROAD CURVE DATA (C11)
P.I. = STA. 51+36.59
Δ = 11°28'30" RT
Dc = 05°30'00"
R = 1,041.74'
T = 104.67'
L = 208.64'

℄ CONST. TAYLOR ROAD SW CURVE DATA (C30)
P.I. = STA. 13+90.69
Δ = 40°13'45" RT
Dc = 15°00'00"
R = 381.97'
T = 139.89'
L = 268.20'

℄ R/W TAYLOR ROAD SW CURVE DATA (C13)
P.I. = STA. 16+74.57
Δ = 41°04'07" LT
Dc = 05°43'46"
R = 1,000.00'
T = 374.57'
L = 716.78'

LICKING COUNTY, ETNA TOWNSHIP
CITY OF REYNOLDSBURG
HALF SEC. 26 & 27, (SEC. 16 & 17)
TWP. 16, RNG. 20
REFUGEE LANDS
(FMR. CONGRESS LANDS E. OF THE SCIOTO RIVER)

C1: CURVE DATA
R = 1,035.00'
L = 269.04'
Δ = 14°53'37"
CH BRG = N11°57'45"E
CH DIST = 268.28'

C2: CURVE DATA
R = 967.00'
L = 130.70'
Δ = 07°44'39"
CH BRG = S21°11'37"W
CH DIST = 130.60'

P1: STA. 49+63.06 OFF. 85.74' LT. (P.O.B. 40-PRW2)

P2: STA. 49+57.09 OFF. 56.34' LT. (P.O.B. 40A-WL2)

P3: STA. 49+53.81 OFF. 40.17' LT.

P4: STA. 50+00.00 OFF. 78.24' LT. (P.O.T. 40-PRW2)

P5: STA. 50+00.00 OFF. 47.62' LT. (P.O.B. 116-WDV)

HORIZONTAL SCALE IN FEET
0 10 20 40

RIGHT-OF-WAY BOUNDARY SHEET - PROP. TAYLOR RD
STA 49+50.00 TO STA 54+00.00

DESIGN AGENCY	
STRUCTUREPOINT LLC	
DESIGNER	JBY
REVIEWER	MJW 07/02/25
PROJECT ID	96808
SHEET	RW.207
TOTAL	RW.220

FAI/LIC-IR 70-0.00/0.00

MODEL: 96808_RB347 PAPERSIZE: 34x22 (in.) DATE: 7/16/2025 TIME: 9:32:32 AM USER: jyoumans
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Fairfield\96808\401-Engineering_StructurePoint\RW\Sheets\96808_RB347.dgn

ODOT RE 205
Rev. 07/2025

QCD
State

QUIT CLAIM DEED

City of Reynoldsburg, the Grantor(s) in consideration of the sum of $GIFT/DONATION PURSUANT TO R.C. 5501.33, does grant, and forever Quit Claim to the State of Ohio and its successors and assigns for the use and benefit of the Department of Transportation, the Grantee, all right, title and interest in fee simple in the following described real estate:

PARCEL(S): 40A-WL1, WL2

FAI/LIC-70-0.00/0.00

SEE EXHIBIT A ATTACHED

No Auditor Parcel Number Assigned
Prior Instrument Reference: OR 1121, Page 670, Fairfield County Recorder's Office.

To have and to hold the parcel(s) unto the Grantee, except: (a) easements, restrictions, conditions, and covenants of record; (b) all legal highways; (c) zoning and building laws, ordinances, rules, and regulations; and (d) any and all taxes and assessments not yet due and payable.

The parcel(s) conveyed to Grantee is being acquired for one of the statutory purposes the Director of Transportation may acquire property under Title LV of the Revised Code, such as but not limited to those purposes enumerated in Sections 5501.31 and 5519.01 of the Revised Code.

In accordance with Ohio Revised Code Section 5501.331, the parties further understand and agree as follows:

(A) All alternatives to a proposed alignment of the highway project shall be studied and considered pursuant to the "National Environmental Policy Act of 1969," 83 Stat. 852, 42 U.S.C.A. 4321 et seq., as amended.

(B) Acceptance of the donation shall not influence the environmental assessment of the highway project, including the decision relative to the need to construct the project or selection of its specific location.

(C) The donated interest shall revert to the grantor or his successors or assigns if the interest is not required for the alignment chosen for the highway project after public hearings, if hearings are required, and adoption of the environmental document.

IN WITNESS WHEREOF City of Reynoldsburg by and through _____, the _____ of City of Reynoldsburg, has hereunto subscribed their name on this _____. day of _____, 2025.

CITY OF REYNOLDSBURG

By: _____

STATE OF OHIO, COUNTY OF _____ SS:

The foregoing instrument was acknowledged before me this _____ day of _____, 2025 _____ as _____ of City of Reynoldsburg.

In Testimony Whereof, I have subscribed my name and affixed my official seal on the day and year last aforesaid.

_____

NOTARY PUBLIC
My Commission expires: _____

This document was prepared by or for the State of Ohio, Department of Transportation, on forms approved by the Attorney General of Ohio.

EXHIBIT A

RX 252 WL

Rev. 06/09

Ver. Date 07/02/2025

PID 96808

PARCEL 40A-WL1
FAI/LIC-IR 70-0.00/0.00

ALL RIGHT, TITLE AND INTEREST IN FEE SIMPLE IN THE FOLLOWING DESCRIBED PROPERTY INCLUDING LIMITATION OF ACCESS

Grantor/Owner, his heirs, executors, administrators, successors and assigns forever, are hereby divested of any and all abutter's rights, including access rights in, over and to the within described real estate, including such rights with respect to any highway facility constructed thereon (as used herein, the expression "Grantor/Owner" includes the plural, and words in the masculine include the feminine or neuter).

[Surveyor's description of the premises follows]

Situated in the State of Ohio, County of Fairfield, City of Reynoldsburg, Township of Violet, being located in Half Section 34, Township 16, Range 20, Refugee Lands, and being located in Section 20 of the former Congress Lands East of the Scioto River, being part of that **0.206 acre** right-of-way parcel described in a deed to **City of Reynoldsburg, Ohio**, of record in **Official Record 1121, Page 670**, all records referenced herein are on file at the Office of the Recorder for Fairfield County, Ohio, unless otherwise noted, being a parcel on the left side of the centerline of right-of-way for Interstate Route 70, being a parcel on the left side of the proposed centerline of right-of-way for Taylor Road, both said centerlines as delineated on the centerline plat for FAI/LIC-IR 70-0.00/0.00, all stationing herein is referenced to said centerline plat, said parcel being further bounded and described as follows:

Commencing for reference at an aluminum disk found in a concrete monument, designated as Franklin County Geodetic Survey monument number FCGS 2219, said disk being at the common corner of said Fairfield County, Franklin County and Licking County, being at the common corner of said Half Section 34, Half Section 33, Half Section 28 and Half Section 27, Township 16, Range 20, Refugee Lands, being at the north Quarter Section corner of said Section 20, and being at the south Quarter Section corner of Section 17 of the former Congress Lands East of the Scioto River, said disk being 1,525.17 feet left of Interstate Route 70 centerline of right-of-way station 88+80.85 and being 2,741.25 feet left of proposed Taylor Road centerline of right-of-way station 50+81.86;

Thence **South 86 degrees 08 minutes 42 seconds East**, along the common line between said Fairfield County and said Licking County, along the common line between said Half Section 34 and said Half Section 27, and along the common line between said Section 20 and said Section 17, a distance of **2,678.16 feet** to a MAG spike set at the northeast corner of said Half Section 34, being the northwest corner of Half Section 35, Township 16, Range 20, Refugee Lands, being the northeast corner of said Section 20, being the northwest corner of Section 21 of the former Congress Lands East of the Scioto

River, being the northeast corner of said 0.206 acre right-of-way parcel, being the northwest corner of that 4.041 acre tract of land described in a deed to Ignacio Carreon Alvarez and Rosario Martinez Gonzalez, of record in Instrument Number 202500003344, being on the historic centerline of right-of-way for Taylor Road (R/W width varies), being on the south line of Half Section 26, Township 16, Range 20, Refugee Lands, being on the south line of Section 16 of the former Congress Lands East of the Scioto River, being on the south line of that 9.60 acre tract of land described in deeds to M. Elizabeth Gill and Jennifer T. Sauter, Successor Co-Trustees of the Roberta A. Gill Trust Dated July 7, 1999, of record in Instrument Number 200005160015386 and Instrument Number 202405150008174, on file at the Office of the Recorder for Licking County, Ohio, and being on the east line of a proposed right-of-way parcel, said MAG nail being 111.62 feet left of Taylor Road proposed centerline of right-of-way station 46+74.76;

Thence **South 03 degrees 49 minutes 05 seconds West**, along the historic centerline of right-of-way for said Taylor Road, along the common line between said Half Section 34 and said Half Section 35, along the common line between said Section 20 and said Section 21, along the east line of said 0.206 right-of-way parcel, along the west line of said 4.041 acre tract, and along the east line of said proposed right-of-way parcel, a distance of **52.45 feet** to an iron pin set at the southeast corner of said proposed right-of-way parcel, said iron pin being 118.39 feet left of Taylor Road proposed centerline of right-of-way station 46+16.28 and being the **TRUE POINT OF BEGINNING** for this description;

Thence **South 03 degrees 49 minutes 05 seconds West**, continuing along the historic centerline of right-of-way for said Taylor Road, along the common line between said Half Section 34 and said Half Section 35, along the common line between said Section 20 and said Section 21, along the east line of said 0.206 right-of-way parcel, and along the west line of said 4.041 acre tract, a distance of **242.35** to a railroad spike found at the southeast corner of said 0.206 acre right-of-way parcel, being the northeast corner of that 0.173 acre standard highway easement described as Parcel No. 316 in a deed to Board of County Commissioners of Fairfield County, Ohio, of record in Deed Book 476, Page 467, being the northeast corner of the remainder of that 80 acre tract of land described in a deed to George A. Page and Violet L. Page, of record in Deed Book 223, Page 34, said railroad spike being 123.53 feet left of Taylor Road proposed centerline of right-of-way station 43+62.11 and being 274.97 feet left of Interstate Route 70 centerline of right-of-way station 112+67.78;

Thence **South 72 degrees 30 minutes 49 seconds West**, across said Taylor Road, along the south line of said 0.206 acre right-of-way parcel, along the north line of said Parcel No. 316, and along the north line of the remainder of said Page tract, a distance of **32.20 feet** to a 3/4-inch iron pipe found with a cap inscribed "EMHT" at a northwest corner of the existing west right-of-way line for Taylor Road, being the southwest corner of said 0.206 acre right-of-way parcel, being a southeast corner of that 23.641 acre tract of land described as Parcel I, Tract I in a deed to Creekside Acquisition Columbus Associates II, LLC, of record in Official Record 1745, Page 4507, said iron pipe being 153.57 feet left of Taylor Road proposed centerline of right-of-way station 43+50.50 and being 274.98 feet left of Interstate Route 70 centerline of right-of-way station 112+35.58;

EXHIBIT A

RX 252 WL

Rev. 06/09

Thence **North 03 degrees 49 minutes 05 seconds East**, along the existing west right-of-way line for Taylor Road, along the west line of said 0.206 acre right-of-way parcel and along the east line of said Parcel I, Tract I, a distance of **254.04 feet** to an iron pin set at the southwest corner of said proposed right-of-way parcel, said iron pin 148.23 feet left of Taylor Road proposed centerline of right-of-way station 46+19.82;

Thence **South 86 degrees 10 minutes 56 seconds East**, across Taylor Road, across said 0.206 acre right-of-way parcel and along the south line of said proposed right-of-way parcel, a distance of **30.00 feet** to the **TRUE POINT OF BEGINNING** for this description.

The above described limited access right-of-way parcel contains a total area of **0.171 acres** (0.171 acres located within present road occupied), none of which are not located within a Fairfield County Auditor's parcel number, but all of which are adjacent to and bounded as follows: to the north by a proposed right-of-way parcel, to the east by Fairfield County Auditor's parcel number 036-00789.00, to the south by said Parcel No. 316 and said Page remainder tract, to the west by the existing west right-of-way line for Taylor Road and Fairfield County Auditor's parcel number 045-03793.10.

Bearings described hereon based on the bearing of South 86 degrees 08 minutes 42 seconds East for the common line between Half Section 27 and Half Section 34, Township 16, Range 20, Refugee Lands, being the common line between Section 17 and Section 20 of the former Congress Lands East of the Scioto River, and being a common line between Fairfield County and Licking County, as measured from Grid North, referenced to the Ohio State Plane Coordinate System (South Zone) and the North American Datum of 1983 (2011 Adjustment), as established utilizing a GNSS survey and a NGS OPUS solution.

Where referenced, iron pins set are 5/8-inch diameter by 30-inch long rebar with a cap inscribed "ASI FIRM 1648".

This description was prepared under the direct supervision of Michael J. Ward, Registered Professional Surveyor No. 8808, on July 2, 2025, is based on an actual field survey performed by American Structurepoint, Inc., and is true and correct to the best of my knowledge and belief.

American Structurepoint, Inc.

Michael J. Ward
Registered Professional Surveyor No. 8808

STATE OF OHIO
MICHAEL J WARD
S-8808
REGISTERED
PROFESSIONAL SURVEYOR

7/14/25
Date

LEGAL DESCRIPTION AND PLAT MEETS MINIMUM STANDARDS FOR BOUNDARY SURVEYS.
FAIRFIELD COUNTY ENGINEER
BY ACS DATE 7/21/25

DESCRIPTION REVIEWED AND APPROVED FOR TRANSFER ONLY FAIRFIELD COUNTY AUDITOR/ENGINEER TAX MAPS.
BY SAK DATE 07/22/25
PAI/LIC-IR 70-0.00/0.00

EXHIBIT A

RX 252 WL

Rev. 06/09

Ver. Date 07/02/2025

PID 96808

PARCEL 40A-WL2
FAI/LIC-IR 70-0.00/0.00

ALL RIGHT, TITLE AND INTEREST IN FEE SIMPLE IN THE FOLLOWING DESCRIBED PROPERTY INCLUDING LIMITATION OF ACCESS

Grantor/Owner, his heirs, executors, administrators, successors and assigns forever, are hereby divested of any and all abutter's rights, including access rights in, over and to the within described real estate, including such rights with respect to any highway facility constructed thereon (as used herein, the expression "Grantor/Owner" includes the plural, and words in the masculine include the feminine or neuter).

[Surveyor's description of the premises follows]

Situated in the State of Ohio, County of Licking, City of Reynoldsburg, Township of Etna, being located in Half Section 27, Township 16, Range 20, Refugee Lands, and being located in Section 17 of the former Congress Lands East of the Scioto River, being part of that **0.263 acre** right-of-way parcel described in a deed to **City of Reynoldsburg, Ohio**, of record in **Instrument Number 200005260016710**, all records referenced herein are on file at the Office of the Recorder for Licking County, Ohio, unless otherwise noted being a parcel on the left side of the proposed centerline of right-of-way for Taylor Road, as delineated on the centerline plat for FAI/LIC-IR 70-0.00/0.00, all stationing herein is referenced to said centerline plat, said parcel being further bounded and described as follows:

Commencing for reference at an aluminum disk found in a concrete monument, designated as Franklin County Geodetic Survey monument number FCGS 2219, said disk being at the common corner of said Licking County, Franklin County and Fairfield County, being at the common corner of said Half Section 27, Half Section 34, Half Section 33 and Half Section 28, Township 16, Range 20, Refugee Lands, being at the south Quarter Section corner of said Section 17, and being at the north Quarter Section corner of Section 20 of the former Congress Lands East of the Scioto River, said disk being 1,525.17 feet left of Interstate Route 70 centerline of right-of-way station 88+80.85 and being 2,741.25 feet left of proposed Taylor Road centerline of right-of-way station 50+81.86;

Thence **South 86 degrees 08 minutes 42 seconds East**, along the common line between said Licking County and said Fairfield County, along the common line between said Half Section 27 and said Half Section 34, and along the common line between said Section 17 and said Section 20, a distance of **2,677.94 feet** to a MAG spike set at the southeast corner of said Half Section 27, being the southwest corner of Half Section 26, Township 16, Range 20, Refugee Lands, being the

southeast corner of said Section 17, being the southwest corner of Section 16 of the former Congress Lands East of the Scioto River, being the southeast corner of said 0.263 acre right-of-way parcel, being the southwest corner of that 9.60 acre tract of land described in deeds to M. Elizabeth Gill and Jennifer T. Sauter, Successor Co-Trustees of the Roberta A. Gill Trust Dated July 7, 1999, of record in Instrument Number 200005160015386 and Instrument Number 202405150008174, being on the historic centerline of right-of-way for Taylor Road (R/W width varies), and being on the east line of a proposed right-of-way parcel, said MAG spike being 111.84 feet left of Taylor Road proposed centerline of right-of-way station 46+74.80;

Thence **North 03 degrees 50 minutes 07 seconds East**, along the historic centerline of right-of-way for Taylor Road, along the common line between said Half Section 27 and said Half Section 26, along the common line between said Section 17 and said Section 16, along the east line of said 0.263 acre right-of-way parcel, along the west line of said 9.60 acre tract, and along the east line of said proposed right-of-way parcel, a distance of **283.19 feet** to an iron pin set at the northeast corner of said proposed right-of-way parcel, said iron pin being the **TRUE POINT OF BEGINNING** for this description and being 56.34 feet left of Taylor Road proposed centerline of right-of-way station 49+57.09;

Thence **North 86 degrees 09 minutes 53 seconds West**, across Taylor Road, across said 0.263 acre right-of-way parcel, and along the north line of said proposed right-of-way parcel, a distance of **30.00 feet** to an iron pin set on the existing west right-of-way line for Taylor Road, being on the west line of said 0.263 acre right-of-way parcel, and being on the east line of that 2.762 acre tract described in a deed to Creekside Acquisition Columbus Associates II, LLC, of record in Instrument Number 201708230017770, and being the northwest corner of said proposed right-of-way parcel, said iron pin being 85.74 feet left of Taylor Road proposed centerline of right-of-way station 49+63.06;

Thence **North 03 degrees 50 minutes 07 seconds East**, along the existing west right-of-way line for Taylor Road, along the west line of said 0.263 acre right-of-way parcel and along the east line of said 2.762 acre tract, a distance of **37.70 feet** to an iron pin set, said iron pin being 78.24 feet left of Taylor Road proposed centerline of right-of-way station 50+00.00;

Thence **North 82 degrees 21 minutes 37 seconds East**, across Taylor Road and across said 0.263 acre right-of-way parcel, a distance of **30.61 feet** to an iron pin set on the historic centerline of right-of-way for Taylor Road, being on the common line between said Half Section 27 and said Half Section 26, being on the common line between said Section 17 and said Section 16, being on the east line of said 0.263 acre right-of-way parcel and being on the west line of said 9.60 acre tract, said iron pin being 47.62 feet left of Taylor Road proposed centerline of right-of-way station 50+00.00;

EXHIBIT A

Thence **South 03 degrees 50 minutes 07 seconds West**, along the historic centerline of right-of-way for Taylor Road, along the common line between said Half Section 27 and said Half Section 26, along the common line between said Section 17 and said Section 16, along the east line of said 0.263 acre right-of-way parcel, and along the west line of said 9.60 acre tract, a distance of **43.79 feet** to the **TRUE POINT OF BEGINNING** for this description.

The above described limited access right-of-way parcel contains a total area of **0.028 acres** (0.028 acres located within present road occupied), none of which are not located within a Licking County Auditor's parcel number, but all of which are adjacent to and bounded as follows: to the north by Taylor Road, to the east by the historic centerline of right-of-way for Taylor Road, to the south by a proposed right-of-way parcel, to the west by the existing west right-of-way line for Taylor Road and Licking County Auditor's parcel number 013-027582-00.001.

Bearings described hereon based on the bearing of South 86 degrees 08 minutes 42 seconds East for the common line between Half Section 27 and Half Section 34, Township 16, Range 20, Refugee Lands, being the common line between Section 17 and Section 20 of the former Congress Lands East of the Scioto River, and being a common line between Fairfield County and Licking County, as measured from Grid North, referenced to the Ohio State Plane Coordinate System (South Zone) and the North American Datum of 1983 (2011 Adjustment), as established utilizing a GNSS survey and a NGS OPUS solution.

Where referenced, iron pins set are 5/8-inch diameter by 30-inch long rebar with a cap inscribed "ASI FIRM 1648".

This description was prepared under the direct supervision of Michael J. Ward, Registered Professional Surveyor No. 8808, on July 2, 2025, is based on an actual field survey performed by American Structurepoint, Inc., and is true and correct to the best of my knowledge and belief.

American Structurepoint, Inc.

Michael J. Ward
Registered Professional Surveyor No. 8808



7/14/25
Date

PRE-APPROVAL
LICKING COUNTY ENGINEER
APPROVED ☑ CONDITIONAL ☐
APPROVED BY:
DATE: 7/17/25

ODOT RE 205
Rev. 07/2025

QCD
State

QUIT CLAIM DEED

City of Reynoldsburg, the Grantor(s) in consideration of the sum of $GIFT/DONATION PURSUANT TO R.C. 5501.33, does grant, and forever Quit Claim to the State of Ohio and its successors and assigns for the use and benefit of the Department of Transportation, the Grantee, all right, title and interest in fee simple in the following described real estate:

PARCEL(S): 40A-WD

FAI/LIC-70-0.00/0.00

SEE EXHIBIT A ATTACHED

No Auditor Parcel Number Assigned
Prior Instrument Reference: OR 1121, Page 670, Fairfield County Recorder's Office.

To have and to hold the parcel(s) unto the Grantee, except: (a) easements, restrictions, conditions, and covenants of record; (b) all legal highways; (c) zoning and building laws, ordinances, rules, and regulations; and (d) any and all taxes and assessments not yet due and payable.

The parcel(s) conveyed to Grantee is being acquired for one of the statutory purposes the Director of Transportation may acquire property under Title LV of the Revised Code, such as but not limited to those purposes enumerated in Sections 5501.31 and 5519.01 of the Revised Code.

In accordance with Ohio Revised Code Section 5501.331, the parties further understand and agree as follows:

(A) All alternatives to a proposed alignment of the highway project shall be studied and considered pursuant to the "National Environmental Policy Act of 1969," 83 Stat. 852, 42 U.S.C.A. 4321 et seq., as amended.

(B) Acceptance of the donation shall not influence the environmental assessment of the highway project, including the decision relative to the need to construct the project or selection of its specific location.

(C) The donated interest shall revert to the grantor or his successors or assigns if the interest is not required for the alignment chosen for the highway project after public hearings, if hearings are required, and adoption of the environmental document.

IN WITNESS WHEREOF City of Reynoldsburg by and through _____, the _____ of City of Reynoldsburg, has hereunto subscribed their name on this _____. day of _____, 2025.

CITY OF REYNOLDSBURG

By: _____

STATE OF OHIO, COUNTY OF _____ SS:

The foregoing instrument was acknowledged before me this _____ day of _____, 2025 _____ as _____ of City of Reynoldsburg.

In Testimony Whereof, I have subscribed my name and affixed my official seal on the day and year last aforesaid.

_____

NOTARY PUBLIC
My Commission expires: _____

This document was prepared by or for the State of Ohio, Department of Transportation, on forms approved by the Attorney General of Ohio.

EXHIBIT A

RX 250 WD

Rev. 06/09

Ver. Date 07/02/2025

PID 96808

PARCEL 40A-WD
FAI/LIC-IR 70-0.00/0.00

ALL RIGHT, TITLE AND INTEREST IN FEE SIMPLE IN THE FOLLOWING DESCRIBED PROPERTY WITHOUT LIMITATION OF EXISTING ACCESS RIGHTS

Grantor/Owner, for himself and his heirs, executors, administrators, successors and assigns, reserves all existing rights of ingress and egress to and from any residual area (as used herein, the expression "Grantor/Owner" includes the plural, and words in the masculine include the feminine or neuter).

[Surveyor's description of the premises follows]

Situated in the State of Ohio, Counties of Fairfield and Licking, City of Reynoldsburg, Townships of Violet and Etna, being located in Half Section 34 and Half Section 27, Township 16, Range 20, Refugee Lands, and being located in Section 20 and Section 17 of the former Congress Lands East of the Scioto River, being part of that **0.206 acre** right-of-way parcel described in a deed to **City of Reynoldsburg, Ohio**, of record in **Official Record 1121, Page 670**, on file at the Office of the Recorder for Fairfield County, Ohio, being part of that **0.263 acre** right-of-way parcel described in a deed to **City of Reynoldsburg, Ohio**, of record in **Instrument Number 200005260016710**, on file at the Office of the Recorder for Licking County, Ohio, being a parcel on the left side of the proposed centerline of right-of-way for Taylor Road, as delineated on the centerline plat for FAI/LIC-IR 70-0.00/0.00, all stationing herein is referenced to said centerline plat, said parcel being further bounded and described as follows:

Commencing for reference at an aluminum disk found in a concrete monument, designated as Franklin County Geodetic Survey monument number FCGS 2219, said disk being at the common corner of said Fairfield County, Franklin County and Licking County, being at the common corner of said Half Section 34, said Half Section 27, Half Section 33 and Half Section 28, Township 16, Range 20, Refugee Lands, being at the north Quarter Section corner of said Section 20, and being at the south Quarter Section corner of said Section 17, said disk being 1,525.17 feet left of Interstate Route 70 centerline of right-of-way station 88+80.85 and being 2,741.25 feet left of proposed Taylor Road centerline of right-of-way station 50+81.86;

Thence **South 86 degrees 08 minutes 42 seconds East**, along the common line between said Fairfield County and said Licking County, along the common line between said Half Section 34 and said Half Section 27, and along the common line between said Section 20 and said Section 17, a distance of **2,678.16 feet** to a MAG spike set at the northeast corner of said Half Section 34, being the northwest corner of Half Section 35, Township 16, Range 20, Refugee Lands, being the northeast corner of said Section 20, being the northwest corner of Section 21 of the former Congress Lands East of the Scioto River, being the northeast corner of said 0.206 acre right-of-way parcel, being the northwest corner of that 4.041 acre tract of land described in a deed to Ignacio Carreon Alvarez and Rosario Martinez Gonzalez, of record in Instrument

Number 202500003344, on file at said Fairfield County Recorder's Office, being on the historic centerline of right-of-way for Taylor Road (R/W width varies), being on the south line of Half Section 26, Township 16, Range 20, Refugee Lands, being on the south line of Section 16 of the former Congress Lands East of the Scioto River, and being on the south line of that 9.60 acre tract of land described in deeds to M. Elizabeth Gill and Jennifer T. Sauter, Successor Co-Trustees of the Roberta A. Gill Trust Dated July 7, 1999, of record in Instrument Number 200005160015386 and Instrument Number 202405150008174, on file at said Licking County Recorder's Office, said MAG spike being the **TRUE POINT OF BEGINNING** for this description and being 111.62 feet left of Taylor Road proposed centerline of right-of-way station 46+74.76;

Thence **South 03 degrees 49 minutes 05 seconds West**, along the historic centerline of right-of-way for said Taylor Road, along the common line between said Half Section 34 and said Half Section 35, along the common line between said Section 20 and said Section 21, along the east line of said 0.206 right-of-way parcel, and along the west line of said 4.041 acre tract, a distance of **52.45 feet** to an iron pin set at the northeast corner of a proposed limited access right-of-way parcel, said iron pin being 118.39 feet left of Taylor Road proposed centerline of right-of-way station 46+16.28;

Thence **North 86 degrees 10 minutes 56 seconds West**, across Taylor Road, across said 0.206 acre right-of-way parcel, and along the north line of said proposed limited access right-of-way parcel, a distance of **30.00 feet** to an iron pin set on the existing west right-of-way line for Taylor Road, being on the west line of said 0.206 acre right-of-way parcel, being on the east line of that 23.641 acre tract described as Parcel I, Tract I in a deed to Creekside Acquisition Columbus Associates II, LLC, of record in Official Record 1745, Page 4507, on file at said Fairfield County Recorder's Office, and being at the northwest corner of said proposed limited access right-of-way parcel, said iron pin being 148.23 feet left of Taylor Road proposed centerline of right-of-way station 46+19.82;

Thence along the existing west right-of-way line for Taylor Road for following three (3) described courses:

1. **North 03 degrees 49 minutes 05 seconds East**, along the west line of said 0.206 acre right-of-way parcel and along the east line of said Parcel I, Tract I, a distance of **52.47 feet** to the northwest corner of said 0.206 acre right-of-way parcel, being the northeast corner of said Parcel I, Tract I, being on the common line between said Fairfield County and said Licking County, being on the common line between said Half Section 34 and said Half Section 27, being on the common line between said Section 20 and said Section 17, and being on the south line of said 0.263 acre right-of-way parcel (reference a 3/4" iron pipe found with a cap inscribed "EMH&T" at a bearing of South 05 degrees 47 minutes 56 seconds West and a distance of 1.21 feet), said point being 141.23 feet left of Taylor Road proposed centerline of right-of-way station 46+80.22;

2. **North 86 degrees 08 minutes 42 seconds West**, along the common line between said Fairfield County and said Licking County, along the common line between said Half Section 34 and said Half Section 27, along the common line between said Section 20 and said Section 17, along the south line of said 0.263 acre right-of-way parcel, and along the north line of said Parcel I, Tract I, a distance of **0.22 feet** to the southwest corner of said 0.263 acre right-of-way parcel, being the southeast corner of that 2.762 acre tract of land described in a deed to Creekside Acquisition Columbus Associates II, LLC, of record in Instrument Number 201708230017770, on file at said Licking County Recorder's Office (reference a 3/4" iron pipe found with a cap inscribed "EMH&T" at a bearing of South 04 degrees 32 minutes 20 seconds West and a distance of 1.22 feet), said corner being 141.45 feet left of Taylor Road proposed centerline of right-of-way station 46+80.26;

3. **North 03 degrees 50 minutes 07 seconds East**, along the west line of said 0.263 acre right-of-way parcel and along the east line of said 2.762 acre tract, a distance of **283.18 feet** to an iron pin set at the southwest corner of another proposed limited access right-of-way parcel, said iron pin being 85.74 feet left of Taylor Road proposed centerline of right-of-way station 49+63.06;

Thence **South 86 degrees 09 minutes 53 seconds East**, across Taylor Road, across said 0.263 acre right-of-way parcel, and along the south line of the previous said proposed limited access right-of-way parcel, a distance of **30.00 feet** to an iron pin set on the historic centerline of right-of-way for Taylor Road, being on the common line between said Half Section 27 and said Half Section 26, being on the common line between said Section 17 and said Section 16, being on the east line of said 0.263 acre right-of-way parcel, being on the west line of said 9.60 acre tract, and being the southeast corner of the previous said proposed limited access right-of-way parcel, said iron pin being 56.34 feet left of Taylor Road proposed centerline of right-of-way station 49+57.09;

Thence **South 03 degrees 50 minutes 07 seconds West**, along the historic centerline of right-of-way for said Taylor Road, along the common line between said Half Section 27 and said Half Section 26, along the common line between said Section 17 and said Section 16, along the east line of said 0.263 right-of-way parcel, and along the west line of said 9.60 acre tract, a distance of **283.19 feet** to a MAG spike set at the southeast corner of said Half Section 27, being the southwest corner of said Half Section 26, being the southeast corner of said Section 17, being the southwest corner of said Section 16, being the southeast corner of said 0.263 acre right-of-way parcel, being the southwest corner of said 9.60 acre tract, being on the common line between said Fairfield County and said Licking County, being on the north line of said Half Section 34, being on the north line of said Section 20, and being on the north line of said 0.206 acre right-of-way parcel, said MAG spike being 111.84 feet left of Taylor Road proposed centerline of right-of-way station 46.74.80;

Thence **South 86 degrees 08 minutes 42 seconds East**, along the common line between said Fairfield County and said Licking County, along the common line between said Half Section 26 and said Half Section 34, along the common line between said Section 20 and said Section 16, along the north line of said 0.206 acre right-of-way parcel and along the south line of said 9.60 acre tract, a distance of **0.22 feet** to the **TRUE POINT OF BEGINNING** for this description.

EXHIBIT A

RX 250 WD

Rev. 06/09

The above described right-of-way parcel contains a total area of **0.231 acres** (0.231 acres located within present road occupied), none of which are located within a Fairfield County Auditor's parcel number nor a Licking County Auditor's parcel number, but all of which are adjacent to and bounded as follows: to the west by the existing west right-of-way line for Taylor Road, Fairfield County Auditor's parcel number 045-03793.10, and Licking County Auditor's parcel number 013-027582-00.001, to the north by a proposed limited access right-of-way parcel, to the east by the historic centerline of right-of-way for Taylor Road, and to the south by a proposed limited access right-of-way parcel.

Bearings described hereon based on the bearing of South 86 degrees 08 minutes 42 seconds East for the common line between Half Section 27 and Half Section 34, Township 16, Range 20, Refugee Lands, being the common line between Section 17 and Section 20 of the former Congress Lands East of the Scioto River, and being a common line between Fairfield County and Licking County, as measured from Grid North, referenced to the Ohio State Plane Coordinate System (South Zone) and the North American Datum of 1983 (2011 Adjustment), as established utilizing a GNSS survey and a NGS OPUS solution.

Where referenced, iron pins set are 5/8-inch diameter by 30-inch long rebar with a cap inscribed "ASI FIRM 1648".

This description was prepared under the direct supervision of Michael J. Ward, Registered Professional Surveyor No. 8808 on July 2, 2025, is based on an actual field survey performed by American Structurepoint, Inc., and is true and correct to the best of my knowledge and belief.

American Structurepoint, Inc.

Michael J. Ward
Registered Professional Surveyor No. 8808

STATE OF OHIO
MICHAEL J WARD
S-8808
REGISTERED
PROFESSIONAL SURVEYOR

7/14/25
Date

PRE-APPROVAL
LICKING COUNTY ENGINEER

APPROVED ☑ CONDITIONAL ☐

APPROVED BY:

DATE: 7/17/25

STATE OF OHIO EASEMENT

This Agreement (hereinafter referred to as "Agreement"), dated as of _____ is made and entered into by and between the State of Ohio, acting by and through the Department of Administrative Services, General Services Division, Office of Real Estate and Planning, 4200 Surface Road, Columbus, Ohio 43228-1395, the Grantor (hereinafter referred to as "State"), for and on behalf of the Department of Agriculture (hereinafter referred to as "Agency"), and City of Reynoldsburg, an Ohio municipal corporation, duly formed and existing under the laws of the State of Ohio (hereinafter referred to as "Grantee"), having its principal place of business located at 7232 East Main Street, Reynoldsburg, Ohio 43068, pursuant to the provisions of Section 123.01(A)(5) of the Ohio Revised Code.

RECITALS

WHEREAS, State is the owner, in fee simple, of the land described in Exhibit "A" attached hereto and made a part hereof and more particularly depicted in Exhibit "B" attached hereto and made a part hereof (hereinafter referred to as "Easement Area"). Further reference is made to DAS File No. 8531-E1 on file with the State; and

WHEREAS, Grantee desires to obtain from State an easement in order to permit the installation, construction, reconstruction, use, operation, maintenance, repair, replacement, removal, servicing and improvement of a certain sanitary sewer line upon the Easement Area; and

WHEREAS, Agency requested the State prepare this Agreement; and

NOW, THEREFORE, in consideration of the terms and conditions contained herein and for other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the parties hereto agree as follows:

I. USE OF PREMISES.

State does hereby grant a non-exclusive easement unto Grantee to be used solely to install, construct, reconstruct, use, operate, maintain, repair, replace, remove, service and improve in, on, over, under, across, through and upon the Easement Area a sanitary sewer line (hereinafter referred to as "Improvement"). On or before the Expiration Date (as defined below) or earlier if this Agreement is terminated pursuant to the provisions hereof, Grantee shall remove, or cause the removal of, all component parts of the Improvement and restore the ground to its original condition at its own cost and expense, unless the parties agree otherwise in writing.

II. TERM.

The term of this Agreement shall be for Fifteen (15) years, commencing on February 1, 2026 (hereinafter referred to as "Commencement Date"), and expiring on January 31, 2041 (hereinafter referred to as "Expiration Date"), unless earlier terminated pursuant to a subsequent agreement between the parties or in accordance with the provisions of Paragraph X hereof.

III. CONSIDERATION.

Grantee shall pay to Agency the total sum of One and 00/100 Dollar ($1.00) in consideration of State's granting an easement. Grantee shall tender such payment payable to the "Treasurer, State of Ohio" to Agency upon delivery to Grantee of a fully executed counterpart of this Agreement.

IV. CONSTRUCTION/MAINTENANCE.

(A) Grantee agrees that the Improvement shall be installed, constructed, reconstructed, used, operated, maintained, repaired, replaced, removed, serviced and improved at all times in accordance with all local, state or federal laws, rules and regulations and applicable industry guidelines, including compliance with all applicable Equal Employment Opportunity laws. If no such laws, rules, regulations or industry guidelines are applicable to the Improvement, then responsible engineering practices shall be the control.

(B) If the surface of the ground in the Easement Area is disturbed at any time, Grantee shall provide necessary fill, re-sod or re-seed any grassed areas, and make such repairs and replacements for a period of not less than one (1) year after the date of such disturbance as may be needed to restore the ground to its former condition or pay State for all damages caused thereto.

(C) Grantee shall notify State immediately when any installation belonging to a party other than Grantee, or any unusual condition, is encountered in the Easement Area.

(D) Grantee shall prior to the commencement of any work permitted hereunder obtain and thereafter maintain, at its sole cost and expense, all licenses, permits, etc. required by law with respect to said work or the Improvement.

(E) State or Agency may locate, relocate, install, construct, reconstruct, maintain, operate, repair, remove, use and place property improvements in, on, over, under, across, through and upon the Easement Area, so long as State's or Agency's improvements do not unreasonably impair the strength of or unreasonably interfere with Grantee's ability to use the Easement Area and maintain its Improvement.

(F) Grantee shall comply with the provisions of Chapter 4115 of the Ohio Revised Code, Prevailing Wage Requirements, as applicable.

(G) Grantee shall maintain and repair its Improvement at its own cost and expense on a continuous and ongoing basis for the term of this Agreement. Any maintenance and repairs shall be performed in a good and workmanlike manner.

V. LIABILITY.

Each party agrees, provided that it is not otherwise immune from liability, that it will accept responsibility for any personal injury or property damage liability to a third party resulting from its own negligent acts or omissions as determined by a court of competent jurisdiction or as the parties may otherwise mutually agree. Each party also agrees to be responsible for civil damages or fines

resulting from its own acts or omissions. Each party understands that it has no right to seek indemnification from the other.

The provisions of this Paragraph V shall survive the expiration or termination of the term of this Agreement.

VI. INSURANCE.

At all times during the term of this Agreement, Grantee shall maintain adequate reserves and funding to compensate for bodily injury, personal injury, wrongful death and property damage or other claims including defense costs and other loss adjustment expenses arising out of or related to the Easement Area. At State's request, Grantee shall provide written proof to assure that the appropriate levels of financial responsibility are being retained. Failure to comply with this clause shall constitute a default of this Agreement.

VII. MECHANIC'S LIENS.

(A) Nothing contained in this Agreement shall be construed as constituting State's consent, express or implied, to or for the performance of any labor or services or furnishing of any materials for the installation, construction, reconstruction, usage, operation, maintenance, repair, replacement or improvement of the Easement Area or any portion thereof or the Improvement or any portion thereof.

(B) Grantee shall not allow any liens or encumbrances to be filed against the Easement Area, or any portion thereof, other than (i) liens created by or resulting from any act or status of State or failure by State to perform any obligation not required to be performed by Grantee hereunder, or (ii) liens created by or resulting from any act or status or failure to act by Grantee to which State shall have expressly consented in writing. If such a lien or encumbrance is placed of record against the Easement Area, or any portion thereof, Grantee shall, within thirty (30) days after receiving notice thereof, remove or discharge same or bond off such lien or encumbrance.

VIII. TAXES/ASSESSMENTS.

If as a result of this Agreement any taxes and/or assessments, whether general or special, ordinary or extraordinary, unforeseen or foreseen, of any kind or nature whatsoever, shall be assessed, levied, confirmed, imposed upon, or grow or become due and payable out of or in respect of, or become a lien on the Easement Area and/or the Improvement, Grantee shall be fully responsible for and shall pay same before any fine, penalty, interest or costs may be added thereto, or become due or be imposed by operation of law for the nonpayment thereof.

IX. ASSIGNMENT.

Grantee may not assign or transfer this Agreement, in whole or in part, without the prior written consent of the State, whose consent may be withheld for any reason. Should consent to any such assignment be approved, Grantee shall notify the Agency. Any approved assignment or transfer shall not relieve Grantee of its obligations and duties under the terms, covenants and conditions of this Agreement. Grantee shall cause any assignee or transferee to expressly assume, and by reason

of such assignment or transfer shall be deemed as having assumed, all of the obligations and duties of Grantee hereunder.

X. TERMINATION.

This Agreement may be terminated by State upon ninety (90) days' notice given to Grantee if the Easement Area, or any portion thereof, is needed by State for any public or quasi-public use or purpose. On or before the date stated in such notice of termination, Grantee shall remove, or cause the removal of all component parts of the Improvement and restore the Easement Area to its original condition, at its own cost and expense, if State so requests. Grantee shall have no claim against State for the value of any unexpired portion of the original term of this Agreement or for the Improvement. Upon termination of this Agreement, State shall have the immediate right to re-enter and repossess all or any portion of the Easement Area.

This Agreement may be terminated at any time by Grantee by delivering written notice to State and Agency setting forth the date Grantee intends to terminate. Upon either the voluntary termination of this Agreement, or the end of the term hereof, Grantee shall remove all of the Improvement prior to termination, at its own cost and expense, if State so requests, and shall restore the Easement Area to its original condition, unless otherwise agreed to in writing by State and Agency. Grantee's obligations hereunder shall continue until such time as the Improvement is fully removed and the Easement Area fully restored as required herein, notwithstanding the stated date of termination in the notice provided by Grantee, or in the Agreement. Failure to remove the Improvement shall not be considered an extension of the term of the Agreement. No portion of any consideration paid pursuant to the terms of the Agreement will be refunded to Grantee.

XI. DEFAULT.

(A) State may find Grantee in default of this Agreement when any one or more of the following events shall have occurred and shall not have been remedied as hereinafter provided: (i) Grantee's failure to make any payment required to be paid by Grantee when the same shall become due and payable or (ii) Grantee's failure to perform or observe any other covenant, term, or condition herein contained on Grantee's part to be performed or observed.

(B) If the State finds Grantee to be in default under Paragraph XI(A), Grantee must cure such default within fifteen (15) days after the giving of notice to Grantee by State of such failure. If Grantee proceeds to promptly and continuously cure the same default with due diligence, then upon receipt by State of notice from Grantee stating the reason that such default cannot be cured within fifteen (15) days and stating that Grantee is proceeding with due diligence to cure such default, the State may extend such time within which such default may be cured for such period as may be necessary to complete the curing of same with due diligence.

(C) If Grantee fails to cure such default, then State may give to Grantee, at State's option, a notice of election to terminate this Agreement upon the date specified in such notice, which date shall not be less than ten (10) days after the date of such notice, and upon the date specified in such notice the term of this Agreement shall expire and terminate as fully and completely and with the same effect as if such date were the Expiration Date, and all rights of Grantee shall thereupon expire and terminate, and Grantee shall remove or cause the

removal of the Improvements and restore the Easement Area to its original condition at its own cost and expense, if State so requests.

(D) Upon termination of this Agreement, State shall have the immediate right to re-enter and repossess all or any portion of the Easement Area.

(E) Upon the termination of this Agreement by reason of the happening of any event of default specified in this Paragraph XI, or in any other manner or circumstances whatsoever pursuant to legal process, by reason of or based upon or arising out of the occurrence of any such event of default under this Agreement, Grantee shall pay to Agency all sums required to be paid by Grantee up to the time of such termination.

XII. RECORDATION.

At its expense and within thirty (30) days of its receipt, Grantee shall present for recording a fully executed Agreement in accordance with Chapter 5301 of the Ohio Revised Code in the office of the County where the Easement Area is located. Grantee shall do likewise with respect to any addendum to this Agreement which may be entered into hereafter by the parties. As proof of recording, Grantee shall promptly return a copy of the recorded Agreement to the State.

XIII. RIGHTS CUMULATIVE.

All rights and remedies of State enumerated in this Agreement shall be cumulative and, except as specifically contemplated otherwise by this Agreement, none shall exclude any other right or remedy allowed at law or in equity, and said rights or remedies may be exercised or enforced concurrently and all obligations, rights or remedies shall survive formal termination of this Agreement.

XIV. WAIVER.

The waiver by State of, or the failure of State to take action with respect to, any breach of any term, covenant or condition herein contained shall not be deemed to be a waiver of such term, covenant or condition, or subsequent breach of the same, or any other term, covenant or condition herein contained. The subsequent acceptance of any payment hereunder by State shall not be deemed to be a waiver of any preceding breach by Grantee of any term, covenant or condition of this Agreement.

XV. NOTICES, DEMANDS OR INSTRUMENTS.

All notices, demands, requests, consents, approvals and other instruments required or permitted to be given pursuant to the terms of this Agreement shall be in writing and shall be deemed to have been properly given when hand-delivered or sent by U.S. certified mail, return receipt requested, postage prepaid,

(a) with respect to State, addressed to:
Ohio Department of Administrative Services
General Services Division
Office of Real Estate and Planning

4200 Surface Road
Columbus, Ohio 43228-1395
Attention: Administrator

(b) with respect to Agency, addressed to:
Department of Agriculture
8995 East Main Street
Reynoldsburg, Ohio 43068
Attention: Director

and,

(c) with respect to Grantee, addressed to:
City of Reynoldsburg
7232 East Main Street
Reynoldsburg, Ohio 43068
Attention: Mayor

Each party shall have the right from time-to-time to specify as its address for purposes of this Agreement any other address in the United States of America upon giving not less than fifteen (15) days' notice thereof, similarly given, as provided for in this paragraph.

XVI. MODIFICATIONS.

This Agreement may not be changed, modified or discharged except by a writing signed by duly authorized representatives of both State and Grantee.

XVII. GOVERNING LAW.

This Agreement shall be governed by and interpreted under the laws of the State of Ohio. Any action or proceeding arising out of the terms of this Agreement shall be brought only in a court of competent jurisdiction located in Franklin County, Ohio.

XVIII. HEADINGS.

The headings to the various paragraphs and exhibits to this Agreement have been inserted for reference only and shall not to any extent have the effect of modifying, amending or changing the express terms and provisions of this Agreement.

XIX. CAMPAIGN CONTRIBUTIONS & ETHICS COMPLIANCE.

Grantee hereby certifies that neither Grantee nor any of Grantee's partners, officers, directors, shareholders, nor the spouse of any such person have made contributions in excess of the limitations specified in Section 3517.13 of the Ohio Revised Code.

Grantee, by signature on this document, certifies that it has reviewed and understands the Ohio ethics and conflict of interest laws, is currently in compliance and will continue to adhere to the requirements of such laws and will take no action inconsistent with those laws.

XX. INDEPENDENT CONTRACTOR STATUS.

It is fully understood and agreed that Grantee is an independent contractor and neither Grantee nor its personnel shall at any time, or for any purpose, be considered agents, servants, or employees of the Agency, or the State of Ohio, or public employees for the purpose of Ohio Public Employees Retirement Systems benefits.

Intentionally Left Blank

DRAFT

The terms of the within State of Ohio Easement are accepted and agreed to by the Department of Agriculture.

By: _____ Date: _____
Brian Baldridge, Director

IN WITNESS WHEREOF, the parties, by their duly authorized representatives, have executed and delivered this Agreement as of the date first set forth above.

GRANTOR
The STATE OF OHIO

By: _____
Director of Administrative Services or
Signatory Designee
Statutory Agent, RC 123.01(A)(5)

ACKNOWLEDGMENT

State of Ohio, Franklin County, ss:

On this _____ day of _____, 2026, before me personally appeared _____ who acknowledged that the foregoing document is being executed for and on behalf of the Department of Administrative Services, acting on behalf of the State of Ohio, that the same is his/her own and the Department of Administrative Services' free and voluntary act and deed and that he/she is duly authorized to enter into said document for and on behalf of the Department of Administrative Services.

_____
Notary Public, State of Ohio
My Commission Expires:_____

DRAFT

GRANTEE
City of Reynoldsburg

By: _____
Joe Begeny

Title: Mayor

APPROVED AS TO FORM
City of Reynoldsburg, Ohio

By: _____
Chris Shook, City Attorney

ACKNOWLEDGMENT

State of Ohio, Licking County, ss:

On this _____ day of _____, 2026, before me personally appeared Joe Begeny, Mayor of Reynoldsburg, an Ohio municipal corporation, who acknowledged that he executed the foregoing State of Ohio Easement for and on behalf of the City of Reynoldsburg and that the same is his and the Grantee's free and voluntary act and deed, and that he is duly authorized to execute the same on behalf of an Ohio municipal corporation.

_____
Notary Public, State of Ohio
My Commission Expires_____

This State of Ohio Easement prepared by:
Ohio Department of Administrative Services
General Services Division
Office of Real Estate and Planning
4200 Surface Road
Columbus, Ohio 43228-1395
Phone No. (614) 387-6049

DRAFT

Exhibit "A"

LEGAL DESCRIPTION

EASEMENT
0.246 ACRES

Situated in the State of Ohio, County of Licking, City of Reynoldsburg, Southeast Quarter, Section 9, Township 16, Range 20, Refugee Lands, and being a strip of land partly all out of a 48.39 acre tract of land as conveyed to State of Ohio, of record in Official Volume 497, Page 604 and a 50.28 acre tract of land as conveyed to State of Ohio, of record in Official Volume 497, Page 601, all deed references refer to the Records of the Recorder's Office, Licking County, Ohio, and described as follows:

Beginning in the southerly right of way line of U.S. Route 40 at the Northeastern corner of said 50.28 acre tract and the Northwestern corner of said 48.39 acre tract;

Thence, North 88°05'34" East with said southerly right of way line and the northerly line of said 48.39 acre tract a distance of 258.90 feet to a point;

Thence, through said 48.39 acre tract and said 50.28 acre tract the following courses:

South 36°20'27" West, through said 48.39 acre tract, a distance of 50.81 feet to a point;

South 87°20'47" West, through said 48.39 acre tract, a distance of 237.72 feet to a point;

North 4°31'47" East, through said 50.28 acre tract, a distance of 43.99 feet to a point;


Thence, South 89°16'09" East, with said southerly right of way line a distance of 13.24 feet to the **Point of Beginning** and containing **0.246** acres of land more or less.

Subject to all covenants, restrictions, reservations and easements contained in any instrument of record pertaining to the above described tract of land.

The basis of bearings for this description are based on a bearing of North 6°49'51" East for the centerline of Hamilton Road, based on Ohio State Plane Coordinate System, Ohio South Zone, NAD83 (2011) as determined by a series of GPS observations using ODOT VRS network.

Exhibit "B"

SURVEY



Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Make Final Appropriations for Expenses and Other Expenditures for the City of Reynoldsburg, State of Ohio, During the Fiscal Year Ending December 31, 2026, and Declaring an Emergency

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

three-read emergency

REASON FOR EMERGENCY:

That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City and further to have the budget in place on January 1, 2026.

STAFF REPORT:

AN ORDINANCE TO MAKE FINAL APPROPRIATIONS FOR EXPENSES AND OTHER EXPENDITURES OF THE CITY OF REYNOLDSBURG, STATE OF OHIO, DURING THE FISCAL YEAR ENDING DECEMBER 31, 2026, AND DECLARING AN EMERGENCY

WHEREAS, pursuant to the provisions of Section 5.03 (4) of the Charter of the City of Reynoldsburg, Ohio, the City Council is authorized to adopt the municipal budget for the fiscal year beginning January 1, 2026 and appropriations are required effective January 1, 2026 and ending December 31, 2026.

WHEREAS, the Mayor has submitted a proposed budget with estimates and explanatory data.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO, a majority of the members elected thereto herein concurring that, to provide for the current expenses and other expenditures of said City of Reynoldsburg during the fiscal year ending December 31, 2026, the following sums be and are hereby set aside and appropriated as follows:

SECTION 1. That the proposed appropriations for the General Fund (110) are shown on the attached Exhibit A.

SECTION 2. That the proposed revenues for the City are shown on the attached Exhibit B.

SECTION 3. That the income tax revenues shall be appropriated and disbursed pursuant to Section 190.01 of the Codified Ordinances of the City of Reynoldsburg.

SECTION 4. That the unencumbered balances as of December 31, 2025 shall be and are hereby appropriated in the Fiduciary Funds, the Capital Improvement Project Funds, and revenues credited to the Fiduciary Funds shall be appropriated upon receipt to the proper associated accounts. That the 2025 capital project encumbrances funded by OPWC are hereby reappropriated. The ending balance in the Water and Wastewater CIP revenue accounts for the prior year shall be appropriated in the general project account for the specific funds to be used later for approved projects.

SECTION 5. That the amounts of public contributions and reimbursements to the City shall be appropriated upon receipt to the proper associated accounts.

SECTION 6. That the amount of $1,000,000 shall be and is hereby appropriated in the Taylor Square School TIEF Fund (970) to comply with the TIF agreement.

SECTION 7. That the amount of $200,000 shall be and is hereby appropriated in the Brice-Main TIF Fund (971) to comply with the TIF agreement.

SECTION 8. That the City Auditor is hereby authorized to draw warrants on the appropriate funds, for payments from any of the foregoing appropriations, upon receiving proper certificates and vouchers; therefore, approved by the officers authorized by law to approve same, or an ordinance of Council to make the expenditures; provided that no warrants shall be drawn or paid for salaries or wages except to persons employed by authority of and in accordance with law or ordinance.

SECTION 9. That the effective date of the appropriations in this Ordinance shall be January 1, 2026.

SECTION 10. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City and further to have the budget in place on January 1, 2026; wherefore, upon adoption by Council this Ordinance shall be in effect immediately upon signature by the Mayor.

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
Fund: 110 - General Fund			
REVENUES			
Department: 000 - General			
411 - Property Taxes			
4110	Real Estate/Pub Util Tax	458,822.99	0.00
4114	Trailer Tax	252.23	0.00
	Account Classification Total: 411 - Property Taxes	$459,075.22	$0.00
412 - Municipal Tax			
4100	Income Tax Proceeds	13,898,163.77	0.00
	Account Classification Total: 412 - Municipal Tax	$13,898,163.77	$0.00
413 - Other Local Taxes			
4131	Hotel Motel Tax	445,945.09	0.00
4133	Cable TV Franchise Tax	194,654.29	0.00
	Account Classification Total: 413 - Other Local Taxes	$640,599.38	$0.00
414-415 - State Levied Shared Taxes			
4141	Real Property Tax-Rollback and Homestead	42,139.78	0.00
4143	Local Govt-County	567,411.75	0.00
4145	Local Govt-State	205,102.86	0.00
4147	Cigarette Tax	713.74	0.00
4148	Liquor and Beer Permits	60,384.45	0.00
	Account Classification Total: 414-415 - State Levied Shared Taxes	$875,752.58	$0.00
421 - Licenses			
4211	Building Trade License	43,650.00	0.00
4212	Dance Hall License	45.00	0.00
4214	Electronic Coin Device License	2,700.00	0.00
4215	Rental Registration License	1,925.00	0.00
	Account Classification Total: 421 - Licenses	$48,320.00	$0.00
422-423 - Permits			
4221	Building Permits	324,185.13	0.00
4222	Plumbing Permits	161,970.10	0.00
4223	Heating Permits	143,296.50	0.00
4225	Electrical Permits	80,236.40	0.00
4226	Zoning Permits	84,950.00	0.00
4227	Burglar Alarm Permits	700.00	0.00
4228	Sign Permits	1,909.60	0.00
4229	Miscellaneous Permits	570.00	0.00
	Account Classification Total: 422-423 - Permits	$797,817.73	$0.00
424 - Fees			
4249	Miscellaneous Fees	45.00	0.00
4250	Plan Administration Fees	28,315.00	0.00
	Account Classification Total: 424 - Fees	$28,360.00	$0.00
433 - Intergovernmental-State			
4335	Grants/Aid	78,000.00	0.00
	Account Classification Total: 433 - Intergovernmental-State	$78,000.00	$0.00
441-442 - Miscellaneous Charges for Services			
4410	Xeroxing	94.90	0.00
4417	Weed Cutting	38,716.15	0.00
4419	Miscellaneous Charges for Service	857.25	0.00
	Account Classification Total: 441-442 - Miscellaneous Charges for Services	$39,668.30	$0.00
445 - Recreational Charges			
4448	Dedication/Legacy Fees	4,855.00	0.00
4449	Recreation Nature Programs	60.00	0.00
4450	Recreational Rental Fees	38,242.00	0.00
4451	Baseball Fees	10,737.00	0.00
4452	Basketball Fees	300.00	0.00
4453	Tennis Fees	1,382.00	0.00
4454	Soccer Fees	42,606.00	0.00
4455	Softball Fees	84.00	0.00
4456	Adult Sports Fees	4,171.00	0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
4457	Arts & Craft Programs	6,265.00	0.00
4458	Volleyball Fees	4,101.00	0.00
4459	Miscellaneous Recreational Fees	63,805.98	0.00
	Account Classification Total: 445 - Recreational Charges	$176,608.98	$0.00
451-452 - Fines and Forfeitures			
4510	Mayors Court Costs	161,427.00	0.00
4512	Mayors Court-Fines and Forfeitures	129,454.00	0.00
4520	Municipal Court-Fines	4,621.50	0.00
	Account Classification Total: 451-452 - Fines and Forfeitures	$295,502.50	$0.00
460 - Investment Earnings			
4601	Interest Earnings	1,349,156.58	0.00
	Account Classification Total: 460 - Investment Earnings	$1,349,156.58	$0.00
461-462 - Other Revenues			
4611	School Resource Officer	108,672.77	0.00
4612	Rentals	293,421.24	0.00
4613	Witness Fees/Jury Duty	180.00	0.00
4629	Miscellaneous Revenue	415,653.03	0.00
4648	Community Events Revenue	233,331.12	0.00
	Account Classification Total: 461-462 - Other Revenues	$1,051,258.16	$0.00
464 - Donations			
4649	Contributions	2,205.53	0.00
	Account Classification Total: 464 - Donations	$2,205.53	$0.00
492-493 - Reimbursements			
4920	Reimburse Prior Year Expense	45,573.22	0.00
4922	Property Damage Reimbursements	3,400.00	0.00
	Account Classification Total: 492-493 - Reimbursements	$48,973.22	$0.00
494 - Sale of Assets			
4941	Sale of Assets	4,143.00	0.00
	Account Classification Total: 494 - Sale of Assets	$4,143.00	$0.00
499 - Transfers/Advances			
4990	Operating Transfers	1,124,312.50	0.00
	Account Classification Total: 499 - Transfers/Advances	$1,124,312.50	$0.00
	Department Total: 000 - General	$20,917,917.45	$0.00
	REVENUES Total	$20,917,917.45	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5501	Transfers	6,345,328.65	0.00
	Account Classification Total: 5500 - Transfers/Other	$6,345,328.65	$0.00
	Department Total: 000 - General	$6,345,328.65	$0.00
Department: 111 - Police Division			
5100 - Personal Services			
5102	Wages-Staff	1,219,973.36	1,614,260.00
5104	Wages-Part time	143,696.26	174,289.00
5105	Overtime	239,249.76	345,000.00
5106	Longevity	46,586.00	67,200.00
5109	HSA Employer Funding	349,928.64	380,496.00
5111	Wages Chief	149,652.41	179,733.00
5113	Wages Enforcement	7,010,492.91	8,514,144.00
5151	PERS Contribution	153,064.09	253,099.00
5152	PFDPF Contribution	1,294,573.92	1,494,003.00
5155	PERS Pickup	46,141.74	72,880.00
5161	Group Insurance	1,089,081.15	2,031,920.00
5166	Medicare	126,607.39	158,184.00
	Account Classification Total: 5100 - Personal Services	$11,869,047.63	$15,285,208.00
5200 - Supplies			
5201	Office Supplies	9,429.17	13,000.00
5202	Photo Copy Supplies	849.80	5,500.00
5203	Computer Supplies	12,272.63	23,000.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5205	Small Tools/Minor Equipment	11,227.58	14,000.00
5206	Evidence	4,000.00	5,000.00
5207	Law Enforcement Supplies	86,372.24	167,000.00
5213	Repair and Maintenance Supplies	6,120.21	17,000.00
5241	Uniforms-Purchased	92,046.52	190,000.00
5251	MV Gas and Oil	100,531.71	175,000.00
	Account Classification Total: 5200 - Supplies	$322,849.86	$609,500.00
5300 - Services			
5311	Utilities	118,095.25	180,000.00
5321	Professional Training	104,021.60	200,000.00
5323	Publications	21,735.99	8,200.00
5324	Professional Association Dues	1,143.00	8,000.00
5325	Educational Assistance	7,518.90	15,000.00
5339	Misc Contract Services	79,291.32	155,000.00
5351	Liability Insurance Deductible	45,965.80	50,000.00
5361	Building Repair/Maintenance	355,990.20	130,000.00
5362	Equipment Maintenance	13,132.14	77,000.00
5363	MV Repair/Maintenance-External	24,113.75	49,000.00
5366	Computer Maintenance	0.00	3,000.00
5375	Prisoner Care	70,745.24	100,000.00
5391	Postage	811.03	8,000.00
5392	Fingerprinting Services	134.00	700.00
5393	L.E.A.D.S Terminal	6,600.00	8,000.00
5395	Printing/Advertising	11,449.21	27,000.00
5396	Uniform Cleaning/Repairs	20,565.75	40,000.00
5399	Other Miscellaneous Services	11,962.53	25,000.00
	Account Classification Total: 5300 - Services	$893,275.71	$1,083,900.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	24,125.16	20,000.00
5632	Motor Vehicles	209,296.02	396,000.00
5633	Machinery and Equipment	11,764.58	50,000.00
5634	Unmarked Vehicles	51,858.00	59,000.00
5639	Other Equipment	90,072.32	193,500.00
	Account Classification Total: 5600 - Capital Purchases	$387,116.08	$718,500.00
	Department Total: 111 - Police Division	$13,472,289.28	$17,697,108.00
Department: 290 - Mechanic			
5100 - Personal Services			
5102	Wages-Staff	108,784.93	143,857.00
5105	Overtime	559.35	0.00
5106	Longevity	650.00	850.00
5109	HSA Employer Funding	6,000.00	2,100.00
5151	PERS Contribution	12,232.67	19,909.00
5161	Group Insurance	18,864.85	25,820.00
5166	Medicare	1,553.46	2,062.00
	Account Classification Total: 5100 - Personal Services	$148,645.26	$194,598.00
5200 - Supplies			
5201	Office Supplies	0.00	200.00
5203	Computer Supplies	441.68	500.00
5205	Small Tools/Minor Equipment	0.00	3,000.00
5213	Repair and Maintenance Supplies	50,548.65	120,000.00
5259	Operating Materials and Supplies	3,102.06	9,500.00
	Account Classification Total: 5200 - Supplies	$54,092.39	$133,200.00
5300 - Services			
5321	Professional Training	0.00	2,000.00
5324	Professional Association Dues	0.00	3,000.00
5363	MV Repair/Maintenance-External	14,689.57	74,000.00
5397	Uniform Rental	1,128.62	2,000.00
5399	Other Miscellaneous Services	776.35	2,500.00
	Account Classification Total: 5300 - Services	$16,594.54	$83,500.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5600 - Capital Purchases			
5633	Machinery and Equipment	0.00	50,000.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$50,000.00
	Department Total: 290 - Mechanic	$219,332.19	$461,298.00
Department:	**340 - Parks and Recreation**		
5100 - Personal Services			
5101	Salary-Elected Officials/Director	111,327.12	129,668.00
5102	Wages-Staff	834,014.98	1,585,090.00
5105	Overtime	11,279.89	40,000.00
5106	Longevity	5,450.00	8,200.00
5109	HSA Employer Funding	50,000.01	79,600.00
5141	Wages-Seasonal Labor	122,151.49	170,000.00
5151	PERS Contribution	118,483.12	246,464.00
5161	Group Insurance	185,651.03	462,356.00
5166	Medicare	15,238.47	25,563.00
	Account Classification Total: 5100 - Personal Services	$1,453,596.11	$2,746,941.00
5200 - Supplies			
5201	Office Supplies	675.54	1,265.00
5203	Computer Supplies	258.80	500.00
5205	Small Tools/Minor Equipment	7,773.99	31,415.00
5209	Chemicals	59,744.55	70,000.00
5213	Repair and Maintenance Supplies	70,750.09	79,300.00
5215	Recreational Supplies	92,264.80	165,000.00
5241	Uniforms-Purchased	8,388.02	30,800.00
5251	MV Gas and Oil	20,088.02	39,900.00
5252	Aggregates	8,063.00	47,300.00
5259	Operating Materials and Supplies	25,731.68	41,650.00
	Account Classification Total: 5200 - Supplies	$293,738.49	$507,130.00
5300 - Services			
5303	Community Events	4,559.47	7,000.00
5304	Recreation Scholarship	0.00	13,500.00
5311	Utilities	39,972.53	55,000.00
5321	Professional Training	1,892.79	8,000.00
5322	Conference/Reimb	11,451.17	21,850.00
5323	Publications	105.67	250.00
5324	Professional Association Dues	3,050.00	3,875.00
5325	Educational Assistance	3,500.00	0.00
5331	Engineering/Architecture	0.00	20,000.00
5338	Personal Service Contracts	60,690.15	110,180.00
5339	Misc Contract Services	86,824.69	190,000.00
5361	Building Repair/Maintenance	9,655.00	47,000.00
5362	Equipment Maintenance	6,162.42	5,000.00
5391	Postage	11,042.57	23,450.00
5395	Printing/Advertising	47,489.12	52,190.00
5399	Other Miscellaneous Services	40,075.88	15,500.00
	Account Classification Total: 5300 - Services	$326,471.46	$572,795.00
5600 - Capital Purchases			
5632	Motor Vehicles	70,241.70	186,400.00
5633	Machinery and Equipment	48,256.01	265,950.00
5639	Other Equipment	10,717.10	20,400.00
	Account Classification Total: 5600 - Capital Purchases	$129,214.81	$472,750.00
	Department Total: 340 - Parks and Recreation	$2,203,020.87	$4,299,616.00
Department:	**343 - Senior Center**		
5100 - Personal Services			
5102	Wages-Staff	125,756.49	148,387.00
5105	Overtime	4,402.57	6,000.00
5106	Longevity	1,050.00	2,500.00
5109	HSA Employer Funding	6,000.00	6,300.00
5151	PERS Contribution	14,301.91	21,964.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5161	Group Insurance	22,068.61	36,087.00
5166	Medicare	1,791.79	2,166.00
	Account Classification Total: 5100 - Personal Services	$175,371.37	$223,404.00
5200 - Supplies			
5201	Office Supplies	1,169.10	2,150.00
5203	Computer Supplies	1,048.84	1,300.00
5213	Repair and Maintenance Supplies	3,060.83	5,000.00
5215	Recreational Supplies	930.69	6,200.00
5216	Contributed Supplies Purchased	2,058.29	0.00
5251	MV Gas and Oil	1,569.22	4,500.00
	Account Classification Total: 5200 - Supplies	$9,836.97	$19,150.00
5300 - Services			
5311	Utilities	9,654.84	15,000.00
5321	Professional Training	0.00	300.00
5322	Conference/Reimb	458.00	2,000.00
5324	Professional Association Dues	206.00	400.00
5339	Misc Contract Services	66,759.10	152,910.00
5361	Building Repair/Maintenance	1,065.00	83,800.00
5391	Postage	0.00	3,000.00
5395	Printing/Advertising	0.00	200.00
	Account Classification Total: 5300 - Services	$78,142.94	$257,610.00
	Department Total: 343 - Senior Center	$263,351.28	$500,164.00
Department:	**344 - Community Events**		
5100 - Personal Services			
5102	Wages-Staff	167,692.52	210,977.00
5105	Overtime	35,681.54	30,000.00
5106	Longevity	900.00	1,250.00
5109	HSA Employer Funding	6,666.67	6,300.00
5141	Wages-Seasonal Labor	0.00	55,000.00
5151	PERS Contribution	23,081.18	33,002.00
5161	Group Insurance	22,195.51	38,762.00
5166	Medicare	2,882.43	3,440.00
	Account Classification Total: 5100 - Personal Services	$259,099.85	$378,731.00
5200 - Supplies			
5201	Office Supplies	315.00	2,000.00
5203	Computer Supplies	0.00	3,500.00
5215	Recreational Supplies	24,082.20	42,000.00
5241	Uniforms-Purchased	294.00	1,000.00
5251	MV Gas and Oil	2,880.60	6,000.00
	Account Classification Total: 5200 - Supplies	$27,571.80	$54,500.00
5300 - Services			
5311	Utilities	127.00	3,000.00
5321	Professional Training	0.00	3,000.00
5322	Conference/Reimb	67.90	4,000.00
5324	Professional Association Dues	0.00	2,500.00
5339	Misc Contract Services	489,313.77	550,000.00
5364	MV Repair/Maintenance-Internal	0.00	12,000.00
5395	Printing/Advertising	78,959.36	140,000.00
5399	Other Miscellaneous Services	10,729.06	47,000.00
	Account Classification Total: 5300 - Services	$579,197.09	$761,500.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	0.00	30,000.00
5632	Motor Vehicles	0.00	40,000.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$70,000.00
	Department Total: 344 - Community Events	$865,868.74	$1,264,731.00
Department:	**448 - Service Department**		
5100 - Personal Services			
5101	Salary-Elected Officials/Director	113,578.09	129,730.00
5102	Wages-Staff	565,285.70	785,594.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5105	Overtime	15,957.29	20,000.00
5106	Longevity	5,000.00	8,450.00
5109	HSA Employer Funding	33,666.66	44,100.00
5151	PERS Contribution	79,107.28	129,958.00
5161	Group Insurance	129,651.09	260,192.00
5166	Medicare	9,798.38	13,460.00
	Account Classification Total: 5100 - Personal Services	$952,044.49	$1,391,484.00
5200 - Supplies			
5201	Office Supplies	1,584.51	2,000.00
5203	Computer Supplies	0.00	3,000.00
5213	Repair and Maintenance Supplies	149.70	30,000.00
5251	MV Gas and Oil	361.13	2,000.00
5259	Operating Materials and Supplies	6,971.25	10,000.00
	Account Classification Total: 5200 - Supplies	$9,066.59	$47,000.00
5300 - Services			
5302	Street Lighting	187,794.29	350,000.00
5303	Community Events	69,980.22	85,000.00
5311	Utilities	81,977.57	15,000.00
5321	Professional Training	332.34	6,000.00
5322	Conference/Reimb	0.00	1,500.00
5323	Publications	0.00	100.00
5324	Professional Association Dues	260.00	1,000.00
5325	Educational Assistance	0.00	500.00
5331	Engineering/Architecture	273,110.51	450,000.00
5339	Misc Contract Services	1,430,440.83	200,000.00
5361	Building Repair/Maintenance	116,377.62	150,000.00
5362	Equipment Maintenance	5,371.98	50,000.00
5366	Computer Maintenance	0.00	1,500.00
5374	Emergency Management Services	0.00	50,000.00
5391	Postage	7,310.67	12,500.00
5395	Printing/Advertising	534.72	1,500.00
5397	Uniform Rental	2,166.26	3,000.00
5398	Tree/Grass Service	45,432.46	52,000.00
5399	Other Miscellaneous Services	0.00	2,000.00
	Account Classification Total: 5300 - Services	$2,221,089.47	$1,431,600.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	0.00	7,500.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$7,500.00
	Department Total: 448 - Service Department	$3,182,200.55	$2,877,584.00
Department:	**479 - Building Department**		
5100 - Personal Services			
5101	Salary-Elected Officials/Director	63,921.90	0.00
5102	Wages-Staff	440,504.60	707,897.00
5105	Overtime	14,558.14	1,500.00
5106	Longevity	3,000.00	3,100.00
5109	HSA Employer Funding	26,000.00	33,600.00
5151	PERS Contribution	56,975.34	99,750.00
5161	Group Insurance	95,185.45	209,594.00
5166	Medicare	7,346.11	10,331.00
	Account Classification Total: 5100 - Personal Services	$707,491.54	$1,065,772.00
5200 - Supplies			
5201	Office Supplies	438.14	3,000.00
5203	Computer Supplies	0.00	3,500.00
5241	Uniforms-Purchased	1,852.51	5,000.00
5251	MV Gas and Oil	3,339.60	7,000.00
	Account Classification Total: 5200 - Supplies	$5,630.25	$18,500.00
5300 - Services			
5311	Utilities	2,681.51	5,000.00
5321	Professional Training	1,853.00	4,000.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5322	Conference/Reimb	0.00	3,000.00
5323	Publications	2,077.99	3,000.00
5324	Professional Association Dues	500.00	2,500.00
5325	Educational Assistance	0.00	1,500.00
5331	Engineering/Architecture	0.00	5,000.00
5339	Misc Contract Services	48,297.50	60,000.00
5362	Equipment Maintenance	4,582.75	7,000.00
5366	Computer Maintenance	0.00	5,000.00
5376	County Health Services	101,010.00	150,000.00
5391	Postage	1,406.80	2,000.00
5395	Printing/Advertising	754.63	2,000.00
5399	Other Miscellaneous Services	4,194.77	5,000.00
	Account Classification Total: 5300 - Services	$167,358.95	$255,000.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	0.00	20,000.00
5632	Motor Vehicles	0.00	60,000.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$80,000.00
	Department Total: 479 - Building Department	$880,480.74	$1,419,272.00
Department: 522 - Mayor			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	111,919.15	129,048.00
5102	Wages-Staff	65,986.28	75,338.00
5104	Wages-Part time	9,120.50	7,000.00
5105	Overtime	569.08	2,500.00
5106	Longevity	650.00	850.00
5109	HSA Employer Funding	6,000.00	6,300.00
5151	PERS Contribution	21,164.57	29,713.00
5161	Group Insurance	21,757.41	35,714.00
5166	Medicare	2,685.83	3,077.00
	Account Classification Total: 5100 - Personal Services	$239,852.82	$289,540.00
5200 - Supplies			
5201	Office Supplies	539.68	1,200.00
5203	Computer Supplies	0.00	500.00
	Account Classification Total: 5200 - Supplies	$539.68	$1,700.00
5300 - Services			
5311	Utilities	450.59	1,200.00
5322	Conference/Reimb	1,050.00	2,500.00
5324	Professional Association Dues	7,230.00	15,000.00
5339	Misc Contract Services	58,418.98	75,000.00
5391	Postage	30.03	500.00
5399	Other Miscellaneous Services	4,549.09	7,000.00
	Account Classification Total: 5300 - Services	$71,728.69	$101,200.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	208.86	2,500.00
	Account Classification Total: 5600 - Capital Purchases	$208.86	$2,500.00
	Department Total: 522 - Mayor	$312,330.05	$394,940.00
Department: 534 - Civil Service Commission			
5100 - Personal Services			
5104	Wages-Part time	60,624.89	76,898.00
5151	PERS Contribution	6,941.18	10,766.00
5166	Medicare	879.06	1,115.00
	Account Classification Total: 5100 - Personal Services	$68,445.13	$88,779.00
5200 - Supplies			
5201	Office Supplies	1,215.58	1,000.00
5203	Computer Supplies	0.00	1,000.00
5259	Operating Materials and Supplies	0.00	1,500.00
	Account Classification Total: 5200 - Supplies	$1,215.58	$3,500.00
5300 - Services			
5321	Professional Training	0.00	600.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5322	Conference/Reimb	0.00	200.00
5332	Legal Services	56.25	7,000.00
5336	Medical Services/Physical Exams	8,775.00	17,000.00
5339	Misc Contract Services	2,551.57	11,000.00
5391	Postage	0.00	200.00
5395	Printing/Advertising	394.32	5,000.00
	Account Classification Total: 5300 - Services	$11,777.14	$41,000.00
5500 - Transfers/Other			
5515	Refunds-Fees	40.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$40.00	$0.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	0.00	4,000.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$4,000.00
	Department Total: 534 - Civil Service Commission	$81,477.85	$137,279.00
Department: 545 - City Auditor			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	79,334.31	95,546.00
5102	Wages-Staff	318,412.36	509,083.00
5104	Wages-Part time	13,190.15	7,000.00
5105	Overtime	513.10	2,000.00
5106	Longevity	1,550.00	850.00
5109	HSA Employer Funding	11,333.33	25,200.00
5151	PERS Contribution	42,598.99	85,537.00
5161	Group Insurance	41,300.89	147,416.00
5166	Medicare	5,836.61	8,859.00
	Account Classification Total: 5100 - Personal Services	$514,069.74	$881,491.00
5200 - Supplies			
5201	Office Supplies	2,763.10	2,800.00
5203	Computer Supplies	0.00	4,000.00
	Account Classification Total: 5200 - Supplies	$2,763.10	$6,800.00
5300 - Services			
5321	Professional Training	250.00	7,600.00
5322	Conference/Reimb	0.00	10,000.00
5324	Professional Association Dues	535.00	2,000.00
5325	Educational Assistance	0.00	1,000.00
5333	Outside Professional Services	20,235.00	100,000.00
5339	Misc Contract Services	25,010.40	65,000.00
5362	Equipment Maintenance	921.61	3,800.00
5366	Computer Maintenance	2,087.00	3,400.00
5391	Postage	2,146.39	2,500.00
5395	Printing/Advertising	0.00	2,100.00
5399	Other Miscellaneous Services	1,986.50	12,000.00
	Account Classification Total: 5300 - Services	$53,171.90	$209,400.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	1,190.00	4,000.00
	Account Classification Total: 5600 - Capital Purchases	$1,190.00	$4,000.00
	Department Total: 545 - City Auditor	$571,194.74	$1,101,691.00
Department: 554 - City Attorney			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	113,169.15	131,547.00
5102	Wages-Staff	270,174.09	532,788.00
5104	Wages-Part time	73,897.58	15,600.00
5106	Longevity	3,350.00	4,150.00
5109	HSA Employer Funding	15,833.33	21,000.00
5151	PERS Contribution	50,750.57	93,238.00
5161	Group Insurance	58,916.09	124,878.00
5166	Medicare	6,503.88	9,693.00
	Account Classification Total: 5100 - Personal Services	$592,594.69	$932,894.00
5200 - Supplies			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5201	Office Supplies	2,851.75	6,500.00
5203	Computer Supplies	0.00	400.00
5205	Small Tools/Minor Equipment	0.00	500.00
	Account Classification Total: 5200 - Supplies	$2,851.75	$7,400.00
5300 - Services			
5311	Utilities	450.59	500.00
5321	Professional Training	1,850.00	2,500.00
5322	Conference/Reimb	51.00	2,500.00
5323	Publications	5,955.00	6,000.00
5324	Professional Association Dues	1,430.00	1,700.00
5332	Legal Services	13,496.10	60,000.00
5333	Outside Professional Services	36,250.10	20,000.00
5337	Public Defender	1,995.00	5,000.00
5339	Misc Contract Services	18,824.93	17,000.00
5341	Court Costs and Fees	1,239.76	3,500.00
5362	Equipment Maintenance	2,554.20	2,900.00
5366	Computer Maintenance	0.00	250.00
5391	Postage	1,399.50	2,000.00
5399	Other Miscellaneous Services	156.00	3,000.00
	Account Classification Total: 5300 - Services	$85,652.18	$126,850.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	21.00	6,000.00
5639	Other Equipment	241.56	3,000.00
	Account Classification Total: 5600 - Capital Purchases	$262.56	$9,000.00
	Department Total: 554 - City Attorney	$681,361.18	$1,076,144.00
Department: 571 - City Council			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	63,864.09	0.00
5102	Wages-Staff	84,559.44	192,980.00
5104	Wages-Part time	23,080.73	0.00
5106	Longevity	650.00	850.00
5109	HSA Employer Funding	2,000.00	2,100.00
5151	PERS Contribution	19,530.58	27,130.00
5161	Group Insurance	6,875.88	10,806.00
5166	Medicare	2,434.12	2,811.00
	Account Classification Total: 5100 - Personal Services	$202,994.84	$236,677.00
5200 - Supplies			
5201	Office Supplies	838.56	1,500.00
5203	Computer Supplies	0.00	500.00
	Account Classification Total: 5200 - Supplies	$838.56	$2,000.00
5300 - Services			
5321	Professional Training	2,000.00	1,000.00
5322	Conference/Reimb	4,760.17	6,000.00
5324	Professional Association Dues	345.00	750.00
5339	Misc Contract Services	30,694.82	175,000.00
5391	Postage	12.57	250.00
5395	Printing/Advertising	0.00	1,000.00
5399	Other Miscellaneous Services	31.95	5,000.00
	Account Classification Total: 5300 - Services	$37,844.51	$189,000.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	0.00	5,000.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$5,000.00
	Department Total: 571 - City Council	$241,677.91	$432,677.00
Department: 580 - Development Department			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	107,998.24	129,568.00
5102	Wages-Staff	212,587.47	296,733.00
5105	Overtime	229.77	10,000.00
5106	Longevity	650.00	850.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5109	HSA Employer Funding	12,833.32	14,700.00
5151	PERS Contribution	34,750.65	59,451.00
5161	Group Insurance	42,081.87	103,168.00
5166	Medicare	4,487.35	6,194.00
	Account Classification Total: 5100 - Personal Services	$415,618.67	$620,664.00
5200 - Supplies			
5201	Office Supplies	416.10	3,000.00
5203	Computer Supplies	0.00	250.00
5241	Uniforms-Purchased	76.00	500.00
5251	MV Gas and Oil	0.00	5,000.00
	Account Classification Total: 5200 - Supplies	$492.10	$8,750.00
5300 - Services			
5301	Boards/Commissions	373.56	3,500.00
5311	Utilities	696.23	2,200.00
5321	Professional Training	320.00	5,000.00
5322	Conference/Reimb	3,949.24	10,600.00
5323	Publications	1,208.38	4,000.00
5324	Professional Association Dues	17,076.84	25,000.00
5325	Educational Assistance	0.00	3,500.00
5331	Engineering/Architecture	82,664.43	210,000.00
5339	Misc Contract Services	75,597.43	173,200.00
5391	Postage	37.91	500.00
5395	Printing/Advertising	654.06	2,000.00
5399	Other Miscellaneous Services	52,740.30	31,000.00
	Account Classification Total: 5300 - Services	$235,318.38	$470,500.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	913.00	4,000.00
	Account Classification Total: 5600 - Capital Purchases	$913.00	$4,000.00
	Department Total: 580 - Development Department	$652,342.15	$1,103,914.00
Department: 582 - Human Resources Department			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	128,073.50	116,626.00
5102	Wages-Staff	65,161.83	72,301.00
5105	Overtime	399.38	5,000.00
5106	Longevity	650.00	850.00
5109	HSA Employer Funding	3,333.33	8,400.00
5151	PERS Contribution	18,819.36	27,269.00
5161	Group Insurance	7,848.69	51,076.00
5166	Medicare	2,797.64	2,824.00
	Account Classification Total: 5100 - Personal Services	$227,083.73	$284,346.00
5200 - Supplies			
5201	Office Supplies	1,529.28	2,500.00
5203	Computer Supplies	456.16	1,000.00
5208	OSHA Supplies	22,045.54	35,000.00
	Account Classification Total: 5200 - Supplies	$24,030.98	$38,500.00
5300 - Services			
5321	Professional Training	2,232.00	5,000.00
5322	Conference/Reimb	250.52	2,000.00
5323	Publications	942.86	1,400.00
5324	Professional Association Dues	514.00	1,800.00
5336	Medical Services/Physical Exams	1,903.00	12,000.00
5339	Misc Contract Services	49,980.93	45,000.00
5391	Postage	64.59	200.00
5395	Printing/Advertising	0.00	2,000.00
5399	Other Miscellaneous Services	14,809.21	30,000.00
	Account Classification Total: 5300 - Services	$70,697.11	$99,400.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	1,944.20	1,250.00
	Account Classification Total: 5600 - Capital Purchases	$1,944.20	$1,250.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Department Total: 582 - Human Resources Department	$323,756.02	$423,496.00
Department:	**584 - Computer Department**		
5200 - Supplies			
5201	Office Supplies	0.00	500.00
5203	Computer Supplies	18,356.02	12,750.00
	Account Classification Total: 5200 - Supplies	$18,356.02	$13,250.00
5300 - Services			
5339	Misc Contract Services	204,731.50	219,696.00
5366	Computer Maintenance	812,503.32	1,908,000.00
	Account Classification Total: 5300 - Services	$1,017,234.82	$2,127,696.00
5600 - Capital Purchases			
5639	Other Equipment	228,715.11	379,350.00
	Account Classification Total: 5600 - Capital Purchases	$228,715.11	$379,350.00
	Department Total: 584 - Computer Department	$1,264,305.95	$2,520,296.00
Department:	**593 - Clerk of Courts**		
5100 - Personal Services			
5101	Salary-Elected Officials/Director	105,640.72	123,556.00
5102	Wages-Staff	115,609.53	190,557.00
5104	Wages-Part time	40,336.40	0.00
5105	Overtime	124.65	0.00
5106	Longevity	3,250.00	4,550.00
5109	HSA Employer Funding	4,000.00	4,200.00
5151	PERS Contribution	29,081.42	43,563.00
5161	Group Insurance	19,233.38	29,720.00
5166	Medicare	3,796.23	4,621.00
	Account Classification Total: 5100 - Personal Services	$321,072.33	$400,767.00
5200 - Supplies			
5201	Office Supplies	2,832.67	2,600.00
5203	Computer Supplies	0.00	1,500.00
	Account Classification Total: 5200 - Supplies	$2,832.67	$4,100.00
5300 - Services			
5321	Professional Training	250.00	1,000.00
5322	Conference/Reimb	0.00	250.00
5324	Professional Association Dues	0.00	600.00
5332	Legal Services	52,000.00	60,000.00
5339	Misc Contract Services	918.87	1,600.00
5344	Witness Fees	0.00	300.00
5362	Equipment Maintenance	0.00	500.00
5377	Municipal Court	7,274.00	12,000.00
5391	Postage	1,143.12	3,000.00
5393	L.E.A.D.S Terminal	600.00	1,200.00
5399	Other Miscellaneous Services	305.00	2,000.00
	Account Classification Total: 5300 - Services	$62,490.99	$82,450.00
5600 - Capital Purchases			
5631	Furniture and Fixtures	0.00	500.00
5639	Other Equipment	0.00	500.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$1,000.00
	Department Total: 593 - Clerk of Courts	$386,395.99	$488,317.00
Department:	**595 - General and Administrative**		
5100 - Personal Services			
5164	Workers Compensation	245,692.04	470,000.00
5165	Unemployment Compensation	4,007.12	25,000.00
	Account Classification Total: 5100 - Personal Services	$249,699.16	$495,000.00
5200 - Supplies			
5202	Photo Copy Supplies	2,324.46	10,000.00
	Account Classification Total: 5200 - Supplies	$2,324.46	$10,000.00
5300 - Services			
5301	Boards/Commissions	4,213.80	50,000.00
5311	Utilities	48,117.87	368,692.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5324	Professional Association Dues	31,155.45	40,250.00
5351	Liability Insurance Deductible	518,932.50	736,000.00
5352	Motor Vehicle Insurance	143,450.50	241,000.00
5361	Building Repair/Maintenance	6,940.25	0.00
5371	Election Expense	723.97	0.00
5372	Delinquent Tax Advertising	951.82	0.00
5373	Auditor/Treasurer Fees	6,118.59	0.00
5391	Postage	(4,757.96)	7,000.00
5394	Taxes/Assessments-City Property	7,407.52	20,000.00
5399	Other Miscellaneous Services	1,053.46	11,500.00
	Account Classification Total: 5300 - Services	$764,307.77	$1,474,442.00
5600 - Capital Purchases			
5639	Other Equipment	0.00	34,500.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$34,500.00
	Department Total: 595 - General and Administrative	$1,016,331.39	$2,013,942.00
Department: 810 - Public Health and Welfare			
5300 - Services			
5376	County Health Services	413,050.31	427,501.00
	Account Classification Total: 5300 - Services	$413,050.31	$427,501.00
	Department Total: 810 - Public Health and Welfare	$413,050.31	$427,501.00
	EXPENSES Total	$33,376,095.84	$38,639,970.00
	Fund REVENUE Total: 110 - General Fund	$20,917,917.45	$0.00
	Fund EXPENSE Total: 110 - General Fund	$33,376,095.84	$38,639,970.00
	Fund Total: 110 - General Fund	($12,458,178.39)	($38,639,970.00)
Fund: 201 - Fema Federal Emergency Mgmt Agen			
REVENUES			
Department: 000 - General			
433 - Intergovernmental-State			
4335	Grants/Aid	177,031.11	0.00
	Account Classification Total: 433 - Intergovernmental-State	$177,031.11	$0.00
	Department Total: 000 - General	$177,031.11	$0.00
	REVENUES Total	$177,031.11	$0.00
	Fund REVENUE Total: 201 - Fema Federal Emergency Mgmt Agen	$177,031.11	$0.00
	Fund EXPENSE Total: 201 - Fema Federal Emergency Mgmt Agen		
	Fund Total: 201 - Fema Federal Emergency Mgmt Agen	$177,031.11	$0.00
Fund: 206 - American Rescue Plan Act			
EXPENSES			
Department: 000 - General			
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	388,633.71	0.00
	Account Classification Total: 5600 - Capital Purchases	$388,633.71	$0.00
	Department Total: 000 - General	$388,633.71	$0.00
	EXPENSES Total	$388,633.71	$0.00
	Fund REVENUE Total: 206 - American Rescue Plan Act		
	Fund EXPENSE Total: 206 - American Rescue Plan Act	$388,633.71	$0.00
	Fund Total: 206 - American Rescue Plan Act	($388,633.71)	$0.00
Fund: 211 - Computerized Needs (courts)			
REVENUES			
Department: 000 - General			
451-452 - Fines and Forfeitures			
4510	Mayors Court Costs	23,709.00	22,000.00
	Account Classification Total: 451-452 - Fines and Forfeitures	$23,709.00	$22,000.00
	Department Total: 000 - General	$23,709.00	$22,000.00
	REVENUES Total	$23,709.00	$22,000.00
EXPENSES			
Department: 000 - General			
5200 - Supplies			
5203	Computer Supplies	1,911.07	15,000.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 5200 - Supplies	$1,911.07	$15,000.00
5300 - Services			
5322	Conference/Reimb	0.00	500.00
5366	Computer Maintenance	24,434.15	37,500.00
5399	Other Miscellaneous Services	2,299.59	15,000.00
	Account Classification Total: 5300 - Services	$26,733.74	$53,000.00
	Department Total: 000 - General	$28,644.81	$68,000.00
	EXPENSES Total	$28,644.81	$68,000.00
	Fund REVENUE Total: 211 - Computerized Needs (courts)	$23,709.00	$22,000.00
	Fund EXPENSE Total: 211 - Computerized Needs (courts)	$28,644.81	$68,000.00
	Fund Total: 211 - Computerized Needs (courts)	($4,935.81)	($46,000.00)
Fund: 220 - Income Tax Fund			
REVENUES			
Department: 000 - General			
412 - Municipal Tax			
4121	Municipal Income Tax	(1,634,583.90)	0.00
	Account Classification Total: 412 - Municipal Tax	($1,634,583.90)	$0.00
460 - Investment Earnings			
4601	Interest Earnings	84,948.06	0.00
	Account Classification Total: 460 - Investment Earnings	$84,948.06	$0.00
492-493 - Reimbursements			
4921	Reimbursements -Regular	529.42	0.00
	Account Classification Total: 492-493 - Reimbursements	$529.42	$0.00
	Department Total: 000 - General	($1,549,106.42)	$0.00
	REVENUES Total	($1,549,106.42)	$0.00
EXPENSES			
Department: 564 - Income Tax Division			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	89,783.22	110,656.00
5106	Longevity	0.00	850.00
5109	HSA Employer Funding	4,000.00	4,200.00
5151	PERS Contribution	10,517.68	15,490.00
5161	Group Insurance	15,498.43	25,700.00
5164	Workers Compensation	2,119.00	2,338.00
5166	Medicare	1,201.80	1,604.00
	Account Classification Total: 5100 - Personal Services	$123,120.13	$160,838.00
5200 - Supplies			
5201	Office Supplies	686.65	2,000.00
5203	Computer Supplies	0.00	1,000.00
	Account Classification Total: 5200 - Supplies	$686.65	$3,000.00
5300 - Services			
5321	Professional Training	250.00	2,500.00
5322	Conference/Reimb	932.20	9,725.00
5323	Publications	369.99	400.00
5324	Professional Association Dues	170.00	950.00
5339	Misc Contract Services	0.00	75,000.00
5353	Employee Fidelity Bond	100.00	150.00
5362	Equipment Maintenance	307.20	550.00
5373	Auditor/Treasurer Fees	252.51	300.00
5379	Other Governmental Billings	3,902.19	10,000.00
5391	Postage	55.99	750.00
5399	Other Miscellaneous Services	280.00	100.00
	Account Classification Total: 5300 - Services	$6,620.08	$100,425.00
5500 - Transfers/Other			
5519	Miscellaneous Costs	(633.27)	110,000.00
5529	Miscellaneous Distributions	(111,629.22)	800,000.00
5530	Enterprise Zone Payment	0.00	200,000.00
	Account Classification Total: 5500 - Transfers/Other	($112,262.49)	$1,110,000.00
5600 - Capital Purchases			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5631	Furniture and Fixtures	0.00	750.00
5639	Other Equipment	0.00	200.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$950.00
	Department Total: 564 - Income Tax Division	$18,164.37	$1,375,213.00
	EXPENSES Total	$18,164.37	$1,375,213.00
	Fund REVENUE Total: 220 - Income Tax Fund	($1,549,106.42)	$0.00
	Fund EXPENSE Total: 220 - Income Tax Fund	$18,164.37	$1,375,213.00
	Fund Total: 220 - Income Tax Fund	($1,567,270.79)	($1,375,213.00)
Fund: 230 - Permissive Tax Fund			
REVENUES			
Department: 000 - General			
414-415 - State Levied Shared Taxes			
4154	MV License - Permissive Tax - County	84,058.14	0.00
4155	MV License - Permissive Tax - Local	168,116.88	0.00
	Account Classification Total: 414-415 - State Levied Shared Taxes	$252,175.02	$0.00
460 - Investment Earnings			
4601	Interest Earnings	506.12	0.00
	Account Classification Total: 460 - Investment Earnings	$506.12	$0.00
	Department Total: 000 - General	$252,681.14	$0.00
	REVENUES Total	$252,681.14	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5501	Transfers	25,000.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$25,000.00	$0.00
Project: 0199 - 2025 Street Improvement Project			
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	242,104.16	0.00
	Account Classification Total: 5600 - Capital Purchases	$242,104.16	$0.00
	Project Total: 0199 - 2025 Street Improvement Project	$242,104.16	$0.00
	Department Total: 000 - General	$267,104.16	$0.00
	EXPENSES Total	$267,104.16	$0.00
	Fund REVENUE Total: 230 - Permissive Tax Fund	$252,681.14	$0.00
	Fund EXPENSE Total: 230 - Permissive Tax Fund	$267,104.16	$0.00
	Fund Total: 230 - Permissive Tax Fund	($14,423.02)	$0.00
Fund: 240 - Police Pension Fund			
REVENUES			
Department: 000 - General			
411 - Property Taxes			
4110	Real Estate/Pub Util Tax	325,643.95	0.00
4114	Trailer Tax	189.46	0.00
	Account Classification Total: 411 - Property Taxes	$325,833.41	$0.00
414-415 - State Levied Shared Taxes			
4141	Real Property Tax-Rollback and Homestead	26,137.67	0.00
	Account Classification Total: 414-415 - State Levied Shared Taxes	$26,137.67	$0.00
	Department Total: 000 - General	$351,971.08	$0.00
	REVENUES Total	$351,971.08	$0.00
EXPENSES			
Department: 000 - General			
5100 - Personal Services			
5152	PFDPF Contribution	0.00	350,000.00
	Account Classification Total: 5100 - Personal Services	$0.00	$350,000.00
5500 - Transfers/Other			
5519	Miscellaneous Costs	4,851.90	4,500.00
	Account Classification Total: 5500 - Transfers/Other	$4,851.90	$4,500.00
	Department Total: 000 - General	$4,851.90	$354,500.00
	EXPENSES Total	$4,851.90	$354,500.00
	Fund REVENUE Total: 240 - Police Pension Fund	$351,971.08	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Fund EXPENSE Total: 240 - Police Pension Fund	$4,851.90	$354,500.00
	Fund Total: 240 - Police Pension Fund	$347,119.18	($354,500.00)
Fund: 250 - Sewer Capacity Fund			
REVENUES			
Department: 000 - General			
Project: 0093 - Pleasantview Hgt Sanitary Sewer			
463 - Special Assesments			
4631	Special Assessment Receipts	2,210.37	0.00
	Account Classification Total: 463 - Special Assesments	$2,210.37	$0.00
	Project Total: 0093 - Pleasantview Hgt Sanitary Sewer	$2,210.37	$0.00
	Department Total: 000 - General	$2,210.37	$0.00
Department: 736 - Wastewater Division			
446-447 - Utility Charges			
4461	Capacity Charges	735,347.50	0.00
	Account Classification Total: 446-447 - Utility Charges	$735,347.50	$0.00
	Department Total: 736 - Wastewater Division	$735,347.50	$0.00
	REVENUES Total	$737,557.87	$0.00
EXPENSES			
Department: 736 - Wastewater Division			
5300 - Services			
5373	Auditor/Treasurer Fees	0.00	500.00
	Account Classification Total: 5300 - Services	$0.00	$500.00
	Department Total: 736 - Wastewater Division	$0.00	$500.00
	EXPENSES Total	$0.00	$500.00
	Fund REVENUE Total: 250 - Sewer Capacity Fund	$737,557.87	$0.00
	Fund EXPENSE Total: 250 - Sewer Capacity Fund	$0.00	$500.00
	Fund Total: 250 - Sewer Capacity Fund	$737,557.87	($500.00)
Fund: 260 - Street Fund			
REVENUES			
Department: 000 - General			
414-415 - State Levied Shared Taxes			
4151	Gasoline Tax	1,501,312.10	0.00
4152	MV License - State Registration	134,348.85	0.00
	Account Classification Total: 414-415 - State Levied Shared Taxes	$1,635,660.95	$0.00
461-462 - Other Revenues			
4629	Miscellaneous Revenue	11,905.85	0.00
	Account Classification Total: 461-462 - Other Revenues	$11,905.85	$0.00
492-493 - Reimbursements			
4921	Reimbursements -Regular	2,604.17	0.00
4922	Property Damage Reimbursements	16,400.58	0.00
	Account Classification Total: 492-493 - Reimbursements	$19,004.75	$0.00
	Department Total: 000 - General	$1,666,571.55	$0.00
	REVENUES Total	$1,666,571.55	$0.00
EXPENSES			
Department: 000 - General			
Project: 0142 - Old Reynoldsburg Improvements			
5600 - Capital Purchases			
5651	Street Resurfacing	81,898.09	0.00
	Account Classification Total: 5600 - Capital Purchases	$81,898.09	$0.00
	Project Total: 0142 - Old Reynoldsburg Improvements	$81,898.09	$0.00
	Department Total: 000 - General	$81,898.09	$0.00
Department: 268 - Street Department			
5100 - Personal Services			
5101	Salary-Elected Officials/Director	82,664.46	117,021.00
5102	Wages-Staff	450,356.34	510,343.00
5105	Overtime	10,681.23	28,000.00
5106	Longevity	5,950.00	8,400.00
5109	HSA Employer Funding	25,000.00	33,600.00
5151	PERS Contribution	60,827.54	92,577.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5161	Group Insurance	88,443.34	172,251.00
5164	Workers Compensation	11,688.00	14,029.00
5166	Medicare	7,763.12	9,588.00
	Account Classification Total: 5100 - Personal Services	$743,374.03	$985,809.00
5200 - Supplies			
5201	Office Supplies	(395.51)	3,500.00
5203	Computer Supplies	673.08	1,000.00
5205	Small Tools/Minor Equipment	413.34	1,500.00
5213	Repair and Maintenance Supplies	0.00	500.00
5241	Uniforms-Purchased	16,611.87	8,000.00
5251	MV Gas and Oil	17,314.24	40,000.00
5252	Aggregates	5,977.90	17,000.00
5253	Ice Control	0.00	140,000.00
5259	Operating Materials and Supplies	131,349.62	200,000.00
	Account Classification Total: 5200 - Supplies	$171,944.54	$411,500.00
5300 - Services			
5311	Utilities	13,002.33	24,200.00
5313	Traffic Light Current	7,962.18	15,400.00
5321	Professional Training	599.00	4,000.00
5322	Conference/Reimb	0.00	1,000.00
5324	Professional Association Dues	260.00	160.00
5331	Engineering/Architecture	0.00	15,000.00
5339	Misc Contract Services	136,485.00	200,000.00
5351	Liability Insurance Deductible	0.00	8,000.00
5352	Motor Vehicle Insurance	12,888.00	8,000.00
5361	Building Repair/Maintenance	0.00	10,000.00
5365	Utility Line Repair/Maintenance	29,921.73	75,000.00
5391	Postage	18.14	100.00
5397	Uniform Rental	1,093.64	2,000.00
5399	Other Miscellaneous Services	502.55	1,500.00
	Account Classification Total: 5300 - Services	$202,732.57	$364,360.00
5600 - Capital Purchases			
5632	Motor Vehicles	0.00	200,000.00
5633	Machinery and Equipment	8,900.00	163,000.00
	Account Classification Total: 5600 - Capital Purchases	$8,900.00	$363,000.00
	Department Total: 268 - Street Department	$1,126,951.14	$2,124,669.00
	EXPENSES Total	$1,208,849.23	$2,124,669.00
	Fund REVENUE Total: 260 - Street Fund	$1,666,571.55	$0.00
	Fund EXPENSE Total: 260 - Street Fund	$1,208,849.23	$2,124,669.00
	Fund Total: 260 - Street Fund	$457,722.32	($2,124,669.00)
Fund: 270 - State Highway Fund			
REVENUES			
Department: 000 - General			
414-415 - State Levied Shared Taxes			
4151	Gasoline Tax	332,064.76	0.00
4152	MV License - State Registration	11,173.94	0.00
	Account Classification Total: 414-415 - State Levied Shared Taxes	$343,238.70	$0.00
	Department Total: 000 - General	$343,238.70	$0.00
	REVENUES Total	$343,238.70	$0.00
EXPENSES			
Department: 268 - Street Department			
5200 - Supplies			
5253	Ice Control	0.00	55,000.00
5259	Operating Materials and Supplies	1,655.00	22,500.00
	Account Classification Total: 5200 - Supplies	$1,655.00	$77,500.00
5300 - Services			
5313	Traffic Light Current	8,930.70	12,850.00
5339	Misc Contract Services	9,644.40	3,000.00
5365	Utility Line Repair/Maintenance	11,888.13	22,000.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 5300 - Services	$30,463.23	$37,850.00
	Department Total: 268 - Street Department	$32,118.23	$115,350.00
	EXPENSES Total	$32,118.23	$115,350.00
	Fund REVENUE Total: 270 - State Highway Fund	$343,238.70	$0.00
	Fund EXPENSE Total: 270 - State Highway Fund	$32,118.23	$115,350.00
	Fund Total: 270 - State Highway Fund	$311,120.47	($115,350.00)
Fund: 288 - OneOhio Opioid Fund			
REVENUES			
Department: 000 - General			
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	33,065.17	0.00
	Account Classification Total: 492-493 - Reimbursements	$33,065.17	$0.00
	Department Total: 000 - General	$33,065.17	$0.00
	REVENUES Total	$33,065.17	$0.00
	Fund REVENUE Total: 288 - OneOhio Opioid Fund	$33,065.17	$0.00
	Fund EXPENSE Total: 288 - OneOhio Opioid Fund		
	Fund Total: 288 - OneOhio Opioid Fund	$33,065.17	$0.00
Fund: 290 - Law Enforcement Fund			
REVENUES			
Department: 111 - Police Division			
461-462 - Other Revenues			
4616	Proceeds for Police Special Revenue Funds	77,698.67	0.00
	Account Classification Total: 461-462 - Other Revenues	$77,698.67	$0.00
	Department Total: 111 - Police Division	$77,698.67	$0.00
	REVENUES Total	$77,698.67	$0.00
EXPENSES			
Department: 111 - Police Division			
5500 - Transfers/Other			
5529	Miscellaneous Distributions	25,046.24	0.00
	Account Classification Total: 5500 - Transfers/Other	$25,046.24	$0.00
	Department Total: 111 - Police Division	$25,046.24	$0.00
	EXPENSES Total	$25,046.24	$0.00
	Fund REVENUE Total: 290 - Law Enforcement Fund	$77,698.67	$0.00
	Fund EXPENSE Total: 290 - Law Enforcement Fund	$25,046.24	$0.00
	Fund Total: 290 - Law Enforcement Fund	$52,652.43	$0.00
Fund: 291 - Drug Enforcement Fund			
REVENUES			
Department: 111 - Police Division			
461-462 - Other Revenues			
4616	Proceeds for Police Special Revenue Funds	1,280.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$1,280.00	$0.00
	Department Total: 111 - Police Division	$1,280.00	$0.00
	REVENUES Total	$1,280.00	$0.00
	Fund REVENUE Total: 291 - Drug Enforcement Fund	$1,280.00	$0.00
	Fund EXPENSE Total: 291 - Drug Enforcement Fund		
	Fund Total: 291 - Drug Enforcement Fund	$1,280.00	$0.00
Fund: 293 - DUI/Education/Enforcement Fund			
REVENUES			
Department: 111 - Police Division			
461-462 - Other Revenues			
4616	Proceeds for Police Special Revenue Funds	897.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$897.00	$0.00
	Department Total: 111 - Police Division	$897.00	$0.00
	REVENUES Total	$897.00	$0.00
	Fund REVENUE Total: 293 - DUI/Education/Enforcement Fund	$897.00	$0.00
	Fund EXPENSE Total: 293 - DUI/Education/Enforcement Fund		
	Fund Total: 293 - DUI/Education/Enforcement Fund	$897.00	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
Fund: 294 - Federal Forfeiture Fund			
REVENUES			
Department: 111 - Police Division			
461-462 - Other Revenues			
4616	Proceeds for Police Special Revenue Funds	392.43	0.00
	Account Classification Total: 461-462 - Other Revenues	$392.43	$0.00
	Department Total: 111 - Police Division	$392.43	$0.00
	REVENUES Total	$392.43	$0.00
	Fund REVENUE Total: 294 - Federal Forfeiture Fund	$392.43	$0.00
	Fund EXPENSE Total: 294 - Federal Forfeiture Fund		
	Fund Total: 294 - Federal Forfeiture Fund	$392.43	$0.00
Fund: 295 - Law Enforcement Asst Fund			
REVENUES			
Department: 111 - Police Division			
461-462 - Other Revenues			
4616	Proceeds for Police Special Revenue Funds	180.80	0.00
	Account Classification Total: 461-462 - Other Revenues	$180.80	$0.00
	Department Total: 111 - Police Division	$180.80	$0.00
	REVENUES Total	$180.80	$0.00
	Fund REVENUE Total: 295 - Law Enforcement Asst Fund	$180.80	$0.00
	Fund EXPENSE Total: 295 - Law Enforcement Asst Fund		
	Fund Total: 295 - Law Enforcement Asst Fund	$180.80	$0.00
Fund: 310 - General Debt Retirement Fund			
REVENUES			
Department: 000 - General			
412 - Municipal Tax			
4100	Income Tax Proceeds	2,284,629.66	0.00
	Account Classification Total: 412 - Municipal Tax	$2,284,629.66	$0.00
461-462 - Other Revenues			
4629	Miscellaneous Revenue	87,280.40	0.00
	Account Classification Total: 461-462 - Other Revenues	$87,280.40	$0.00
	Department Total: 000 - General	$2,371,910.06	$0.00
	REVENUES Total	$2,371,910.06	$0.00
EXPENSES			
Department: 991 - Debt Service			
5400 - Debt Service			
5414	G. O. Bond-Principal	54,269.19	0.00
5424	G. O. Bond-Interest	822,659.27	0.00
	Account Classification Total: 5400 - Debt Service	$876,928.46	$0.00
	Department Total: 991 - Debt Service	$876,928.46	$0.00
	EXPENSES Total	$876,928.46	$0.00
	Fund REVENUE Total: 310 - General Debt Retirement Fund	$2,371,910.06	$0.00
	Fund EXPENSE Total: 310 - General Debt Retirement Fund	$876,928.46	$0.00
	Fund Total: 310 - General Debt Retirement Fund	$1,494,981.60	$0.00
Fund: 410 - Capital Improvements Fund			
REVENUES			
Department: 000 - General			
412 - Municipal Tax			
4100	Income Tax Proceeds	2,855,787.09	0.00
	Account Classification Total: 412 - Municipal Tax	$2,855,787.09	$0.00
460 - Investment Earnings			
4601	Interest Earnings	656,063.02	0.00
	Account Classification Total: 460 - Investment Earnings	$656,063.02	$0.00
492-493 - Reimbursements			
4921	Reimbursements -Regular	974,123.54	0.00
	Account Classification Total: 492-493 - Reimbursements	$974,123.54	$0.00
499 - Transfers/Advances			
4990	Operating Transfers	3,047,395.05	0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 499 - Transfers/Advances	$3,047,395.05	$0.00
Project:	**0205 - Waggoner Rd Improvement Phase 2**		
433 - Intergovernmental-State			
4335	Grants/Aid	246,000.00	0.00
	Account Classification Total: 433 - Intergovernmental-State	$246,000.00	$0.00
	Project Total: 0205 - Waggoner Rd Improvement Phase 2	$246,000.00	$0.00
	Department Total: 000 - General	$7,779,368.70	$0.00
	REVENUES Total	$7,779,368.70	$0.00
EXPENSES			
Department:	**000 - General**		
Project:	**0170 - Olde Reyn - Davidson-Jackson**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	442,325.91	0.00
	Account Classification Total: 5600 - Capital Purchases	$442,325.91	$0.00
	Project Total: 0170 - Olde Reyn - Davidson-Jackson	$442,325.91	$0.00
Project:	**0182 - Main St Phase 2 Jackson-Waggoner**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	252,278.90	0.00
	Account Classification Total: 5600 - Capital Purchases	$252,278.90	$0.00
	Project Total: 0182 - Main St Phase 2 Jackson-Waggoner	$252,278.90	$0.00
Project:	**0194 - Combined Public Service Bldg**		
5600 - Capital Purchases			
5611	Buildings	16,932,443.18	0.00
	Account Classification Total: 5600 - Capital Purchases	$16,932,443.18	$0.00
	Project Total: 0194 - Combined Public Service Bldg	$16,932,443.18	$0.00
Project:	**0198 - Waggoner Rd Improvement Phase 1**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	3,647,578.66	0.00
	Account Classification Total: 5600 - Capital Purchases	$3,647,578.66	$0.00
	Project Total: 0198 - Waggoner Rd Improvement Phase 1	$3,647,578.66	$0.00
Project:	**0199 - 2025 Street Improvement Project**		
5600 - Capital Purchases			
5651	Street Resurfacing	60,921.92	0.00
5659	Miscellaneous Infrastructure	466,992.85	0.00
	Account Classification Total: 5600 - Capital Purchases	$527,914.77	$0.00
	Project Total: 0199 - 2025 Street Improvement Project	$527,914.77	$0.00
Project:	**0200 - Birchview Drive**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	69,558.80	0.00
	Account Classification Total: 5600 - Capital Purchases	$69,558.80	$0.00
	Project Total: 0200 - Birchview Drive	$69,558.80	$0.00
Project:	**0201 - Brice Park**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	712,553.19	0.00
	Account Classification Total: 5600 - Capital Purchases	$712,553.19	$0.00
	Project Total: 0201 - Brice Park	$712,553.19	$0.00
Project:	**0202 - JFK Park Tennis Court Conversion**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	41,598.77	0.00
	Account Classification Total: 5600 - Capital Purchases	$41,598.77	$0.00
	Project Total: 0202 - JFK Park Tennis Court Conversion	$41,598.77	$0.00
Project:	**0203 - Summit Road Improvement Project**		
5600 - Capital Purchases			
5659	Miscellaneous Infrastructure	129,060.92	0.00
	Account Classification Total: 5600 - Capital Purchases	$129,060.92	$0.00
	Project Total: 0203 - Summit Road Improvement Project	$129,060.92	$0.00
	Department Total: 000 - General	$22,755,313.10	$0.00
	EXPENSES Total	$22,755,313.10	$0.00
	Fund REVENUE Total: 410 - Capital Improvements Fund	$7,779,368.70	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
Fund EXPENSE	Total: 410 - Capital Improvements Fund	$22,755,313.10	$0.00
	Fund Total: 410 - Capital Improvements Fund	($14,975,944.40)	$0.00
Fund: 420 - Sidewalk Construction Fund			
REVENUES			
Department: 000 - General			
422-423 - Permits			
4230	Sidewalk Permits	20,748.76	0.00
	Account Classification Total: 422-423 - Permits	$20,748.76	$0.00
Project: 0007 - Phase VII			
463 - Special Assesments			
4631	Special Assessment Receipts	33,988.77	0.00
	Account Classification Total: 463 - Special Assesments	$33,988.77	$0.00
	Project Total: 0007 - Phase VII	$33,988.77	$0.00
Project: 0010 - Phase X			
463 - Special Assesments			
4631	Special Assessment Receipts	764.00	0.00
	Account Classification Total: 463 - Special Assesments	$764.00	$0.00
	Project Total: 0010 - Phase X	$764.00	$0.00
	Department Total: 000 - General	$55,501.53	$0.00
	REVENUES Total	$55,501.53	$0.00
EXPENSES			
Department: 000 - General			
Project: 0007 - Phase VII			
5600 - Capital Purchases			
5653	Sidewalk Construction	173.52	0.00
	Account Classification Total: 5600 - Capital Purchases	$173.52	$0.00
	Project Total: 0007 - Phase VII	$173.52	$0.00
Project: 0010 - Phase X			
5600 - Capital Purchases			
5653	Sidewalk Construction	28,672.81	0.00
	Account Classification Total: 5600 - Capital Purchases	$28,672.81	$0.00
	Project Total: 0010 - Phase X	$28,672.81	$0.00
	Department Total: 000 - General	$28,846.33	$0.00
	EXPENSES Total	$28,846.33	$0.00
Fund REVENUE	Total: 420 - Sidewalk Construction Fund	$55,501.53	$0.00
Fund EXPENSE	Total: 420 - Sidewalk Construction Fund	$28,846.33	$0.00
	Fund Total: 420 - Sidewalk Construction Fund	$26,655.20	$0.00
Fund: 640 - Supervision and Inspection			
REVENUES			
Department: 000 - General			
Project: 0000 - General			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	154,100.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$154,100.00	$0.00
	Project Total: 0000 - General	$154,100.00	$0.00
Project: 6361 - Heart Food Pantry and Market			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	15,800.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$15,800.00	$0.00
	Project Total: 6361 - Heart Food Pantry and Market	$15,800.00	$0.00
Project: 6368 - Victoria's Secret Lot Expansion			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	16,615.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$16,615.00	$0.00
	Project Total: 6368 - Victoria's Secret Lot Expansion	$16,615.00	$0.00
Project: 6369 - Summit Crossing Section 1A			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	149,777.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$149,777.00	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Project Total: 6369 - Summit Crossing Section 1A	$149,777.00	$0.00
Project:	**6372 - One Alliance Place - 2nd**		
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	5,460.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$5,460.00	$0.00
	Project Total: 6372 - One Alliance Place - 2nd	$5,460.00	$0.00
Project:	**6374 - Trivium 1122 Lancaster Ave**		
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	146,318.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$146,318.00	$0.00
	Project Total: 6374 - Trivium 1122 Lancaster Ave	$146,318.00	$0.00
Project:	**6376 - Core 5 Taylor Road Industrial**		
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	(77,050.00)	0.00
	Account Classification Total: 461-462 - Other Revenues	($77,050.00)	$0.00
	Project Total: 6376 - Core 5 Taylor Road Industrial	($77,050.00)	$0.00
	Department Total: 000 - General	$411,020.00	$0.00
	REVENUES Total	$411,020.00	$0.00
EXPENSES			
Department:	**000 - General**		
Project:	**6192 - Village at Slate Ridge**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,319.62	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,319.62	$0.00
	Project Total: 6192 - Village at Slate Ridge	$3,319.62	$0.00
Project:	**6297 - Robertson Trucking**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	915.65	0.00
	Account Classification Total: 5500 - Transfers/Other	$915.65	$0.00
	Project Total: 6297 - Robertson Trucking	$915.65	$0.00
Project:	**6298 - Bigham Building Addition**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,341.85	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,341.85	$0.00
	Project Total: 6298 - Bigham Building Addition	$1,341.85	$0.00
Project:	**6300 - Inn at Summit Trail**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	422.02	0.00
	Account Classification Total: 5500 - Transfers/Other	$422.02	$0.00
	Project Total: 6300 - Inn at Summit Trail	$422.02	$0.00
Project:	**6302 - Reyn UMC Parking Lot Exp Ph1**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	261.02	0.00
	Account Classification Total: 5500 - Transfers/Other	$261.02	$0.00
	Project Total: 6302 - Reyn UMC Parking Lot Exp Ph1	$261.02	$0.00
Project:	**6303 - Truro Ave Group Home**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	36.55	0.00
	Account Classification Total: 5500 - Transfers/Other	$36.55	$0.00
	Project Total: 6303 - Truro Ave Group Home	$36.55	$0.00
Project:	**6305 - Kroger Main Street**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	117.23	0.00
	Account Classification Total: 5500 - Transfers/Other	$117.23	$0.00
	Project Total: 6305 - Kroger Main Street	$117.23	$0.00
Project:	**6307 - UDF at Broad and Waggoner**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	12,352.60	0.00
	Account Classification Total: 5500 - Transfers/Other	$12,352.60	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Project Total: 6307 - UDF at Broad and Waggoner	$12,352.60	$0.00
Project:	**6308 - St Pius X Traffic Study**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,000.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,000.00	$0.00
	Project Total: 6308 - St Pius X Traffic Study	$1,000.00	$0.00
Project:	**6309 - Dollar General-Main @ Waggoner**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	675.95	0.00
	Account Classification Total: 5500 - Transfers/Other	$675.95	$0.00
	Project Total: 6309 - Dollar General-Main @ Waggoner	$675.95	$0.00
Project:	**6314 - Truro Fire Station #161**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,341.06	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,341.06	$0.00
	Project Total: 6314 - Truro Fire Station #161	$1,341.06	$0.00
Project:	**6318 - Blacklick Golf Course**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,654.29	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,654.29	$0.00
	Project Total: 6318 - Blacklick Golf Course	$1,654.29	$0.00
Project:	**6321 - Oak Valley Road**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	433.31	0.00
	Account Classification Total: 5500 - Transfers/Other	$433.31	$0.00
	Project Total: 6321 - Oak Valley Road	$433.31	$0.00
Project:	**6324 - Valvoline Instant Oil E. Broad**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,446.56	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,446.56	$0.00
	Project Total: 6324 - Valvoline Instant Oil E. Broad	$3,446.56	$0.00
Project:	**6329 - M/I Homes SpringHill Farms Sec 1**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	27,912.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$27,912.00	$0.00
	Project Total: 6329 - M/I Homes SpringHill Farms Sec 1	$27,912.00	$0.00
Project:	**6332 - ROSEHILL TOWNHOMES**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	127.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$127.50	$0.00
	Project Total: 6332 - ROSEHILL TOWNHOMES	$127.50	$0.00
Project:	**6333 - MI Homes/Spring Hill Farm Sec 2**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	4,250.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$4,250.00	$0.00
	Project Total: 6333 - MI Homes/Spring Hill Farm Sec 2	$4,250.00	$0.00
Project:	**6335 - Sheetz-E. Broad and Cedar Cliff**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	74.75	0.00
	Account Classification Total: 5500 - Transfers/Other	$74.75	$0.00
	Project Total: 6335 - Sheetz-E. Broad and Cedar Cliff	$74.75	$0.00
Project:	**6337 - Springhill Farms Sec 3**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,280.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,280.00	$0.00
	Project Total: 6337 - Springhill Farms Sec 3	$1,280.00	$0.00
Project:	**6339 - Wilson Ridge Townhomes**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	7,495.38	0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 5500 - Transfers/Other	$7,495.38	$0.00
	Project Total: 6339 - Wilson Ridge Townhomes	$7,495.38	$0.00
Project:	**6342 - Eastwood Lot 4 - Thornton Hall**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,781.96	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,781.96	$0.00
	Project Total: 6342 - Eastwood Lot 4 - Thornton Hall	$1,781.96	$0.00
Project:	**6343 - West Licking Fire Station Taylor**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,064.91	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,064.91	$0.00
	Project Total: 6343 - West Licking Fire Station Taylor	$1,064.91	$0.00
Project:	**6344 - Sheetz-Taylor & Main**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	2,590.15	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,590.15	$0.00
	Project Total: 6344 - Sheetz-Taylor & Main	$2,590.15	$0.00
Project:	**6345 - Moo Moo Car Wash E. Broad St**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	310.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$310.00	$0.00
	Project Total: 6345 - Moo Moo Car Wash E. Broad St	$310.00	$0.00
Project:	**6346 - Central Oh Primary Care**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,258.75	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,258.75	$0.00
	Project Total: 6346 - Central Oh Primary Care	$3,258.75	$0.00
Project:	**6347 - Columbus Metropolitan Library**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	0.52	0.00
	Account Classification Total: 5500 - Transfers/Other	$0.52	$0.00
	Project Total: 6347 - Columbus Metropolitan Library	$0.52	$0.00
Project:	**6348 - Caribou Coffee**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,901.31	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,901.31	$0.00
	Project Total: 6348 - Caribou Coffee	$1,901.31	$0.00
Project:	**6349 - Trivium Reynoldsburg**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,120.95	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,120.95	$0.00
	Project Total: 6349 - Trivium Reynoldsburg	$1,120.95	$0.00
Project:	**6350 - Maplewood Sections 1 & 2**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,711.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,711.50	$0.00
	Project Total: 6350 - Maplewood Sections 1 & 2	$1,711.50	$0.00
Project:	**6351 - Eastwood Phase 1 Single Family**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	551.97	0.00
	Account Classification Total: 5500 - Transfers/Other	$551.97	$0.00
	Project Total: 6351 - Eastwood Phase 1 Single Family	$551.97	$0.00
Project:	**6352 - Home 2 Suite**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	376.58	0.00
	Account Classification Total: 5500 - Transfers/Other	$376.58	$0.00
	Project Total: 6352 - Home 2 Suite	$376.58	$0.00
Project:	**6354 - Christian & Missionary Alliance**		
5500 - Transfers/Other			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5518	Plan Review/Inspection	783.40	0.00
	Account Classification Total: 5500 - Transfers/Other	$783.40	$0.00
	Project Total: 6354 - Christian & Missionary Alliance	$783.40	$0.00
Project: 6356 - Eastwood Phase 2 &3 Sanitary/PGU			
5500 - Transfers/Other			
5518	Plan Review/Inspection	8,245.27	0.00
	Account Classification Total: 5500 - Transfers/Other	$8,245.27	$0.00
	Project Total: 6356 - Eastwood Phase 2 &3 Sanitary/PGU	$8,245.27	$0.00
Project: 6357 - Truro Twp Maintenance Bldg			
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,153.21	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,153.21	$0.00
	Project Total: 6357 - Truro Twp Maintenance Bldg	$1,153.21	$0.00
Project: 6358 - JP Morgan Chase			
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,710.27	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,710.27	$0.00
	Project Total: 6358 - JP Morgan Chase	$1,710.27	$0.00
Project: 6361 - Heart Food Pantry and Market			
5500 - Transfers/Other			
5518	Plan Review/Inspection	8,183.17	0.00
	Account Classification Total: 5500 - Transfers/Other	$8,183.17	$0.00
	Project Total: 6361 - Heart Food Pantry and Market	$8,183.17	$0.00
Project: 6362 - Spring Hill Sect 4A, 4B & 5			
5500 - Transfers/Other			
5518	Plan Review/Inspection	149,325.96	0.00
	Account Classification Total: 5500 - Transfers/Other	$149,325.96	$0.00
	Project Total: 6362 - Spring Hill Sect 4A, 4B & 5	$149,325.96	$0.00
Project: 6363 - Spring Hill Sect 6A & B			
5500 - Transfers/Other			
5518	Plan Review/Inspection	18,419.60	0.00
	Account Classification Total: 5500 - Transfers/Other	$18,419.60	$0.00
	Project Total: 6363 - Spring Hill Sect 6A & B	$18,419.60	$0.00
Project: 6368 - Victoria's Secret Lot Expansion			
5500 - Transfers/Other			
5518	Plan Review/Inspection	4,019.94	0.00
	Account Classification Total: 5500 - Transfers/Other	$4,019.94	$0.00
	Project Total: 6368 - Victoria's Secret Lot Expansion	$4,019.94	$0.00
Project: 6369 - Summit Crossing Section 1A			
5500 - Transfers/Other			
5518	Plan Review/Inspection	113,102.81	0.00
	Account Classification Total: 5500 - Transfers/Other	$113,102.81	$0.00
	Project Total: 6369 - Summit Crossing Section 1A	$113,102.81	$0.00
Project: 6376 - Core 5 Taylor Road Industrial			
5500 - Transfers/Other			
5518	Plan Review/Inspection	787.20	0.00
	Account Classification Total: 5500 - Transfers/Other	$787.20	$0.00
	Project Total: 6376 - Core 5 Taylor Road Industrial	$787.20	$0.00
	Department Total: 000 - General	$388,856.77	$0.00
	EXPENSES Total	$388,856.77	$0.00
	Fund REVENUE Total: 640 - Supervision and Inspection	$411,020.00	$0.00
	Fund EXPENSE Total: 640 - Supervision and Inspection	$388,856.77	$0.00
	Fund Total: 640 - Supervision and Inspection	$22,163.23	$0.00
Fund: 650 - Plot Grade & Utility			
REVENUES			
Department: 000 - General			
Project: 0000 - General			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	1,300.00	0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 461-462 - Other Revenues	$1,300.00	$0.00
	Project Total: 0000 - General	$1,300.00	$0.00
Project: 6358 - JP Morgan Chase			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	1,440.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$1,440.00	$0.00
	Project Total: 6358 - JP Morgan Chase	$1,440.00	$0.00
Project: 6362 - Spring Hill Sect 4A, 4B & 5			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	2,340.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$2,340.00	$0.00
	Project Total: 6362 - Spring Hill Sect 4A, 4B & 5	$2,340.00	$0.00
Project: 6368 - Victoria's Secret Lot Expansion			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	2,500.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$2,500.00	$0.00
	Project Total: 6368 - Victoria's Secret Lot Expansion	$2,500.00	$0.00
Project: 6369 - Summit Crossing Section 1A			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	2,000.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$2,000.00	$0.00
	Project Total: 6369 - Summit Crossing Section 1A	$2,000.00	$0.00
Project: 6370 - Summit Crossing Section 1B			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	1,200.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$1,200.00	$0.00
	Project Total: 6370 - Summit Crossing Section 1B	$1,200.00	$0.00
Project: 6371 - DSFM - Ohio Fire Academy			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	3,100.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$3,100.00	$0.00
	Project Total: 6371 - DSFM - Ohio Fire Academy	$3,100.00	$0.00
Project: 6372 - One Alliance Place - 2nd			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	900.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$900.00	$0.00
	Project Total: 6372 - One Alliance Place - 2nd	$900.00	$0.00
Project: 6373 - 6493 E. Main Street			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	3,000.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$3,000.00	$0.00
	Project Total: 6373 - 6493 E. Main Street	$3,000.00	$0.00
Project: 6374 - Trivium 1122 Lancaster Ave			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	17,860.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$17,860.00	$0.00
	Project Total: 6374 - Trivium 1122 Lancaster Ave	$17,860.00	$0.00
Project: 6375 - Marriott Townplace Suites			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	12,060.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$12,060.00	$0.00
	Project Total: 6375 - Marriott Townplace Suites	$12,060.00	$0.00
Project: 6376 - Core 5 Taylor Road Industrial			
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	20,900.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$20,900.00	$0.00
	Project Total: 6376 - Core 5 Taylor Road Industrial	$20,900.00	$0.00
Project: 6377 - CMHA - The Heights on Main			
461-462 - Other Revenues			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
4622	Plan Review/Inspection Deposits	3,000.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$3,000.00	$0.00
	Project Total: 6377 - CMHA - The Heights on Main	$3,000.00	$0.00
Project:	**6378 - Summit Crossing Reserve D**		
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	14,920.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$14,920.00	$0.00
	Project Total: 6378 - Summit Crossing Reserve D	$14,920.00	$0.00
Project:	**6379 - Brookside Ridge**		
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	3,000.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$3,000.00	$0.00
	Project Total: 6379 - Brookside Ridge	$3,000.00	$0.00
Project:	**6380 - Take 5 Oil Change**		
461-462 - Other Revenues			
4622	Plan Review/Inspection Deposits	3,000.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$3,000.00	$0.00
	Project Total: 6380 - Take 5 Oil Change	$3,000.00	$0.00
	Department Total: 000 - General	$92,520.00	$0.00
	REVENUES Total	$92,520.00	$0.00
EXPENSES			
Department:	**000 - General**		
Project:	**6298 - Bigham Building Addition**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	50.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$50.00	$0.00
	Project Total: 6298 - Bigham Building Addition	$50.00	$0.00
Project:	**6300 - Inn at Summit Trail**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	2,880.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,880.00	$0.00
	Project Total: 6300 - Inn at Summit Trail	$2,880.00	$0.00
Project:	**6302 - Reyn UMC Parking Lot Exp Ph1**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	375.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$375.00	$0.00
	Project Total: 6302 - Reyn UMC Parking Lot Exp Ph1	$375.00	$0.00
Project:	**6307 - UDF at Broad and Waggoner**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	7,500.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$7,500.00	$0.00
	Project Total: 6307 - UDF at Broad and Waggoner	$7,500.00	$0.00
Project:	**6308 - St Pius X Traffic Study**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	562.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$562.50	$0.00
	Project Total: 6308 - St Pius X Traffic Study	$562.50	$0.00
Project:	**6309 - Dollar General-Main @ Waggoner**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	2,062.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,062.50	$0.00
	Project Total: 6309 - Dollar General-Main @ Waggoner	$2,062.50	$0.00
Project:	**6314 - Truro Fire Station #161**		
5500 - Transfers/Other			
5518	Plan Review/Inspection	2,250.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,250.00	$0.00
	Project Total: 6314 - Truro Fire Station #161	$2,250.00	$0.00
Project:	**6318 - Blacklick Golf Course**		
5500 - Transfers/Other			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5518	Plan Review/Inspection	562.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$562.50	$0.00
	Project Total: 6318 - Blacklick Golf Course	$562.50	$0.00
Project: 6319 - Chic-Fil-A			
5500 - Transfers/Other			
5518	Plan Review/Inspection	800.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$800.00	$0.00
	Project Total: 6319 - Chic-Fil-A	$800.00	$0.00
Project: 6324 - Valvoline Instant Oil E. Broad			
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,375.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,375.00	$0.00
	Project Total: 6324 - Valvoline Instant Oil E. Broad	$3,375.00	$0.00
Project: 6339 - Wilson Ridge Townhomes			
5500 - Transfers/Other			
5518	Plan Review/Inspection	4,500.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$4,500.00	$0.00
	Project Total: 6339 - Wilson Ridge Townhomes	$4,500.00	$0.00
Project: 6341 - Taylor Rd Elementary Drop Off			
5500 - Transfers/Other			
5518	Plan Review/Inspection	2,740.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,740.00	$0.00
	Project Total: 6341 - Taylor Rd Elementary Drop Off	$2,740.00	$0.00
Project: 6342 - Eastwood Lot 4 - Thornton Hall			
5500 - Transfers/Other			
5518	Plan Review/Inspection	555.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$555.00	$0.00
	Project Total: 6342 - Eastwood Lot 4 - Thornton Hall	$555.00	$0.00
Project: 6354 - Christian & Missionary Alliance			
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,000.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,000.00	$0.00
	Project Total: 6354 - Christian & Missionary Alliance	$3,000.00	$0.00
Project: 6358 - JP Morgan Chase			
5500 - Transfers/Other			
5518	Plan Review/Inspection	2,520.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,520.00	$0.00
	Project Total: 6358 - JP Morgan Chase	$2,520.00	$0.00
Project: 6361 - Heart Food Pantry and Market			
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,488.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,488.00	$0.00
	Project Total: 6361 - Heart Food Pantry and Market	$1,488.00	$0.00
Project: 6362 - Spring Hill Sect 4A, 4B & 5			
5500 - Transfers/Other			
5518	Plan Review/Inspection	6,087.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$6,087.50	$0.00
	Project Total: 6362 - Spring Hill Sect 4A, 4B & 5	$6,087.50	$0.00
Project: 6365 - Glenrest Memorial			
5500 - Transfers/Other			
5518	Plan Review/Inspection	520.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$520.00	$0.00
	Project Total: 6365 - Glenrest Memorial	$520.00	$0.00
Project: 6367 - Carpenter's Son Sanitary Swr Ext			
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,000.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,000.00	$0.00
	Project Total: 6367 - Carpenter's Son Sanitary Swr Ext	$3,000.00	$0.00
Project: 6368 - Victoria's Secret Lot Expansion			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5500 - Transfers/Other			
5518	Plan Review/Inspection	12,540.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$12,540.00	$0.00
	Project Total: 6368 - Victoria's Secret Lot Expansion	$12,540.00	$0.00
Project: 6369 - Summit Crossing Section 1A			
5500 - Transfers/Other			
5518	Plan Review/Inspection	9,720.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$9,720.00	$0.00
	Project Total: 6369 - Summit Crossing Section 1A	$9,720.00	$0.00
Project: 6370 - Summit Crossing Section 1B			
5500 - Transfers/Other			
5518	Plan Review/Inspection	5,100.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$5,100.00	$0.00
	Project Total: 6370 - Summit Crossing Section 1B	$5,100.00	$0.00
Project: 6371 - DSFM - Ohio Fire Academy			
5500 - Transfers/Other			
5518	Plan Review/Inspection	9,300.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$9,300.00	$0.00
	Project Total: 6371 - DSFM - Ohio Fire Academy	$9,300.00	$0.00
Project: 6372 - One Alliance Place - 2nd			
5500 - Transfers/Other			
5518	Plan Review/Inspection	7,580.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$7,580.00	$0.00
	Project Total: 6372 - One Alliance Place - 2nd	$7,580.00	$0.00
Project: 6373 - 6493 E. Main Street			
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,000.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,000.00	$0.00
	Project Total: 6373 - 6493 E. Main Street	$3,000.00	$0.00
Project: 6374 - Trivium 1122 Lancaster Ave			
5500 - Transfers/Other			
5518	Plan Review/Inspection	17,860.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$17,860.00	$0.00
	Project Total: 6374 - Trivium 1122 Lancaster Ave	$17,860.00	$0.00
Project: 6375 - Marriott Townplace Suites			
5500 - Transfers/Other			
5518	Plan Review/Inspection	8,670.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$8,670.00	$0.00
	Project Total: 6375 - Marriott Townplace Suites	$8,670.00	$0.00
Project: 6376 - Core 5 Taylor Road Industrial			
5500 - Transfers/Other			
5518	Plan Review/Inspection	20,900.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$20,900.00	$0.00
	Project Total: 6376 - Core 5 Taylor Road Industrial	$20,900.00	$0.00
Project: 6377 - CMHA - The Heights on Main			
5500 - Transfers/Other			
5518	Plan Review/Inspection	3,000.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$3,000.00	$0.00
	Project Total: 6377 - CMHA - The Heights on Main	$3,000.00	$0.00
Project: 6378 - Summit Crossing Reserve D			
5500 - Transfers/Other			
5518	Plan Review/Inspection	14,920.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$14,920.00	$0.00
	Project Total: 6378 - Summit Crossing Reserve D	$14,920.00	$0.00
Project: 6379 - Brookside Ridge			
5500 - Transfers/Other			
5518	Plan Review/Inspection	1,707.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,707.00	$0.00
	Project Total: 6379 - Brookside Ridge	$1,707.00	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Department Total: 000 - General	$159,125.00	$0.00
	EXPENSES Total	$159,125.00	$0.00
	Fund REVENUE Total: 650 - Plot Grade & Utility	$92,520.00	$0.00
	Fund EXPENSE Total: 650 - Plot Grade & Utility	$159,125.00	$0.00
	Fund Total: 650 - Plot Grade & Utility	($66,605.00)	$0.00
Fund: 660 - Unclaimed Funds			
REVENUES			
Department: 000 - General			
492-493 - Reimbursements			
4933	Unclaimed Funds	2,409.00	0.00
4934	Found Money	2,018.59	0.00
	Account Classification Total: 492-493 - Reimbursements	$4,427.59	$0.00
	Department Total: 000 - General	$4,427.59	$0.00
	REVENUES Total	$4,427.59	$0.00
	Fund REVENUE Total: 660 - Unclaimed Funds	$4,427.59	$0.00
	Fund EXPENSE Total: 660 - Unclaimed Funds		
	Fund Total: 660 - Unclaimed Funds	$4,427.59	$0.00
Fund: 710 - Water Fund			
REVENUES			
Department: 000 - General			
446-447 - Utility Charges			
4470	Utility CIP Fee	873,953.14	0.00
	Account Classification Total: 446-447 - Utility Charges	$873,953.14	$0.00
492-493 - Reimbursements			
4922	Property Damage Reimbursements	540.00	0.00
	Account Classification Total: 492-493 - Reimbursements	$540.00	$0.00
	Department Total: 000 - General	$874,493.14	$0.00
Department: 735 - Water Division			
433 - Intergovernmental-State			
4335	Grants/Aid	40,000.00	0.00
	Account Classification Total: 433 - Intergovernmental-State	$40,000.00	$0.00
446-447 - Utility Charges			
4460	Utility Charges	7,534,108.02	0.00
4461	Capacity Charges	416,275.50	0.00
4463	Meter Sales	89,386.10	0.00
4464	Utility Licenses	525.00	0.00
4465	Fireline Charges	18,692.50	0.00
4468	Bulk Sales	300.00	0.00
	Account Classification Total: 446-447 - Utility Charges	$8,059,287.12	$0.00
461-462 - Other Revenues			
4469	Utility Permits	4,416.00	0.00
4479	Miscellaneous	3,540.00	0.00
4992	Consumer on Account	(103,044.34)	0.00
	Account Classification Total: 461-462 - Other Revenues	($95,088.34)	$0.00
492-493 - Reimbursements			
4921	Reimbursements -Regular	1,588.26	0.00
	Account Classification Total: 492-493 - Reimbursements	$1,588.26	$0.00
	Department Total: 735 - Water Division	$8,005,787.04	$0.00
	REVENUES Total	$8,880,280.18	$0.00
EXPENSES			
Department: 000 - General			
Project: 0194 - Combined Public Service Bldg			
5600 - Capital Purchases			
5621	Water Lines	20,000.00	0.00
	Account Classification Total: 5600 - Capital Purchases	$20,000.00	$0.00
	Project Total: 0194 - Combined Public Service Bldg	$20,000.00	$0.00
Project: 0196 - 2023 Water Line Replacement			
5600 - Capital Purchases			
5621	Water Lines	946.37	0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 5600 - Capital Purchases	$946.37	$0.00
	Project Total: 0196 - 2023 Water Line Replacement	$946.37	$0.00
Project:	**0198 - Waggoner Rd Improvement Phase 1**		
5600 - Capital Purchases			
5621	Water Lines	273,378.20	0.00
	Account Classification Total: 5600 - Capital Purchases	$273,378.20	$0.00
	Project Total: 0198 - Waggoner Rd Improvement Phase 1	$273,378.20	$0.00
	Department Total: 000 - General	$294,324.57	$0.00
Department:	**735 - Water Division**		
5100 - Personal Services			
5101	Salary-Elected Officials/Director	41,690.14	49,380.00
5102	Wages-Staff	285,747.86	451,781.00
5105	Overtime	5,591.46	15,400.00
5106	Longevity	2,425.00	2,925.00
5109	HSA Employer Funding	18,166.67	28,350.00
5151	PERS Contribution	36,542.77	74,128.00
5161	Group Insurance	54,842.58	122,113.00
5164	Workers Compensation	8,822.00	11,192.00
5166	Medicare	4,696.85	7,678.00
	Account Classification Total: 5100 - Personal Services	$458,525.33	$762,947.00
5200 - Supplies			
5201	Office Supplies	12,577.62	17,000.00
5203	Computer Supplies	0.00	7,500.00
5213	Repair and Maintenance Supplies	4,942.88	15,000.00
5241	Uniforms-Purchased	5,737.53	14,000.00
5251	MV Gas and Oil	7,113.61	15,000.00
5252	Aggregates	28,534.91	65,000.00
5259	Operating Materials and Supplies	117,368.42	160,000.00
5263	Meters-Resale	0.00	20,000.00
	Account Classification Total: 5200 - Supplies	$176,274.97	$313,500.00
5300 - Services			
5311	Utilities	23,570.46	30,000.00
5321	Professional Training	2,237.05	17,000.00
5322	Conference/Reimb	1,466.26	5,000.00
5323	Publications	8,988.00	10,000.00
5324	Professional Association Dues	0.00	5,000.00
5325	Educational Assistance	1,045.12	1,000.00
5331	Engineering/Architecture	2,370.30	20,000.00
5339	Misc Contract Services	404,126.10	55,000.00
5351	Liability Insurance Deductible	0.00	4,500.00
5352	Motor Vehicle Insurance	4,430.00	2,750.00
5361	Building Repair/Maintenance	0.00	2,000.00
5362	Equipment Maintenance	921.61	15,000.00
5363	MV Repair/Maintenance-External	0.00	2,500.00
5364	MV Repair/Maintenance-Internal	0.00	8,500.00
5365	Utility Line Repair/Maintenance	0.00	35,000.00
5366	Computer Maintenance	0.00	5,000.00
5378	Columbus Contract	6,480,605.16	7,828,120.00
5379	Other Governmental Billings	0.00	10,000.00
5391	Postage	1,977.14	15,000.00
5399	Other Miscellaneous Services	120,059.22	520,000.00
	Account Classification Total: 5300 - Services	$7,051,796.42	$8,591,370.00
5600 - Capital Purchases			
5611	Buildings	0.00	37,500.00
5631	Furniture and Fixtures	0.00	1,000.00
5632	Motor Vehicles	29,855.50	300,000.00
5633	Machinery and Equipment	195,305.98	450,000.00
5639	Other Equipment	0.00	250,000.00
	Account Classification Total: 5600 - Capital Purchases	$225,161.48	$1,038,500.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Department Total: 735 - Water Division	$7,911,758.20	$10,706,317.00
Department:	**991 - Debt Service**		
5400 - Debt Service			
5424	G. O. Bond-Interest	149,770.59	0.00
	Account Classification Total: 5400 - Debt Service	$149,770.59	$0.00
	Department Total: 991 - Debt Service	$149,770.59	$0.00
	EXPENSES Total	$8,355,853.36	$10,706,317.00
	Fund REVENUE Total: 710 - Water Fund	$8,880,280.18	$0.00
	Fund EXPENSE Total: 710 - Water Fund	$8,355,853.36	$10,706,317.00
	Fund Total: 710 - Water Fund	$524,426.82	($10,706,317.00)
Fund:	**720 - Wastewater/Sewer Fund**		
REVENUES			
Department:	**000 - General**		
446-447 - Utility Charges			
4470	Utility CIP Fee	510,586.69	0.00
	Account Classification Total: 446-447 - Utility Charges	$510,586.69	$0.00
499 - Transfers/Advances			
4990	Operating Transfers	45,000.00	0.00
	Account Classification Total: 499 - Transfers/Advances	$45,000.00	$0.00
	Department Total: 000 - General	$555,586.69	$0.00
Department:	**736 - Wastewater Division**		
446-447 - Utility Charges			
4460	Utility Charges	7,591,429.11	0.00
4464	Utility Licenses	275.00	0.00
	Account Classification Total: 446-447 - Utility Charges	$7,591,704.11	$0.00
461-462 - Other Revenues			
4469	Utility Permits	4,475.00	0.00
4479	Miscellaneous	3,275.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$7,750.00	$0.00
492-493 - Reimbursements			
4921	Reimbursements -Regular	1,588.26	0.00
	Account Classification Total: 492-493 - Reimbursements	$1,588.26	$0.00
499 - Transfers/Advances			
4990	Operating Transfers	3,277,933.60	0.00
	Account Classification Total: 499 - Transfers/Advances	$3,277,933.60	$0.00
	Department Total: 736 - Wastewater Division	$10,878,975.97	$0.00
	REVENUES Total	$11,434,562.66	$0.00
EXPENSES			
Department:	**000 - General**		
Project:	**0146 - 2015 Sanitary Sewer Rehab Projec**		
5600 - Capital Purchases			
5622	Sewer Lines	2,216,474.30	0.00
	Account Classification Total: 5600 - Capital Purchases	$2,216,474.30	$0.00
	Project Total: 0146 - 2015 Sanitary Sewer Rehab Projec	$2,216,474.30	$0.00
Project:	**0195 - 2023 Sewer Rehabilitation**		
5600 - Capital Purchases			
5622	Sewer Lines	3,242.63	0.00
	Account Classification Total: 5600 - Capital Purchases	$3,242.63	$0.00
	Project Total: 0195 - 2023 Sewer Rehabilitation	$3,242.63	$0.00
Project:	**0200 - Birchview Drive**		
5600 - Capital Purchases			
5622	Sewer Lines	228,979.46	0.00
	Account Classification Total: 5600 - Capital Purchases	$228,979.46	$0.00
	Project Total: 0200 - Birchview Drive	$228,979.46	$0.00
Project:	**0204 - 2025 Manhole Inspections Project**		
5600 - Capital Purchases			
5622	Sewer Lines	40,972.53	0.00
	Account Classification Total: 5600 - Capital Purchases	$40,972.53	$0.00
	Project Total: 0204 - 2025 Manhole Inspections Project	$40,972.53	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Department Total: 000 - General	$2,489,668.92	$0.00
Department:	**736 - Wastewater Division**		
5100 - Personal Services			
5101	Salary-Elected Officials/Director	41,690.10	49,380.00
5102	Wages-Staff	252,052.64	432,432.00
5105	Overtime	21,088.81	3,500.00
5106	Longevity	1,225.00	1,525.00
5109	HSA Employer Funding	14,333.33	30,450.00
5151	PERS Contribution	36,995.64	68,157.00
5161	Group Insurance	47,023.67	153,114.00
5164	Workers Compensation	8,028.00	10,290.00
5166	Medicare	4,413.54	7,059.00
	Account Classification Total: 5100 - Personal Services	$426,850.73	$755,907.00
5200 - Supplies			
5201	Office Supplies	13,618.49	15,000.00
5203	Computer Supplies	0.00	14,000.00
5213	Repair and Maintenance Supplies	6,625.74	10,000.00
5241	Uniforms-Purchased	5,737.53	10,000.00
5251	MV Gas and Oil	7,113.65	18,000.00
5252	Aggregates	0.00	5,000.00
5259	Operating Materials and Supplies	34,704.33	100,000.00
	Account Classification Total: 5200 - Supplies	$67,799.74	$172,000.00
5300 - Services			
5311	Utilities	11,923.12	25,000.00
5321	Professional Training	1,767.05	6,500.00
5322	Conference/Reimb	1,009.31	6,500.00
5324	Professional Association Dues	0.00	4,000.00
5325	Educational Assistance	1,045.13	2,000.00
5331	Engineering/Architecture	1,100.00	20,000.00
5339	Misc Contract Services	326,941.52	50,000.00
5351	Liability Insurance Deductible	0.00	1,750.00
5352	Motor Vehicle Insurance	4,833.00	3,000.00
5361	Building Repair/Maintenance	0.00	9,000.00
5362	Equipment Maintenance	921.61	7,500.00
5363	MV Repair/Maintenance-External	0.00	2,500.00
5364	MV Repair/Maintenance-Internal	0.00	6,000.00
5365	Utility Line Repair/Maintenance	0.00	130,000.00
5366	Computer Maintenance	0.00	18,000.00
5378	Columbus Contract	6,192,508.60	7,040,520.00
5391	Postage	0.00	15,000.00
5399	Other Miscellaneous Services	12,369.05	370,000.00
	Account Classification Total: 5300 - Services	$6,554,418.39	$7,717,270.00
5600 - Capital Purchases			
5611	Buildings	0.00	25,000.00
5631	Furniture and Fixtures	0.00	1,000.00
5632	Motor Vehicles	29,855.50	350,000.00
5633	Machinery and Equipment	174,311.02	250,000.00
5639	Other Equipment	0.00	250,000.00
	Account Classification Total: 5600 - Capital Purchases	$204,166.52	$876,000.00
	Department Total: 736 - Wastewater Division	$7,253,235.38	$9,521,177.00
Department:	**991 - Debt Service**		
5400 - Debt Service			
5424	G. O. Bond-Interest	146,098.09	0.00
	Account Classification Total: 5400 - Debt Service	$146,098.09	$0.00
	Department Total: 991 - Debt Service	$146,098.09	$0.00
	EXPENSES Total	$9,889,002.39	$9,521,177.00
	Fund REVENUE Total: 720 - Wastewater/Sewer Fund	$11,434,562.66	$0.00
	Fund EXPENSE Total: 720 - Wastewater/Sewer Fund	$9,889,002.39	$9,521,177.00
	Fund Total: 720 - Wastewater/Sewer Fund	$1,545,560.27	($9,521,177.00)

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
Fund: 730 - Utility Deposits Fund			
REVENUES			
Department: 735 - Water Division			
461-462 - Other Revenues			
4620	Consumer Deposits	225.00	0.00
	Account Classification Total: 461-462 - Other Revenues	$225.00	$0.00
	Department Total: 735 - Water Division	$225.00	$0.00
	REVENUES Total	$225.00	$0.00
	Fund REVENUE Total: 730 - Utility Deposits Fund	$225.00	$0.00
	Fund EXPENSE Total: 730 - Utility Deposits Fund		
	Fund Total: 730 - Utility Deposits Fund	$225.00	$0.00
Fund: 740 - Storm Water Drainage Fund			
REVENUES			
Department: 737 - Storm Water Division			
446-447 - Utility Charges			
4472	ERU Charges	2,007,554.19	0.00
	Account Classification Total: 446-447 - Utility Charges	$2,007,554.19	$0.00
492-493 - Reimbursements			
4921	Reimbursements -Regular	1,058.84	0.00
	Account Classification Total: 492-493 - Reimbursements	$1,058.84	$0.00
	Department Total: 737 - Storm Water Division	$2,008,613.03	$0.00
	REVENUES Total	$2,008,613.03	$0.00
EXPENSES			
Department: 737 - Storm Water Division			
5100 - Personal Services			
5102	Wages-Staff	218,722.89	275,656.00
5105	Overtime	11,717.00	4,900.00
5106	Longevity	1,850.00	2,250.00
5109	HSA Employer Funding	8,000.00	12,600.00
5151	PERS Contribution	26,660.00	39,243.00
5161	Group Insurance	26,394.68	67,032.00
5164	Workers Compensation	5,220.00	0.00
5166	Medicare	3,283.13	4,101.00
	Account Classification Total: 5100 - Personal Services	$301,847.70	$405,782.00
5200 - Supplies			
5201	Office Supplies	629.29	6,500.00
5203	Computer Supplies	400.00	750.00
5205	Small Tools/Minor Equipment	0.00	1,500.00
5241	Uniforms-Purchased	9,897.48	2,500.00
5251	MV Gas and Oil	6,201.35	12,500.00
5252	Aggregates	231.00	1,250.00
5259	Operating Materials and Supplies	17,471.50	47,000.00
	Account Classification Total: 5200 - Supplies	$34,830.62	$72,000.00
5300 - Services			
5311	Utilities	3,798.13	11,000.00
5321	Professional Training	2,654.75	5,000.00
5322	Conference/Reimb	1,904.58	3,000.00
5324	Professional Association Dues	35.00	220.00
5331	Engineering/Architecture	2,219.84	8,000.00
5339	Misc Contract Services	42,235.20	59,000.00
5351	Liability Insurance Deductible	0.00	2,500.00
5352	Motor Vehicle Insurance	4,430.00	2,750.00
5361	Building Repair/Maintenance	0.00	4,000.00
5364	MV Repair/Maintenance-Internal	0.00	3,500.00
5365	Utility Line Repair/Maintenance	0.00	7,500.00
5378	Columbus Contract	932,248.68	1,320,000.00
5391	Postage	0.00	22,000.00
5397	Uniform Rental	0.00	2,000.00
5399	Other Miscellaneous Services	4,442.45	41,000.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Account Classification Total: 5300 - Services	$993,968.63	$1,491,470.00
5600 - Capital Purchases			
5632	Motor Vehicles	0.00	120,000.00
5633	Machinery and Equipment	0.00	134,250.00
	Account Classification Total: 5600 - Capital Purchases	$0.00	$254,250.00
	Department Total: 737 - Storm Water Division	$1,330,646.95	$2,223,502.00
Department: 991 - Debt Service			
5400 - Debt Service			
5424	G. O. Bond-Interest	148,810.09	0.00
	Account Classification Total: 5400 - Debt Service	$148,810.09	$0.00
	Department Total: 991 - Debt Service	$148,810.09	$0.00
	EXPENSES Total	$1,479,457.04	$2,223,502.00
	Fund REVENUE Total: 740 - Storm Water Drainage Fund	$2,008,613.03	$0.00
	Fund EXPENSE Total: 740 - Storm Water Drainage Fund	$1,479,457.04	$2,223,502.00
	Fund Total: 740 - Storm Water Drainage Fund	$529,155.99	($2,223,502.00)
Fund: 750 - Solid Waste Fund			
REVENUES			
Department: 738 - Refuse Collection			
446-447 - Utility Charges			
4471	Residential Charges	2,394,040.32	0.00
	Account Classification Total: 446-447 - Utility Charges	$2,394,040.32	$0.00
461-462 - Other Revenues			
4479	Miscellaneous	247.72	0.00
	Account Classification Total: 461-462 - Other Revenues	$247.72	$0.00
	Department Total: 738 - Refuse Collection	$2,394,288.04	$0.00
	REVENUES Total	$2,394,288.04	$0.00
EXPENSES			
Department: 738 - Refuse Collection			
5300 - Services			
5315	Private Hauler Contract	2,353,016.10	2,700,000.00
5391	Postage	0.00	5,000.00
5399	Other Miscellaneous Services	3,842.45	60,000.00
	Account Classification Total: 5300 - Services	$2,356,858.55	$2,765,000.00
	Department Total: 738 - Refuse Collection	$2,356,858.55	$2,765,000.00
	EXPENSES Total	$2,356,858.55	$2,765,000.00
	Fund REVENUE Total: 750 - Solid Waste Fund	$2,394,288.04	$0.00
	Fund EXPENSE Total: 750 - Solid Waste Fund	$2,356,858.55	$2,765,000.00
	Fund Total: 750 - Solid Waste Fund	$37,429.49	($2,765,000.00)
Fund: 910 - Miscellaneous Agency			
REVENUES			
Department: 000 - General			
492-493 - Reimbursements			
4929	Miscellaneous Reimbursements	10,038.48	0.00
4939	Miscellaneous Agency Receipts	293,214.82	0.00
	Account Classification Total: 492-493 - Reimbursements	$303,253.30	$0.00
	Department Total: 000 - General	$303,253.30	$0.00
Department: 343 - Senior Center			
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	28,836.00	0.00
	Account Classification Total: 492-493 - Reimbursements	$28,836.00	$0.00
	Department Total: 343 - Senior Center	$28,836.00	$0.00
	REVENUES Total	$332,089.30	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5520	Insurance Payments-Co-pay	248,520.30	0.00
5529	Miscellaneous Distributions	8,801.67	0.00
	Account Classification Total: 5500 - Transfers/Other	$257,321.97	$0.00
	Department Total: 000 - General	$257,321.97	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
Department: 343 - Senior Center			
5500 - Transfers/Other			
5527	Agency/Tief Distributions	17,923.31	0.00
	Account Classification Total: 5500 - Transfers/Other	$17,923.31	$0.00
	Department Total: 343 - Senior Center	$17,923.31	$0.00
	EXPENSES Total	$275,245.28	$0.00
	Fund REVENUE Total: 910 - Miscellaneous Agency	$332,089.30	$0.00
	Fund EXPENSE Total: 910 - Miscellaneous Agency	$275,245.28	$0.00
	Fund Total: 910 - Miscellaneous Agency	$56,844.02	$0.00
Fund: 915 - Board of Building Standards			
REVENUES			
Department: 000 - General			
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	13,922.32	0.00
	Account Classification Total: 492-493 - Reimbursements	$13,922.32	$0.00
	Department Total: 000 - General	$13,922.32	$0.00
	REVENUES Total	$13,922.32	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5527	Agency/Tief Distributions	14,272.80	0.00
	Account Classification Total: 5500 - Transfers/Other	$14,272.80	$0.00
	Department Total: 000 - General	$14,272.80	$0.00
	EXPENSES Total	$14,272.80	$0.00
	Fund REVENUE Total: 915 - Board of Building Standards	$13,922.32	$0.00
	Fund EXPENSE Total: 915 - Board of Building Standards	$14,272.80	$0.00
	Fund Total: 915 - Board of Building Standards	($350.48)	$0.00
Fund: 920 - Visitors Bureau Fund			
REVENUES			
Department: 000 - General			
413 - Other Local Taxes			
4131	Hotel Motel Tax	148,648.30	0.00
	Account Classification Total: 413 - Other Local Taxes	$148,648.30	$0.00
	Department Total: 000 - General	$148,648.30	$0.00
	REVENUES Total	$148,648.30	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5527	Agency/Tief Distributions	151,638.57	0.00
	Account Classification Total: 5500 - Transfers/Other	$151,638.57	$0.00
	Department Total: 000 - General	$151,638.57	$0.00
	EXPENSES Total	$151,638.57	$0.00
	Fund REVENUE Total: 920 - Visitors Bureau Fund	$148,648.30	$0.00
	Fund EXPENSE Total: 920 - Visitors Bureau Fund	$151,638.57	$0.00
	Fund Total: 920 - Visitors Bureau Fund	($2,990.27)	$0.00
Fund: 925 - Demolition Expense Fund			
REVENUES			
Department: 000 - General			
441-442 - Miscellaneous Charges for Services			
4621	Other Deposits	179,792.70	0.00
	Account Classification Total: 441-442 - Miscellaneous Charges for Services	$179,792.70	$0.00
	Department Total: 000 - General	$179,792.70	$0.00
	REVENUES Total	$179,792.70	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5512	Deposit Refunds	33,507.37	0.00
	Account Classification Total: 5500 - Transfers/Other	$33,507.37	$0.00

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Department Total: 000 - General	$33,507.37	$0.00
	EXPENSES Total	$33,507.37	$0.00
	Fund REVENUE Total: 925 - Demolition Expense Fund	$179,792.70	$0.00
	Fund EXPENSE Total: 925 - Demolition Expense Fund	$33,507.37	$0.00
	Fund Total: 925 - Demolition Expense Fund	$146,285.33	$0.00
Fund: 930 - Columbus Sewer Capacity			
REVENUES			
Department: 000 - General			
446-447 - Utility Charges			
4461	Capacity Charges	729,259.50	0.00
	Account Classification Total: 446-447 - Utility Charges	$729,259.50	$0.00
	Department Total: 000 - General	$729,259.50	$0.00
	REVENUES Total	$729,259.50	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5527	Agency/Tief Distributions	614,888.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$614,888.00	$0.00
	Department Total: 000 - General	$614,888.00	$0.00
	EXPENSES Total	$614,888.00	$0.00
	Fund REVENUE Total: 930 - Columbus Sewer Capacity	$729,259.50	$0.00
	Fund EXPENSE Total: 930 - Columbus Sewer Capacity	$614,888.00	$0.00
	Fund Total: 930 - Columbus Sewer Capacity	$114,371.50	$0.00
Fund: 941 - JEDD1-ETNA-REYNOLDSBURG			
REVENUES			
Department: 000 - General			
460 - Investment Earnings			
4601	Interest Earnings	839.33	0.00
	Account Classification Total: 460 - Investment Earnings	$839.33	$0.00
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	430,213.22	0.00
	Account Classification Total: 492-493 - Reimbursements	$430,213.22	$0.00
	Department Total: 000 - General	$431,052.55	$0.00
	REVENUES Total	$431,052.55	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5529	Miscellaneous Distributions	709,365.47	700,000.00
	Account Classification Total: 5500 - Transfers/Other	$709,365.47	$700,000.00
	Department Total: 000 - General	$709,365.47	$700,000.00
	EXPENSES Total	$709,365.47	$700,000.00
	Fund REVENUE Total: 941 - JEDD1-ETNA-REYNOLDSBURG	$431,052.55	$0.00
	Fund EXPENSE Total: 941 - JEDD1-ETNA-REYNOLDSBURG	$709,365.47	$700,000.00
	Fund Total: 941 - JEDD1-ETNA-REYNOLDSBURG	($278,312.92)	($700,000.00)
Fund: 942 - JEDD2-ETNA-REYNOLDSBURG			
REVENUES			
Department: 000 - General			
460 - Investment Earnings			
4601	Interest Earnings	6.39	0.00
	Account Classification Total: 460 - Investment Earnings	$6.39	$0.00
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	144,910.10	0.00
	Account Classification Total: 492-493 - Reimbursements	$144,910.10	$0.00
	Department Total: 000 - General	$144,916.49	$0.00
	REVENUES Total	$144,916.49	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
5529	Miscellaneous Distributions	354,622.10	225,000.00
	Account Classification Total: 5500 - Transfers/Other	$354,622.10	$225,000.00
	Department Total: 000 - General	$354,622.10	$225,000.00
	EXPENSES Total	$354,622.10	$225,000.00
	Fund REVENUE Total: 942 - JEDD2-ETNA-REYNOLDSBURG	$144,916.49	$0.00
	Fund EXPENSE Total: 942 - JEDD2-ETNA-REYNOLDSBURG	$354,622.10	$225,000.00
	Fund Total: 942 - JEDD2-ETNA-REYNOLDSBURG	($209,705.61)	($225,000.00)
Fund: 943 - JEDD3-ETNA-REYNOLDSBURG			
REVENUES			
Department: 000 - General			
460 - Investment Earnings			
4601	Interest Earnings	20.44	0.00
	Account Classification Total: 460 - Investment Earnings	$20.44	$0.00
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	370,087.81	0.00
	Account Classification Total: 492-493 - Reimbursements	$370,087.81	$0.00
	Department Total: 000 - General	$370,108.25	$0.00
	REVENUES Total	$370,108.25	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5529	Miscellaneous Distributions	678,570.63	643,000.00
	Account Classification Total: 5500 - Transfers/Other	$678,570.63	$643,000.00
	Department Total: 000 - General	$678,570.63	$643,000.00
	EXPENSES Total	$678,570.63	$643,000.00
	Fund REVENUE Total: 943 - JEDD3-ETNA-REYNOLDSBURG	$370,108.25	$0.00
	Fund EXPENSE Total: 943 - JEDD3-ETNA-REYNOLDSBURG	$678,570.63	$643,000.00
	Fund Total: 943 - JEDD3-ETNA-REYNOLDSBURG	($308,462.38)	($643,000.00)
Fund: 944 - JEDD4-ETNA-REYNOLDSBURG			
REVENUES			
Department: 000 - General			
460 - Investment Earnings			
4601	Interest Earnings	0.03	0.00
	Account Classification Total: 460 - Investment Earnings	$0.03	$0.00
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	131,021.03	0.00
	Account Classification Total: 492-493 - Reimbursements	$131,021.03	$0.00
	Department Total: 000 - General	$131,021.06	$0.00
	REVENUES Total	$131,021.06	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5529	Miscellaneous Distributions	227,522.17	200,000.00
	Account Classification Total: 5500 - Transfers/Other	$227,522.17	$200,000.00
	Department Total: 000 - General	$227,522.17	$200,000.00
	EXPENSES Total	$227,522.17	$200,000.00
	Fund REVENUE Total: 944 - JEDD4-ETNA-REYNOLDSBURG	$131,021.06	$0.00
	Fund EXPENSE Total: 944 - JEDD4-ETNA-REYNOLDSBURG	$227,522.17	$200,000.00
	Fund Total: 944 - JEDD4-ETNA-REYNOLDSBURG	($96,501.11)	($200,000.00)
Fund: 947 - JEDD 7- REYNOLDSBURG-ETNA			
REVENUES			
Department: 000 - General			
492-493 - Reimbursements			
4939	Miscellaneous Agency Receipts	177,932.57	0.00
	Account Classification Total: 492-493 - Reimbursements	$177,932.57	$0.00
	Department Total: 000 - General	$177,932.57	$0.00
	REVENUES Total	$177,932.57	$0.00
EXPENSES			


Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
Department: 000 - General			
5500 - Transfers/Other			
5529	Miscellaneous Distributions	299,463.49	330,000.00
	Account Classification Total: 5500 - Transfers/Other	$299,463.49	$330,000.00
	Department Total: 000 - General	$299,463.49	$330,000.00
	EXPENSES Total	$299,463.49	$330,000.00
	Fund REVENUE Total: 947 - JEDD 7- REYNOLDSBURG-ETNA	$177,932.57	$0.00
	Fund EXPENSE Total: 947 - JEDD 7- REYNOLDSBURG-ETNA	$299,463.49	$330,000.00
	Fund Total: 947 - JEDD 7- REYNOLDSBURG-ETNA	($121,530.92)	($330,000.00)
Fund: 960 - Eng Fees/Plan Review Deposits			
REVENUES			
Department: 000 - General			
492-493 - Reimbursements			
4929	Miscellaneous Reimbursements	11,000.00	0.00
4939	Miscellaneous Agency Receipts	55,577.60	0.00
	Account Classification Total: 492-493 - Reimbursements	$66,577.60	$0.00
	Department Total: 000 - General	$66,577.60	$0.00
	REVENUES Total	$66,577.60	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5527	Agency/Tief Distributions	43,765.00	0.00
5529	Miscellaneous Distributions	10,750.00	0.00
	Account Classification Total: 5500 - Transfers/Other	$54,515.00	$0.00
	Department Total: 000 - General	$54,515.00	$0.00
	EXPENSES Total	$54,515.00	$0.00
	Fund REVENUE Total: 960 - Eng Fees/Plan Review Deposits	$66,577.60	$0.00
	Fund EXPENSE Total: 960 - Eng Fees/Plan Review Deposits	$54,515.00	$0.00
	Fund Total: 960 - Eng Fees/Plan Review Deposits	$12,062.60	$0.00
Fund: 970 - Taylor Sq School Tief			
REVENUES			
Department: 000 - General			
Project: 0002 - Phase II			
465 - Tief Receipts			
4651	Tief Receipts	1,761,943.57	0.00
	Account Classification Total: 465 - Tief Receipts	$1,761,943.57	$0.00
	Project Total: 0002 - Phase II	$1,761,943.57	$0.00
	Department Total: 000 - General	$1,761,943.57	$0.00
	REVENUES Total	$1,761,943.57	$0.00
EXPENSES			
Department: 000 - General			
Project: 0002 - Phase II			
5300 - Services			
5373	Auditor/Treasurer Fees	27,392.18	0.00
	Account Classification Total: 5300 - Services	$27,392.18	$0.00
5500 - Transfers/Other			
5527	Agency/Tief Distributions	2,078,429.61	0.00
	Account Classification Total: 5500 - Transfers/Other	$2,078,429.61	$0.00
	Project Total: 0002 - Phase II	$2,105,821.79	$0.00
	Department Total: 000 - General	$2,105,821.79	$0.00
	EXPENSES Total	$2,105,821.79	$0.00
	Fund REVENUE Total: 970 - Taylor Sq School Tief	$1,761,943.57	$0.00
	Fund EXPENSE Total: 970 - Taylor Sq School Tief	$2,105,821.79	$0.00
	Fund Total: 970 - Taylor Sq School Tief	($343,878.22)	$0.00
Fund: 971 - Brice Main Tif			
REVENUES			
Department: 000 - General			
Project: 4001 - Tief-Home Depot			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
465 - Tief Receipts			
4651	Tief Receipts	158,874.20	0.00
	Account Classification Total: 465 - Tief Receipts	$158,874.20	$0.00
	Project Total: 4001 - Tief-Home Depot	$158,874.20	$0.00
Project: 4002 - Tief-Walgreens			
465 - Tief Receipts			
4651	Tief Receipts	(23,491.30)	0.00
	Account Classification Total: 465 - Tief Receipts	($23,491.30)	$0.00
	Project Total: 4002 - Tief-Walgreens	($23,491.30)	$0.00
	Department Total: 000 - General	$135,382.90	$0.00
	REVENUES Total	$135,382.90	$0.00
EXPENSES			
Department: 000 - General			
5500 - Transfers/Other			
5527	Agency/Tief Distributions	248,895.88	0.00
	Account Classification Total: 5500 - Transfers/Other	$248,895.88	$0.00
Project: 4001 - Tief-Home Depot			
5300 - Services			
5373	Auditor/Treasurer Fees	1,790.75	0.00
	Account Classification Total: 5300 - Services	$1,790.75	$0.00
	Project Total: 4001 - Tief-Home Depot	$1,790.75	$0.00
Project: 4002 - Tief-Walgreens			
5300 - Services			
5373	Auditor/Treasurer Fees	330.37	0.00
	Account Classification Total: 5300 - Services	$330.37	$0.00
	Project Total: 4002 - Tief-Walgreens	$330.37	$0.00
	Department Total: 000 - General	$251,017.00	$0.00
	EXPENSES Total	$251,017.00	$0.00
	Fund REVENUE Total: 971 - Brice Main Tif	$135,382.90	$0.00
	Fund EXPENSE Total: 971 - Brice Main Tif	$251,017.00	$0.00
	Fund Total: 971 - Brice Main Tif	($115,634.10)	$0.00
Fund: 973 - Summit Rd Tif #1			
REVENUES			
Department: 000 - General			
Project: 4003 - Tief-Summit Place			
465 - Tief Receipts			
4651	Tief Receipts	54,065.45	0.00
	Account Classification Total: 465 - Tief Receipts	$54,065.45	$0.00
	Project Total: 4003 - Tief-Summit Place	$54,065.45	$0.00
Project: 4004 - Tief-Maple Wood Farms			
465 - Tief Receipts			
4651	Tief Receipts	23,401.86	0.00
	Account Classification Total: 465 - Tief Receipts	$23,401.86	$0.00
	Project Total: 4004 - Tief-Maple Wood Farms	$23,401.86	$0.00
	Department Total: 000 - General	$77,467.31	$0.00
	REVENUES Total	$77,467.31	$0.00
EXPENSES			
Department: 000 - General			
Project: 4000 - Tief-General			
5300 - Services			
5373	Auditor/Treasurer Fees	954.05	0.00
	Account Classification Total: 5300 - Services	$954.05	$0.00
	Project Total: 4000 - Tief-General	$954.05	$0.00
	Department Total: 000 - General	$954.05	$0.00
	EXPENSES Total	$954.05	$0.00
	Fund REVENUE Total: 973 - Summit Rd Tif #1	$77,467.31	$0.00
	Fund EXPENSE Total: 973 - Summit Rd Tif #1	$954.05	$0.00
	Fund Total: 973 - Summit Rd Tif #1	$76,513.26	$0.00
Fund: 974 - Taylor Rd Tif #1			

Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
REVENUES			
Department: 000 - General			
Project: 4006 - Tief-Taylor Chase			
465 - Tief Receipts			
4651	Tief Receipts	103,150.06	0.00
	Account Classification Total: 465 - Tief Receipts	$103,150.06	$0.00
	Project Total: 4006 - Tief-Taylor Chase	$103,150.06	$0.00
	Department Total: 000 - General	$103,150.06	$0.00
	REVENUES Total	$103,150.06	$0.00
EXPENSES			
Department: 000 - General			
Project: 4000 - Tief-General			
5300 - Services			
5373	Auditor/Treasurer Fees	1,394.68	0.00
	Account Classification Total: 5300 - Services	$1,394.68	$0.00
	Project Total: 4000 - Tief-General	$1,394.68	$0.00
	Department Total: 000 - General	$1,394.68	$0.00
	EXPENSES Total	$1,394.68	$0.00
	Fund REVENUE Total: 974 - Taylor Rd Tif #1	$103,150.06	$0.00
	Fund EXPENSE Total: 974 - Taylor Rd Tif #1	$1,394.68	$0.00
	Fund Total: 974 - Taylor Rd Tif #1	$101,755.38	$0.00
Fund: 975 - Taylor Rd Tif #2			
REVENUES			
Department: 000 - General			
Project: 4005 - Tief-Glen O Bard Jr			
465 - Tief Receipts			
4651	Tief Receipts	35,097.04	0.00
	Account Classification Total: 465 - Tief Receipts	$35,097.04	$0.00
	Project Total: 4005 - Tief-Glen O Bard Jr	$35,097.04	$0.00
	Department Total: 000 - General	$35,097.04	$0.00
	REVENUES Total	$35,097.04	$0.00
EXPENSES			
Department: 000 - General			
Project: 4000 - Tief-General			
5300 - Services			
5373	Auditor/Treasurer Fees	434.57	0.00
	Account Classification Total: 5300 - Services	$434.57	$0.00
	Project Total: 4000 - Tief-General	$434.57	$0.00
	Department Total: 000 - General	$434.57	$0.00
	EXPENSES Total	$434.57	$0.00
	Fund REVENUE Total: 975 - Taylor Rd Tif #2	$35,097.04	$0.00
	Fund EXPENSE Total: 975 - Taylor Rd Tif #2	$434.57	$0.00
	Fund Total: 975 - Taylor Rd Tif #2	$34,662.47	$0.00
Fund: 976 - Broad Street TIF			
REVENUES			
Department: 000 - General			
Project: 4000 - Tief-General			
465 - Tief Receipts			
4651	Tief Receipts	322,878.01	0.00
	Account Classification Total: 465 - Tief Receipts	$322,878.01	$0.00
	Project Total: 4000 - Tief-General	$322,878.01	$0.00
	Department Total: 000 - General	$322,878.01	$0.00
	REVENUES Total	$322,878.01	$0.00
EXPENSES			
Department: 000 - General			
Project: 4000 - Tief-General			
5300 - Services			
5373	Auditor/Treasurer Fees	3,664.84	0.00
	Account Classification Total: 5300 - Services	$3,664.84	$0.00


Account Number	Account Description	2025 Actual Amount	2026 Mayor's Budget
	Project Total: 4000 - Tief-General	$3,664.84	$0.00
	Department Total: 000 - General	$3,664.84	$0.00
	EXPENSES Total	$3,664.84	$0.00
	Fund REVENUE Total: 976 - Broad Street TIF	$322,878.01	$0.00
	Fund EXPENSE Total: 976 - Broad Street TIF	$3,664.84	$0.00
	Fund Total: 976 - Broad Street TIF	$319,213.17	$0.00
Fund: 977 - 2018 Main St/Brice Rd TIF			
REVENUES			
Department: 000 - General			
Project: 4000 - Tief-General			
414-415 - State Levied Shared Taxes			
4141	Real Property Tax-Rollback and Homestead	246.88	0.00
	Account Classification Total: 414-415 - State Levied Shared Taxes	$246.88	$0.00
465 - Tief Receipts			
4651	Tief Receipts	1,540,456.66	0.00
	Account Classification Total: 465 - Tief Receipts	$1,540,456.66	$0.00
	Project Total: 4000 - Tief-General	$1,540,703.54	$0.00
	Department Total: 000 - General	$1,540,703.54	$0.00
	REVENUES Total	$1,540,703.54	$0.00
EXPENSES			
Department: 000 - General			
Project: 4000 - Tief-General			
5300 - Services			
5373	Auditor/Treasurer Fees	23,021.08	0.00
	Account Classification Total: 5300 - Services	$23,021.08	$0.00
5500 - Transfers/Other			
5501	Transfers	1,124,312.50	0.00
	Account Classification Total: 5500 - Transfers/Other	$1,124,312.50	$0.00
	Project Total: 4000 - Tief-General	$1,147,333.58	$0.00
	Department Total: 000 - General	$1,147,333.58	$0.00
	EXPENSES Total	$1,147,333.58	$0.00
	Fund REVENUE Total: 977 - 2018 Main St/Brice Rd TIF	$1,540,703.54	$0.00
	Fund EXPENSE Total: 977 - 2018 Main St/Brice Rd TIF	$1,147,333.58	$0.00
	Fund Total: 977 - 2018 Main St/Brice Rd TIF	$393,369.96	$0.00
	REVENUE GRAND Totals:	$65,169,745.41	$22,000.00
	EXPENSE GRAND Totals:	$88,563,980.88	$69,992,198.00
	Grand Totals:	($23,394,235.47)	($69,970,198.00)


CITY OF REYNOLDSBURG, OHIO



(1) Revenues for 2025 are based on annualized year-to-date data as of 11/24/2025.

CITY OF REYNOLDSBURG, OHIO





(1) Revenues for 2025 are based on 105% of the adopted revenue budget. Expenses are assumed at 90% of the 2025 adopted budget.

(2) Revenues for 2026 are based on 105% of the proposed revenue budget. Expenses are assumed at 90% of the 2026 proposed budget.

CITY OF REYNOLDSBURG, OHIO

BUDGET REVENUE ESTIMATES - *DRAFT #3*
CALENDAR YEAR 2026

Fund	Account Number	Account Description	Method / Assumption	Sum of 2026 Preliminary Budget
110 - General Fund	**110.000.4100**	Income Tax Proceeds	2025 Actuals - 0% growth	$ 22,326,900
	110.000.4110	Real Estate/Pub Util Tax	2025 YTD	459,000
	110.000.4114	Trailer Tax	3 Yr Avg	300
	110.000.4131	Hotel Motel Tax	3 Yr Avg	350,000
	110.000.4133	Cable TV Franchise Tax	3 Yr Avg	216,000
	110.000.4141	Real Property Tax-Rollback and Homestead	2025 Budget	43,000
	110.000.4143	Local Govt-County	3 Yr Avg	720,000
	110.000.4145	Local Govt-State	3 Yr Avg	195,000
	110.000.4147	Cigarette Tax	2025 Budget	1,400
	110.000.4148	Liquor and Beer Permits	2025 Budget	50,000
	110.000.4211	Building Trade License	2025 Budget	55,000
	110.000.4214	Electronic Coin Device License	2025 Budget	3,000
	110.000.4215	Rental Registration License	2025 Budget	3,000
	110.000.4221	Building Permits	3 Yr Avg	408,000
	110.000.4222	Plumbing Permits	3 Yr Avg	185,000
	110.000.4223	Heating Permits	3 Yr Avg	133,000
	110.000.4225	Electrical Permits	3 Yr Avg	92,000
	110.000.4226	Zoning Permits	Historical Trends	80,000
	110.000.4227	Burglar Alarm Permits	2025 Budget	500
	110.000.4228	Sign Permits	Historical Trends	2,000
	110.000.4229	Miscellaneous Permits	3 Yr Avg	1,000
	110.000.4249	Miscellaneous Fees	2025 Budget	100
	110.000.4250	Plan Administration Fees	2025 Budget	25,000
	110.000.4410	Xeroxing	3 Yr Avg	100
	110.000.4417	Weed Cutting	3 Yr Avg	35,000
	110.000.4448	Dedication/Legacy Fees	3 Yr Avg	3,000
	110.000.4449	Recreation Nature Programs	3 Yr Avg	400
	110.000.4450	Recreational Rental Fees	3 Yr Avg	40,000
	110.000.4451	Baseball Fees	3 Yr Avg	12,500
	110.000.4452	Basketball Fees	3 Yr Avg	6,000
	110.000.4453	Tennis Fees	3 Yr Avg	2,000
	110.000.4454	Soccer Fees	3 Yr Avg	48,000
	110.000.4455	Softball Fees	3 Yr Avg	1,700
	110.000.4456	Adult Sports Fees	3 Yr Avg	8,000
	110.000.4457	Arts & Craft Programs	3 Yr Avg	5,000
	110.000.4458	Volleyball Fees	3 Yr Avg	5,000
	110.000.4459	Miscellaneous Recreational Fees	3 Yr Avg	62,000
	110.000.4510	Mayors Court Costs	Historical Trends	135,000
	110.000.4512	Mayors Court-Fines and Forfeitures	Historical Trends	100,000
	110.000.4520	Municipal Court-Fines	Historical Trends	3,000

(Preliminary - Subject to Change)

CITY OF REYNOLDSBURG, OHIO

BUDGET REVENUE ESTIMATES - *DRAFT #3*
CALENDAR YEAR 2026

Fund	Account Number	Account Description	Method / Assumption	Sum of 2026 Preliminary Budget
110 - General Fund	**110.000.4601**	Interest Earnings	80% of 2025 YTD Annualized	$ 1,201,000
	110.000.4612	Rentals	3 Yr Avg	231,000
	110.000.4629	Miscellaneous Revenue	Historical Trends	200,000
	110.000.4648	Community Events Revenue	3 Yr Avg	188,000
	110.000.4649	Contributions	3 Yr Avg	3,000
	110.000.4920	Reimburse Prior Year Expense	2025 Budget	50,000
	110.000.4922	Property Damage Reimbursements	Historical Trends	5,000
	110.000.4941	Sale of Assets	2025 Budget	5,000
	New?	Recreational Marijuana Revenue	State Estimates	700,000
110 - General Fund Total				**$ 28,398,900**
211 - Computerized Needs (courts)	**211.000.4510**	Mayors Court Costs	3 Yr Avg	$ 21,000
211 - Computerized Needs (courts) Total				**$ 21,000**
220 - Income Tax Fund	**220.000.4121**	Municipal Income Tax	2025 Actuals - 0% growth	$ 956,900
	220.000.4601	Interest Earnings	80% of 2025 YTD Annualized	70,000
	220.000.4921	Reimbursements -Regular	3 Yr Avg	600
220 - Income Tax Fund Total				**$ 1,027,500**
230 - Permissive Tax Fund	**230.000.4154**	MV License - Permissive Tax - County	3 Yr Avg	$ 82,000
	230.000.4155	MV License - Permissive Tax - Local	3 Yr Avg	163,000
230 - Permissive Tax Fund Total				**$ 245,000**
240 - Police Pension Fund	**240.000.4110**	Real Estate/Pub Util Tax	2025 YTD	$ 326,000
	240.000.4114	Trailer Tax	3 Yr Avg	200
	240.000.4141	Real Property Tax-Rollback and Homestead	2025 Budget	28,000
240 - Police Pension Fund Total				**$ 354,200**
250 - Sewer Capacity Fund	**250.736.4461**	Capacity Charges	3 Yr Avg	$ 652,000
250 - Sewer Capacity Fund Total				**$ 652,000**
260 - Street Fund	**260.000.4151**	Gasoline Tax	3 Yr Avg	$ 1,604,000
	260.000.4152	MV License - State Registration	3 Yr Avg	180,000
	260.000.4921	Reimbursements -Regular	3 Yr Avg	3,000
	260.000.4922	Property Damage Reimbursements	2025 Budget	12,500
260 - Street Fund Total				**$ 1,799,500**
270 - State Highway Fund	**270.000.4151**	Gasoline Tax	3 Yr Avg	$ 184,000
	270.000.4152	MV License - State Registration	3 Yr Avg	15,000
270 - State Highway Fund Total				**$ 199,000**
287 - Reynoldsburg Recovery Court	**287.000.4939**	Miscellaneous Agency Receipts	3 Yr Avg	$ 19,000
287 - Reynoldsburg Recovery Court Total				**$ 19,000**
290 - Law Enforcement Fund	**290.111.4616**	Proceeds for Police Special Revenue Funds	3 Yr Avg	$ 48,000
290 - Law Enforcement Fund Total				**$ 48,000**
291 - Drug Enforcement Fund	**291.111.4616**	Proceeds for Police Special Revenue Funds	3 Yr Avg	$ 1,000
291 - Drug Enforcement Fund Total				**$ 1,000**
293 - DUI/Education/Enforcement Fund	**293.111.4616**	Proceeds for Police Special Revenue Funds	3 Yr Avg	$ 1,000

(Preliminary - Subject to Change)

CITY OF REYNOLDSBURG, OHIO

BUDGET REVENUE ESTIMATES - *DRAFT #3*
CALENDAR YEAR 2026

Fund	Account Number	Account Description	Method / Assumption	Sum of 2026 Preliminary Budget
293 - DUI/Education/Enforcement Fund Total				**$ 1,000**
295 - Law Enforcement Asst Fund	**295.111.4616**	Proceeds for Police Special Revenue Funds	Historical Trends	$ 5,000
295 - Law Enforcement Asst Fund Total				**$ 5,000**
310 - General Debt Retirement Fund	**310.000.4100**	Income Tax Proceeds	2025 Actuals - 0% growth	$ 3,827,500
	310.000.4629	Miscellaneous Revenue	3 Yr Avg	178,000
310 - General Debt Retirement Fund Total				**$ 4,005,500**
410 - Capital Improvements Fund	**410.000.4100**	Income Tax Proceeds	2025 Actuals - 0% growth	$ 4,784,300
	410.000.4601	Interest Earnings	80% of 2025 YTD Annualized	584,000
	410.000.4921	Reimbursements -Regular	2025 Budget	500,000
410 - Capital Improvements Fund Total				**$ 5,868,300**
420 - Sidewalk Construction Fund	**420.000.4230**	Sidewalk Permits	3 Yr Avg	$ 18,000
420 - Sidewalk Construction Fund Total				**$ 18,000**
640 - Supervision and Inspection	**640.000.0000.4622**	Plan Review/Inspection Deposits	2025 Budget	$ 500,000
640 - Supervision and Inspection Total				**$ 500,000**
650 - Plot Grade & Utility	**650.000.0000.4622**	Plan Review/Inspection Deposits	3 Yr Avg	$ 93,000
650 - Plot Grade & Utility Total				**$ 93,000**
660 - Unclaimed Funds	**660.000.4933**	Unclaimed Funds	3 Yr Avg	$ 3,100
660 - Unclaimed Funds Total				**$ 3,100**
690 - Employees Fund	**690.000.4415**	Employee Fund - General	3 Yr Avg	$ 300
690 - Employees Fund Total				**$ 300**
710 - Water Fund	**710.000.4470**	Utility CIP Fee	Historical Trends	$ 800,000
	710.735.4460	Utility Charges	Historical Trends	7,500,000
	710.735.4461	Capacity Charges	3 Yr Avg	372,000
	710.735.4462	Front Foot Charges	3 Yr Avg	4,000
	710.735.4463	Meter Sales	3 Yr Avg	82,000
	710.735.4465	Fireline Charges	3 Yr Avg	31,000
	710.735.4469	Utility Permits	2025 Budget	5,000
710 - Water Fund Total				**$ 8,794,000**
720 - Wastewater/Sewer Fund	**720.000.4470**	Utility CIP Fee	Historical Trends	$ 415,000
	720.736.4460	Utility Charges	Historical Trends	7,400,000
	720.736.4469	Utility Permits	3 Yr Avg	4,000
720 - Wastewater/Sewer Fund Total				**$ 7,819,000**
730 - Utility Deposits Fund	**730.735.4620**	Consumer Deposits	2025 Budget	$ 2,000
730 - Utility Deposits Fund Total				**$ 2,000**
740 - Storm Water Drainage Fund	**740.737.4472**	ERU Charges	Historical Trends	$ 2,225,000
740 - Storm Water Drainage Fund Total				**$ 2,225,000**
750 - Solid Waste Fund	**750.738.4471**	Residential Charges	2025 Budget	$ 2,575,000
750 - Solid Waste Fund Total				**$ 2,575,000**
910 - Miscellaneous Agency	**910.000.4929**	Miscellaneous Reimbursements	2025 Budget	$ 15,000
	910.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	336,000

(Preliminary - Subject to Change)

CITY OF REYNOLDSBURG, OHIO

BUDGET REVENUE ESTIMATES - *DRAFT #3*
CALENDAR YEAR 2026

Fund	Account Number	Account Description	Method / Assumption	Sum of 2026 Preliminary Budget
910 - Miscellaneous Agency Total				**$ 351,000**
915 - Board of Building Standards	915.000.4939	Miscellaneous Agency Receipts	2025 Budget	$ 15,000
915 - Board of Building Standards Total				**$ 15,000**
920 - Visitors Bureau Fund	920.000.4131	Hotel Motel Tax	3 Yr Avg	$ 117,000
920 - Visitors Bureau Fund Total				**$ 117,000**
930 - Columbus Sewer Capacity	930.000.4461	Capacity Charges	3 Yr Avg	$ 650,000
930 - Columbus Sewer Capacity Total				**$ 650,000**
941 - JEDD1-ETNA-REYNOLDSBURG	941.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	$ 555,000
941 - JEDD1-ETNA-REYNOLDSBURG Total				**$ 555,000**
942 - JEDD2-ETNA-REYNOLDSBURG	942.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	$ 410,000
942 - JEDD2-ETNA-REYNOLDSBURG Total				**$ 410,000**
943 - JEDD3-ETNA-REYNOLDSBURG	943.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	$ 487,000
943 - JEDD3-ETNA-REYNOLDSBURG Total				**$ 487,000**
944 - JEDD4-ETNA-REYNOLDSBURG	944.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	$ 124,000
944 - JEDD4-ETNA-REYNOLDSBURG Total				**$ 124,000**
947 - JEDD 7- REYNOLDSBURG-ETNA	947.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	$ 309,000
947 - JEDD 7- REYNOLDSBURG-ETNA Total				**$ 309,000**
960 - Eng Fees/Plan Review Deposits	960.000.4939	Miscellaneous Agency Receipts	3 Yr Avg	$ 66,000
960 - Eng Fees/Plan Review Deposits Total				**$ 66,000**
970 - Taylor Sq School Tief	970.000.0002.4651	Tief Receipts	2025 Budget	$ 1,700,000
970 - Taylor Sq School Tief Total				**$ 1,700,000**
971 - Brice Main Tif	971.000.4001.4651	Tief Receipts	2025 Budget	$ 125,000
	971.000.4002.4651	Tief Receipts	2025 Budget	150,000
971 - Brice Main Tif Total				**$ 275,000**
973 - Summit Rd Tif #1	973.000.4003.4651	Tief Receipts	2025 Budget	$ 40,000
	973.000.4004.4651	Tief Receipts	2025 Budget	5,000
973 - Summit Rd Tif #1 Total				**$ 45,000**
974 - Taylor Rd Tif #1	974.000.4006.4651	Tief Receipts	2025 Budget	$ 99,000
974 - Taylor Rd Tif #1 Total				**$ 99,000**
975 - Taylor Rd Tif #2	975.000.4005.4651	Tief Receipts	2025 Budget	$ 17,500
	975.000.4007.4651	Tief Receipts	2025 Budget	17,500
975 - Taylor Rd Tif #2 Total				**$ 35,000**
976 - Broad Street TIF	976.000.4000.4651	Tief Receipts	2025 Budget	$ 200,000
976 - Broad Street TIF Total				**$ 200,000**
977 - 2018 Main St/Brice Rd TIF	977.000.4000.4651	Tief Receipts	2025 Budget	$ 1,499,000
977 - 2018 Main St/Brice Rd TIF Total				**$ 1,499,000**
Grand Total				**$ 71,611,300**

(Preliminary - Subject to Change)

CITY OF REYNOLDSBURG, OHIO

BUDGET REVENUE ESTIMATES - *DRAFT #3*
CALENDAR YEAR 2026

Budget Fund	Fund	Sum of 2024 Adopted Budget	Sum of 2025 Final Budget	Sum of 2026 Preliminary Budget
110 - General Fund	110 - General Fund	$ 24,944,192	$ 27,567,284	$ 28,398,900
	287 - Reynoldsburg Recovery Court	25,000	20,000	19,000
	410 - Capital Improvements Fund	7,317,450	6,542,834	5,868,300
	420 - Sidewalk Construction Fund	18,000	60,000	18,000
	640 - Supervision and Inspection	350,000	500,000	500,000
	650 - Plot Grade & Utility	140,000	135,000	93,000
	660 - Unclaimed Funds	6,100	6,100	3,100
	690 - Employees Fund	700	500	300
	710 - Water Fund	782,000	750,000	800,000
	720 - Wastewater/Sewer Fund	380,000	365,000	415,000
	730 - Utility Deposits Fund	5,000	2,000	2,000
	910 - Miscellaneous Agency	400,000	390,000	351,000
	915 - Board of Building Standards	9,500	15,000	15,000
	920 - Visitors Bureau Fund	88,000	110,000	117,000
	930 - Columbus Sewer Capacity	380,000	350,000	650,000
	960 - Eng Fees/Plan Review Deposits	46,000	60,000	66,000
110 - General Fund Total		**$ 34,891,942**	**$ 36,873,718**	**$ 37,316,600**
201 - Fema Federal Emergency Mgmt Agen		$ -	$ -	$ -
206 - American Rescue Plan Act		$ -	$ -	$ -
207 - ARPA Police Retention Grant		$ -	$ -	$ -
211 - Computerized Needs (courts)		$ 20,000	$ 15,000	$ 21,000
220 - Income Tax Fund		$ 800,000	$ 890,950	$ 1,027,500
230 - Permissive Tax Fund		$ 300,000	$ 280,000	$ 245,000
240 - Police Pension Fund		$ 273,535	$ 278,250	$ 354,200
250 - Sewer Capacity Fund		$ 390,000	$ 352,300	$ 652,000
260 - Street Fund		$ 2,100,000	$ 2,165,000	$ 1,799,500
270 - State Highway Fund		$ 170,000	$ 174,500	$ 199,000
285 - Endowments & Contributions		$ 1,000	$ -	$ -

(Preliminary - Subject to Change)

CITY OF REYNOLDSBURG, OHIO

BUDGET REVENUE ESTIMATES - *DRAFT #3*
CALENDAR YEAR 2026

Budget Fund	Fund	Sum of 2024 Adopted Budget	Sum of 2025 Final Budget	Sum of 2026 Preliminary Budget
288 - OneOhio Opioid Fund		$ -	$ -	$ -
290 - Law Enforcement Fund		$ 40,000	$ 20,000	$ 48,000
291 - Drug Enforcement Fund		$ 8,000	$ 7,500	$ 1,000
293 - DUI/Education/Enforcement Fund		$ 2,800	$ 2,000	$ 1,000
294 - Federal Forfeiture Fund		$ 1,500	$ 1,000	$ -
295 - Law Enforcement Asst Fund		$ 36,000	$ 15,000	$ 5,000
297 - Edward Byrne Fund		$ -	$ -	$ -
310 - General Debt Retirement Fund		$ 3,353,771	$ 3,843,742	$ 4,005,500
330 - Taylor Sq Tief Debt Retirement		$ -	$ -	$ -
710 - Water Fund		$ 7,518,000	$ 7,631,000	$ 7,994,000
720 - Wastewater/Sewer Fund		$ 7,120,000	$ 7,260,000	$ 7,404,000
740 - Storm Water Drainage Fund		$ 2,100,000	$ 2,161,000	$ 2,225,000
750 - Solid Waste Fund		$ 2,600,000	$ 2,575,000	$ 2,575,000
925 - Demolition Expense Fund		$ -	$ -	$ -
941 - JEDD1-ETNA-REYNOLDSBURG		$ 660,000	$ 600,000	$ 555,000
942 - JEDD2-ETNA-REYNOLDSBURG		$ 550,000	$ 125,000	$ 410,000
943 - JEDD3-ETNA-REYNOLDSBURG		$ 580,000	$ 600,000	$ 487,000
944 - JEDD4-ETNA-REYNOLDSBURG		$ 45,000	$ 200,000	$ 124,000
947 - JEDD 7- REYNOLDSBURG-ETNA		$ 350,000	$ 360,000	$ 309,000
970 - Taylor Sq School Tief		$ 1,750,000	$ 1,700,000	$ 1,700,000
971 - Brice Main Tif		$ 180,000	$ 275,000	$ 275,000
973 - Summit Rd Tif #1		$ 45,000	$ 45,000	$ 45,000
974 - Taylor Rd Tif #1		$ 35,000	$ 99,000	$ 99,000
975 - Taylor Rd Tif #2		$ 1,800	$ 35,000	$ 35,000
976 - Broad Street TIF		$ -	$ 200,000	$ 200,000
977 - 2018 Main St/Brice Rd TIF		$ -	$ 1,500,000	$ 1,499,000
Grand Total		**$ 65,923,348**	**$ 70,284,960**	**$ 71,611,300**

(Preliminary - Subject to Change)

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Transfer Funds Among Various General Fund Accounts, and Declaring an Emergency

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

three-read emergency

REASON FOR EMERGENCY:

This Ordinance is deemed an emergency measure necessary for the City's financial needs and, further to comply with the ORC year-end requirements.

STAFF REPORT:

This legislation is the annual request to transfer funds from various accounts to bring all funds into balnance.

AN ORDINANCE TO TRANSFER FUNDS AMONG VARIOUS GENERAL FUND ACCOUNTS, AND DECLARING AN EMERGENCY

NOW, THEREOFRE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That Council unappropriate and appropriate funds to the following accounts:

Appropriate $100,000.00 from Parks and Recreation account 110.340.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $20,000.00 from Service account 110.448.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $20,000.00 from Water account 710.735.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $20,000.00 from Wastewater account 720.736.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $30,000.00 from the unppropriated Senior Center account 110.343.5361 Building Repair and appropriate to the unappropriated General Fund (110)

From the unappropriated General Fund (110) appropriate:

110.343.5105 Overtime Senior Center	$ 5,000.00
110,343.5151 PERS Contribution	$ 1,000.00
110.343.5161 Group Insurance Senior Center	$ 5,000.00
110.344.5105 Overtime	$ 6,000.00
110.479.5102 Wages-Staff	$40,000.00
110.479.5105 Overtime	$10,000.00
110.479.5161 Group Insurance	$ 5,000.00
110.522.5161 Group Insurance	$ 9,000.00
110.584.5203 Computer Supplies	$ 3,950.20
110.584.5366 Computer Maintenance	$37,000.00
110.593.5161 Group Insurance	$ 2,500.00
110.595.5164 Workers Compensation	$45,000.00

Appropriate $42,164.27 from the unappropriated Debt Fund (310) and appropriate to account number 310.991.5424 Bond-Interest

Appropriate $195.78 from the unappropriated Sidewalk Fund (420) and appropriate to account numbers:

420.000.0007.5653 Sidewalk Construction Phase VII	$ 173.52
420.000.0010.5653 Sidewalk Construction Phase X	$ 22.26

Appropriate $18,00 from the unappropriated Storm Water Fund (740) and appropriate to account numbers:

740.737.5105 Overtime	$ 7,000.00
740.737.5109 HSA Employee Funding	$ 1,000.00

Appropriate $151,000.000 from the unappropriated Visitor's Bureau Fund (920) and appropriate to account number 920.000.5527 Agency Distributions Visitor's Bureau

Appropriate $27,392.18 from the unappropriated Taylor Square TIF (970) to
970.000.0002.5373 Treasurer Fees

Appropriate $790.75 from the unappropriated Brice/Main TIF (971) to
971.000.4001.5373 Treasurer Fees

Appropriate $394.68 from the unappropriated Taylor Road #1 TIF (974) to
974.000.4000.5373 Treasurer Fees

Appropriate $664.84 from the unappropriated Broad Street TIF (976) to 976.000.4000.5373

Treasurer Fees

SECTION 2. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City, and further in order to be in compliance with ORC year end requirements; wherefore upon adoption by Council, this Ordinance shall be in effect immediately upon signature by the Mayor.

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance Authorizing the Mayor to Enter into a Contract with Builderscape, Inc. for the JFK Park Pickleball Improvements Project, Appropriate Funds Therefor, and Declaring an Emergency

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

3-read emergency

REASON FOR EMERGENCY:

For the financial needs of the City in order to meet contratual deadlines

STAFF REPORT:

The City Engineer has reviewed the bid proposals submitted and determined that the lowest and best bidder for the project is Builderscape Inc. Therefore, we request authorization for the Mayor to enter into a contract with Builderscape Inc. for the JFK Park Pickleball Improvements for $760,913.00, with a contingency of 12.025% ($91,500.00), for a total of $852,413.00.

Requesting $852,413.00 be appropriated from the unappropriated Capital Improvement Fund (410) into line item 410.000.0202.5659 JFK Park Tennis Court Conversion

Upon project completion, a reimbursement request totaling $150,000 will be submitted to the Ohio Department of Natural Resources (ODNR), in accordance with the terms of the awarded grant.

AN ORDINANCE AUTHORIZING THE MAYOR TO ENTER INTO A CONTRACT WITH BUILDERSCAPE INC. FOR THE CONSTRUCTION OF PICKLEBALL COURTS IN JFK PARK, APPROPRIATE FUNDS THEREFOR, AND DECLARING AN EMERGENCY

WHEREAS, the City of Reynoldsburg has determined the need to convert a number of tennis courts in JFK Park into pickleball courts to meet a community need; and

WHEREAS, the City Engineer has reviewed the bid proposals submitted for this project and

determined that the lowest and best bidder for the project is Builderscape Inc.; and

WHEREAS, the City Engineer has also concluded that Builderscape Inc. has the ability, resources, and experience to properly complete the project as well as recommending moving forward with a contract for the JFK Park pickleball courts at a cost of $760,913.00 with a five percent (12.025%) contingency of $91,310.00 for a total amount of $852,413.00 be awarded to Builderscape Inc.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That the Mayor is hereby authorized to enter into a contract with Builderscape Inc. for pickleball courts in JFK Park in the amount of $760,913.00 with a contingency of (12.025%) amount of $91,500.00 for a total of $852,413.00
.
SECTION 2. That the funds necessary to carry out the purpose of this Ordinance are hereby deemed appropriated and the City Auditor shall establish such project codes as necessary.

SECTION 3. The City Auditor is hereby authorized to appropriate funds from the unappropriated Capital Improvement Fund (CIP 410) and appropriate to project number 410.000.0202.5659 JFK Park Tennis Court Conversion
.
SECTION 4. That a portion of this project is reimbursable by the Ohio Department of Natural Resources (ODNR), based on the approved grant, to the City of Reynoldsburg; therefore, when those funds are returned, they should be deposited into the unappropriated Capital Improvement Fund (CIP 410).
SECTION 5. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City, and further so that construction can begin as soon as possible in order to meet contract deadlines; wherefore upon adoption by Council, this Ordinance shall be in effect immediately upon signature by the Mayor.

Engineers, Surveyors, Planners, Scientists

MEMO

Date: October 27, 2025

To: Donna Bauman, Director of Parks and Recreation, CPRP

From: Mitchell Yake, EI

Subject: JFK Park, Pickleball Improvements Project - Bid Results

Copies: File

EMH&T has completed bid tabulation and analysis. The following is a budget summary for the construction phase of the subject project based on bid pricing from contractors and 10% for Contingency. Budget for Construction Services is not included, please have DLZ prepare proposal for those services to include in the City's budget.

Base Bid Amount:	$ 385,460.50
Recommended Contingency (~12%):	$ 46,500.00
Additional Bid 1 Amount:	$ 375,452.50
Recommended Contingency (~12%):	$ 45,000.00
Construction Management/Inspection (~12%):	$ 90,000.00
Total Construction Phase Budget:	**$ 942,413.00**

I have attached the Bid Tabulation to this memorandum for your review. The prices for all bids are competitive and within reason of our probable engineers estimate. EMH&T has prepared a formal Award Recommendation Letter and Notice of Award for the City's execution. Once the funding legislation is in place, return signed copies of the Notices of Award to EMH&T to prepare the contracts to be routed for execution and deliver to City. If you have any other questions, please feel free to contact me at 614-775-4209.

Attachments: Bid Tabulation
Award Recommendation Letters
Notice of Award

City of Reynoldsburg, Ohio

JFK Park, Pickleball Improvements Project

EMH&T JN: 2025-0293

Bids Received: October 13, 2025

Ref. No.	Spec	Item No.	Description	Quantity	Units	Engineer's Estimate		Builderscape, Inc. 10496 Parks Court Marysville, Ohio 43040		Vasco Sports Contractors 4270 Sterilite Street SE Massillon, Ohio 44646		Strawser Paving Co. Inc 1595 Frank Road Columbus, Ohio 43223	
						Price	Extension	Price	Extension	Price	Extension	Price	Extension
Base Bid													
1	CMSC	202	Miscellaneous Removals (Fencing, Net Post)	1	LS	$20,000.00	$20,000.00	$24,996.00	$24,996.00	$47,000.00	$47,000.00	$20,000.00	$20,000.00
2	CMSC	253*	Full Depth Pavement Repair	25	SY	$130.00	$3,250.00	$320.00	$8,000.00	$430.00	$10,750.00	$1,600.00	$40,000.00
3	CMSC	254	Planing, T=1.5" +/-	2,950	SY	$5.50	$16,225.00	$11.71	$34,544.50	$8.00	$23,600.00	$18.00	$53,100.00
4	SPEC	SPEC	Asphaly Sport Court Paving and Surfacing, Complete, As Per Plan	2,950	SY	$60.00	$177,000.00	$44.00	$129,800.00	$72.00	$212,400.00	$75.00	$221,250.00
5	SPEC	SPEC	Pickleball Court Net, Complete, As Per Plan	6	EA	$4,500.00	$27,000.00	$1,750.00	$10,500.00	$4,195.00	$25,170.00	$4,200.00	$25,200.00
6	SPEC	SPEC	Tennis Court Net, Complete, As Per Plan	2	EA	$5,500.00	$11,000.00	$2,250.00	$4,500.00	$4,195.00	$8,390.00	$4,000.00	$8,000.00
7	SPEC	SPEC	Chain Link Fence, Vinyl Coated, Color Black, 4' (Interior)	520	LF	$90.00	$46,800.00	$108.00	$56,160.00	$72.00	$37,440.00	$57.00	$29,640.00
8	SPEC	SPEC	Chain Link Fence and Gates, Vinyl Coated, Color Black, 10' (Perimeter)	680	LF	$160.00	$108,800.00	$172.00	$116,960.00	$125.00	$85,000.00	$120.00	$81,600.00
		*Contingency Items											
			BIDDER'S TOTAL FOR BASE BID =				$410,075.00		**$385,460.50**		$449,750.00		$478,790.00
			CORRECTED BIDDER'S TOTAL FOR BASE BID =				NA		NA		NA		NA
Additional Bid 1													
1	CMSC	203	Excavation/Embankment, As Per Plan	1	LS	$3,500.00	$3,500.00	$12,500.00	$12,500.00	$4,390.00	$4,390.00	$40,000.00	$40,000.00
2	CMSC	207	Temporary Sediment and Erosion Control, As Per Plan	1	LS	$2,200.00	$2,200.00	$3,000.00	$3,000.00	$1,660.00	$1,660.00	$3,000.00	$3,000.00
3	CMSC	608	Concrete Pad, As Per Plan	1,800	SF	$25.00	$45,000.00	$20.00	$36,000.00	$24.50	$44,100.00	$35.00	$63,000.00
4	CMSC	608	Asphalt Shared-Use Path, Per R-20	1,600	SF	$16.50	$26,400.00	$30.00	$48,000.00	$16.00	$25,600.00	$18.00	$28,800.00
5	CMSC	653	Topsoil Furnished and Placed, T=3"	60	CY	$85.00	$5,100.00	$90.00	$5,400.00	$80.00	$4,800.00	$180.00	$10,800.00
6	SPEC	659	Seeding and Mulching	710	SY	$3.00	$2,130.00	$2.75	$1,952.50	$6.00	$4,260.00	$6.00	$4,260.00
7	SPEC	SPEC	Canopy Structure, Complete, As Per Plan	6	EA	$35,000.00	$210,000.00	$33,000.00	$198,000.00	$31,000.00	$186,000.00	$23,000.00	$138,000.00
8	SPEC	SPEC	Bench, Complete, As Per Plan	12	EA	$7,500.00	$90,000.00	$5,500.00	$66,000.00	$6,980.00	$83,760.00	$6,200.00	$74,400.00
9	SPEC	SPEC	Court Number Signage, As Per Plan	8	EA	$135.00	$1,080.00	$200.00	$1,600.00	$80.00	$640.00	$1,200.00	$9,600.00
10	SPEC	SPEC	Paddle Rack, as Per Plan	6	EA	$550.00	$3,300.00	$500.00	$3,000.00	$355.00	$2,130.00	$2,000.00	$12,000.00
		*Contingency Items											
			BIDDER'S TOTAL FOR ADDITIONAL BID 1 =				$388,710.00		**$375,452.50**		$357,340.00		$383,860.00
			CORRECTED BIDDER'S TOTAL FOR ADDITIONAL BID 1 =				NA		NA		NA		NA

A Correct Bidder's Calculated Unit Price: labor + material was incorrectly calculated by Bidder

B Correct Bidder's Total: price x quantity was incorrectly calculated by Bidder

BIDDER'S TOTAL FOR CONTRACT =	$798,785.00	**$760,913.00**	$807,090.00	$862,650.00

BY: Mitchell Yake

Mitchell Yake, PE

Evans, Mechwart, Hambleton & Tilton, Inc.
5500 New Albany Road
Columbus, OH 43054

EMH&T

Engineers, Surveyors, Planners, Scientists

October 27, 2025

Ms. Donna Bauman
Director of Parks and Recreation, CPRP
City of Reynoldsburg
7232 East Main Street
Reynoldsburg, Ohio 43068

Re: JFK Park, Pickleball Improvements Project

Dear Ms. Donna Bauman,

We have completed our analysis of the bids received on October 13, 2025, for the Reynoldsburg **JFK Park Pickleball Improvements Project**. Based on our review of the public bid results, we recommend that the contract be awarded to **Builderscape, Inc.** for the amount of **$ 760,913** for the work included under the Base Bid plus Additional Bid 1. Builderscape, Inc. appears to be qualified for this type of work, and their prices are competitive compared to recent projects of similar scope. Builderscape has completed work in the City in recent years.

Please review the enclosed information. Once City Council authorizes the contracts for construction, please have the Mayor sign the Notice of Award and forward it to me. Once I receive that, we will prepare conformed copies of the contract documents and forward them to the selected Contractors for execution. Please do not hesitate to contact me if you should have any additional questions.

Sincerely,

EVANS, MECHWART, HAMBLETON & TILTON, INC.



Mitchell Yake, PE

Attachments:
Bid Tabulation
Notice of Award

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Amend Chapter 953 Water Charges, Section 953.01(a) Water Rate Schedule of the Code of Ordinances for the City of Reynoldsburg, Ohio, and Declaring an Emergency

APPROVALS:

William Dorman
Joe Begeny
Chris Shook
Stephen Cicak
Mollie Prasher

EMERGENCY:

two-read emergency

REASON FOR EMERGENCY:

for the financial needs of the City and to be effective January 1, 2026

STAFF REPORT:

AN ORDINANCE TO AMEND CHAPTER 953 WATER CHARGES, SECTION 953.01(a) WATER RATE SCHEDULE OF THE CODE OF ORDINANCES FOR THE CITY OF REYNOLDSBURG, OHIO

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That Section 953.01(a) Water Rate Schedule of Chapter 953 Water Charges of the Code of Ordinances for the City of Reynoldsburg be and is hereby amended to read as follows:

953.01 Water Rate Schedule
(a) Charges for water furnished by the municipally-owned water system shall be at the rate of twelve dollars and fifty-five cents ($12.55) per 1,000 gallons,
effective January 1, 2026. A ten percent (10%) discount shall be applied to all seniors (65 and older), up to the first ten thousand gallons of consumption.

SECTION 2. That existing Section 953.01(a) of Chapter 953 Water Charges be and is hereby repealed and replaced.

SECTION 3. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the city and shall be effective as of January 1, 2026, following adoption by Council and the signature by the Mayor.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Amend Chapter 945 Sewer Charges, Section 945.02(c) Rate Schedule of the Code of Ordinances for the City of Reynoldsburg, and Declaring an Emergency

APPROVALS:

William Dorman
Joe Begeny
Chris Shook
Stephen Cicak
Mollie Prasher

EMERGENCY:

two-read emergency

REASON FOR EMERGENCY:

for the financial needs of the City to go into effect on January 1, 2026

STAFF REPORT:

AN ORDINANCE TO AMEND CHAPTER 945 SEWER CHARGES, SECTION 945.02(c) RATE SCHEDULE OF THE CODE OF ORDINANCES FOR THE CITY OF REYNOLDSBURG, OHIO

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That Section 945.02(c) Rate Schedule of Chapter 945 Sewer Charges of the Code of Ordinances for the City of Reynoldsburg be and is hereby amended to read as follows:

945.02 Sewer Rate Schedule

(c) Sewer charges for any building or premises shall be based on water consumption for new buildings. Sewer rental charges are hereby established for all residential, commercial and industrial users, effective January 1, 2026, at the rate of twelve dollars and twenty cents ($12.20) per 1,000 gallons.

SECTION 2. That existing Section 945.02(c) of Chapter 945 Sewer Charges be and is hereby

repealed and replaced.

SECTION 3. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the city and shall be effective as of January 1, 2026, following adoption by Council and the signature by the Mayor.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Amend Chapter 958 Stormwater Charges, Section 958.06 Equivalent Residential Unit of the Code of Ordinances for the City of Reynoldsburg, and Declaring an Emergency

APPROVALS:

William Dorman
Joe Begeny
Chris Shook
Stephen Cicak
Mollie Prasher

EMERGENCY:

two read emergency

REASON FOR EMERGENCY:

for the financial needs of the City to go into effect January 1, 2026

STAFF REPORT:

AN ORDINANCE TO AMEND CHAPTER 958 STORMWATER CHARGES, SECTION 958.06 EQUIVALENT RESIDENTIAL UNIT ASSIGNMENT OF THE CODE OF ORDINANCES FOR THE CITY OF REYNOLDSBURG

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That Section 958.06 Equivalent Residential Unit Assignment of Chapter 958 Stormwater Charges of the Codified Ordinances for the City of Reynoldsburg be and is hereby amended to read as follows:

958.06 EQUIVALENT RESIDENTIAL UNIT ASSIGNMENT.

For the purpose stated in this chapter, there is hereby charged to each Utility user and property, lot, parcel of land, building or premises (collectively "properties") situated within the corporate limits of the City that is tributary directly or indirectly to the stormwater system - Utility Service Charges determined, as provided in this section.

All properties having impervious areas within the City shall be assigned an Equivalent Residential Unit (ERU), or a multiple thereof, which will be at a minimum one ERU.

All improved single-family residential properties are assigned one ERU. A flat rate will apply to all single-family residential properties. All improved single-family residential properties are determined to include impervious areas typical of a single-family residence.

All properties having an impervious area which are not improved single-family residential properties are to be assigned by the City Engineer an ERU multiple based upon the properties' estimated impervious areas (in square feet) divided by 2,530 square feet (one ERU). This division will be calculated to the second decimal place and rounded according to mathematical convention to the nearest whole ERU.

The Utility Service Charge is six dollars and fifty-eight ($6.58) per month per Equivalent Residential Unit (ERU), which shall be effective from and after January 1, 2026.

SECTION 2. That existing Section 958.06 of Chapter 958 Stormwater Charges be and is hereby repealed and replaced.

SECTION 3. That this Ordinance is deemed to be an emergency to meet the effective date of January 1, 2026, following adoption by Council and the signature by the Mayor.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance Authorizing the Mayor to Grant the Ohio Department of Transportation (ODOT) a Highway Easement (0.470 Acres), and Declaring an Emergency

APPROVALS:

Joe Begeny
Chris Shook
Mollie Prasher

EMERGENCY:

single-read emergency

REASON FOR EMERGENCY:

for the health and safety of the City to facilitate the continuation of the road project

STAFF REPORT:

AN ORDINANCE AUTHORIZING THE MAYOR TO GRANT THE OHIO DEPARTMENT OF TRANSPORTATION (ODOT) A HIGHWAY EASEMENT (0.470 ACRES), AND DECLARING AN EMERGENCY

WHEREAS, ODOT is currently in the construction design phase of the I-70 Improvements Project between Taylor Road and Baltimore-Reynoldsburg Road (310); and

WHEREAS, the current design includes a full interchange at Taylor Road (currently only one exit for eastbound traffic on I-70); and

WHEREAS, this design necessitates the need for several deeds/easements from various property owners including the City of Reynoldsburg; and

WHEREAS, the City is amenable to providing ODOT with the necessary Warranty Deeds for the project, given the overall benefit this work will provide the City and its residents.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That the Mayor be and is hereby authorized to grant ODOT three (3) Warranty Deeds per the attachment for the construction of the I-70 and Taylor Road interchange.

SECTION 2. That an amount to be determined shall be paid to the City of Reynoldsburg for compensation of said Warranty Deed.

SECTION 3. That the following unrecorded Warranty Deed (0.470 acres) from the City of Reynoldsburg, be and is hereby transferred as Exhibit A attached hereto and made a part hereof.

SECTION 4. This Ordinance is declared to be an emergency measure necessary for the immediate preservation of the public peace, health and safety, and for the further reason that this Ordinance is required to be immediately effective in order to enable

the City to timely enter into contracts for the construction of the Improvement; wherefore, this Ordinance shall be in full force and effect immediately upon its passage.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Make Final Appropriations for Expenses and Other Expenditures for the City of Reynoldsburg, State of Ohio, During the Fiscal Year Ending December 31, 2026, and Declaring an Emergency

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

three-read emergency

REASON FOR EMERGENCY:

That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City and further to have the budget in place on January 1, 2026.

STAFF REPORT:

AN ORDINANCE TO MAKE FINAL APPROPRIATIONS FOR EXPENSES AND OTHER EXPENDITURES OF THE CITY OF REYNOLDSBURG, STATE OF OHIO, DURING THE FISCAL YEAR ENDING DECEMBER 31, 2026, AND DECLARING AN EMERGENCY

WHEREAS, pursuant to the provisions of Section 5.03 (4) of the Charter of the City of Reynoldsburg, Ohio, the City Council is authorized to adopt the municipal budget for the fiscal year beginning January 1, 2026 and appropriations are required effective January 1, 2026 and ending December 31, 2026.

WHEREAS, the Mayor has submitted a proposed budget with estimates and explanatory data.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO, a majority of the members elected thereto herein concurring that, to provide for the current expenses and other expenditures of said City of Reynoldsburg during the fiscal year ending December 31, 2026, the following sums be and are hereby set aside and appropriated as follows:

SECTION 1. That the proposed appropriations for the General Fund (110) are shown on the attached Exhibit A.

SECTION 2. That the proposed revenues for the City are shown on the attached Exhibit B.

SECTION 3. That the income tax revenues shall be appropriated and disbursed pursuant to Section 190.01 of the Codified Ordinances of the City of Reynoldsburg.

SECTION 4. That the unencumbered balances as of December 31, 2025 shall be and are hereby appropriated in the Fiduciary Funds, the Capital Improvement Project Funds, and revenues credited to the Fiduciary Funds shall be appropriated upon receipt to the proper associated accounts. That the 2025 capital project encumbrances funded by OPWC are hereby reappropriated. The ending balance in the Water and Wastewater CIP revenue accounts for the prior year shall be appropriated in the general project account for the specific funds to be used later for approved projects.

SECTION 5. That the amounts of public contributions and reimbursements to the City shall be appropriated upon receipt to the proper associated accounts.

SECTION 6. That the amount of $1,000,000 shall be and is hereby appropriated in the Taylor Square School TIEF Fund (970) to comply with the TIF agreement.

SECTION 7. That the amount of $200,000 shall be and is hereby appropriated in the Brice-Main TIF Fund (971) to comply with the TIF agreement.

SECTION 8. That the City Auditor is hereby authorized to draw warrants on the appropriate funds, for payments from any of the foregoing appropriations, upon receiving proper certificates and vouchers; therefore, approved by the officers authorized by law to approve same, or an ordinance of Council to make the expenditures; provided that no warrants shall be drawn or paid for salaries or wages except to persons employed by authority of and in accordance with law or ordinance.

SECTION 9. That the effective date of the appropriations in this Ordinance shall be January 1, 2026.

SECTION 10. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City and further to have the budget in place on January 1, 2026; wherefore, upon adoption by Council this Ordinance shall be in effect immediately upon signature by the Mayor.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Transfer Funds Among Various General Fund Accounts, and Declaring an Emergency

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

three-read emergency

REASON FOR EMERGENCY:

This Ordinance is deemed an emergency measure necessary for the City's financial needs and, further to comply with the ORC year-end requirements.

STAFF REPORT:

This legislation is the annual request to transfer funds from various accounts to bring all funds into balnance.

AN ORDINANCE TO TRANSFER FUNDS AMONG VARIOUS GENERAL FUND ACCOUNTS, AND DECLARING AN EMERGENCY

NOW, THEREOFRE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That Council unappropriate and appropriate funds to the following accounts:

Appropriate $100,000.00 from Parks and Recreation account 110.340.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $20,000.00 from Service account 110.448.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $20,000.00 from Water account 710.735.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $20,000.00 from Wastewater account 720.736.5102 Wages-Staff and return to the unappropriated General Fund (110)

Appropriate $30,000.00 from the unppropriated Senior Center account 110.343.5361 Building Repair and appropriate to the unappropriated General Fund (110)

From the unappropriated General Fund (110) appropriate:

110.343.5105 Overtime Senior Center	$ 5,000.00
110,343.5151 PERS Contribution	$ 1,000.00
110.343.5161 Group Insurance Senior Center	$ 5,000.00
110.344.5105 Overtime	$ 6,000.00
110.479.5102 Wages-Staff	$40,000.00
110.479.5105 Overtime	$10,000.00
110.479.5161 Group Insurance	$ 5,000.00
110.522.5161 Group Insurance	$ 9,000.00
110.584.5203 Computer Supplies	$ 3,950.20
110.584.5366 Computer Maintenance	$37,000.00
110.593.5161 Group Insurance	$ 2,500.00
110.595.5164 Workers Compensation	$45,000.00

Appropriate $42,164.27 from the unappropriated Debt Fund (310) and appropriate to account number 310.991.5424 Bond-Interest

Appropriate $195.78 from the unappropriated Sidewalk Fund (420) and appropriate to account numbers:

420.000.0007.5653 Sidewalk Construction Phase VII	$ 173.52
420.000.0010.5653 Sidewalk Construction Phase X	$ 22.26

Appropriate $18,00 from the unappropriated Storm Water Fund (740) and appropriate to account numbers:

740.737.5105 Overtime	$ 7,000.00
740.737.5109 HSA Employee Funding	$ 1,000.00

Appropriate $151,000.000 from the unappropriated Visitor's Bureau Fund (920) and appropriate to account number 920.000.5527 Agency Distributions Visitor's Bureau

Appropriate $27,392.18 from the unappropriated Taylor Square TIF (970) to
970.000.0002.5373 Treasurer Fees

Appropriate $790.75 from the unappropriated Brice/Main TIF (971) to
971.000.4001.5373 Treasurer Fees

Appropriate $394.68 from the unappropriated Taylor Road #1 TIF (974) to
974.000.4000.5373 Treasurer Fees

Appropriate $664.84 from the unappropriated Broad Street TIF (976) to 976.000.4000.5373

Treasurer Fees

SECTION 2. That this Ordinance is deemed to be an emergency measure necessary for the financial needs of the City, and further in order to be in compliance with ORC year end requirements; wherefore upon adoption by Council, this Ordinance shall be in effect immediately upon signature by the Mayor.

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance Providing for the Issuance and Sale of Bonds in the Maximum Principal Amount of $1,300,000, for the Purpose of Paying the Costs of Improving the Municipal Waterworks System, and Declaring an Emergency

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

two-read emergency

REASON FOR EMERGENCY:

for the financial needs of the city

STAFF REPORT:

AN ORDINANCE PROVIDING FOR THE ISSUANCE AND SALE OF BONDS IN THE MAXIMUM PRINCIPAL AMOUNT OF $1,300,000, FOR THE PURPOSE OF PAYING THE COSTS OF IMPROVING THE MUNICIPAL WATERWORKS SYSTEM, AND DECLARING AN EMERGENCY

WHEREAS, this City Council has requested that the City Auditor, as fiscal officer of this City, certify the estimated life or period of usefulness of the improvement described in Section 2 and the maximum maturity of the Bonds described in Section 2; and

WHEREAS, the City Auditor has certified to this City Council that the estimated life or period of usefulness of the Improvement is at least five (5) years and that the maximum maturity of the Bonds is forty (40) years;

NOW, THEREFORE, BE IT ORDAINED by the Council of the City of Reynoldsburg, Fairfield, Franklin and Licking Counties, Ohio, that:
Section 1. Definitions and Interpretation. In addition to the words and terms elsewhere defined in this Ordinance, unless the context or use clearly indicates another or different meaning or intent:

"*Authorized Denominations*" means the denomination of $5,000 or any integral multiple in excess thereof.

"*Bond Proceedings*" means, collectively, this Ordinance, the Certificate of Award, the Continuing Disclosure Agreement, the Registrar Agreement and such other proceedings of the City, including the Bonds, that provide collectively for, among other things, the rights of holders and beneficial owners of the Bonds.

"*Bond Register*" means all books and records necessary for the registration, exchange and transfer of Bonds as provided in Section 5.

"*Bond Registrar*" means a bank or trust company authorized to do business in the State of Ohio and designated by the City Auditor in the Certificate of Award pursuant to Section 4 as the initial authenticating agent, bond registrar, transfer agent and paying agent for the Bonds under the Registrar Agreement and until a successor Bond Registrar shall have become such pursuant to the provisions of the Registrar Agreement and, thereafter,

"*Bond Registrar*" shall mean the successor Bond Registrar.

"*Bonds*" means, collectively, the Serial Bonds and the Term Bonds, each as is designated as such in the Certificate of Award.

"*Book entry form*" or "*book entry system*" means a form or system under which (a) the ownership of beneficial interests in the Bonds and the principal of and interest and any premium on the Bonds may be transferred only through a book entry, and (b) physical Bond certificates in fully registered form are issued by the City and payable only to a Depository or its nominee as registered owner, with the certificates deposited with and "immobilized" in the custody of the Depository or its designated agent for that purpose. The book entry maintained by others than the City is the record that identifies the owners of beneficial interests in the Bonds and that principal and interest.

"*Certificate of Award*" means the certificate authorized by Section 6, to be executed by the City Auditor, setting forth and determining those terms or other matters pertaining to the Bonds and their issuance, sale and delivery as this Ordinance requires or authorizes, to be set forth or determined therein.

"*City Attorney*" means the City Attorney of the City or any person serving in an interim or acting capacity with respect to that office.

"*City Auditor*" means the City Auditor of the City or any person serving in an interim or acting capacity with respect to that office.

"*Clerk of Council*" means the Clerk of Council of the City Council or any person serving in an interim or acting capacity with respect to that office.

"*Closing Date*" means the date of physical delivery of, and payment of the purchase price for, the Bonds.

"*Code*" means the Internal Revenue Code of 1986, as amended, the Regulations (whether temporary or final) under that Code or the statutory predecessor of that Code, and any amendments of, or successor provisions to, the foregoing and any official rulings, announcements, notices, procedures and judicial determinations regarding any of the foregoing, all as and to the extent applicable. Unless otherwise indicated, reference to a Section of the Code includes any applicable successor section or provision and such applicable Regulations, rulings, announcements, notices, procedures and determinations pertinent to that Section.

"*Continuing Disclosure Agreement*" means the Continuing Disclosure Agreement, which shall constitute the continuing disclosure agreement made by the City for the benefit of the holders and beneficial owners of the Bonds in accordance with the Rule, as it may be modified from the form on file with the Clerk of Council and executed by the Mayor and the City Auditor, all in accordance with Section 9(c).

"*Depository*" means any securities depository that is a clearing agency registered pursuant to the provisions of Section 17A of the Securities Exchange Act of 1934, operating and maintaining, with its Participants or otherwise, a book entry system to record ownership of beneficial interests in the Bonds or the principal of and interest and any premium on the Bonds, and to effect transfers of the Bonds, in book entry form, and includes and means initially The Depository Trust Company (a limited purpose trust company).

"*Financing Costs*" shall have the meaning given in Section 133.01 of the Ohio Revised Code.

"*Interest Payment Dates*" means, unless otherwise specified in the Certificate of Award, June 1 and December 1 of each year that the Bonds are outstanding, commencing on the date specified in the Certificate of Award.

"*Mandatory Redemption Date*" shall have the meaning set forth in Section 3(b).

"*Mandatory Sinking Fund Redemption Requirements*" shall have the meaning set forth in Section 3(e)(i).

"*Mayor*" means the Mayor of the City or any person serving in an interim or acting capacity with respect to that office.

"*Original Purchaser*" means the purchaser of the Bonds specified in the Certificate of Award.

"*Participant*" means any participant contracting with a Depository under a book entry system and includes securities brokers and dealers, banks and trust companies and clearing corporations.

"*Principal Payment Dates*" means, unless otherwise specified in the Certificate of Award, December 1 in each of the years from and including 2026 to and including 2045; *provided* that the first Principal Payment Date may be deferred or advanced up to one year and the last Principal Payment Date may be deferred up to one year or advanced by such number of years as determined necessary by the City Auditor, and *provided further* that in no case shall the final Principal Payment Date exceed the maximum maturity limitation referred to in the preambles hereto, all of which determinations shall be made by the City Auditor in the

Certificate of Award in such manner as to be in the best interest of and financially advantageous to the City.

"*Registrar Agreement*" means the Bond Registrar Agreement between the City and the Bond Registrar, as it may be modified from the form on file with the Clerk of Council and executed by the Mayor and the City Auditor, all in accordance with Section 4.

"*Regulations*" means Treasury Regulations issued pursuant to the Code or to the statutory predecessor of the Code.

"*Rule*" means Rule 15c2-12 prescribed by the SEC pursuant to the Securities Exchange Act of 1934.

"*SEC*" means the Securities and Exchange Commission.

"*Serial Bonds*" means those Bonds designated as such and maturing on the dates set forth in the Certificate of Award, bearing interest payable on each Interest Payment Date and not subject to mandatory sinking fund redemption.

"*Term Bonds*" means those Bonds designated as such and maturing on the date or dates set forth in the Certificate of Award, bearing interest payable on each Interest Payment Date and subject to mandatory sinking fund redemption.

The captions and headings in this Ordinance are solely for convenience of reference and in no way define, limit or describe the scope or intent of any Sections, subsections, paragraphs, subparagraphs or clauses hereof. Reference to a Section means a section of this Ordinance unless otherwise indicated.

Section 2. Authorized Principal Amount and Purpose; Application of Proceeds. This City Council determines that it is necessary and in the best interest of the City to issue bonds of this City in the maximum principal amount of $1,300,000 (the "*Bonds*") for the purpose of paying the costs of improving the municipal waterworks system by constructing waterlines and acquiring any related interests in real estate, together with all necessary and related appurtenances thereto (the "*Improvement*"). The Bonds shall be issued pursuant to Chapter 133 of the Ohio Revised Code, the Charter of the City, this Ordinance and the Certificate of Award.

The principal amount of Bonds to be issued shall not exceed the maximum principal amount specified in this Section 2 and shall be an amount determined by the City Auditor in the Certificate of Award to be the principal amount of Bonds that is required to be issued at this time for the purpose stated in this Section 2, taking into account the costs of the Improvement, the estimates of the Financing Costs and the interest rates on the Bonds.

The proceeds from the sale of the Bonds received by the City (or withheld by the Original Purchaser on behalf of the City) shall be paid into the proper fund or funds, and those proceeds are hereby appropriated and shall be used for the purpose for which the Bonds are being issued, including without limitation but only to the extent not paid by others, the payment of the costs of issuing and servicing the Bonds, printing and delivery of the Bonds, legal services including obtaining the approving legal opinion of bond counsel, fees and expenses of any municipal advisor, paying agent and rating agency, any fees or premiums relating to municipal bond insurance or other security arrangements determined necessary by the City

Auditor, and all other Financing Costs and costs incurred incidental to those purposes. The Certificate of Award may authorize the Original Purchaser to withhold certain proceeds from the purchase price of the Bonds to provide for the payment of Financing Costs related to the Bonds on behalf of the City. Any portion of those proceeds received by the City representing premium (after payment of any Financing Costs identified in the Certificate of Award and/or the Registrar Agreement) or accrued interest shall be paid into the Bond Retirement Fund.

Section 3. Denominations; Dating; Principal and Interest Payment and Redemption Provisions. The Bonds shall be issued in one lot and only as fully registered bonds, in Authorized Denominations, but in no case as to a particular maturity date exceeding the principal amount maturing on that date. The Bonds shall be dated as provided in the Certificate of Award, *provided* that their dated date shall not be more than sixty (60) days prior to the Closing Date.

(a) Interest Rates and Payment Dates. The Bonds shall bear interest at the rate or rates per year (computed on the basis of a 360-day year consisting of twelve 30-day months) as shall be determined by the City Auditor, subject to subsection (c) of this Section 3, in the Certificate of Award. Interest on the Bonds shall be payable at such rate or rates on the Interest Payment Dates until the principal amount has been paid or provided for. The Bonds shall bear interest from the most recent date to which interest has been paid or provided for or, if no interest has been paid or provided for, from their date.

(b) Principal Payment Schedule. The Bonds shall mature or be payable pursuant to Mandatory Sinking Fund Redemption Requirements on the Principal Payment Dates in principal amounts as shall be determined by the City Auditor, subject to subsection (c) of this Section 3, in the Certificate of Award, which determination shall be in the best interest of and financially advantageous to the City.

Consistent with the foregoing and in accordance with the determination of the best interest of and financial advantages to the City, the City Auditor shall specify in the Certificate of Award (i) the aggregate principal amount of Bonds to be issued as Serial Bonds, the Principal Payment Date or Dates on which those Bonds shall be stated to mature and the principal amount thereof that shall be stated to mature on each such Principal Payment Date and (ii) the aggregate principal amount of Bonds to be issued as Term Bonds, the Principal Payment Date or Dates on which those Bonds shall be stated to mature, the principal amount thereof that shall be stated to mature on each such Principal Payment Date, the Principal Payment Date or Dates on which Term Bonds shall be subject to mandatory sinking fund redemption (each a "*Mandatory Redemption Date*") and the principal amount thereof that shall be payable pursuant to Mandatory Sinking Fund Redemption Requirements on each Mandatory Redemption Date.

(c) Conditions for Establishment of Interest Rates and Principal Payment Dates and Amounts. The rate or rates of interest per year to be borne by the Bonds, and the principal amount of Bonds maturing or payable pursuant to Mandatory Sinking Fund Redemption Requirements on each Principal Payment Date, shall be such that the total principal and interest payments on the Bonds in any fiscal year in which principal is payable is not more than three times the amount of those payments in any other fiscal year. The net interest cost for the Bonds determined by taking into account the respective principal amounts of the Bonds and terms to maturity or Mandatory Sinking Fund Redemption Requirements of those principal amounts of Bonds shall not exceed 6.00%.

(d) Payment of Debt Charges. The debt charges on the Bonds shall be payable in lawful money of the United States of America without deduction for the services of the Bond Registrar

as paying agent. Principal of and any premium on the Bonds shall be payable when due upon presentation and surrender of the Bonds at the designated corporate trust office of the Bond Registrar. Interest on a Bond shall be paid on each Interest Payment Date by check or draft mailed to the person in whose name the Bond was registered, and to that person's address appearing, on the Bond Register at the close of business on the 15th day of the calendar month next preceding that Interest Payment Date. Notwithstanding the foregoing, if and so long as the Bonds are issued in a book entry system, principal of and interest and any premium on the Bonds shall be payable in the manner provided in any agreement entered into by the City Auditor, in the name and on behalf of the City, in connection with the book entry system.

(e) Redemption Provisions. The Bonds shall be subject to redemption prior to stated maturity as follows:

(i) Mandatory Sinking Fund Redemption of Term Bonds. If any of the Bonds are issued as Term Bonds, the Term Bonds shall be subject to mandatory redemption in part by lot and be redeemed pursuant to mandatory sinking fund redemption requirements, at a redemption price of 100% of the principal amount redeemed, plus accrued interest to the redemption date, on the applicable Mandatory Redemption Dates and in the principal amounts payable on those Dates, for which provision is made in the Certificate of Award (such Dates and amounts being referred to as the "*Mandatory Sinking Fund Redemption Requirements*").

The aggregate of the moneys to be deposited with the Bond Registrar for payment of principal of and interest on any Term Bonds on each Mandatory Redemption Date shall include an amount sufficient to redeem on that Date the principal amount of Term Bonds payable on that Date pursuant to the Mandatory Sinking Fund Redemption Requirements (less the amount of any credit as hereinafter provided).

The City shall have the option to deliver to the Bond Registrar for cancellation Term Bonds in any aggregate principal amount and to receive a credit against the then current or any subsequent Mandatory Sinking Fund Redemption Requirement (and corresponding mandatory redemption obligation) of the City, as specified by the City Auditor, for Term Bonds stated to mature on the same Principal Payment Date and bearing interest at the same rate as the Term Bonds so delivered. That option shall be exercised by the City on or before the 45th day preceding any Mandatory Redemption Date with respect to which the City wishes to obtain a credit, by furnishing the Bond Registrar a certificate, signed by the City Auditor, setting forth the extent of the credit to be applied with respect to the then current or any subsequent Mandatory Sinking Fund Redemption Requirement for Term Bonds stated to mature on the same Principal Payment Date and bearing interest at the same rate as the Term Bonds so delivered. If the certificate is not timely furnished to the Bond Registrar, the current Mandatory Sinking Fund Redemption Requirement (and corresponding mandatory redemption obligation) shall not be reduced. A credit against the then current or any subsequent Mandatory Sinking Fund Redemption Requirement (and corresponding mandatory redemption obligation), as specified by the City Auditor, also shall be received by the City for any Term Bonds which prior thereto have been redeemed (other than through the operation of the applicable Mandatory Sinking Fund Redemption Requirements) or purchased for cancellation and canceled by the Bond Registrar, to the extent not applied theretofore as a credit against any Mandatory Sinking Fund Redemption Requirement, for Term Bonds stated to mature on the same Principal Payment Date and bearing interest at the same rate as the Term Bonds so redeemed or purchased and canceled.

Each Term Bond so delivered, or previously redeemed, or purchased and canceled, shall be credited by the Bond Registrar at 100% of the principal amount thereof against the then current or subsequent Mandatory Sinking Fund Redemption Requirements (and corresponding mandatory redemption obligations), as specified by the City Auditor, for Term Bonds stated to mature on the same Principal Payment Date and bearing interest at the same rate as the Term Bonds so delivered, redeemed or purchased and canceled.

(ii) Optional Redemption. The Bonds of the maturities and interest rates specified in the Certificate of Award (if any are so specified) shall be subject to optional redemption by and at the sole option of the City, in whole or in part in integral multiples of $5,000, on the dates and at the redemption prices (expressed as a percentage of the principal amount to be redeemed), plus accrued interest to the redemption date, to be determined by the City Auditor in the Certificate of Award; *provided* that the redemption price for any optional redemption date shall not be greater than 103%.

If optional redemption of Term Bonds at a redemption price exceeding 100% of the principal amount to be redeemed is to take place as of any Mandatory Redemption Date applicable to those Term Bonds, the Term Bonds, or portions thereof, to be redeemed optionally shall be selected by lot prior to the selection by lot of the Term Bonds of the same maturity (and interest rate within a maturity if applicable) to be redeemed on the same date by operation of the Mandatory Sinking Fund Redemption Requirements. Bonds to be redeemed pursuant to this paragraph shall be redeemed only upon written notice from the City Auditor to the Bond Registrar, given upon the direction of the City by passage of an ordinance or adoption of a resolution. That notice shall specify the redemption date and the principal amount of each maturity (and interest rate within a maturity if applicable) of Bonds to be redeemed, and shall be given at least 45 days prior to the redemption date or such shorter period as shall be acceptable to the Bond Registrar.

(iii) Partial Redemption. If fewer than all of the outstanding Bonds are called for optional redemption at one time and Bonds of more than one maturity (or interest rate within a maturity if applicable) are then outstanding, the Bonds that are called shall be Bonds of the maturity or maturities and interest rate or rates selected by the City. If fewer than all of the Bonds of a single maturity (or interest rate within a maturity if applicable) are to be redeemed, the selection of Bonds of that maturity (or interest rate within a maturity if applicable) to be redeemed, or portions thereof in amounts of $5,000 or any integral multiple thereof, shall be made by the Bond Registrar by lot in a manner determined by the Bond Registrar. In the case of a partial redemption of Bonds by lot when Bonds of denominations greater than $5,000 are then outstanding, each $5,000 unit of principal thereof shall be treated as if it were a separate Bond of the denomination of $5,000. If it is determined that one or more, but not all, of the $5,000 units of principal amount represented by a Bond are to be called for redemption, then, upon notice of redemption of a $5,000 unit or units, the registered owner of that Bond shall surrender the Bond to the Bond Registrar (A) for payment of the redemption price of the $5,000 unit or units of principal amount called for redemption (including, without limitation, the interest accrued to the date fixed for redemption and any premium), and (B) for issuance, without charge to the registered owner, of a new Bond or Bonds of any Authorized Denomination or Denominations in an aggregate principal amount equal to the unmatured and unredeemed portion of, and bearing interest at the same rate and maturing on the same date as, the Bond surrendered.

(iv) Notice of Redemption. The notice of the call for redemption of Bonds shall identify (A) by designation, letters, numbers or other distinguishing marks, the Bonds or portions thereof to

be redeemed, (B) the redemption price to be paid, (C) the date fixed for redemption, and (D) the place or places where the amounts due upon redemption are payable. The notice shall be given by the Bond Registrar on behalf of the City by mailing a copy of the redemption notice by first-class mail, postage prepaid, at least 30 days prior to the date fixed for redemption, to the registered owner of each Bond subject to redemption in whole or in part at the registered owner's address shown on the Bond Register maintained by the Bond Registrar at the close of business on the 15th day preceding that mailing. Failure to receive notice by mail or any defect in that notice regarding any Bond, however, shall not affect the validity of the proceedings for the redemption of any Bond.

(v) Payment of Redeemed Bonds. In the event that notice of redemption shall have been given by the Bond Registrar to the registered owners as provided above, there shall be deposited with the Bond Registrar on or prior to the redemption date, moneys that, in addition to any other moneys available therefor and held by the Bond Registrar, will be sufficient to redeem at the redemption price thereof, plus accrued interest to the redemption date, all of the redeemable Bonds for which notice of redemption has been given. Notice having been mailed in the manner provided in the preceding paragraph hereof, the Bonds and portions thereof called for redemption shall become due and payable on the redemption date, and, subject to the provisions of Sections 3(d) and 5, upon presentation and surrender thereof at the place or places specified in that notice, shall be paid at the redemption price, plus accrued interest to the redemption date. If moneys for the redemption of all of the Bonds and portions thereof to be redeemed, together with accrued interest thereon to the redemption date, are held by the Bond Registrar on the redemption date, so as to be available therefor on that date and, if notice of redemption has been deposited in the mail as aforesaid, then from and after the redemption date those Bonds and portions thereof called for redemption shall cease to bear interest and no longer shall be considered to be outstanding. If those moneys shall not be so available on the redemption date, or that notice shall not have been deposited in the mail as aforesaid, those Bonds and portions thereof shall continue to bear interest, until they are paid, at the same rate as they would have borne had they not been called for redemption. All moneys held by the Bond Registrar for the redemption of particular Bonds shall be held in trust for the account of the registered owners thereof and shall be paid to them, respectively, upon presentation and surrender of those Bonds; *provided* that any interest earned on the moneys so held by the Bond Registrar shall be for the account of and paid to the City to the extent not required for the payment of the Bonds called for redemption.

Section 4. Execution and Authentication of Bonds; Appointment of Bond Registrar. The Bonds shall be signed by the Mayor and the City Auditor, in the name of the City and in their official capacities; *provided* that either or both of those signatures may be a facsimile. The Bonds shall be issued in the Authorized Denominations and numbers as requested by the Original Purchaser and approved by the City Auditor, shall be numbered as determined by the City Auditor in order to distinguish each Bond from any other Bond, and shall express upon their faces the purpose, in summary terms, for which they are issued and that they are issued pursuant to Chapter 133 of the Ohio Revised Code, the Charter of the City, this Ordinance and the Certificate of Award.

The City Auditor is hereby authorized to designate in the Certificate of Award a bank or trust company authorized to do business in the State of Ohio to act as the initial Bond Registrar. The Mayor and the City Auditor shall sign and deliver, in the name and on behalf of the City, the Registrar Agreement between the City and the Bond Registrar, in substantially the form as is now on file with the Clerk of Council. The Registrar Agreement is approved, together with

any changes or amendments that are not inconsistent with this Ordinance and not substantially adverse to the City and that are approved by the Mayor and the City Auditor on behalf of the City, all of which shall be conclusively evidenced by the signing of the Registrar Agreement or amendments thereto. The City Auditor shall provide for the payment of the services rendered and for reimbursement of expenses incurred pursuant to the Registrar Agreement, except to the extent paid or reimbursed by the Original Purchaser and/or the Bond Registrar pursuant to the Certificate of Award and/or the Registrar Agreement, from the proceeds of the Bonds to the extent available and then from other money lawfully available and appropriated or to be appropriated for that purpose.

No Bond shall be valid or obligatory for any purpose or shall be entitled to any security or benefit under the Bond Proceedings unless and until the certificate of authentication printed on the Bond is signed by the Bond Registrar as authenticating agent. Authentication by the Bond Registrar shall be conclusive evidence that the Bond so authenticated has been duly issued, signed and delivered under, and is entitled to the security and benefit of, the Bond Proceedings. The certificate of authentication may be signed by any authorized officer or employee of the Bond Registrar or by any other person acting as an agent of the Bond Registrar and approved by the City Auditor on behalf of the City. The same person need not sign the certificate of authentication on all of the Bonds.

Section 5. Registration; Transfer and Exchange; Book Entry System.

(a) Bond Register. So long as any of the Bonds remain outstanding, the City will cause the Bond Registrar to maintain and keep the Bond Register at its designated corporate trust office. Subject to the provisions of Sections 3(d) and 9(c), the person in whose name a Bond is registered on the Bond Register shall be regarded as the absolute owner of that Bond for all purposes of the Bond Proceedings. Payment of or on account of the debt charges on any Bond shall be made only to or upon the order of that person; neither the City nor the Bond Registrar shall be affected by any notice to the contrary, but the registration may be changed as provided in this Section 5. All such payments shall be valid and effectual to satisfy and discharge the City's liability upon the Bond, including interest, to the extent of the amount or amounts so paid.

(b) Transfer and Exchange. Any Bond may be exchanged for Bonds of any Authorized Denomination upon presentation and surrender at the designated corporate trust office of the Bond Registrar, together with a request for exchange signed by the registered owner or by a person legally empowered to do so in a form satisfactory to the Bond Registrar. A Bond may be transferred only on the Bond Register upon presentation and surrender of the Bond at the designated corporate trust office of the Bond Registrar together with an assignment signed by the registered owner or by a person legally empowered to do so in a form satisfactory to the Bond Registrar. Upon exchange or transfer the Bond Registrar shall complete, authenticate and deliver a new Bond or Bonds of any Authorized Denomination or Denominations requested by the owner equal in the aggregate to the unmatured principal amount of the Bond surrendered and bearing interest at the same rate and maturing on the same date.

If manual signatures on behalf of the City are required, the Bond Registrar shall undertake the exchange or transfer of Bonds only after the new Bonds are signed by the authorized officers of the City. In all cases of Bonds exchanged or transferred, the City shall sign and the Bond Registrar shall authenticate and deliver Bonds in accordance with the provisions of the Bond Proceedings. The exchange or transfer shall be without charge to the owner, except that the City and Bond Registrar may make a charge sufficient to reimburse them for any tax or other governmental charge required to be paid with respect to the exchange or transfer. The City or the Bond Registrar may require that those charges, if any, be paid before the procedure is

begun for the exchange or transfer. All Bonds issued and authenticated upon any exchange or transfer shall be valid obligations of the City, evidencing the same debt, and entitled to the same security and benefit under the Bond Proceedings as the Bonds surrendered upon that exchange or transfer. Neither the City nor the Bond Registrar shall be required to make any exchange or transfer of (i) Bonds then subject to call for redemption between the 15th day preceding the mailing of notice of Bonds to be redeemed and the date of that mailing, or (ii) any Bond selected for redemption, in whole or in part.

(c) Book Entry System. Notwithstanding any other provisions of this Ordinance, if the City Auditor determines in the Certificate of Award that it is in the best interest of and financially advantageous to the City, the Bonds may be issued in book entry form in accordance with the following provisions of this Section 5.

The Bonds may be issued to a Depository for use in a book entry system and, if and as long as a book entry system is utilized: (i) the Bonds may be issued in the form of a single, fully registered Bond representing each maturity, and, if applicable, each interest rate within a maturity, and registered in the name of the Depository or its nominee, as registered owner, and immobilized in the custody of the Depository or its designated agent for that purpose, which may be the Bond Registrar; (ii) the beneficial owners of Bonds in book entry form shall have no right to receive Bonds in the form of physical securities or certificates; (iii) ownership of beneficial interests in book entry form shall be shown by book entry on the system maintained and operated by the Depository and its Participants, and transfers of the ownership of beneficial interests shall be made only by book entry by the Depository and its Participants; and (iv) the Bonds as such shall not be transferable or exchangeable, except for transfer to another Depository or to another nominee of a Depository, without further action by the City.

If any Depository determines not to continue to act as a Depository for the Bonds for use in a book entry system, the City Auditor may attempt to establish a securities depository/book entry relationship with another qualified Depository. If the City Auditor does not or is unable to do so, the City Auditor, after making provision for notification of the beneficial owners by the then Depository and any other arrangements deemed necessary, shall permit withdrawal of the Bonds from the Depository, and shall cause Bond certificates in registered form and Authorized Denominations to be authenticated by the Bond Registrar and delivered to the assigns of the Depository or its nominee, all at the cost and expense (including any costs of printing), if the event is not the result of City action or inaction, of those persons requesting such issuance.

The City Auditor is hereby authorized and directed, to the extent necessary or required, to enter into any agreements, in the name and on behalf of the City, that the City Auditor determines to be necessary in connection with a book entry system for the Bonds.

Section 6. Sale of the Bonds to the Original Purchaser. The City Auditor is authorized to sell the Bonds at private sale to the Original Purchaser at a purchase price, not less than 97% of the aggregate principal amount thereof, as shall be determined by the City Auditor in the Certificate of Award, plus accrued interest (if any) on the Bonds from their date to the Closing Date, and shall be awarded by the City Auditor with and upon such other terms as are required or authorized by this Ordinance to be specified in the Certificate of Award, in accordance with law and the provisions of this Ordinance and the Certificate of Award. The City Auditor is authorized, if it is determined to be in the best interest of the City, to combine the issue of Bonds with one or more other bond issues of the City into a consolidated bond issue pursuant to Section 133.30(B) of the Ohio Revised Code in which case a single Certificate of Award may be utilized for the consolidated bond issue if appropriate and consistent with the terms of

this Ordinance.
The City Auditor shall sign and deliver the Certificate of Award and shall cause the Bonds to be prepared and signed and delivered, together with a true transcript of proceedings with reference to the issuance of the Bonds, to the Original Purchaser upon payment of the purchase price.
The Mayor, the City Auditor, the City Attorney, the Clerk of Council and other City officials, as appropriate, are each authorized and directed to sign any transcript certificates, financial statements and other documents and instruments and to take such actions as are necessary or appropriate to consummate the transactions contemplated by this Ordinance. Any actions heretofore taken by the Mayor, the City Auditor, the City Attorney, the Clerk of Council or other City official, as appropriate, in doing any and all acts necessary in connection with the issuance and sale of the Bonds are hereby ratified and confirmed.

Section 7. Provision for Tax Levy. There shall be levied on all the taxable property in the City, in addition to all other taxes, a direct tax annually during the period the Bonds are outstanding in an amount sufficient to pay the debt charges on the Bonds when due, which tax shall not be less than the interest and sinking fund tax required by Section 11 of Article XII of the Ohio Constitution. The tax shall be within the ten-mill limitation imposed by law, shall be and is ordered computed, certified, levied and extended upon the tax duplicate and collected by the same officers, in the same manner and at the same time that taxes for general purposes for each of those years are certified, levied, extended and collected, and shall be placed before and in preference to all other items and for the full amount thereof. The proceeds of the tax levy shall be placed in the Bond Retirement Fund, which is irrevocably pledged for the payment of the debt charges on the Bonds when and as the same fall due.
In each year to the extent the net revenues from the municipal waterworks system are available for the payment of the debt charges on the Bonds and are appropriated for that purpose, the amount of the tax shall be reduced by the amount of such net revenues so available and appropriated.
In each year to the extent receipts from the municipal income tax are available for the payment of the debt charges on the Bonds and are appropriated for that purpose, and to the extent not paid from net revenues of the municipal waterworks system, the amount of the tax shall be reduced by the amount of such receipts so available and appropriated in compliance with the following covenant. To the extent necessary, the debt charges on the Bonds shall be paid from municipal income taxes lawfully available therefor under the Constitution and the laws of the State of Ohio, and the Charter of the City; and the City hereby covenants, subject and pursuant to such authority, including particularly Section 133.05(B)(7) of the Ohio Revised Code, to appropriate annually from such municipal income taxes such amount as is necessary to meet such annual debt charges.
Nothing in the two preceding paragraphs in any way diminishes the irrevocable pledge of the full faith and credit and general property taxing power of the City to the prompt payment of the debt charges on the Bonds.

Section 8. Federal Tax Considerations. The City covenants that it will use, and will restrict the use and investment of, the proceeds of the Bonds in such manner and to such extent as may be necessary so that (a) the Bonds will not (i) constitute private activity bonds or arbitrage bonds under Sections 141 or 148 of the Code or (ii) be treated other than as bonds the interest on which is excluded from gross income under Section 103 of the Code, and (b) the interest on the Bonds will not be an item of tax preference under Section 57 of the Code.

The City further covenants that (a) it will take or cause to be taken such actions that may be required of it for the interest on the Bonds to be and remain excluded from gross income for federal income tax purposes, (b) it will not take or authorize to be taken any actions that would adversely affect that exclusion, and (c) it, or persons acting for it, will, among other acts of compliance, (i) apply the proceeds of the Bonds to the governmental purpose of the borrowing, (ii) restrict the yield on investment property, (iii) make timely and adequate payments to the federal government, (iv) maintain books and records and make calculations and reports and (v) refrain from certain uses of those proceeds, and, as applicable, of property financed with such proceeds, all in such manner and to the extent necessary to assure such exclusion of that interest under the Code.

The City Auditor or any other officer of the City having responsibility for issuance of the Bonds is hereby authorized (a) to make or effect any election, selection, designation, choice, consent, approval, or waiver on behalf of the City with respect to the Bonds as the City is permitted to or required to make or give under the federal income tax laws, including, without limitation thereto, any of the elections available under Section 148 of the Code, for the purpose of assuring, enhancing or protecting favorable tax treatment or status of the Bonds or interest thereon or assisting compliance with requirements for that purpose, reducing the burden or expense of such compliance, reducing the rebate amount or payments or penalties with respect to the Bonds, or making payments of special amounts in lieu of making computations to determine, or paying, excess earnings as rebate, or obviating those amounts or payments with respect to the Bonds, which action shall be in writing and signed by the officer, (b) to take any and all other actions, make or obtain calculations, make payments, and make or give reports, covenants and certifications of and on behalf of the City, as may be appropriate to assure the exclusion of interest from gross income and the intended tax status of the Bonds, and (c) to give one or more appropriate certificates of the City, for inclusion in the transcript of proceedings for the Bonds, setting forth the reasonable expectations of the City regarding the amount and use of all the proceeds of the Bonds, the facts, circumstances and estimates on which they are based, and other facts and circumstances relevant to the tax treatment of the interest on and the tax status of the Bonds. The City Auditor or any other officer of the City having responsibility for issuance of the Bonds is specifically authorized to designate the Bonds as “qualified tax-exempt obligations” if such designation is applicable and desirable, and to make any related necessary representations and covenants.

Section 9. Official Statement, Rating, Bond Insurance, Continuing Disclosure and Financing Costs.

(a) Primary Offering Disclosure -- Official Statement. The Mayor and the City Auditor are each authorized and directed, on behalf of the City and in their official capacities, to (i) prepare or cause to be prepared, and make or authorize modifications, completions or changes of or supplements to, a disclosure document in the form of an official statement relating to the original issuance of the Bonds in substantially the form as is now on file with the Clerk of Council, (ii) determine, and to certify or otherwise represent, when the official statement is to be “deemed final” (except for permitted omissions) by the City as of its date or is a final official statement for purposes of paragraph (b) of the Rule, (iii) use and distribute, or authorize the use and distribution of those official statements and any supplements thereto in connection with the original issuance of the Bonds, and (iv) complete and sign those official statements and any supplements thereto as so approved, together with such certificates, statements or other documents in connection with the finality, accuracy and completeness of those official statements and any supplements, as they may deem necessary or appropriate.

(b) Application for Rating or Bond Insurance. If, in the judgment of the City Auditor, the filing of an application for (i) a rating on the Bonds by one or more nationally-recognized rating agencies, or (ii) a policy of insurance from a company or companies to better assure the payment of principal of and interest on the Bonds, is in the best interest of and financially advantageous to this City, the City Auditor is authorized to prepare and submit those applications, to provide to each such agency or company such information as may be required for the purpose, and to provide further for the payment of the cost of obtaining each such rating or policy, except to the extent otherwise paid or reimbursed pursuant to the Certificate of Award and/or the Registrar Agreement, from the proceeds of the Bonds to the extent available and otherwise from any other funds lawfully available and that are appropriated or shall be appropriated for that purpose. The City Auditor is hereby authorized, to the extent necessary or required, to enter into any agreements, in the name of and on behalf of the City, that the City Auditor determines to be necessary in connection with the obtaining of that bond insurance.

(c) Agreement to Provide Continuing Disclosure. For the benefit of the holders and beneficial owners from time to time of the Bonds, the City agrees to provide or cause to be provided such financial information and operating data, audited financial statements and notices of the occurrence of certain events, in such manner as may be required for purposes of the Rule. The Mayor and the City Auditor are each authorized and directed to complete, sign and deliver the Continuing Disclosure Agreement, in the name and on behalf of the City, in substantially the form as is now on file with the Clerk of Council. The Continuing Disclosure Agreement is approved, together with any changes or amendments that are not inconsistent with this Ordinance and not substantially adverse to the City and that are approved by the Mayor and the City Auditor on behalf of the City, all of which shall be conclusively evidenced by the signing of the Continuing Disclosure Agreement or amendments thereto.

The City Auditor is further authorized and directed to establish procedures in order to ensure compliance by the City with its Continuing Disclosure Agreement, including timely provision of information and notices as described above. Prior to making any filing required under the Rule, the City Auditor shall consult with and obtain legal advice from, as appropriate, the City Attorney and bond or other qualified independent special counsel selected by the City. The City Auditor, acting in the name and on behalf of the City, shall be entitled to rely upon any such legal advice in determining whether a filing should be made. The performance by the City of its Continuing Disclosure Agreement shall be subject to the annual appropriation of any funds that may be necessary to perform it.

(d) Financing Costs. The expenditure of the amounts necessary to pay any Financing Costs in connection with the Bonds, to the extent not paid or reimbursed by the Original Purchaser and/or the Bond Registrar in accordance with the Certificate of Award and/or the Registrar Agreement, is authorized and approved, and the City Auditor is authorized to provide for the payment of any such amounts and costs from the proceeds of the Bonds to the extent available and otherwise from any other funds lawfully available that are appropriated or shall be appropriated for that purpose.

Section 10. Bond Counsel. The legal services of the law firm of Squire Patton Boggs (US) LLP, as bond counsel, are hereby retained. Those legal services shall be in the nature of legal advice and recommendations as to the documents and the proceedings in connection with the authorization, sale and issuance of the Bonds and rendering at delivery related legal opinions, all as set forth in the form of engagement letter from that firm which is now on file in the office of the Clerk of Council. In providing those legal services, as an independent contractor and in

an attorney-client relationship, that firm shall not exercise any administrative discretion on behalf of this City in the formulation of public policy, expenditure of public funds, enforcement of laws, rules and regulations of the State of Ohio, any county or municipal corporation or of this City, or the execution of public trusts. For those legal services, that firm shall be paid just and reasonable compensation and shall be reimbursed for actual out-of-pocket expenses incurred in providing those legal services.

To the extent they are not paid or reimbursed pursuant to the Certificate of Award and/or the Registrar Agreement, the City Auditor is authorized and directed to make appropriate certification as to the availability of funds for those fees and any reimbursement and to issue an appropriate order for their timely payment as written statements are submitted by that firm. The amounts necessary to pay those fees and any reimbursement are hereby appropriated from the proceeds of the Bonds, if available, and otherwise from available moneys in the General Fund.

Section 11. Municipal Advisor. The services of Baker Tilly Municipal Advisors, LLC, as municipal advisor, are hereby retained. The municipal advisory services shall be in the nature of financial advice and recommendations in connection with the issuance and sale of the Bonds. In rendering those municipal advisory services, as an independent contractor, that firm shall not exercise any administrative discretion on behalf of the City in the formulation of public policy, expenditure of public funds, enforcement of laws, rules and regulations of the State of Ohio, the City or any other political subdivision, or the execution of public trusts. That firm shall be paid just and reasonable compensation for those municipal advisory services and shall be reimbursed for the actual out-of pocket expenses it incurs in rendering those municipal advisory services. To the extent they are not paid or reimbursed pursuant to the Certificate of Award and/or the Registrar Agreement, the City Auditor is authorized and directed to make appropriate certification as to the availability of funds for those fees and any reimbursement and to issue an appropriate order for their timely payment as written statements are submitted by that firm. The amounts necessary to pay those fees and any reimbursement are hereby appropriated from the proceeds of the Bonds, if available, and otherwise from available moneys in the General Fund.

Section 12. Certification and Delivery of Ordinance and Certificate of Award. The Clerk of Council is directed to promptly deliver or cause to be delivered a certified copy of this Ordinance and an executed copy of the Certificate of Award to the County Auditors of Fairfield, Franklin and Licking Counties, Ohio.

Section 13. Satisfaction of Conditions for Bond Issuance. This City Council determines that all acts and conditions necessary to be done or performed by the City or to have been met precedent to and in the issuing of the Bonds in order to make them legal, valid and binding general obligations of the City have been performed and have been met, or will at the time of delivery of the Bonds have been performed and have been met, in regular and due form as required by law; that the full faith and credit and general property taxing power (as described in Section 7) of the City are pledged for the timely payment of the debt charges on the Bonds; that no statutory or constitutional limitation of indebtedness or taxation will have been exceeded in the issuance of the Bonds; and that the Bonds are being authorized and issued pursuant to Chapter 133 of the Ohio Revised Code, the Charter of the City, this Ordinance, the Certificate of Award and other authorizing provisions of law.

Section 14. Compliance with Open Meeting Requirements. This City Council finds and determines that all formal actions of this City Council and any of its committees concerning and relating to the passage of this Ordinance were taken in an open meeting of this City Council or any of its committees, and that all deliberations of this City Council and of any of its committees that resulted in those formal actions were in meetings open to the public, all in compliance with the law, including Section 121.22 of the Ohio Revised Code.

Section 15. Effective Date. This Ordinance is declared to be an emergency measure necessary for the immediate preservation of the public peace, health and safety, and for the further reason that this Ordinance is required to be immediately effective in order to issue and sell the Bonds, which is necessary to enable the City to timely enter into contracts for the construction of the Improvement; wherefore, this Ordinance shall be in full force and effect immediately upon its passage.

BOND REGISTRAR AGREEMENT

This BOND REGISTRAR AGREEMENT (the "*Agreement*") is made and entered into as of March ___, 2026, and under the circumstances summarized in the following recitals, by and between the City of Reynoldsburg, Ohio (the "*Issuer*"), a municipal corporation and political subdivision duly organized and validly existing under the Constitution and laws of the State of Ohio and its Charter and Argent Institutional Trust Company, in Columbus, Ohio (the "*Bond Registrar*"), a national banking association duly organized and validly existing under the laws of the United States of America and authorized to exercise corporate trust powers under the laws of the State of Ohio, in connection with the issuance and servicing of $_____ Various Purpose Bonds, Series 2026, dated March ___, 2026 (the "*Bonds*"):

A. By Ordinances No. _____-2025 and No. _____-2025, each passed by the City Council of the Issuer on December ___, 2025 (collectively, the "*Bond Ordinance*"), and the Certificate of Award dated February ___, 2026 and signed by the City Auditor pursuant to the Bond Ordinance (the "*Certificate of Award*" and together with the Bond Ordinance, the "*Bond Legislation*"), a copy of which is attached hereto as **EXHIBIT A**, the Issuer has authorized the issuance and sale of the Bonds.

B. By the Bond Legislation and pursuant to Section 9.96 and Chapter 133 of the Ohio Revised Code, the Issuer has appointed the Bond Registrar as its agent to act as authenticating agent, bond registrar, transfer agent and paying agent for and in connection with the Bonds, and has authorized and directed the Bond Registrar to keep all the books and records necessary for registration, exchange and transfer of the Bonds (the "*Bond Register*").

C. The Issuer has determined that the Bonds will be initially issued and issuable in book entry form, with one fully registered Bond for each maturity, registered in the name of Cede & Co., as nominee for The Depository Trust Company ("*DTC*"). The fully registered Bonds will be deposited with and retained in the custody of DTC or the Bond Registrar as its agent pursuant to any custodial relationship between the Bond Registrar and DTC with respect to the holding of the Bonds by the Bond Registrar under the DTC-FAST system for use in a book entry system. The Issuer has executed, and DTC has accepted, a Blanket Issuer Letter of Representations to DTC (the "*DTC Letter*") pertaining to the book entry system, a copy of which DTC Letter is included in the transcript of proceedings for the Bonds.

D. Capitalized words and terms used herein and not otherwise defined shall have the meanings set forth in the Bond Legislation.

NOW, THEREFORE, in consideration of the premises and the mutual agreements hereinafter contained, the Issuer and the Bond Registrar agree as follows:

Section 1. In connection with the original issuance and delivery of the Bonds:

(a) The Issuer will deliver to the Bond Registrar no later than two (2) business days prior to the day set for delivery of the Bonds to the Original Purchaser (the "*Closing*"):

(i) specimens of the signatures or facsimile signatures of the officers of the Issuer whose signatures or facsimile signatures appear on the Bonds;

Draft of 12-4-2025

(ii) _____ (__) Bond certificates (one for each maturity of the Bonds), completed with numbers, principal amounts, and denominations and listing Cede & Co., as nominee for DTC, as the registered owner, to be delivered at the Closing and such additional bond forms with appropriate blank spaces to be filled in (the "*Bond Forms*"), in sufficient number to provide for future transfers, as agreed upon by the Issuer and the Bond Registrar; and

(iii) a completed Request to Authenticate and Deliver in the form attached hereto as **EXHIBIT B**.

(b) The Bond Registrar shall review the Bonds to be delivered at the Closing to confirm the numbers, principal amounts, interest rates, denominations and other pertinent information and record the name and address of Cede & Co., as nominee for DTC, as registered owner of the Bonds, in the Bond Register, all so as to permit delivery of those Bonds at the time and place of the Closing.

(c) No later than two (2) business days before the Closing, the Bond Registrar, through one or more duly authorized officers or employees, or through another authorized person acting as an agent of the Bond Registrar and approved by the Issuer, shall sign the Certificate of Authentication on each of the Bonds to be delivered at the Closing. At least two (2) business days prior to the Closing, the authenticated Bonds shall be delivered to DTC, or retained by the Bond Registrar as DTC's agent pursuant to a custodial relationship between the Bond Registrar and DTC with respect to the holding of the Bonds by the Bond Registrar under the DTC-FAST system, against a safekeeping receipt provided by DTC. No further disposition or release will be made of the Bonds or interests in the Bonds until payment for the Bonds has been made by _____, in _____, ____ (the "*Original Purchaser*"), to the Issuer in accordance with the instructions in the Request to Authenticate and Deliver.

(d) Upon confirmation by the Issuer of its receipt of payment of the purchase price for the Bonds, the Bond Registrar, on behalf of the Issuer, will contact DTC and authorize the release and delivery of the Bonds in accordance with the instructions in the Request to Authenticate and Deliver.

(e) **[**As requested by the Original Purchaser and in accordance with the Bond Legislation, the Bond Registrar shall establish a Cost of Issuance Fund and provide for the payment of certain Financing Costs as described in **EXHIBIT D**. Any balance remaining in the Cost of Issuance Fund after thirty (30) days from the date of this Agreement shall be forwarded to the Issuer and the Cost of Issuance Fund shall be closed. For this service, the Bond Registrar shall be paid a fee of $_____ at Closing.**]**

(f) The Issuer consents to the Bond Registrar acting as agent for DTC pursuant to an existing custodial relationship between the Bond Registrar and DTC with respect to the holding of the Bonds by the Bond Registrar under the DTC-FAST system.

Section 2. The Bond Registrar shall hold in safekeeping any Bond Forms delivered to it by the Issuer and not delivered at the Closing, as set forth in the form of Receipt attached hereto as **EXHIBIT C**, and shall notify the Issuer of any need for additional Bond Forms in sufficient time

Draft of 12-4-2025

to permit an adequate supply to be available for the purposes set forth in Section 1(a)(ii) and Section 4 of this Agreement.

Section 3. So long as any of the Bonds remain outstanding, the Bond Registrar will keep and maintain, at its designated corporate trust office, the Bond Register, initially its Columbus, Ohio corporate trust office, on which it will maintain a current and accurate record of the names and addresses of the registered owners of the Bonds (the "*Owners*"), and shall perform, without limitation, authentication, registration, exchange, transfer and paying agent functions and related mechanical, clerical and record or bookkeeping functions in connection with the Bonds, all in accordance with this Agreement, the Bond Legislation, Section 9.96 of the Ohio Revised Code, the DTC Letter and any applicable requirements of Section 149(a) of the Internal Revenue Code of 1986, as amended, and regulations, proposed regulations and rulings under that Section 149(a).

As used in this Section:

"*Book Entry Form*" or "*Book Entry System*" means a form or system under which (a) the ownership of beneficial interests in the Bonds and the principal of and interest and any premium on the Bonds may be transferred only through a book entry, and (b) physical Bond certificates in fully registered form are issued by the Issuer and payable only to a Depository or its nominee as registered owner, with the certificates deposited with and "immobilized" in the custody of the Depository or its designated agent for that purpose. The book entry maintained by others than the Issuer or the Bond Registrar is the record that identifies the owners of beneficial interests in the Bonds and that principal and interest.

"*Depository*" means any securities depository that is a clearing agency registered pursuant to the provisions of Section 17A of the Securities Exchange Act of 1934, operating and maintaining, with its Participants or otherwise, a Book Entry System to record ownership of beneficial interests in the Bonds or the principal of and interest and any premium on the Bonds, and to effect transfers of the Bonds, in Book Entry Form, and includes and means initially DTC.

"*Participant*" means any participant contracting with a Depository under a Book Entry System and includes securities brokers and dealers, banks and trust companies and clearing corporations.

The Bonds shall be originally issued to a Depository for use in a Book Entry System and: (a) such Bonds shall be registered in the name of the Depository or its nominee, as Owner, and deposited with and retained in the custody of the Depository or its agent; (b) there shall be a single, fully registered Bond representing each maturity; and (c) such Bonds shall not be transferable or exchangeable, except for transfer to another Depository or another nominee of a Depository, without further action by the Issuer as set forth in the Bond Legislation. The owners of book entry interests in the Bonds shall not, except as provided in the Bond Legislation, have any right to receive Bonds in the form of physical securities or certificates. The Issuer and the Bond Registrar shall have no duties, obligations or responsibilities in connection with transfers or sales of book entry interests.

Except as provided in subsection (c) of Section 9 of the Bond Ordinance, the Issuer and the Bond Registrar will recognize and treat the Depository as the owner of the Bonds for all

Draft of 12-4-2025

purposes, including payment of debt charges, redemption and other notices and enforcement of remedies. Crediting of debt charge payments and transmittal of notices and other communications by the Depository to Participants, by Participants to indirect Participants, and by Participants and indirect Participants to the book entry interest owners, will be handled under arrangements among them.

Neither the Issuer nor the Bond Registrar shall have any responsibility or liability for any aspects of the records relating to, or payments made on account of, book entry interest ownership, or for maintaining, supervising or reviewing any records relating to such ownership; or for the distribution by the Depository, Participants or others to the book entry interest owners of (a) payments of debt charges paid on the Bonds, or (b) redemption or other notices sent to the Depository as the registered owner, or that they will do so on a timely basis.

If any Depository determines not to continue to act as a Depository for the Bonds for use in a Book Entry System, the Issuer may attempt to have established a securities depository/Book Entry System relationship with another qualified Depository pursuant to the Bond Legislation. If the Issuer does not or is unable to do so, the Issuer, after the Bond Registrar, at the direction of the Issuer, has made provision for notification of the owners of book entry interests in the Bonds by appropriate notice to the then Depository, shall permit withdrawal of the Bonds from the Depository or its agent, and shall authenticate and deliver Bond certificates in fully registered form to the assignees of the Depository or its nominee. If the event is not the result of Issuer action or inaction, such withdrawal, authentication and delivery shall be at the cost and expense (including costs of printing, or otherwise preparing, and delivering such replacement Bonds), of those persons requesting that authentication and delivery. Such replacement Bonds shall be in Authorized Denominations.

The Issuer and the Bond Registrar hereby covenant and agree to perform any and all of their respective duties and obligations arising out of the representations made by the Issuer in the DTC Letter.

Section 4. In accordance with the Bond Legislation and except as provided with respect to Bonds in Book Entry Form as provided in Section 3 hereof, the Bond Registrar shall:

(a) Exchange or transfer Bonds upon presentation and surrender at the designated corporate trust office of the Bond Registrar, together with a request for exchange or an assignment signed by the Owner or by a person legally empowered to do so, in a form satisfactory to the Bond Registrar, and shall complete, authenticate and deliver new Bonds to the Owner or the new Owner of the transferred Bonds or its agent in an authorized denomination or denominations equal in the aggregate to the unmatured principal amount of the Bonds surrendered. The new Bonds will bear interest at the same rate and mature on the same date as the surrendered Bonds.

(b) Record the exchange or transfer of any Bond on the Bond Register.

(c) If manual signatures on behalf of the Issuer are required, undertake the above actions only after the new Bonds are signed by the authorized officers of the Issuer.

(d) Complete the transfer or exchange, and completion, authentication and delivery of the new Bonds, in accordance with the standards and conditions applicable to registered corporate

Draft of 12-4-2025

securities established in the Securities and Exchange Commission regulation §240.17 Ad-1 and -2 as promulgated under Section 17A of the Securities Exchange Act of 1934, as amended.

(e) Give notice on behalf of the Issuer of any calls for redemption of Bonds.

(f) Hold moneys provided by the Issuer for redemption of particular Bonds in trust for the account of the Owners of those Bonds, and pay those moneys to those Owners upon presentation and surrender of those Bonds.

Section 5. Every exchange or transfer of the Bonds will be made without charge to the Owners, except that the Issuer and the Bond Registrar may make a charge sufficient to reimburse them for any tax or other governmental charge required to be paid with respect to the exchange or transfer. The Bond Registrar may require that those charges, if any, be paid before it begins the procedure for the exchange or transfer.

Section 6. The Bonds shall be subject to optional **[**and mandatory**]** redemption prior to maturity as provided in the Bond Legislation. To exercise its right of optional redemption, the Issuer shall give written notice to the Bond Registrar of its election to redeem and of the redemption date and the principal amount of Bonds to be redeemed. That notice shall be given at least 45 days prior to the redemption date or such shorter period as shall be acceptable to the Bond Registrar. Upon receipt of such notice, the Bond Registrar shall give notice of redemption of Bonds, call Bonds, hold moneys provided by the Issuer for redemption of particular Bonds in trust for the account of the Owners of those Bonds, and pay those moneys to those Owners, all in accordance with the provisions of the Bond Legislation, this Agreement and the DTC Letter.

The Bond Registrar shall not be required to make any exchange or transfer of a Bond during the period beginning at the opening of business 15 days before the day of the mailing of a notice of redemption of Bonds to the Owners and ending at the close of business on the day of such mailing or to transfer or exchange any Bond selected for redemption, in whole or in part.

Section 7. The Bond Registrar shall complete, authenticate, deliver and register new Bonds to replace Bonds lost, stolen, destroyed or mutilated upon receiving written instructions to do so from the City Auditor together with evidence of indemnification by the Owner of the Issuer and the Bond Registrar in a form satisfactory to the Issuer and the Bond Registrar.

Section 8. The Bond Registrar shall cancel any Bonds surrendered to it pursuant to the Bond Legislation for payment or retirement or for exchange, replacement or transfer. Written reports of surrender and cancellation of the Bonds shall be made to the City Auditor by the Bond Registrar upon written request. Unless otherwise directed by the Issuer or other lawful authority, cancelled Bonds shall be retained and stored by the Bond Registrar for a period of seven (7) years. After that time, or at any earlier time as authorized by the Issuer, the cancelled Bonds may, at the direction of the City Auditor, be either returned to the Issuer or destroyed by the Bond Registrar by shredding or cremation, and certificates of that destruction (describing the manner of that destruction) shall be provided by the Bond Registrar to the City Auditor.

Section 9. The Bond Registrar shall retain and store the Bond Register for seven (7) years after payment of all of the Bonds. At any time and upon request by the Issuer, the Bond Registrar shall permit the Issuer to inspect the Bond Register and will provide the Issuer with a

Draft of 12-4-2025

copy of the Bond Register. The Bond Registrar and the Issuer acknowledge that pursuant to Section 9.96 of the Ohio Revised Code the Bond Register is not a "public record" under Ohio law. In the event of a request to the Bond Registrar by any person other than the Issuer for inspection of the Bond Register, the Bond Registrar shall notify the City Auditor and will not permit that inspection unless it is approved by the City Auditor, except that the Bond Registrar may permit an inspection pursuant to an order of a court of competent jurisdiction.

Section 10. The Bond Registrar shall pay the debt charges on the Bonds in accordance with the Bond Legislation and the DTC Letter, but only from money deposited with the Bond Registrar by the Issuer for that purpose. The Issuer shall cause funds to be on deposit with the Bond Registrar in an amount sufficient and available to pay the interest, or principal and interest, then to be due no later than 10:00 a.m. (Ohio time) on the business day immediately preceding the date on which that payment is to be made.

The Bond Registrar will keep and maintain records of its receipt of moneys from the Issuer and its disbursement of those moneys and will make those records available to the City Auditor upon request.

Section 11. The Bond Registrar agrees to undertake **[**the**]** **[**all other**]** duties and obligations and to perform all services contemplated to be performed under this Agreement. For its ordinary services, the Issuer shall pay the Bond Registrar a **[**fee of $_____ [at Closing] [within thirty (30) days after the Closing], together with an annual fee of $_____ thereafter within forty-five (45) days of receipt of invoice from the Bond Registrar in each year that Bonds are outstanding,**]** **[**single one-time fee of $_____ within thirty (30) days after the Closing**]**, plus reasonable out-of-pocket expenses, disbursements and advances made by the Bond Registrar in accordance with the terms of this Agreement (including attorney fees and expenses), which the Bond Registrar hereby acknowledges to be the compensation due to it during the life of the Bonds for the performance of its ordinary services contemplated by this Agreement. If the Bond Registrar is required by a governmental agency or court proceeding initiated by a third party to undertake actions or duties beyond those which are set forth herein but related thereto, the Bond Registrar shall promptly provide written notice thereof to the Issuer. Payment of the Bond Registrar's fees and expenses for such extraordinary services shall be made by the Issuer only after such notice and shall be subject to Issuer approval and appropriation of funds for that purpose.

Section 12. In the absence of bad faith on its part in the performance of its services under this Agreement, the Bond Registrar will be protected in acting upon any notice, request, certificate, affidavit, letter, telegram or other paper or document believed reasonably by it to be genuine and correct and to have been signed or sent by the proper party or parties.

At any time, the Bond Registrar may apply to the City Auditor for instructions, and may, with the consent of the Issuer, consult with bond counsel for the Issuer, or, in the discretion of the Bond Registrar, it may consult with its own counsel, as to anything arising in connection with the duties herein undertaken, and it shall not be liable for any action taken or omitted by it in good faith in reliance upon such written instructions or upon the written opinions of such counsel; *provided*, *however*, that before relying upon the opinion of its own counsel it shall furnish to both the Issuer and to bond counsel for the Issuer a copy of such opinion.

Draft of 12-4-2025

Section 13. No provision of this Agreement shall be construed to relieve the Bond Registrar from liability for its negligent action, its negligent failure to act, or its willful misconduct, except that:

(a) the Bond Registrar shall not be liable for any error of judgment made in good faith by one of its officers unless it shall be proved that it was negligent in ascertaining the pertinent facts; and

(b) no provision of this Agreement shall require the Bond Registrar to expend or risk its own funds or otherwise incur any financial liability in the performance of any of its duties hereunder, or in the exercise of any of its rights or powers.

Section 14. The Bond Registrar may resign as Bond Registrar at any time by giving ninety (90) days (or such shorter time as is approved in writing by the City Auditor) written notice of resignation to the Issuer. The Bond Registrar may be removed at any time by written notice to that effect specifying the date and time of termination, signed on behalf of the Issuer by the City Auditor and delivered to the Bond Registrar. Upon the effectiveness of the resignation or termination, the Bond Registrar shall deliver to the Issuer, or such other person designated by the Issuer, the Bond Register and all other records (or copies of those records) pertaining to the Bonds and all Bond Forms and canceled Bonds.

Any corporation or association with or into which the Bond Registrar or any successor may be merged or converted or with which it or any successor may be consolidated, or any corporation or association resulting from any merger, consolidation or conversion to which the Bond Registrar or any successor shall be a party, or any corporation or association succeeding to all or substantially all of the corporate trust business of the Bond Registrar or any successor, shall be the successor of the Bond Registrar hereunder, if that successor corporation or association is otherwise eligible hereunder and is approved by the City Auditor on behalf of the Issuer, without the signing or filing of any paper or any other act on the part of the parties hereto or the Bond Registrar or such successor corporation.

Section 15. Notice from one of the parties to the other under this Agreement will be sufficient for the purpose if it is contained in a writing mailed by first-class mail postage prepaid to the Issuer at 7232 East Main Street, Reynoldsburg, Ohio 43068, Attention: City Auditor and to the Bond Registrar at 7 Easton Oval – EA5W63, Columbus, Ohio 43219, Attention: Corporate Trust Department, or to any other address which may be designated from time to time by either party in writing delivered to the other party.

Section 16. Where a Bond certificate, for any reason, is in the possession of the Bond Registrar and has not been claimed by the Owner or cannot be delivered to the Owner through usual channels, the Bond Registrar shall, after the expiration of four (4) years from the date said certificate was issued, return said certificate to the Issuer to be held by the Issuer for the Owner or transferred in accordance with applicable laws. Any moneys deposited with the Bond Registrar for the payment of principal or interest that remain unclaimed by the person or persons entitled thereto at the end of four (4) years from the date those moneys became payable to that person or those persons, shall be returned to the Issuer, and thereafter any person entitled to payment of those moneys shall look only to the Issuer for payment thereof, regardless of whether that person may

Draft of 12-4-2025

have in his possession a check for the payment of that interest or principal drawn by the Bond Registrar as agent of the Issuer.

Section 17. Neither this Agreement nor any provision hereof may be changed, revised or amended, except by a writing signed on behalf of the Issuer and the Bond Registrar.

Section 18. In case any section or provision of this Agreement, or any agreement, obligation, act or action, or part thereof, made, assumed, entered into, done or taken under this Agreement, or any application thereof, is held to be illegal or invalid for any reason, or is inoperable at any time, that illegality, invalidity or inoperability shall not affect the remainder of this Agreement or any other section or provision of this Agreement or any other agreement, obligation, act or action, or part thereof, made, assumed, entered into, done or taken under this Agreement, all of which shall be construed and enforced at the time as if the illegal, invalid or inoperable portion were not contained therein. Any illegality, invalidity or inoperability shall not affect any legal, valid and operable section, provision, agreement, obligation, act, action, part or application, all of which shall be deemed to be effective, operative, made, assumed, entered into, done or taken in the manner and to the full extent permitted by law from time to time.

Section 19. This Agreement is and shall be deemed to be a contract for services made under the laws of the State of Ohio and for all purposes shall be governed by and construed in accordance with the laws of the State of Ohio. This Agreement shall inure to the benefit of and shall be binding upon the parties hereto and their respective successors. This Agreement may be signed in several counterparts, each of which shall be deemed an original.

(REMAINDER OF PAGE INTENTIONALLY LEFT BLANK – SIGNATURE PAGES TO FOLLOW)

Draft of 12-4-2025

IN WITNESS WHEREOF, the parties hereto have signed this Bond Registrar Agreement as of the day and year first above written.

CITY OF REYNOLDSBURG, OHIO

By: _____

Title: Mayor

By: _____

Title: City Auditor

Approved as to form and correctness:

By: _____

Title: City Attorney

ARGENT INSTITUTIONAL TRUST COMPANY

By: _____

Title: _____

Draft of 12-4-2025

FISCAL OFFICER'S CERTIFICATE – BOND REGISTRAR AGREEMENT

As the fiscal officer of the City of Reynoldsburg, Ohio, I certify that the money required to meet the obligations of the Issuer during Fiscal Year 2026 under the foregoing Bond Registrar Agreement has been lawfully appropriated by the City Council of the Issuer for those purposes and is in the treasury of the Issuer or in the process of collection to the credit of an appropriate fund, free from any previous encumbrances. This Certificate is given in compliance with Sections 5705.41 and 5705.44 of the Ohio Revised Code.

Dated: March ___, 2026

_____

City Auditor
City of Reynoldsburg, Ohio

Draft of 12-4-2025

EXHIBIT A

CERTIFICATE OF AWARD

FOR PURPOSES OF COMPILING THE TRANSCRIPT OF PROCEEDINGS IN WHICH THIS BOND REGISTRAR AGREEMENT IS INCLUDED, THE CERTIFICATE OF AWARD REFERRED TO IN THIS EXHIBIT A IS CONTAINED IN THE TRANSCRIPT OF PROCEEDINGS BEHIND TAB NO. ___.

Draft of 12-4-2025

EXHIBIT B

$_____
City of Reynoldsburg, Ohio
Various Purpose Bonds, Series 2026

REQUEST TO AUTHENTICATE AND DELIVER

The City of Reynoldsburg, Ohio (the "*Issuer*"), by its undersigned officer, requests and authorizes Argent Institutional Trust Company (formerly The Huntington National Bank), in Columbus, Ohio, as Bond Registrar under the Bond Registrar Agreement between the Issuer and the Bond Registrar dated March ___, 2026, and pertaining to the Bonds identified in the caption (the "*Bonds*"), to complete and to authenticate or cause to be authenticated, and to deliver on this date, the initial Bonds as authorized by Ordinances No. _____-2025 and No. _____-2025, each passed by the City Council of the Issuer on December ___, 2025, and awarded to _____ (the "*Original Purchaser*") by a Certificate of Award dated February ___, 2026 (collectively, the "*Bond Legislation*").

The Bonds shall be delivered to or on the order of the Original Purchaser upon payment in federal funds of $_____, which amount reflects (i) the purchase price of the Bonds in the amount of $_____, with no accrued interest, less (ii) a portion of the purchase price in the amount of $_____ which the Original Purchaser is **[**withholding to pay certain issuance expenses on behalf of the Issuer**] [**providing to the Bond Registrar for the further payment of certain issuance expenses**]**, all in accordance with the Bond Legislation.

The Bonds to be initially authenticated and delivered will be dated March ___, 2026, and will bear interest and mature on the dates and in the principal amounts all as provided in the Certificate of Award.

The Bonds shall be fully registered, one for each maturity of the Bonds, numbered as determined by the Bond Registrar, and registered in the name of Cede & Co., as nominee of The Depository Trust Company, as designated by the Original Purchaser.

Dated: March ___, 2026

_____*[Exhibit – Not for Signature]*_____
City Auditor
City of Reynoldsburg, Ohio

Draft of 12-4-2025

EXHIBIT C

$_____
City of Reynoldsburg, Ohio
Various Purpose Bonds, Series 2026

BOND REGISTRAR'S CERTIFICATE OF COMPLETION, AUTHENTICATION AND RECEIPT FOR UNISSUED BONDS

Argent Institutional Trust Company, in Columbus, Ohio, as Bond Registrar under the Bond Registrar Agreement between it and the City of Reynoldsburg, Ohio, certifies that:

(a) The following individuals have signed, on behalf of the Bond Registrar as authenticating agent, the Certificate of Authentication appearing on the Bonds identified in the caption (the "*Bonds*") and initially delivered on this date, each being an officer or employee of the Bond Registrar duly qualified, empowered and authorized so to act on behalf of the Bond Registrar and holding the office or title set forth opposite the name:

Name	Signature Sample	Office or Title
_____	_____	_____
_____	_____	_____
_____	_____	_____

(b) All blanks on the Bonds requiring completion by the Bond Registrar have been properly, completely and accurately completed and verified by the Bond Registrar.

(c) The Bonds so completed and authenticated are in the denominations and registered in the names of the registered owners as directed in, and have been delivered in accordance with, the Issuer's Request to Authenticate and Deliver.

(d) The Bond Registrar has not received and does not retain control of any unissued or unauthenticated Bond certificates.

ARGENT INSTITUTIONAL TRUST COMPANY, as Bond Registrar

Dated: March ___, 2026

By: *[Exhibit – Not for Signature]*

Title: _____

Draft of 12-4-2025

[EXHIBIT D

DISPOSITION OF BOND PROCEEDS]

In accordance with the Bond Legislation, the Bond Registrar shall establish a Cost of Issuance Fund. On the Closing Date, the Original Purchaser will pay to the Bond Registrar $_____ for deposit in the Cost of Issuance Fund.

From the Cost of Issuance Fund, the Bond Registrar will thereafter pay, on the Closing Date, as costs of issuance of the Bonds:

(a) $_____ to Squire Patton Boggs (US) LLP, Bond Counsel.

(b) $_____ to Moody's Ratings.

(c) $_____ to _____ for providing and distributing the Preliminary Official Statement and the Official Statement.

(d) $_____ to the Bond Registrar as described in Sections 1(e) and 11 of this Agreement.

(e) $_____ to Baker Tilly Municipal Advisors, LLC, as Municipal Advisor.

(f) $_____ to the Ohio Municipal Advisory Council.

(g) $_____ as a contingency to provide for any other costs incidental to the issuance of the Bonds; in the event any amounts are not distributed, the Bond Registrar will provide an accounting to the Issuer of all expenses paid under this **EXHIBIT D** and any amounts not distributed will be distributed to the Issuer.

Upon the payment of the amounts described above, the Cost of Issuance Fund will be closed.

Draft of 12-4-2025

CONTINUING DISCLOSURE AGREEMENT

This CONTINUING DISCLOSURE AGREEMENT, dated March ___, 2026 (the "*Agreement*"), is made, signed and delivered by the City of Reynoldsburg, Ohio (the "*City*"), a municipal corporation and political subdivision duly organized and existing under the Constitution and laws of the State of Ohio and its Charter, for the benefit of the Holders and Beneficial Owners (as defined herein) from time to time of the City's $_____ Various Purpose Bonds, Series 2026 (the "*Bonds*"), authorized by Ordinances No. _____-2025 and No. _____-2025, each passed by the City Council of the City on December ___, 2025 (collectively, the "*Bond Ordinance*").

RECITAL

The City, by passage of the Bond Ordinance, has determined to issue the Bonds to provide funds for City purposes, and _____ (the "*Participating Underwriter*") has agreed to provide those funds to the City by purchasing the Bonds. As a condition to the purchase of the Bonds from the City and the sale of Bonds to Holders and Beneficial Owners, the Participating Underwriter is required to reasonably determine that the City has undertaken, in a written agreement for the benefit of Holders and Beneficial Owners of the Bonds, to provide certain information in accordance with the Rule (as defined herein).

NOW, THEREFORE, in accordance with the Bond Ordinance, the City covenants and agrees as set forth in this Continuing Disclosure Agreement.

Section 1. Purpose of Continuing Disclosure Agreement. This Agreement is being entered into, signed and delivered for the benefit of the Holders and Beneficial Owners of the Bonds and in order to assist the Participating Underwriter of the Bonds in complying with Rule 15c2-12(b)(5) promulgated by the Securities and Exchange Commission (SEC) pursuant to the Securities Exchange Act of 1934, as may be amended from time to time (the "*Rule*").

Section 2. Definitions. In addition to the definitions set forth above, the following capitalized terms shall have the following meanings in this Agreement, unless the context clearly otherwise requires. Reference to "Sections" shall mean sections of this Agreement.

"*Annual Filing*" means any Annual Information Filing provided by the City pursuant to, and as described in, Sections 3 and 4.

"*Audited Financial Statements*" means the audited basic financial statements of the City, prepared in conformity with generally accepted accounting principles.

"*Beneficial Owner*" means any person that (a) has the power, directly or indirectly, to vote or consent with respect to, or to dispose of ownership of, any Bonds (including persons holding Bonds through nominees, depositories or other intermediaries), or (b) is treated as the owner of any Bonds for federal income tax purposes.

"*EMMA*" means the Electronic Municipal Market Access system of the MSRB; information regarding submissions to EMMA is available at http://emma.msrb.org.

Draft of 12-4-2025

"*Filing Date*" means the last day of the ninth month following the end of each Fiscal Year (or the next succeeding business day if that day is not a business day), beginning September 30, 2026.

"*Financial Obligation*" means a (a) debt obligation, (b) derivative instrument entered into in connection with, or pledged as security or a source of payment for, an existing or planned debt obligation, or (c) guarantee of an obligation or instrument described in either clause (a) or (b). Financial Obligation shall not include municipal securities as to which a final official statement has been provided to the MSRB consistent with the Rule.

"*Fiscal Year*" means the 12-month period beginning on January 1 of each year or such other 12-month period as the City shall adopt as its fiscal year.

"*Holder*" means, with respect to the Bonds, the person in whose name a Bond is registered in accordance with the Bond Ordinance.

"*MSRB*" means the Municipal Securities Rulemaking Board.

"*Obligated Person*" means, any person, including the issuer of municipal securities (such as the Bonds), who is generally committed by contract or other arrangement to support payment of all or part of the obligations on the municipal securities being sold in an offering document (such as the Official Statement); the City is the only Obligated Person for the Bonds.

"*Official Statement*" means the Official Statement for the Bonds dated February ___, 2026.

"*Participating Underwriter*" means any of the original underwriters of the Bonds required to comply with the Rule in connection with offering of the Bonds.

"*Specified Events*" means any of the events with respect to the Bonds as set forth in Section 5(a).

"*State*" means the State of Ohio.

Section 3. <u>Provision of Annual Information</u>.

(a) The City shall provide (or cause to be provided) not later than the Filing Date to the MSRB an Annual Filing, which is consistent with the requirements of Section 4. The Annual Filing shall be submitted in an electronic format through EMMA, or as otherwise prescribed by the MSRB, and contain such identifying information as is prescribed by the MSRB, and may be submitted as a single document or as separate documents comprising a package, and may cross-reference other information as provided in Section 4; provided that the Audited Financial Statements of the City may be submitted separately from the balance of the Annual Filing and later than the Filing Date if they are not available by that date. If the City's Fiscal Year changes, it shall give notice of such change in the same manner as for a Specified Event under Section 5.

(b) If the City is unable to provide to the MSRB an Annual Filing by the Filing Date, the City shall, in a timely manner, send a notice to the MSRB in an electronic format through EMMA, or as otherwise prescribed by the MSRB.

Draft of 12-4-2025

Section 4. Content of Annual Filing. The City's Annual Filing shall contain or include by reference the following:

(a) Financial information and operating data of the type included in the Official Statement under the captions: **AD VALOREM PROPERTY TAXES AND SPECIAL ASSESSMENTS – Collections** and – **Delinquencies**, together with information as to aggregate assessed valuation of the City and overlapping and City tax rates; **MUNICIPAL INCOME TAX**; **STATE LOCAL GOVERNMENT FUNDS**; **CITY DEBT AND OTHER LONG-TERM OBLIGATIONS**, including **Debt Tables**, as applicable; and **Appendices A** and **B**.

(b) The Audited Financial Statements of the City utilizing generally accepted accounting principles applicable to governmental units as described in the Official Statement, except as may be modified from time to time and described in such financial statements.

The foregoing shall not obligate the City to prepare or update projections of any financial information or operating data.

Any or all of the items listed above may be included by specific reference to other documents, including annual informational statements of the City or official statements of debt issues of the City or related public entities, which have been submitted to the MSRB or the Securities and Exchange Commission. The City shall clearly identify each such other document so included by reference.

Section 5. Reporting Specified Events.

(a) The City shall provide to the MSRB, in an electronic format through EMMA, or as otherwise prescribed by the MSRB, and containing such identifying information as is prescribed by the MSRB and in a timely manner but not later than ten business days after the occurrence of the event, notice of any of the following events with respect to the Bonds, as specified by the Rule:

(1) Principal and interest payment delinquencies;

(2) Non-payment related defaults, if material;

(3) Unscheduled draws on debt service reserves reflecting financial difficulties; [(a)]

(4) Unscheduled draws on credit enhancements reflecting financial difficulties; [(a)]

(5) Substitution of credit or liquidity providers, or their failure to perform; [(a)]

(6) (Issuance of) Adverse tax opinions, the issuance by the Internal Revenue Service of proposed or final determinations of taxability, Notices of Proposed Issue (IRS Form 5701-TEB) or other material notices or determinations with respect to the tax status of the security (*i.e.*, the Bonds), or other material events affecting the tax status of the security;

Draft of 12-4-2025

(7) Modifications to rights of security holders, if material;

(8) Bond calls, if material, and tender offers; [(b)]

(9) Defeasances;

(10) Release, substitution, or sale of property securing repayment of the securities, if material; (c)

(11) Rating changes;

(12) Bankruptcy, insolvency, receivership or similar event of the Obligated Person; *Note: For the purposes of the event identified in this subparagraph, the event is considered to occur when any of the following occur: the appointment of a receiver, fiscal agent or similar officer for an Obligated Person in a proceeding under the U.S. Bankruptcy Code or in any other proceeding under state or federal law in which a court or governmental authority has assumed jurisdiction over substantially all of the assets or business of the Obligated Person, or if such jurisdiction has been assumed by leaving the existing governmental body and officials or officers in possession but subject to the supervision and orders of a court or governmental authority, or the entry of an order confirming a plan of reorganization, arrangement or liquidation by a court or governmental authority having supervision or jurisdiction over substantially all of the assets or business of the Obligated Person.*

(13) The consummation of a merger, consolidation, or acquisition involving an Obligated Person or the sale of all or substantially all of the assets of the Obligated Person, other than in the ordinary course of business, the entry into a definitive agreement to undertake such an action or the termination of a definitive agreement relating to any such actions, other than pursuant to its terms, if material;

(14) Appointment of a successor or additional trustee or the change of name of a trustee, if material;

(15) Incurrence of a Financial Obligation of the Obligated Person, if material, or agreement to covenants, events of default, remedies, priority rights, or other similar terms of a Financial Obligation of the Obligated Person, any of which affect security holders, if material; and

(16) Default, event of acceleration, termination event, modification of terms, or other similar events under the terms of a Financial Obligation of the Obligated Person, any of which reflect financial difficulties.

Draft of 12-4-2025

Note:

(a) The City has not obtained or provided, and does not expect to obtain or provide, any debt service reserves, credit enhancements or credit or liquidity providers for the Bonds.

(b) [Any scheduled redemption of Bonds pursuant to mandatory sinking fund redemption requirements does not constitute a specified event within the meaning of the Rule.

(c)] Repayment of the Bonds is not secured by a lien on any property capable of release or sale or for which other property may be substituted.

For the Specified Events described in Section 5(a) (2), (6, as applicable), (7), (8, as applicable), (10), (13), (14) and (15), the City acknowledges that it must make a determination whether such Specified Event is material under applicable federal securities laws in order to determine whether a filing is required.

Section 6. Amendments. The City reserves the right to amend this Agreement, and noncompliance with any provision of this Agreement may be waived, as may be necessary or appropriate to (a) achieve its compliance with any applicable federal securities law or rule, (b) cure any ambiguity, inconsistency or formal defect or omission and (c) address any change in circumstances arising from a change in legal requirements, change in law or change in the identity, nature or status of the City or type of business conducted by the City. Any such amendment or waiver shall not be effective unless this Agreement (as amended or taking into account such waiver) would have materially complied with the requirements of the Rule at the time of the primary offering of the Bonds, after taking into account any applicable amendments to or official interpretations of the Rule, as well as any change in circumstances, and until the City shall have received either (i) a written opinion of bond counsel or other qualified independent special counsel selected by the City that the amendment or waiver would not materially impair the interests of Holders or Beneficial Owners or (ii) the written consent to the amendment or waiver of the Holders of at least a majority of the principal amount of the Bonds then outstanding. An Annual Filing containing any revised operating data or financial information shall explain, in narrative form, the reasons for any such amendment or waiver and the impact of the change on the type of operating data or financial information being provided. If the amendment relates to the accounting principles to be followed in preparing Audited Financial Statements, (A) the City shall provide notice of such change in the same manner as for a Specified Event under Section 5 and (B) the Annual Filing for the year in which the change is made should present a comparison (in narrative form and also, if feasible, in quantitative form) between the financial statements or information as prepared on the basis of the new accounting principles and those prepared on the basis of the former accounting principles.

Section 7. Additional Information. Nothing in this Agreement shall be deemed to prevent the City from disseminating any other information, using the means of dissemination set forth in this Agreement or providing any other means of communication, or including any other information in any Annual Filing or providing notice of the occurrence of an event, in addition to that which is required by this Agreement. If the City chooses to include any information in any document or notice of occurrence of an event in addition to that which is specifically required by this Agreement, the City shall have no obligation under this Agreement to update such information or include it in any future Annual Filing or notice of occurrence of a Specified Event.

Draft of 12-4-2025

Section 8. Remedy for Breach. This Agreement shall be solely for the benefit of the Holders and Beneficial Owners from time to time of the Bonds. The exclusive remedy for any breach of this Agreement by the City shall be limited, to the extent permitted by law, to a right of Holders and Beneficial Owners to institute and maintain, or to cause to be instituted and maintained, such proceedings as may be authorized at law or in equity to obtain the specific performance by the City of its obligations under this Agreement in a court in Franklin County, Ohio. Any such proceedings shall be instituted and maintained only in accordance with Section 133.25(B)(4)(b) or (C)(1) of the Revised Code (or any like or comparable successor provisions); provided that any Holder or Beneficial Owner may exercise individually any such right to require the City to specifically perform its obligation to provide or cause to be provided a pertinent filing if such a filing is due and has not been made. Any Beneficial Owner seeking to require the City to comply with this Agreement shall first provide at least 30 days' prior written notice to the City of the City's failure, giving reasonable detail of such failure, following which notice the City shall have 30 days to comply. A default under this Agreement shall not be deemed an event of default under the Bond Ordinance, and the sole remedy under this Agreement in the event of any failure of the City to comply with this Agreement shall be an action to compel performance. No person or entity shall be entitled to recover monetary damages under this Agreement.

Section 9. Appropriation. The performance by the City of its obligations under this Agreement shall be subject to the availability of funds and their annual appropriation to meet costs that the City would be required to incur to perform those obligations. The City shall provide notice to the MSRB in the same manner as for a Specified Event under Section 5 of the failure to appropriate funds to meet costs to perform the obligations under this Agreement.

Section 10. Termination. The obligations of the City under this Agreement shall remain in effect only for such period that the Bonds are outstanding in accordance with their terms and the City remains an Obligated Person with respect to the Bonds within the meaning of the Rule. The obligation of the City to provide the information and notices of the events described above shall terminate, if and when the City no longer remains such an Obligated Person. If any person, other than the City, becomes an Obligated Person relating to the Bonds, the City shall use its best efforts to require such Obligated Person to comply with all provisions of the Rule applicable to such Obligated Person.

Section 11. Dissemination Agent. The City may, from time to time, appoint or engage a dissemination agent to assist it in carrying out its obligations under this Agreement, and may discharge any such agent, with or without appointing a successor dissemination agent.

Section 12. Beneficiaries. This Agreement shall inure solely to the benefit of the City, any dissemination agent, the Participating Underwriter and Holders and Beneficial Owners from time to time of the Bonds, and shall create no rights in any other person or entity.

Section 13. Recordkeeping. The City shall maintain records of all Annual Filings and notices of Specified Events and other events including the content of such disclosure, the names of the entities with whom such disclosures were filed and the date of filing such disclosure.

Section 14. Governing Law. This Agreement shall be governed by the laws of the State.

Draft of 12-4-2025

IN WITNESS WHEREOF, the City has caused this Continuing Disclosure Agreement to be duly signed and delivered to the Participating Underwriter, as part of the Bond proceedings and in connection with the original delivery of the Bonds to the Participating Underwriter, on its behalf by its officials signing below, all as of the date set forth above, and the Holders and Beneficial Owners from time to time of the Bonds shall be deemed to have accepted this Agreement made in accordance with the Rule.

CITY OF REYNOLDSBURG, OHIO

By: _____

Title: Mayor

By: _____

Title: City Auditor

Approved as to form and correctness:

By: _____

Title: City Attorney

Draft of 12-4-2025

FISCAL OFFICER'S CERTIFICATE – CONTINUING DISCLOSURE AGREEMENT

As fiscal officer of the City of Reynoldsburg, Ohio, I certify that the money required to meet the obligations of the City under the foregoing Continuing Disclosure Agreement made by the City in accordance with the Rule, as set forth in the Bond Ordinance and the attached Continuing Disclosure Agreement, during Fiscal Year 2026, has been lawfully appropriated by the City for those purposes and is in the City treasury or in the process of collection to the credit of an appropriate fund, free from any previous encumbrances. This Certificate is given in compliance with Sections 5705.41 and 5705.44 of the Revised Code.

Dated: March ___, 2026

_____

City Auditor
City of Reynoldsburg, Ohio

Draft of 12-4-2025

Reynoldsburg
OHIO • 1839

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance to Amend Chapter Eleven — Planning and Zoning Code for the City of Reynoldsburg, Ohio

APPROVALS:

Chris Shook
Mollie Prasher

EMERGENCY:

REASON FOR EMERGENCY:

STAFF REPORT:

The Following Items Are Included in the Proposed Zoning Code Edits:

1. **Summary Sheet**: Proposed Reynoldsburg Zoning Code Changes 2026: This shee describes the changes made to the Planning and Zoning Code and where they can b in the new, clean zoning code document provided.

2. **New Proposed Zoning Code Changes:** This is the clean document that includes the proposed zoning code changes. This document is the governing document and staff is asking to vote upon.

3. **Redlined Zoning Code Changes:** When created in 2020, the Reynoldsburg Zonir was prepared in Adobe InDesign. Unfortunately, this file type and software program not have a track changes function like in Adobe Reader and is intended to be used v compiling a finished product, not for edits. In an attempt to provide a redlined docu for the Planning and Zoning Board to review, staff exported the InDesign file into Adc Reader and manually included redlined changes. This process modifies the formatt the InDesign Document. This document is to be referred to as a guide that supplem items #1 and #2 above.

An Ordinance to amend Chapter Eleven — Planning and Zoning Code for the City of Reynoldsburg, Ohio

WHEREAS, the City of Reynoldsburg has determined that the Zoning Code of the City should be revised to improve efficiency, address concerns of residents, and maintain consistency with the Reynoldsburg Comprehensive Master Plan from 2018; and

WHEREAS, the modifications are to be made to the Code that went into effect on August 24, 2024, and subsequently amended, most recently by Ordinance No. 40-2024; and

WHEREAS, these amendments are to align and re-calibrate the text to better conform to the usefulness of the code; and

WHEREAS, the Reynoldsburg code should continually be revised to better suit new policies and practices.

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That Chapter 11 — Planning and Zoning Code will be amended as shown in Exhibit A attached hereto and incorporated herein.

SECTION 2. That upon adoption by Council, this Ordinance shall be in effect thirty days following the signature of the Mayor.

Summary of 2025 Zoning Code Changes

1. Innovation Development Standards & Parking
2. Setbacks regarding townhomes and accessory structures for townhome developments
3. Electric Vehicles
4. Fencing – Innovation
5. Supplementary use for pools & temporary uses (mayor direction) for street sales on main street
6. Lighting Standards
7. Landscaping Standards
8. Signage
9. Large Developments – That can parcel off later
10. Commercial Design Standards
11. Temporary Storage Containers on Construction and Renovation Sites
12. Property Without Direct Street Frontage standards
13. Non-Conforming Section
14. Dwelling – Group Home/ Dwelling – Developmental Disabilities
15. Home Occupation
16. Zoning Certificates
17. Conditional Use Factors
18. Definitions

TABLE 1105.05B: SUMMARY OF BUFFER REQUIREMENTS		
ZONE OR DISTRICT REQUIRING BUFFER	ADJACENT ZONE OR DISTRICT TO REQUIRED TO PROVIDE BUFFER	BUFFER REQUIREMENTS
SR or RM	ORD-C, EMD, or BMD	• 10 foot (10') buffer along all common boundaries; • One (1) tree for every forty feet (40') of linear boundary or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
SR or RM	CC	• 15 foot (15') buffer along all common boundaries; • One (1) tree for every forty feet (40') of linear boundary or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
Any residential use in any zoning district	Any non-residential use in SR or RM	• 5 foot (5') buffer along all common boundaries; • One (1) tree for every fifty feet (50') of linear boundary or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
SR, RM, or residential use in other zoning district	I	• 15 foot (15') buffer along all common boundaries; • One (1) tree for every twenty feet (20') of linear boundary or fraction thereof; • Continuous ten foot (10') high planting, hedge, fence, wall, earth mound or combination thereof.
Any zone (except for Innovation)	Adjacent freeway or arterial	• Twenty feet (20') for residential zones and fifteen feet (15') for all other zones adjacent to a freeway or arteria • One (1) tree for each thirty feet (30') of linear boundary, or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
Any zone (except for Innovation) adjoining a railroad	Any property with a railroad	• Twenty feet (20') for residential zones and fifteen feet (15') for all other zones adjacent to railroad boundaries; • One (1) tree for each thirty feet (30') of linear boundary, or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.

(b) Twenty thousand and one to fifty thousand (20,001 - 50,000) square feet: a total trunk diameter of ten inches (10"), plus one-half inch (1/2") of trunk diameter for every two thousand (2,000) square feet over twenty thousand (20,000) square feet or fraction thereof.

(c) Over fifty thousand (50,000) square feet: a total trunk diameter of twenty inches (20"), plus one inch (1") of trunk diameter for every four thousand (4,000) square feet over fifty thousand (50,000) square feet or fraction thereof.

~~1)~~ ~~All office uses, institutional uses, convalescent and nursing homes and child daycare facilities, including related parking, loading and trash storage areas:~~

(d) Up to nineteen thousand and five hundred (19,500) square feet: one inch (1") in trunk diameter for every fifteen hundred (1,500) square feet or fraction thereof, with a minimum of two inches (2") of total trunk diameter.

(e) Nineteen thousand, five hundred and one to forty-nine thousand and five hundred (19,501 – 49,500) square feet: a total trunk diameter of thirteen inches (13"), plus two inches (2") of trunk diameter for every two thousand (2,000) square feet over nineteen thousand and five hundred (19,500) square feet or fraction thereof.

(f) Forty-nine thousand, five hundred and one (49,501) square feet and more: a total trunk diameter of twenty-five inches (25"), plus two inches (2") of trunk diameter for every three thousand (3,000) square feet over forty-nine thousand and five hundred (49,500) square feet or fraction thereof.

ii. Existing healthy trees and shrubs shall be preserved and incorporated into the overall site and landscape design to the maximum extent practical as determined by the City. Existing trees may be credited toward minimum tree planting requirements as follows:

1. Existing trees, which are preserved, may be credited toward the tree planting requirements of this section according to Table 1105.05A - Credit for Existing Trees. Tree credits shall be given as long as all other provisions and the intent of this Zoning Code are met. Fractional caliper measurements shall be attributed to the next lowest category.
2. No credit shall be given for existing preserved trees that are:
   (a) Not located on the actual development site;
   (b) Not properly protected from damage during the construction process;
   (c) Prohibited species under the caliper size of thirteen inches (13") measured at four and one-half feet (4 ½') above the ground; or
   (d) Dead, dying, diseased, or infested with harmful insects.

iii. In order to apply for credit, existing trees must be protected during construction. All existing trees shall be protected by the placement of an orange construction fence around the perimeter of the tree/trees. In order to protect the root system of the existing trees, said fence shall be installed at a minimum radius from the trunk. The minimum shall be one foot (1') of radius per one inch (1") of caliper of the tree. (ex. On a six inches (6") diameter tree, the fence shall be placed a minimum of six feet (6') from the trunk of the tree.)

iv. No new tree plantings shall be required if existing trees to remain on the site after development, and the aggregate trunk sizes of such trees, meet or exceed the requirements as set forth above.

v. Any combination of existing and new trees may be used to meet the requirements of this section.

I. Property Buffer Requirements.

i. **Grass or Ground Cover Required.** Grass or ground cover shall be planted on all portions of the required buffer not occupied by other landscape material. Trees do not have to be equally spaced but may be grouped. All landscape requirements shall be met by the applicant if his/her property is contiguous to property fully developed prior to the passage of this chapter. A landscape plan meeting the requirements of this section shall be approved by the Planning and Zoning Board or the Planning and Zoning Administrator in conjunction with the site plan and design review process before the commencement of construction on the subject property.

ii. **Community or Club Swimming Pool.** A community or club swimming pool means any pool constructed by an association of property owners or by a private club for use and enjoyment by members of the association or club and their families. Community and club swimming pools are permitted in any district, but shall comply with the following conditions and requirements:

1. A community or club swimming pool shall be intended and used solely for the enjoyment of the members, their families and guests, and guests of the association or club under whose ownership or jurisdiction the pool is operated.
2. A community or club swimming pool and accessory structures thereto, including the areas used by the bathers, shall not be closer than one hundred feet (100') to any lot line.
3. A community or club swimming pool and all of the area used by the bathers, including all adjacent deck areas, shall be so walled or fenced as to prevent uncontrolled access by children.

~~iii. **Fish Pond, Water Garden.** A body of water designed and used as a fish pond or as a water garden shall conform with all yard and setback requirements for accessory structures in the district in which it is located, as well as the following requirements.~~

~~1. Water depth shall not exceed twenty four inches (24") unless enclosed by a fence forty eight inches (48") in height with a locking gate.~~

~~2. Water surface area shall not exceed one hundred (100) square feet.~~

D. **Portable Temporary Storage Units.** A zoning certificate shall be obtained from the Zoning Administrator prior to the placement of a portable temporary storage unit on a property when the unit will be on the property for a period of more than seven days. No more than one unit is permitted on a property at any given time, the duration of which shall not exceed a period of fourteen days total. The unit must be placed on a hard surface (not grass), and must be on the property for which it is being used. The use of these units shall be limited to no more than twice in any twelve month period. Permission to exceed these limitations may be granted by the Planning and Zoning Board. A portable temporary storage units is not permitted as a permanent accessory structure regardless of the proposed location of the unit on a parcel.

i. **Calamity exception**. If the portable temporary storage unit is being used to store personal property as a result of major calamity (e.g. fire, flood, or other event where there is significant property damage), the Planning and Zoning Board or Zoning Administrator may extend these time periods.

ii. **Approved construction project.** If the portable temporary storage unit is being used to store materials as part of an approved construction project, the portable temporary storage unit may remain onsite as long as there is a valid open building permit obtained through the City of Reynoldsburg.

E. **Outdoor Storage. The following regulations shall apply to the approval and operation of outdoor storage as an accessory use:**

i. Outdoor storage shall only be permitted in areas identified on the approved site plan. No such activity shall be located closer than fifty feet (50FT) to a residential zoning district boundary or road right-of-way abutting any residential zoning district or within ten feet (10FT) of any road right-of-way. Such activities shall not occupy any required parking area or driveway;

ATTACHMENT SHEET (C)

1107 NON-CONFORMITIES

Non-Conformities

SECTION 1107.01 ADMINISTRATION OF NON-CONFORMITIES

A. The following sets forth the rights of a property owner to continue, enlarge, repair, alter, replace, or discontinue a non-conforming use or structure.

B. Table 1107.01 A summarizes the decisions relative to nonconformities and the role of each of the administrative, quasi-judicial, quasi-legislative, and legislative reviewing parties.

SECTION 1107.03 APPLICABILITY

A. Non-conforming uses are declared by this Code to be incompatible with permitted uses in the zones and districts involved. A non-conforming use of a structure, a non-conforming use of land, or a non-conforming use of structure and land in combination, shall not be extended or enlarged after passage of this Code by attachment on a building or premises of additional signs intended to be seen from off the premises, or by the addition of other uses, of a nature which would not be permitted generally in the zone or district involved.

SECTION 1107.05 EFFECT OF ACTUAL CONSTRUCTION

A. To avoid undue hardship, nothing in this Code shall be deemed to require a change in the plans, construction or designated use of any building on which actual construction was lawfully begun prior to the effective date of adoption or amendment of this Code and upon which actual building construction has been carried on diligently. Actual construction is hereby defined to include the placing of construction materials in permanent position and fastened in a permanent manner. Where excavation or demolition or removal of an existing building has been substantially commenced, such substantial excavation, demolition or removal shall be deemed to be actual construction, provided that work is carried on diligently after such excavation, demolition or removal. For the purposes of this Section 1107.05 substantial excavation, demolition or removal shall mean the completion of at least 75% of the scope of applicable work.

TABLE 1107.01 A		
DETERMINATIONS OF:	ZONING ADMINISTRATOR	PLANNING AND ZONING BOARD (PZB)
ENLARGEMENT		
Application Submitted To:	X	
Decision By:		X
Appeal To:		
REPAIR OR ALTERATION		
Application Submitted To:	X	
Decision By:	X	
Appeal To:		QJ
REPLACEMENT		
Application Submitted To:	X	
Decision By:	X	
Appeal To:		QJ
DISCONTINUANCE		
Application Submitted To:	X	
Decision By:	X	
Appeal To:		QJ

KEY	
QJ	Quasi-Judicial Decision

SECTION 1107.07 SINGLE-FAMILY DWELLINGS

A. In any zone or district in which single-family dwellings are permitted, a single-family dwelling and customary accessory buildings may be erected on any single lot of record at the effective date of adoption or amendment of this Code notwithstanding limitations imposed by other provisions of this Code. Such lot must be in separate ownership and not of continuous frontage with other lots in the same ownership. This provision shall apply even though such lot fails to meet the requirements for area or width, or both, that are generally applicable in the district or zone, provided that yard dimensions and requirements other than those applying to area or width, or both, of the lot shall conform to the regulations for the district or zone in which such lot is located, except that the minimum side yards may be reduced ten percent (10%) of the width of the lot, provided that no side yard shall be less than the least of the applicable district or zone regulation and three feet (3FT). Variance of yard requirements shall be obtained only through action of the Planning and Zoning Board (PZB).

SECTION 1107.09 CONTIGUOUS LOT

A. If two (2) or more lots or combinations of lots and portions of lots with continuous frontage in single ownership are of record at the time of passage or amendment of this Code, and if all or part of the lots do not meet the requirements established for lot width and area, the lands involved shall be considered to be an undivided parcel for the purpose of this Code, and no portion of such parcel shall be used or sold in a manner which diminishes compliance with lot width and area requirements established by this Code, nor shall any division of any parcel be made which creates a lot width or area below the requirements stated in this Code.

SECTION 1107.11 ALTERATION OF NON-CONFORMING STRUCTURE

A. No such non-conforming structure may be enlarged or altered in a manner which increases its nonconformity, but any structure or portion thereof may be altered to decrease its nonconformity.

B. If lawful use of a structure, or of structure and premises in combination, exists at the effective date of adoption or amendment of this Code that would not be allowed in the district under the terms of this Code, the lawful use may be continued so long as it remains otherwise lawful, subject to the following provisions:

i. No existing structure devoted to a use not permitted by this Code in the zone or district in which it is located shall be enlarged, extended, constructed, reconstructed, moved or structurally altered, except in changing the use of the structure to a use permitted in the zone or district in which it is located.

ii. Any non-conforming use may be extended throughout any of the parts of a building which were manifestly arranged or designated for such use at the time of adoption or amendment of this Code, but no such use shall be extended to occupy any land outside such building.

iii. Any structure, or structure and land in combination, in or on which a non-conforming use is superseded by a permitted use, shall thereafter conform to the regulations for the applicable zone or district, and the non-conforming use may not thereafter be resumed.

iv. Where a non-conforming use has been discontinued, meaning that the structure containing the use has remained vacant, unoccupied, unused or has ceased the daily activities or operations which had occurred, for a period of 3 or more continuous months, the non-conforming use shall be permanently terminated.

v. Any non-conforming structure damaged to an extent of more than 75% of its then fair market value, exclusive of foundations, shall not be restored or reconstructed, used or occupied as a non-conforming use. If such damage amounts to 75% or less of the fair market value, the non-conforming structure may be restored, provided a building permit is obtained and that such restoration shall begin within one year from the time of damage. The PZB may approve the reconstruction of a non-conforming structure damaged to a greater extent than permitted herein upon review of a site and design plan submitted in accordance with the requirements for site and design plan submittal under Chapter 1109.

SECTION 1107.13 CONTINUATION OF NON-CONFORMITY

A. If lawful use of a structure, or of structure and premises in combination, exists at the effective date of adoption or amendment of this Code that would not be allowed in the district under the terms of this Code, the lawful use may be continued so long as it remains otherwise lawful, subject to the following provisions:

i. No existing structure devoted to a use not permitted by this Code in the zone or district in which it is located shall be enlarged, extended, constructed, reconstructed, moved or structurally altered, except in changing the use of the structure to a use permitted in the zone or district in which it is located.

ii. Any non-conforming use may be extended throughout any of the parts of a building which were manifestly arranged or designated for such use at the time of adoption or amendment of this Code, but no such use shall be extended to occupy any land outside such building.

iii. Any structure, or structure and land in combination, in or on which a non-conforming use is superseded by a permitted use, shall thereafter conform to the regulations for the applicable zone or district, and the non-conforming use may not thereafter be resumed.

iv. Where a non-conforming use has been discontinued, meaning that the structure containing the use has remained vacant, unoccupied, unused or has ceased the daily activities or operations which had occurred, for a period of 3 or more continuous months, the non-conforming use shall be permanently terminated.

v. Any non-conforming structure damaged to an extent of more than 75% of its then fair market value, exclusive of foundations, shall not be restored or reconstructed, used or occupied as a non-conforming use. If such damage amounts to 75% or less of the fair market value, the non-conforming structure may be restored, provided a building permit is obtained and that such restoration shall begin within one year from the time of damage.

vi. The PZB may approve the reconstruction of a non-conforming structure damaged to a greater extent than permitted herein upon review of an application for variance submitted pursuant to Chapter 1109 of this Code.

SECTION 1107.15 REPAIRS AND ALTERATIONS

A. Repairs, alterations and maintenance work as required to keep said non-conforming structure in sound condition and repair may be made to a non-conforming structure; provided that the total repairs and alterations shall not exceed 50% of the structure's then fair market value.

B. Nothing in this Code shall be deemed to prevent the strengthening or restoring to a safe condition of any building or part thereof declared to be unsafe by any official charged with protecting the public safety, upon order of such official.

SECTION 1107.17 EFFECT OF PRIORI REGULATIONS

A. Chapter 1195 of Ordinance 37-69 (passed May 12, 1969) established requirements for certificates for those lawful non-conforming uses which were established prior to the effective date of that ordinance. The adoption of this Code shall not repeal or diminish those requirements or rights which were applicable to the lawful non-conforming uses which were subject to Ordinance 37-69.

B. Uses and structures established subsequent to the effective date of Ordinance 37-69 shall have been established in conformance with the provisions of that ordinance and its subsequent amendments in order to be deemed lawful.

C. Any lawfully existing use or structure existing on the effective date of this Code, which use or structure does not conform with one (1) or more of the provisions of this Code, shall be deemed a non-conforming use or structure under the provisions of this Code. Provided that such non-conforming use or structure was established in conformance with the zoning provisions in effect prior to adoption of this Code, and provided that such use or structure was established under authorization of and in conformance with a permit or other authorization issued by the City, then such use or structure shall be a lawful non-conforming use or structure and shall be permitted to continue under the provisions of this Code.

This page intentionally left blank.

ATTACHMENT SHEET D

SECTION 1105.07 LANDSCAPING AND BUFFERING

A. **Purpose and Intent.** These standards are intended to establish landscaping regulations that:

i. Improve the aesthetic appearance of setback areas, common open space areas, public rights-of-way and off-street vehicular parking areas

ii. Encourage the preservation of existing trees and natural features;

iii. Promote compatibility among different land uses;

iv. Promote the use of generally accepted landscape design principles; and

v. Protect public health, safety and welfare by minimizing the impact of all forms of physical and visual pollution, controlling soil erosion, screening unsightly areas, preserving the integrity of neighborhoods and enhancing pedestrian and vehicular traffic and safety.

B. **Application.** The Planning and Zoning Administrator may require a landscape plan and/or tree survey to be submitted in conjunction with any application for a zoning certificate, a variance, a conditional use permit, a similar use determination, a subdivision plat, or a site plan and design review approval. Such landscape plan and/or tree survey shall include the following:

i. The present location, size, and description of all existing major trees, with a designation of existing major trees sought to be removed. A major tree is a tree that is 18 inches (18") or greater at DBH (Diameter at Breast Height).

ii. The location, size and description of landscaping materials proposed to be placed on the lot in order to comply with this section.

iii. The location and size of any structures presently on the lot, and those proposed to be placed on the lot.

iv. The proposed location and description of screening to be placed on the lot in order to comply with this section.

Summary Sheet - Proposed Reynoldsburg Zoning Code Changes 2025:

Points highlighted in purple are new from Council Meeting

Cover Sheet:
- Updated year on cover page from 2024 to 2026

Page 3 (Table of Contents):
- Added sections:

1105.21 Commercial Design Standards
1105.23 Property Without Direct Street Frontage
1105.25 Temporary Storage Containers on Construction and Renovation Sites

Page 4 (Table of Contents):
- Changed color of 1109.05

Page 5 (Table of Contents):
- Moved 214 up in line with line

Page 12 (Section 1101.13.B.ii):
- Amended to “When measuring a required distance, such as the maximum distance between a structure and another structure, the measurement is made at the farthest or longest distance between them.” under Section 1101.13 B.
    - Changed due to duplicate above

Page 14 (Section 1101.13.G.vi):
- Added “With the exception of Dwelling – Attached single-family land uses, which would have a zero (0) foot setback from the vertical plane of any side lot line.”

Page 14 (Section 1101.13.G.viii):
- Added “balconies” to “Front porches and balconies may encroach into a front setback provided that such encroachment is no greater than six (6) feet from the front building facade, and no closer than 10 feet from the vertical plane of any lot line.”

Page 14 (Section 1101.13.G):
- Add Section 1101.13.G.ix which reads “Dwelling – Attached Single-Family land use in residential zoned districts are permitted to have front porches, balconies, sidewalks, driveways, patios, decks, and terraces encroach into the side setback for a zero (0) foot side setback.”

Page 21 (Section 1103.09)
- Delete “A” in first sentence after “Figure 1103.09”

- On the image, move D over

Page 22 (Table 1103.10 District and Zones Map
- Take out map and legend.

Page 24 (Section 1103.11.D.Height):
- Remove every ‘clear’

Page 25 (Section 1103.11.E.Notes):
- Change from “At least one bicycle space shall be provided or every 1,000 square feet of gross floor area of the principle building” to “At least one bicycle space shall be provided for every 10,000 square feet of gross floor area of the principle building”
- Add a “Q” next to Parking Drive Width

Page 26 (Table 1103 A Allowed Land Uses and Permit Requirements):
- Delete Dwelling – Developmental Disability from the table.
- Add the P and C key table on this page

Page 27 (Section 1103.11, Table 1103 A):
- Add Food Service – Commercial Kitchen as a permitted land use.

Page 29 (Section 1103.11.i.Design Guidelines for Olde Reynoldsburg.C.6.ii):
- Removed two ii due to it being a continuation of i.

Page 30 (Section 1103.11.i.Design Guidelines for Olde Reynoldsburg.D.1.C):
- Building materials on this page are listed twice. On the sheet, there is duplication of text.
- Added “materials” to “Railings and balustrades may be constructed of the following materials.”
- Combined “(b) Fiber cement board siding, (c) smooth finish;” to be “(b) Fiber cement board siding, smooth finish;”
- Letters thereafter should be corrected accordingly.

Page 31 (Section 1103.11.i.Design Guidelines for Olde Reynoldsburg.D.1.C):
- Changed “viii. Doors shall be made of wood, metal, glass, or fiberglass.” To “v. Doors shall be made of wood, metal, glass, or fiberglass.”
- Numbers thereafter should be corrected accordingly.

Page 32 (Section 1103.13):
- Should change the first sentence to: "Because of its location adjacent to the Olde Reynoldsburg Commercial District (ORD-C), future....."

Page 33 (Section 1103.13.E):
- Add M, N, O, P to setback table

Page 35 (Table 1103 B Allowed Land Uses and Permit Requirements):

- Delete Dwelling – Developmental Disability from the table.
- Add the P and C key table on this page

Page 39 (1105.13.C.ii.5):
- Add period to end of sentence

Page 41 (1103.15.I :
- (fourth bullet) Changed the word “are” to “be”
- (fifth bullet) Took out period after colon

Page 43 (Section 1103.15.II):
- Add Food Service – Commercial Kitchen as a permitted land use in the EMD and BMD.

Page 44 (Section 1103.15.II.Repair Services):
- Changed to
    - Vehicular Care Services – Minor - without Drive-Thru
    - Vehicular Care Services – Minor - with Drive-Thru
- Add “C” for conditional for both in EMD only

Page 44 (Section 1105.13.Uses.Repair Services):
- Add “See 1105.13(L)” to Vehicular Care Services – Minor – with Drive-Thru

Page 45 (Section 1105.13.Uses.Sales and Exhibition):
- Add “See 1105.13(K)” to Retail – Convenience with gasoline
- Remove the word “section” from Retail – Pharmacy with Drive-Thru notes

Page 46 (Section 1105.13.III.B):
- Remove B from the image

Page 46 (Table 1103.15.III.Insight District Development Standards.Table A.Setbacks):
- Added “*” to Front Yard Setback. Now reads “20 feet from ROW*”
- Added section at bottom to follow asterisk: “*If a municipal landscape easements exists on the parcel, then the maximum building setback may be increased to 45 feet from the right-of-way.”

Page 48 (Table 1103.15.III.Insight Zone Development Standards.Table A.Setbacks):
- Added “*” to Front Yard Setback. Now reads “20 feet from ROW*”
- Added section at bottom to follow asterisk: “*If a municipal landscape easements exists on the parcel, then the maximum building setback may be increased to 45 feet from the right-of-way.”

Page 49 (1103.15.III.C.Design.Site Plan Standards):
- Change 1109.19 to 1109.17

Page 50 (Section 1103.15):
- Add in word “is” to beginning paragraph
    - Now reads “The intent of these regulations is to promote the development…”

Page 52 (Section 1103.17.District Uses):
- Delete Dwelling – Developmental Disability from the table.

Page 53 (Section 1103.17.III.Development Standards.Lot Dimensions):
- Changed Lot Width Townhomes and Condos Only (min. ft.) from 23’ to 21’.
- Added Lot Depth Townhomes and Condos Only (min. ft.) – 75’
- Changed Lot Frontage Townhomes and Condos Only (min. ft.) from 23’ to 21’.

Page 53 (Section 1103.17.III.Development Standards.Setbacks):
- Added Rear Yard for Townhomes and Condos Only (min. ft.) – 20’

Page 54 (Section 1103.17.III.Development Standards.Accessory Structure Dimensions.Accessory Building Location):
- Replace “Rear yard, 3 feet from all lot lines, 10 feet from house” to say “See Section 1105.05”

Page 55 (Section 1103.19.District Uses.Conditional Uses):
- Delete Dwelling – Developmental Disability from the table.

Page 56 (Section 1103.19.III.Development Standards.Lot Dimensions):
- Changed Lot Width Townhomes and Condos Only (min. ft.) from 23’ to 21’.
- Added Lot Depth Townhomes and Condos Only (min. ft.) – 75’
- Changed Lot Frontage Townhomes and Condos Only (min. ft.) from 23’ to 21’.

Page 57 (Section 1103.19.III.Accessory Structure Dimensions)
- Change accessory building location note to say See Section 1105.05

Page 57 (Section 1103.19.III.Sign Regulations)
- Change note to say Refer to Section 1105.03 – Signs

Page 57 (Section 1103.19.III.Design)
- Change site plan standards note to say 1109.17 instead of 1109.19

Page 58 (Section 1103.21.II.Permitted Uses):
- Add Food Service – Commercial Kitchen as a permitted land use.
- Add (See 1105.13(L)) after Food Service – Quick Serve/Fast Food with Drive Thru

Page 59 (Section 1103.21.II.Permitted Uses):
- Add Retail – Extra Large Format
- Add Retail – Shopping Center – Enclosed
- Add (See 1105.13(L)) after Retail – Pharmacy with Drive Thru

- Delete duplicate of Retail – Medium Format

Page 59 (Section 1103.21.II.Conditional Uses):
- Changed Vehicular Care Services – Minor to:
    - Vehicular Care Services – Minor - without Drive-Thru
    - Vehicular Care Services – Minor - with Drive-Thru
- Delete Dwelling – Developmental Disability from the table.
- Add Retail – Vape Shop/Smoke Shop
- Add (See 1105.13(K)) after Retail – Convenience with gasoline
- Add (See 1105.13(L)) after Vehicular Care Services – Minor – with Drive Thru

Page 60 (Section 1103.21.III.Development Standards.Setbacks):
- Change rear yard setback to 10 feet

Page 61 (Section 1103.21.III.Sign Regulations):
- Change note to say Refer to Section 1105.03 – Signs

Page 61 (Section 1103.21.III.Design)
- Change to say See site plan review, Chapter 1109.17

Page 61 (Section 1103.21.III.Landscape Review):
- Change note to say See Section 1105.07 – Landscaping and Buffering

Page 63 (Section 1103.23.II.Conditional Uses):
- Add (See 1105.13.(H)) after Child Day Care - Center

Page 64 (Section 1103.23.III.Development Standards.Lot Dimensions):
- Changed Lot Width (min. ft.) from 200’ to 80’

Page 64 (Section 1103.23.III.Development Standards.Setbacks):
- Changed Front Yard Setback (max. ft.) from 20’ to NA
- Changed second Rear Yard Setback (min. ft.) to (max. ft.)

Page 64 (Section 1103.23.III.Development Standards.Lot Coverage/Open Space):
- Changed Lot Coverage (max.) – Including Impervious sfc. from 70% to 80%.

Page 65 (Section 1103.23.III.Development Standards.Accessory Structure Dimensions):
- Changed ADU Height (max. ft.) from NA to NP

Page 65 (Section 1103.23.III.Sign Regulations):
- Change note to say Refer to Section 1105.03 – Signs

Page 65 (Section 1103.23.III.Design)
- Change to say See site plan review, Chapter 1109.17

Page 65 (Section 1103.23.III.Landscape Review):
- Change note to say See Section 1105.07 – Landscaping and Buffering

Page 68 (Section 1103.25.III.Sign Regulations):
- Change note to say Refer to Section 1105.03 – Signs

Page 68 (Section 1103.25.III.Design)
- Change to say See site plan review, Chapter 1109.17

Page 68 (Section 1103.25.III.Landscape Review):
- Change note to say See Section 1105.07 – Landscaping and Buffering

Page 69 (Section 1103.27):
- Added missing table back to redlined document, okay in clean document

Page 105 (Section 1105.01.C.ii):
- Remove extra colon from end of paragraph.

Page 107 (Section 1105.01.F.vii):
- Remove extra space after this section.

Page 107 (Section 1105.01.F.viii):
- Capitalize “zoning”

Page 108 (Section 1105.01.G.iii.4):
- Capitalize “the” – beginning of sentence

Page 108 (Section 1105.01.G.v):
- Move table under Section 1105.01.G.vi (Page 108)

Page 109 (Section 1105.01.G.viii.1):
- Added “Gravel is not a permitted surface”

Page 110 (Section 1105.01.J):
- Added new EV Parking Section and Standards:
- **J. Electric Vehicle (EV) Parking and Infrastructure.**
    - **i. Purpose.** To facilitate the transition to electric vehicles by requiring and regulating the provision of Electric Vehicle charging infrastructure in new and existing developments.
    - **ii. Applicability.**
        - 1. All new off-street parking lots with 20 or more spaces. (added the period)
    - **iii. Required Minimums.**
        - New Off-Street Parking:
            - (a) 1 Electric Vehicle Supply Equipment (EVSE) Installed for 20 or more parking spaces
        - Electric Vehicle Supply Equipment (EVSE) Installed spaces count

toward total required parking.

- **iv. Location and Design.**
  - Electric Vehicle spaces shall be located as close as feasible to building entrances or pedestrian access points.
  - Electric Vehicle Supply Equipment Installed spaces shall be marked with signage indicating they are for Electric Vehicle use only.
  - Electric Vehicle charging cords shall not interfere with pedestrian walkways or ADA access.
  - At least one Electric Vehicle Supply Equipment Installed space shall be ADA accessible in compliance with federal and state accessibility standards.
  - The charging station must be located a minimum of 10 feet from any property line, unless the adjacent property is a public right-of-way. In that case, the station must meet the minimum parking setback requirement adjacent to a right-of way.
  - All above-ground utility structures must be located outside any visibility triangles at intersections or driveways.
- **v. Shared Use.** Public and shared parking facilities may satisfy Electric Vehicle requirements for multiple uses on the same or adjacent parcels, subject to cross-access agreements.

- Add (EV) after Electric Vehicle in title
- Replace every “EV” with electric vehicle
- Identified EVSE as Electric Vehicle Supply Equipment

Page 111 (Table 1105.01.A):
- Changed each “s.f.” to “sq. ft.”
- Delete Dwelling – Developmental Disability from the table.

Page 111 (Table 1105.01.A):
- Add Food Service – Commercial Kitchen as a permitted land use.
  - 1 per 200 sq. ft.
- Add 1 per 200 sq. ft. back in for Adult Oriented Business

Page 112 (Table 1105.01.A):
- Changed each “s.f.” to “sq. ft.”
- Add Retail – Extra Large Format
  - 1 for each 600 sq. ft. of floor area
- Add Retail – Vape Shop/Smoke Shop under Retail – Small Format
  - 1 for each 200 sq. ft. of floor area
- Add 1 for each 200 sq. ft. of floor area for retail - large format, medium format, pharmacy, shopping center, small format, tattoo/piercing

Page 113 (Table 1105.01.A):
- Changed each “s.f.” to “sq. ft.”
- Changed Manufacturing/Processing/Laboratory Section standards from “1 for each 200 s.f. of floor area” to “1 for each 1,000 sq. ft. of gross floor area”

Page 114 (Table 1105.01.A):
- Changed each “s.f.” to “sq. ft.”

Page 115 (Table 1105.01.A):
- Changed Warehouse/Storage Section standards from “1 per 1,000 sq. ft. of gross building area” to “1 space is required for every 1,000 sq. ft. of gross floor area for buildings up to 20,000 sq. ft.”
- Added to Warehouse/Storage Section standards, “After the first 20,000 sq. ft. of building area, 1 space is required for every 5,000 sq. ft. of gross floor area for buildings between 20,001 to 120,000 sq. ft.”
- Added to Warehouse/Storage Section standards, “After the 120,000 sq. ft. of building area, 1 space is required for every 10,000 sq. ft. of gross floor area for buildings over 120,000 sq. ft.”

Page 117 (Section 1105.03.C.v.1):
- Amended sentence on corner lots to say “Where a building is located on a corner lot, one (1) additional wall sign may be permitted on both front facade walls which parallel the intersecting streets, for a total of three (3) signs.”

Page 118 (Section 1105.03.Cv.2):
- Delete the word “for” from last sentence

Page 119 (Section 1105.03.C.vii):
- Delete “or the, as applicable,”

Page 119 (Section 1105.03.C.vii.1)
- Amended sentence on corner lots to say “Where a building is located on a corner lot, one (1) additional wall sign may be permitted on both front facade walls which parallel the intersecting streets, for a total of three (3) signs.”
- Added section a:
    a. One (1) Pickup sign is permitted for any use which utilizes pickup of goods from the existing business. The pickup sign should be located near the pickup area. To utilize this sign, a designated pickup area must be identified on the site.

Page 120 (Section 1105.03.C.vii.2):
- Delete the word “for” from last sentence

Page 120 (Section 1105.03.C.vii.4)
- Add subsection a, “Monument signs for parcels exceeding three (3) acres, and having two or more independent land uses, not accessory land uses to the principle land use; may have a monument sign identifying the complex name, along with one (1) additional monument sign at every point of ingress and egress location onto the overall development from the public right-of-way.
    - Subsection was there twice, deleted the duplicate.

Page 121 (Section 1105.03.F.ii.1 & 2):

- Updated Non-Conforming Signs:
- 1. For all signs, except Wall, Projecting and Awning signs: The size and shape of the sign structure shall not be altered, except that sign face panels may be replaced.
- 2. For Wall, Projecting, and Awning signs only: The size and shape of the sign structure –which includes the sign face, sign panels, and the sign cabinet – shall not be altered. Neither the width, nor the height, nor the square footage of the nonconforming sign shall be increased, and the replacement sign shall not exceed the width, height and square footage respectively of the existing nonconforming sign. All other components of the zoning code applicable to signage must be met.
- 3. If damage occurs to a sign to the extent of sixty percent (60%) or more of either the structure or its replacement cost at the time of destruction, the sign shall be brought into compliance with the provisions of this Zoning Code.

Page 123 (Section 1105.05.A.vii.2):

- Amended to “Shall not be located closer than three feet (3FT) to any rear lot line and not closer than three feet (3FT) to any side lot line with the exception of Dwelling – Attached Single-Family land uses, which would have a zero foot (0 FT) side lot line setback.”

Page 124 (Section 1105.05.B.ii.4)

- Add “A detached ADU.” Now reads, “A detached ADU shall not be located closer than ten feet (10FT) to a main building.”

Page 125 (Section 1105.05.D.ii):

- Amended to “Service structures shall maintain a three (3) foot setback from all lot lines, with the exception of Dwelling – Attached Single-Family land uses, which would have a zero foot (0 FT) side lot line setback.”

Page 125 (Section 1105.06.B):

- Added ‘be’ to read “Entries shall be visible from the front of the building and shall be connected to a paved driveway or sidewalk by a clearly delineated pedestrian walkway.”

Page 125 (Section 1105.06.C):

- Amended to say “All dwellings must incorporate design features such as offsets, balconies, projections, recesses or covered entrances, windows, doors, window reveals, or similar elements to create horizontal and vertical relief and avoid box–like forms.”

Page 127 (Section 1105.07.A & .B):

- Added back in the sections that were accidentally removed

Page 129 (Table 1105.07A):

- Changed “Maximum % of species” to “number of tree credits”

Page 129 (Section 1105.07.B)
- Minimum Plant Size table needs to be moved to Section 1105.07.F.ii right after wording.

Page 130 (Section 1105.07.C.i):
- Maximum use of species table needs to be moved to Section 1105.07.F.iv right after wording.

Page 129 (Table 1105.07C)
- Changed table 1105.07C to 1105.07A, which matches the section called out in Section 1105.07.F.vi
- Move to 1105.07.D.v after wording.

Page 134 (Table 1105.05B):
- Change name to Table 1105.07B, and moved to Section 1105.07.I.ii

Page 132-133 (Section 1105.07.H.):
- Remove section 1105.07.H.i.2.c.1, 1105.07.H.i.2.d, 1105.07.H.i.2.e, and 1105.07.H.i.2.f. **KEEP** 1105.07.H.i.2.c, just remove subsection 1.

Page 129 (Section 1105.07.H.ii.1):
- Change it from saying Table 1105.05A to Table 1105.07A

Page 134 (Table 1105.07B):
- Remove the word “to” from “Adjacent zone or district to required to provide buffer”

Page 135 (Section 1105.07.J.v.):
- Add to end of bullet, “Required interior lot landscaping shall not be applied as parking lot area landscaping and vice-versa.”

Page 138 (Section 1105.07.I.iv.10):
- Remove extra period

Page 139 (Section 1105.09.A):
- Unbold the T

Page 139 (Section 1105.09.B.ii):
- Amended to “The height of parking lot lighting shall not exceed twenty feet (20’) above grade and shall direct light downward, i.e. cut-off type fixtures. In conjunction with a major site plan review, the Planning and Zoning Board or Administrator may require a lower standard based upon specific characteristics of the site.”

Page 139 (Section 1105.09.B.iii):

- Added “The height of light poles in loading areas and parking areas of semi-trailer trucks, tractor trucks, and similar vehicles in the I, Innovation zoning district only, shall not exceed thirty feet (30’) above grade and shall direct light downwards, i.e. cut-off type fixtures. In conjunction with a major site plan review, the Planning and Zoning Board or Administrator may require a lower standard based upon specific characteristics of the site.”

Page 140 (Section 1105.09):
- Add sections C and D:
    - **C. Photometric Plan Requirements.** For developments requiring site plan review, a photometric lighting plan shall be submitted and shall include:
        - Location and height of all proposed fixtures
        - Type and wattage of lamps
        - ISO-footcandle diagrams showing light levels at ground level, including property lines
        - Fixture cut sheets demonstrating shielding and photometric distribution
    - **D. Parking Lot Lighting.**
        - Any parking lot containing ten (10) or more parking spaces, which is used during non-daylight hours, shall be illuminated during such hours to assist both motorists and pedestrians in avoiding accidents. Non-daylight hours are defined as sunset to sunrise.
        - For aesthetic compatibility, light fixtures in parking lots shall be of the same or similar type and color.
        - Light fixtures shall be placed in parking lot islands or solid bases to protect both lights and vehicles from possible damage.

Page 142 (Table 1105.11B)
- Change Innovation Zone Max Height for Front and Corner Yard Fences to eight (8) feet.

Page 143 (Section 1105.11.A.ii.7):
- Added a period after the sentence “This includes but is not limited to, painted or treated lumber, vinyl, wrought iron, painted aluminum, brick, stone.”

Page 144 (Section 1105.11.A.iv.1):
    - Remove four and change to eight, remove 4 and change to 8
    - Now reads:
    - **Front and Corner Yard Fences—Height.** Between the front setback line for structures and the front facade of the principal structure, fences shall be no higher than eight feet (8FT).

Page 146 (Section 1105.11)
- C should be B, and the rest of the lettering should change accordingly.

Page 147 (Section 1105.13.A.i):
- Added “and the Olde Reynoldsburg Commercial District (ORD-C).”

- Now reads “Temporary special land uses for tent sales, sidewalk sales, or seasonal sales of produce, plants, firewood, or Christmas trees shall only be permitted in the Community Commercial Zone (CC), the Brice & East Main Street District (BMD), the East Main Street District (EMD), and the Olde Reynoldsburg Commercial District (ORD-C).”

Page 149 (Section 1105.13.C):
- Deleted “Fish Ponds, and Water Parks” from title, and “fish pond, or water park” from description.

Page 150 (Section 1105.13.C.i.2):
- Added “(including decks)”.
- Changed “principle” to “principal”
- Now reads “The pool, including any walks or paved areas or accessory structures (including decks) adjacent thereto, shall not be located closer than ten feet (10’) to any lot line, shall not be closer than 10’ from the principal structure, and shall not be closer to any frontage than a distance ten feet (10’) greater than the setback required for a principal building. A pool is not permitted in the front yard or side front yard.”

Page 150 (Section 1105.13.C.iii):
- Deleted section.

Page 153 (Section 1105.13.I):
- ii - Updated to say “The home occupation shall be clearly incidental and subordinate to the dwelling use, with a minimum permitted square footage of three hundred square feet (300) or no more than thirty percent (30%) of the floor area of the principal building, whichever is greater.”
- iii – Added new bullet to say “The home occupation shall only be conducted in the principal building on the parcel.”
- Numbering thereafter shifted down

Page 153 (Section 1105.13.J):
- Remove “body piercing establishment, tattoo establishment.”

Page 155 (Section 1105.13.M.i):
- Changed last sentence to say “A zoning certificate is required for freestanding solar panels, roof solar panel arrays, and roof solar shingles.”

Page 155 (Section 1105.13.M.iv.7):
- Amended to say “7. Such other information as the Planning and Zoning Administrator may determine to be necessary to evaluate compliance with this section and with the Zoning Code.”
    - “determine” had a “d” at the end

Page 156 (Section 1105.13.O):
- Add Supplemental Use section for Retail – Smoke Shop/Vape Shop

- **Retail – Vape Shop/Smoke Shop.** The following regulations shall apply to conditional use permits for any retail – vape shop/smoke shop facility:
  - No vape shop/smoke shop facility shall be located within a five hundred (500) feet radius of another such vape shop/smoke shop facility measured from the centerline of the front door of the establishment.
  - No vape shop/smoke shop facility shall be located within a five hundred (500) feet radius of any public park, residential district, or school, as measured from the centerline of the front door of the establishment.
  - Any vape shop/smoke shop facility shall not be permitted with any other use located on the same parcel of land or located within the same building.

Page 156 (Section 1105.13.P):

- Add Supplemental Use section for Dwelling – Group
  - **Dwelling – Group**. The following regulations shall apply to conditional use permits for any Dwelling-Group:
    - The site will be staffed 24 hours a day.
    - No commercial activities will be conducted on the site.
    - The land use will not be located within 500 feet of another parcel where an existing Dwelling –Group is located. This requirement is measured from the parcel boundary.

Page 162 (AFTER Section 1105.19):

- 162 Add Section 1105.21 – Commercial Design Standards
- *A. Purpose. The design standards in this section are intended to:*
  - *i. Promote a visually appealing built environment with human-scale design.*
  - *ii. Reinforce the identity and character of mixed-use centers and corridors.*
  - *iii. Encourage architectural variety while maintaining a unified streetscape.*
  - *iv. Ensure that new development complements surrounding structures and the public realm.*
- *B. Applicability. These standards shall apply to all new construction, and the expansion of an existing structure of Community Commercial (CC), Brice and Main Street District, (BMD) and the East Main Street District (EMD).*
- *C. Street Orientation.*
  - *i. All buildings shall have a primary façade and functional entrance oriented toward the primary public street or plaza.*
  - *ii. Buildings located on corners shall address both the primary and secondary streets through façade articulation.*
- *D. Transparency Requirements.*
  - *i. Ground floor façades along primary streets must have a minimum of 20% transparency (clear, non-reflective glass).*
- *E. Blank Walls.*
  - *i. No street-facing façade shall contain a blank wall.*
  - *ii. Architectural features or landscaping shall be used to break up large walls.*

- *F. Entries.*
    - *i. Primary entries shall be clearly identifiable with architectural detailing, awnings, or recesses.*
- *G. Façade Articulation. Façades longer than 30 feet must include at least one of the following:*
    - *i. Wall plane projections/recesses (minimum 12 inches)*
    - *ii. Material or color changes*
    - *iii. Vertical bays or pilasters*
    - *iv. Variation in roof height*
- *H. Material Requirements.*
    - *i. Acceptable materials include:*
        - *Brick (clay or cast)*
    - *Stone or cast stone or synthetic stone*
    - *Wood or fiber-cement siding*
    - *Architectural metal panels*
    - *Glass*
    - *Stucco (cementitious)*
    - *Decorative tile*
    - *Natural wood elements*
    - *Other materials as approved by the Zoning and Planning Administrator, based on visual commutability with listed approved materials.*
- *I. Prohibited Materials.*
    - *i. Vinyl siding (except as an accent material)*
    - *ii. Mirrored or opaque glass*
    - *iii. Unfinished concrete block*
- *J. Roof Design.*
    - *i. All roof designs are permitted.*
    - *ii Flat Roofs*
        - *Flat roofs must include parapets or a pronounced cornice line.*
    - *Mechanical equipment shall be screened by the parapet and not visible from the street.*
    - *iii. Pitched Roofs*
        - *Minimum slope: 4:12*
- *K. Building Lighting.*
    - *i. Accent lighting may highlight architectural features but must be fully shielded to prevent light trespassing, glare and light pollution.*

- 164 Add Section 1105.23 – Property without Direct Street Frontage
    - *A. Purpose and Intent. The purpose of this section is to regulate the subdivision and redevelopment of landlocked parcels in order to:*
        - *Ensure safe and functional access for – residents, customers, employees, and emergency services.*
        - *Prevent traffic congestion and circulation issues within developments.*
        - *Promote economic development and property utilization while maintaining access to essential infrastructure.*
        - *Require public or private street connections when necessary for safe*

and efficient site access.

- *B. General Access Standards.*
  - *No new parcel shall be created unless it has legal access to a public or private street.*
  - *Access to landlocked parcels may be established through:*
    - *A recorded easement sufficient to engineering requirements for two-way traffic.*
    - *A shared access driveway with adjacent properties sufficient to engineering's requirements.*
    - *A new private street or service road meeting engineering standards.*
- *C. Minimum Street Frontage for Subdivision.*
  - *If a parcel is subdivided without direct frontage, a cross-access agreement with an adjacent property is required.*
- *D. Private Streets and Shared Access Drives.*
  - *Private streets serving commercial developments must include:*
    - *A minimum pavement width that meets engineering standards.*
    - *Legal agreements for maintenance and repair among benefiting properties.*
    - *Compliance with Section 1111.15, Standards.*
  - *Shared access drives must:*
    - *Meet engineering's design standards for traffic.*
    - *Have clear directional signage and striping to ensure visibility and traffic flow.*
    - *Connect to at least one public street or service road.*
- *E. Cross-Access Requirements.*
  - *i. All redevelopments on landlocked parcels must provide a cross-access driveway to adjacent commercial properties, unless infeasible due to:*
    - *1. Significant grade changes or environmental constraints.*
    - *2. Incompatible land uses that prevent safe shared access.*
  - *ii. Where feasible, sites should incorporate a service road or access lane to reduce curb cuts on primary streets.*
- *F. Parking and Loading Access.*
  - *i. Shared parking arrangements must be recorded in a cross-easement agreement or a reciprocal easement agreement when access is shared between parcels.*
  - *ii. Loading zones and service areas must be accessible from a private street, service road, or dedicated access lane, and not require backing movements onto public roads. Except for the ORD-C & ORD-N commercial land uses.*
- *G. Exclusion.*
  - *i. This section does not apply to new residential subdivision of lots.*

- 166 Add Section 1105.25 – Temporary Storage Containers on Construction and Renovation Sites

- *Purpose. To permit the temporary use of storage containers for securing materials and equipment during active construction or renovation, while protecting public safety, minimizing visual impacts, and ensuring timely removal.*
- *Applicability. Storage containers are permitted only in association with the following:*
  - *An active construction or renovation project with a valid building permit;*
  - *As an Accessory Dwelling Unit (ADU), meeting all residential design standards and ADU requirements;*
  - *A construction job site trailer, with an active construction or renovation project with a valid building permit.*
- *Standards.*
  - *i. Permit and Duration*
    - *Containers must be included in an approved building permit or a separate temporary use permit.*
    - *Storage containers are permitted only for the duration of active construction activity.*
    - *Extensions beyond the permitted construction period require approval of a temporary use extension by the Zoning Administrator.*
  - *ii. Location.*
    - *Containers must be placed on the same lot as the construction or renovation project.*
    - *Containers shall not be placed within public rights-of-way, required landscape areas, sidewalks, fire lanes, or designated parking spaces without specific approval.*
    - *Containers must comply with required setbacks unless otherwise authorized.*
  - *iii. Size and Quantity.*
    - *1. The number and size of containers shall be appropriate to the scale of the construction or renovation project and subject to review by the Zoning Administrator.*
    - *2. For single-family residential construction or renovation, no more than one (1) container, not exceeding 320 square feet in area, shall be permitted unless otherwise approved.*
  - *iv. Appearance and Maintenance:*
    - *1. Containers shall be maintained in good condition, free of graffiti, peeling paint, or visible damage.*
    - *2. Only identification signage (maximum 6 square feet per side) is permitted.*
  - *v. Prohibited Use as Permanent or Accessory Structures.*
    - *1. Storage containers shall not be used as a permanent structure, accessory structure, or storage building on any property.*
    - *2. Storage containers shall not be used for storage purposes on vacant lots or properties without active construction or*

renovation.

- *3. Storage containers shall not be converted for occupancy, commercial operations, or any other use not directly related to construction or renovation activities under an active permit, with the exception of an Accessory Dwelling Unit (ADU) meeting all residential design standards and ADU requirements.*

- *vi. Exceptions. The Zoning Administrator may approve administrative modifications to these standards in cases of unusual site conditions, large-scale development projects, or for the protection of public health, safety, or welfare.*

Page 170 (1107 Non-Conformities):

- Changed Section:
  - *SECTION 1107.01 PURPOSE OF NONCONFORMITIES*
    - *A. This section's regulations are intended to minimize governmental takings of private property rights resulting from the enactment of new land use regulations by permitting certain legal nonconforming uses, lots, and structures to continue to exist.*
  - *SECTION 1107.03 UNLAWFUL LOTS, USES, AND STRUCTURES, GENERALLY*
    - *A. This chapter does not allow for the perpetuation of uses or structures that were unlawfully established or constructed. Such uses or structures are not "legally nonconforming," but instead remain "unlawful," and are subject to all of the provisions of this Code and any other applicable law. Likewise, this chapter does not legitimize unlawful subdivisions of property.*
  - *SECTION 1107.05 LEGAL NONCONFORMING STATUS ATTACHED TO THE LAND*
    - *A. The status of a use as a legal nonconforming use shall run with the land and be independent of the identity of the property owner and of the structure in which the nonconforming use is conducted. The status of a structure as a legal nonconforming structure shall run with the land and be independent of the identity of the property owner and of the use conducted within, around, or on such structure.*
  - *SECTION 1107.07 UNDERSIZED OR OVERSIZED LOTS*
    - *A. Undersized or Oversized Lots Definition. An undersized or oversized lot is any lot that was legally created prior to the enactment of this Zoning Code and has dimensions that do not comply with the minimum or maximum lot area, lot frontage, lot width, and/or lot depth standards required by this Zoning Code.*
    - *B. Undersized or Oversized Lots Continuance. An undersized or oversized lot shall be permitted to support structures that are legally situated or were legally situated at their time of erection, provided that the structure is not determined by the City to pose an immediate risk to public safety. An undersized or oversized lot shall be permitted to be put to use by any legal land use, provided that the lot*

has sufficient frontage on a public street to provide emergency response access that is appropriate for the proposed use, and shall be permitted to continue to be put to use by a legal nonconforming use, subject to the regulations of Section 1107.09 "Nonconforming Uses."

- *SECTION 1107.09 NONCONFORMING USES*
  - *A. Legal Nonconforming Uses Definition. For the purposes of this section, a legal nonconforming use shall be any use of a particular lot that fulfills one (1) of the following:*
    - *i. The use of that lot was a permitted land use by the previously effective Zoning Code, either by right or as Conditional Use, and was appropriately permitted by the City, but that use of land is no longer a permitted land use in the district in which it is located by this Zoning Code; or*
    - *ii. The use of land was deemed a legal nonconforming use by the previously effective Zoning Code, but that use of land is no longer a permitted land use in the district in which it is located by this Zoning Code.*
  - *B. Abandonment of Use. Whenever a nonconforming use has been discontinued for a period of six (6) months, it shall be considered abandoned, and any subsequent use shall conform to the regulations of this Zoning Code.*
  - *C. Nonconforming Uses Burden of Proof. When ambiguity exists, it shall be the burden of the property owner to prove to the City that a particular land use on their property, which does not conform to the standards of this Zoning Code, was put into use on a date in which such land use was a permitted use under a former Zoning Code and that such land use has not since been intentionally abandoned.*
  - *D. Nonconforming Uses Continuance. A legal nonconforming use shall be permitted to continue, provided that all of the following conditions are met:*
    - *i. The legal nonconforming use was not considered intentionally abandoned on the effective date of this Zoning Code or at any point thereafter;*
    - *ii. The legal nonconforming use continues to occur on the same lot as was previously occupied by such land use, and the legal nonconforming use is not expanded to another lot;*
    - *iii. The specific nature of the legal nonconforming use is not changed, or the specific nature of the legal nonconforming use is changed in a manner consistent with Section 1107.09 (E) "Change of Legal Nonconforming Use"; and*
    - *iv. The legal nonconforming use is not expanded in its intensity, including hours of operation, average number of working hours per week, capacity for customers, and footprint of the lot area dedicated to the use, except where specifically permitted by the following subsection, Section 1107.09 (F) "Expansion of Nonconforming Uses."*

- *E. Change of Legal Nonconforming Uses. No change to the specifications of a legal nonconforming use shall be permitted where such a change, according to the City, may result in an increased risk to public safety.*
- *F. Expansion of Nonconforming Uses. A legal nonconforming use shall not be expanded in its intensity, including in its hours of operation, average number of working hours per week, capacity for customers, and footprint of the lot area dedicated to the use, except that a nonconforming use shall be permitted to expand into a portion of the lot or structure that was manifestly arranged for such use while such legal nonconforming use was a conforming use of the land and was not abandoned, and such expansion shall permit a proportional increase in customer capacity and working hours.*

- *SECTION 1107.11 NONCONFORMING STRUCTURES*
  - *A. Legal Nonconforming Structures Definition. For the purposes of this chapter, a legal nonconforming structure is any structure that was existing and lawful as of the date of adoption of this Zoning Code, or in the case of amendment to this Zoning Code, then at the time of such amendment, and which does not now conform to the provisions of this Zoning Code or amendment thereto with respect to setback, height, building footprint or lot coverage, impervious coverage percentage, building type, or architectural design standards.*
  - *B. Legal Nonconforming Structures Continuance.*
    - *i. A legal nonconforming structure shall be permitted to continue existing, provided that all of the following conditions are met:*
      - *1. The legal nonconforming structure does not pose an immediate risk to the public safety, as determined by the City;*
      - *2. The legal nonconforming structure is not reconstructed, repaired, or expanded, except according to the provisions described in this section.*
    - *ii. All existing portions of a legal nonconforming structure may be put to use, provided that such use is not illegal and provided that such use does not violate this Zoning Code, including use specific standards, and does not violate any other City, County, State, or Federal statute.*
  - *C. Reconstruction or Repair of a Legal Nonconforming Structure. The reconstruction, repair, or maintenance of a legal nonconforming structure shall be permitted to occur, provided that the nonconforming feature is not enlarged, increased, or extended more than 50 % of the structure's then fair market value; that no new nonconforming feature is created; and that reconstruction or repair occurs within six (6) months of the legal nonconforming structure's disrepair, destruction, or demolition. If reconstruction, repair, or maintenance does not occur within six (6) months, a written request*

for extension may be submitted to a designee of the Development Department.

- *D. Expansion of a Legal Nonconforming Structure. A legal nonconforming structure may be expanded or reduced, provided that the expansion or reduction does not intensify the nonconforming nature of the structure and does not result in any additional nonconforming feature. For example, a structure that is legally nonconforming because it has a lesser front setback than required by this Zoning Code in the district in which it is located may be expanded, provided that the expansion does not occur within the required front yard setback and does not violate any other structure focused provision, including height limits, building footprint limits, impervious coverage limits, minimum setbacks from lot lines, or design standards.*

- *SECTION 1107.13 OTHER NONCONFORMITIES*
  - *A. Nonconforming Signs Regulated Elsewhere. Nonconforming signs are regulated by Section 1105.03 "Nonconforming Signs."*
  - *B. Nonconforming Parking.*
    - *i. Any nonconforming parking behavior, including the parking of vehicles on areas of a lot where prohibited by the standards in this Zoning Code, shall be considered an immediate violation of this Zoning Code.*
    - *ii. Any nonconforming impervious surface coverage caused in part by parking areas shall be regulated as a parking area infrastructure nonconformity according to the subsection below.*
    - *iii. All nonconforming parking area infrastructure on a lot, such as not providing the correct number of bicycle parking spaces or electric vehicle charging stations or building a number of parking spaces in excess of parking maximums, shall be permitted to continue, provided that such nonconformities are brought into conformity during any of the following occurrences:*
      - *1. The complete reconstruction of the principal structure on the lot, or the piecemeal reconstruction of such entire structure over the course of two (2) years or less; or*
      - *2. A net increase in vehicle parking area on the lot.*

Page 179 (Section 1109.05.B.ix):

- Add ".11" to "1109"

Page 179 (Section 1109.05.B.xi):

- Change 1109.17 to 1109.15

Page 181 (Section 1109.09.B):

- Add "This includes changes of the name and/or ownership of a business."
  - Now reads "No use of land, building or structure and no construction or alteration of an existing use, building, or structure shall commence until a zoning certificate is issued by the Planning and Zoning Administrator

certifying that the intended use of the premises has been documented, reviewed, and approved in conformance with the provisions of this Zoning Code. This includes changes of the name and/or ownership of a business. A zoning certificate shall only be issued by the Planning and Zoning Administrator subsequent to completion of all procedures and approvals required by this Code. The Planning and Zoning Administrator shall not be required to issue a zoning certificate where the subject property is not in compliance with the Zoning Code, Building Code, or Property Maintenance Code."

Page 181 (Section 1109.09.C):

- Adding back in after wording was lost, subsections i – iv.
    - Locating, erecting, constructing, reconstructing, altering or moving any building/structure, including accessory structures such as a sign or fence;
    - Occupying or using land or a building or changing the use of land or of a building in whole or in part for a different use;
    - Changing a nonconforming use to a different use of extending or expanding a nonconforming use or structure.
    - Where a non-conforming use has been discontinued, meaning the structures containing the use has remained vacant, unoccupied, unused or has ceased the daily activities or operations which had occurred for a period of 6 or more continuous months, the non-conforming use shall be permanently terminated. Please refer to Section 1107 for additional information on Non-Conformities.

Page 182 (Section 1109.11.B):

- Add the two additional points after iii to match the variance application
    - *B. An applicant seeking a variance shall submit a written request for variance on forms provided by the Planning Zoning Administrator together with the applicable fee. In addition to information relating to the subject property and the applicant, the request for a variance shall include the following information:*
        - *The name, address, and telephone number of the property owner (s) and owner's agent(s);*
        - *The legal description, address, tax district and parcel number of the property;*
        - *A description of the nature of the variance requested and a statement demonstrating the extent to which the requested variance conforms to the standards for variance in this Code;*
        - *A statement of hardship; and*
        - *Such other information and exhibits as may be appropriate to establish the facts of the appeal and the grounds for relief.*

Page 183 (Section 1109.11.D.iii):

- Separated the existing factors for iii into two separate factors. Now 10 total factors.
- Within the new iv, replace 'must be' with 'is':
    - Revise the new iv to say "There is a deprivation of the beneficial use of

land, as opposed to mere loss in value as justification for the variance."
- Update numbering of factors thereafter

Page 187 (Section 1109.13.K):
- Add period after PZB

Page 188 (Section 1109.15.F):
- Change 1109.25 to 1109.23

Page 188 (Section 1109.15.G):
- Change 1109.15(J) to 1109.13(J)

Page 190 (Section 1109.17.C.ii)
- Add in numbers 1 and 2:
    - 1. Shall be signed and sealed by a professional engineer, architect, or landscape architect registered with the State of Ohio.
    - 2. Each sheet shall contain a title block with the name of the project and the address of the project.
- Update numbers accordingly thereafter

Page 190 (Section 1109.17.C.ii.6):
- Remove the word "concept" from the sentence.

Page 192 (Section 1109.19.B):
- Delete this bullet.

Page 193 (Section 1109.19.F):
- Edited "th" to "the" and added in "PZB"
    - Now reads "**Other Land Use Approvals.** An application for a COA in which the design under consideration would require a variance granted by the Planning and Zoning Board or a site plan and design review by the Planning and Zoning Board prior to construction shall not be considered until a final determination has been made on all required variances or site plan and design reviews. If during the course of a review, the PZB determines that a zoning variance or other approval will be required in order to implement the proposal under consideration, it shall suspend further action on the application until such time as the additional approval has been heard and approved by the PZB or the application has been amended to eliminate the need for such additional approval.

Page 194 (Section 1109.21.B):
- Delete B

Page 195 (Section 1109.21.H):
- Add period after Planning and Zoning Board in first sentence

Page 196 (Section 1109.23.B):

- Add period after PZB

Page 231 (Glossary):
- Take out the definition for Dwelling – Developmental Disability.

Page 227 (Glossary):
- Add these definitions:
    - **Electric Vehicle (EV).** A motor vehicle that uses one or more electric motors for propulsion. Onboard batteries provide electricity for propulsion, which can be charged using Electric Vehicle Supply Equipment.
    - **Electric Vehicle Supply Equipment (EVSE Installed).** Are parking spaces reserved for Electric Vehicles (EV) and provide dedicated panel capacity, conduit, and EVSE installed.

Page 233 (Glossary):
- Add definition of Food Service – Commercial Kitchen
    - A commercial food facility in which goods are processed or otherwise prepared for off-site sale or consumption. Facilities may operate as a shared facility where multiple individual or businesses lease shared space or may be used by a single operator. This use classification includes catering, as well as ghost kitchen, where customers are served exclusively by delivery and pick-up based on phone and online ordering. No customer dining is provided on the premises. Does not include eating establishments where customers are served from a walk-up ordering counter for either on- or off-premises consumption and establishments where most customers are served food at table for on-premises consumption. This listing also excludes commercial kitchens that are incidental and accessory to the primary use.

Page 236 (Glossary):
- Change definition of Food Service – Commissary/Bakery
    - A facility that produces food and baked goods for distribution or sale to restaurants and retail bakeries. Any on-site and/or direct-to-consumer sales are prohibited. This specifically excludes Food Service – Commercial Kitchen.

Page 239 (Glossary)
- Change definition:
    - Home Occupation. An occupation conducted in a dwelling unit, provided that no person who is not a permanent resident of the dwelling shall be employed in the home occupation. The use of the dwelling unit for the home occupation shall be clearly incidental and subordinate to its use for residential purposes by its occupants, and not more than thirty percent (30%) of floor area of the dwelling unit shall be used in the conduct of the home occupation. There shall be no change in the outside appearance of the building or premises, or other visible evidence of the conduct of such home occupation. No traffic shall be generated by the conduct of such

home occupation and any need for parking generated by the conduct of such home occupation shall meet the off-street parking requirements as specified in this Zoning Ordinance, and shall not be located in a required front yard.

Page 249 (Glossary):

- Add definition of Office - Professional Services – Tarot Card Reading/Palm Reader/Fortune Teller/Psychic
    - A business or individual providing services involving the prediction of future events, insight into personal issues, or spiritual guidance through means such as tarot card reading, palmistry, astrology, clairvoyance, mediumship, or similar methods. This definition does not include licensed counseling services, religious institutions, or medical or psychological services.

Page 258 (Glossary):

- Take out the definition for Residential Care and Congregate Residential.

Page 258 (Glossary):

- Change Retail – Large Format definition to say “A retail establishment containing consumer goods that is 20,000 to 50,000 square feet.”

Page 257 (Glossary):

- Add definition of Retail – Extra Large Format
    - A retail establishment containing consumer goods that exceeds 50,000 square

Page 258 (Glossary):

- Add definition of Retail – Vape Shop/Smoke Shop
    - A retail establishment primarily engaged in the sale of tobacco products, electronic nicotine delivery systems (ENDS) such as e-cigarettes or vape pens, cigars, hookahs, pipes, smoking accessories, and related paraphernalia. This use may also include the on-site sampling of tobacco or vapor products, where permitted by law. This definition does not include licensed medical or recreational marijuana dispensaries or general retail establishments where tobacco or vape products are incidental to the primary business.

Page 270 (Glossary):

- Vehicular Rental Facility definition added.
    - A facility primarily engaged in the short-term rental or leasing of automobiles, light trucks, vans, trailers, or similar vehicles or equipment. Such facilities may include customer service offices, vehicle and trailer storage areas, minor maintenance activities related to the rental fleet, and associated parking. This use does not include the sale of vehicles as a principal use or heavy vehicle storage or repair.

Page 280 (Last Page):

- Change year from 2024 to 2026

REYNOLDSBURG ZONING CODE

REYNOLDSBURG, OH

~~2024~~ 2026

TABLE OF CONTENTS

1101 INTRODUCTION AND HOW TO USE THIS CODE

1101.01 Title 8
1101.03 Purpose and Intent 8
1101.05 Applicability 9
1101.07 Zones, Districts and Overlays 9
1101.09 Zoning Map 10
1101.11 Rules for Interpreting District Boundaries on the Zoning Map 11
1101.13 Rules of Measurement and Calculation 11
1101.15 Rules of Interpretation 14
1101.17 Minimum Requirements 15
1101.19 Effects of Annexation on Zoning 16
1101.21 Private Provisions 16
1101.23 Conflicting Provisions 16
1101.25 Determination of Land Uses Not Listed in this Code 16
1101.27 Saving Provision for Pending Enforcement Actions 17
1101.29 How to Navigate this Code 17

1103 DISTRICTS

1103.01 Intent 20
1103.03 Compliance with Regulations 20
1103.05 Official Schedule of District Regulations Adopted 21
1103.07 Building Typologies 21
1103.09 Development Standards 21

DISTRICTS

1103.11 Olde Reynoldsburg Commercial District (ORD-C) 23
1103.13 Olde Reynoldsburg Neighborhood District (ORD-N) 32
1103.15 Brice & East Main Street and East Main Street Insight Districts (BMD and EMD) 40

ZONES

1103.17 Suburban Residential Zone (SR) 52
1103.19 Residential Medium Zone (RM) 55

TABLE OF CONTENTS CONT.

1103.21	Community Commercial Zone (CC)	58
1103.23	Innovation Zone (I)	62
1103.25	Open Space / Schools Zone (OS)	66
	BUILDING TYPOLOGIES	
1103.27	Building Typologies	69
	OPEN SPACE TYPOLOGIES	
1103.29	Open Space Typologies	91
	FRONTAGE TYPOLOGIES	
1103.31	Frontage Typologies	96

1105 COMMON REGULATIONS

1105.01	Off-Street Parking and Loading	102
1105.03	Signs	114
1105.05	Accessory Structures	121
1105.06	Residential Design Standards	123
1105.07	Landscaping and Buffering	125
1105.09	Exterior Lighting	136
1105.11	Fences and Screening	138
1105.13	Supplementary Use Conditions	144
1105.15	Telecommunications Facilities	153
1105.17	Conversion of Dwelling Units	156
1105.19	Performance Standards	156
1105.21	**Commercial Design Standards**	**158**
1105.23	**Property Without Direct Street Frontage**	**159**
1105.25	**Temporary Storage Containers on Construction and Renovation Sites**	**161**

TABLE OF CONTENTS CONT.

1107 NON-CONFORMITIES

1107.01	Purpose of Nonconformities	162
1107.03	Unlawful Lots, Uses, and Structures, Generally	162
1107.05	Legal Nonconforming Status Attached to the Land	162
1107.07	Undersized or Oversized Lots	162
1107.09	Nonconforming Uses	163
1107.11	Nonconforming Structures	164
1107.13	Other Nonconformities	165

1109 ADMINISTRATION AND PROCEDURES

1109.01	Review and Approvals Summary	170
1109.03	Planning and Zoning Administrator	172
1109.05	Planning and Zoning Board	172
1109.07	Applications	174
1109.09	Zoning Certificates	175
1109.11	Variances	176
1109.13	Conditional Uses	178
1109.15	Similar Use Determination	181
1109.17	Site Plan and Design Review	183
1109.19	Certificate of Appropriateness - Olde Reynoldsburg Districts	186
1109.21	Zoning Map (Rezoning) and Text Amendment	187
1109.23	Appeals	189
1109.25	Duration of Certificates, Permits, Approvals	190
1109.27	Violation; Remedies	190

TABLE OF CONTENTS CONT.

1111 SUBDIVISION REGULATIONS

1111.01	Variances	196
1111.03	Approval of Subdivision without Plat	196
1111.05	Preliminary Plat	196
1111.07	Final Plat	199
1111.09	Additional Required Information	199
1111.11	Required Improvements	202
1111.13	Street Lights	203
1111.15	Standards	205

1113 GLOSSARY OF TERMS 214



1101 INTRODUCTION AND HOW TO USE THIS CODE

Introduction and How to Use this Code

SECTION 1101.01 TITLE

A. This Code shall hereinafter be known and cited as "The City of Reynoldsburg Zoning Code," and hereinafter referred to as the/this "Code" or "these regulations."

SECTION 1101.03 PURPOSE AND INTENT

A. In adopting this Code, Council has given reasonable consideration to, among other things:

i. the comprehensive plan;

ii. current conditions and the character of current structures and uses in each district;

iii. the most desirable use for which the land in each district is adapted;

iv. the conservation of property values throughout the City of Reynoldsburg; and,

v. responsible development and growth of the City of Reynoldsburg and hereby adopts this Code for the following purposes:

1. To promote the achievement of the Comprehensive Land Use Plan for the City;
2. To advance the position of the City as a center of commerce, industry, recreation and culture;
3. To provide for desirable, appropriately located living areas in a variety of dwelling types and at a suitable range of population densities, with adequate provision for sunlight, fresh air and usable open space;
4. To protect residential, commercial, industrial and civic areas from the intrusions of incompatible uses, and to provide opportunities for establishments to concentrate for efficient operation in mutually beneficial relationship to each other and to share services;
5. To ensure preservation of adequate space for commercial, industrial and other activities necessary for a healthy economy;
6. To promote safe, fast and efficient movement of people and goods without sacrifice to the quality of the City's environment and to provide adequate off-street parking;

7. To stabilize expectations regarding future development of the City, thereby providing a basis for wise decisions with respect to such development;
8. To preserve and enhance the quality of the City's environment;
9. To provide for effective signage that is compatible with the surrounding urban environment; and
10. To maintain the safety and potability of public water supplies located within the City.

SECTION 1101.05 APPLICABILITY

A. In their interpretation and application, the provisions of this Code shall be held to be minimum requirements (unless a maximum standard is established) adopted for the promotion of the public health, safety, convenience, comfort, prosperity or general welfare. Wherever the requirements of the Code are at variance with the requirements of any other lawfully adopted rules, regulations, codes, deed restrictions or covenants, the provisions of this Code shall control.

B. No building, structure or land shall hereafter be used or occupied, and no building or structure or part thereof shall hereafter be erected, constructed, reconstructed, moved or altered except in conformity with all of the regulations herein specified for the zone or district in which it is located.

SECTION 1101.07 ZONES, DISTRICTS AND OVERLAYS

A. The following zones and districts are hereby established for the corporate limits of the City of Reynoldsburg, and land within said areas shall be designated on the Zoning Map by the following symbols:

B. The Planned Development districts (PNDD and PCDD) are no longer included in the zoning districts applicable to this Code. No new projects or developments shall use the Planned Development district. All projects previously designated PNDD or PCDD shall be assigned a different zoning district with

DISTRICTS	SYMBOL	REPLACES
ZONES		
Suburban Residential Zone	SR	R-1; R-2; R-3
Residential Medium Zone	RM	R-4; R-20; AR-1; AR-1; AR-2; AR-3; MH
Community Commercial Zone	CC	CC; CO; NC
Innovation	I	RI; GI
Open Space/Schools	OS	CS

DISTRICTS	SYMBOL	REPLACES
	DISTRICTS	
Olde Reynoldsburg Commercial District	ORD-C	HOD
Olde Reynoldsburg Neighborhood District	ORD-N	HOD
Brice and Main District	BMD	NA
East Main District	EMD	NA
	OVERLAYS	
Flood Plain Overlay District	FPO	No change
Historic Overlay District	ORD-C; ORD-N	HOD

Not Applicable	NA
Not Permitted	NP

Allowable Use	P
Conditional Use	C

the adoption of this Code; provided, however, they may continue to function under the established PNDD or PCDD regulations previously adopted and specific to that development. Any project within the same geographic boundaries of the existing Planned Development may be redeveloped under the same provisions that were previously adopted. An owner of property greater than two acres in total area, with the approval of the Planning and Zoning Administrator, may instead select to designate the existing Planned Development into applicable zoning districts that most closely relate to the existing uses and building form.

SECTION 1101.09 ZONING MAP

A. The City is divided into zones and districts as shown on the Zoning Map, which, together with all explanatory matter thereon, is adopted by reference and declared to be a part of this Code.

B. The Zoning Map shall be located in the office of the Director of Development of the City of Reynoldsburg, maintained on file in the office of the Clerk of Council, and on the City's official website, and this map shall be the final authority as to the current zoning status of land and water areas, building, and other structures in the City.

C. No changes of any nature shall be made in the Zoning Map or matter shown thereon except in accordance with the procedures set forth in Title Eleven of this Code. Any unauthorized change of whatever kind by any person or persons shall be considered a violation of this Code and punishable as provided under this Code.

D. Visit https://www.reynoldsburg.gov to view the most recent and interactive zoning map.

SECTION 1101.11 RULES FOR INTERPRETING DISTRICT BOUNDARIES ON THE ZONING MAP

A. The following rules shall apply to the interpretation of district and zone boundaries on the Zoning Map:

i. Boundaries indicated as approximately following the centerlines of streets, highways, or alleys shall be construed to follow such centerlines;

ii. Boundaries indicated as approximately following platted lot lines shall be construed as following such lot lines;

iii. Boundaries indicated as approximately following City limits shall be construed as following such City limits;

iv. Boundaries indicated as following railroad lines shall be construed to be midway between the main tracks;

v. Boundaries indicated as following shorelines shall be construed as moving with the actual shoreline; boundaries indicated as approximately following the centerlines of streams, rivers, canals, lakes, or other bodies of water shall be construed to follow such centerlines; and

vi. Boundaries indicated as parallel to or extensions of features listed above shall be so construed. Distances not specifically indicated on the Zoning Map shall be determined by the scale of the map.


B. Lots Divided by District Boundaries

i. Where a district boundary line divides a lot that was in single ownership at the time of passage of this Code, the Planning and Zoning Board may permit the extension of the regulations for either portion of the lot beyond the district line into the remaining portion of the lot.

SECTION 1101.13 RULES OF MEASUREMENT AND CALCULATION

A. Height Measurement

i. Building height is measured as the distance between a horizontal line at the average existing pre-development grade of the lot directly beside the structure, and the highest point of the coping of a flat roof, the top of a mansard roof, the midpoint of any pitched gable, hip or the upper portion of a gambrel roof, or measured between the top floor ceiling and the peak of the roof on an "A" framed structure. Chimneys, elevators, poles, spires, tanks, towers, and other projections not used for human occupancy are not included in calculating height and may extend above the height limit.



HEIGHT MEASUREMENT

B. Measuring Distance

i. When measuring a required distance, such as the minimum distance between a structure and a lot line, the measurement is made at the closest or shortest distance between them.

ii. When measuring a required distance, such as the ~~minimum~~ **maximum** distance between a structure and another structure, the measurement is made at the ~~closest or shortest~~ **furthest or longest** distance between them.

C. Measuring Setbacks

i. The front street setback is measured at a right angle from the private and/or public right-of-way line.


ii. Where a lot extends through the block from street to street, the required front yard must be provided along each street.

iii. The side street setback is measured at a right angle from the side street right-of-way line.

iv. The rear setback is measured at a right angle from the rear lot line or the rear right-of-way or easement line where there is an alley. The rear lot line is the lot line opposite to the front street lot line. Where there is more than one front street, the Planning and Zoning Administrator will determine the rear lot line

v. All lot lines which do not front a street, side street or rear lot lines are considered side interior lot lines.

vi. For the purpose of measuring setbacks, side interior setbacks are measured at a right angle from the side lot line.




MEASURING SETBACKS

D. Determining Average Grade

i. Average grade is determined by calculating the average of the highest and lowest elevation along natural or improved grade (whichever is more restrictive) along the front of the building parallel to the front street setback line.

E. Yards, Open Space, and Parking

i. Unless otherwise permitted herein, no part of a yard, or other open space, or off-street parking or loading space required about or in connection with any building for the purpose of complying with this Code shall be included as part of a yard, open space, or off-street parking or loading space similarly required for any other building.



DETERMINING AVERAGE GRADE

F. Lot or Yard Dimensions

i. No yard or lot existing at the time of passage of this Code shall be reduced in dimension or area below the minimum or above the maximum requirements set forth herein. Yards or lots created after the effective date of this Code shall meet at least the minimum or maximum requirements established by this Code. The Planning and Zoning Administrator will determine setbacks for irregular shaped lots.

G. Permitted Encroachments into Setbacks

i. Fences and walls may encroach into a required setback.

ii. Sidewalks and driveways may encroach into a required front setback.

iii. A required buffer yard may encroach into a required setback.

iv. Landscaping may encroach into a required setback.

v. Building eaves, roof overhangs, gutters, downspouts, light shelves, bay windows and oriels less than ten (10) feet wide, chimneys, flues cornices, belt courses, sills, buttresses or other similar architectural features may encroach up to three (3) feet into a required setback, provided that such extension is at least two (2) feet from the vertical plane of any lot line.

vi. Unenclosed patios, decks, terraces or porte cochere may encroach into a side interior or rear setback, provided that such extension is at least three (3) feet from the vertical plane of any lot line. With the exception of Dwelling – Attached Single-Family land uses, which would have a zero (0) foot setback from the vertical plane of any side lot line.

vii. An awning, canopy or gallery may encroach into a front or side street setback provided that such extension is at least one (1) foot from the vertical plane of any lot line.

viii. Front porches and balconies may encroach into a front setback provided that such encroachment is no greater than six (6) feet from the front building facade, and no closer than 10 feet from the vertical plane of any lot line.

ix. Dwelling – Attached Single-Family land uses in residential zoned districts are permitted to have front porches, balconies, sidewalks, driveways, patios, decks, and terraces encroach into the side setback for a zero (0) foot side setback.

SECTION 1101.15 RULES OF INTERPRETATION

A. Whenever a defined word appears in the Code, its meaning is as set forth in this article. Words not defined in this Code are interpreted in accordance with their usual dictionary meaning and customary usage.

B. All references to other regulations or manuals in this Code refer to the most current version and citation for those regulations or manuals, unless expressly indicated otherwise. When the referenced regulations or documents have been repealed and not replaced by other regulations or manuals, Code requirements for compliance are no longer in effect.

C. Illustrations, diagrams, and flowcharts are included in this Code to illustrate the intent and requirements of the text. In the case of a conflict between the text and any illustration, diagram, or flowchart, the text controls.

D. Except as otherwise noted, any fraction greater than or equal to 0.5 will be rounded up to the nearest whole number. Any fraction less than 0.5 will be rounded down to the nearest whole number.

E. The language of this Code shall be interpreted in accordance with the following regulations:

i. The word "person" includes a firm, association, organization, partnership, trust, limited liability company, corporation, or other legal entity, as well as an individual.

ii. The present tense includes the future tense, the singular number includes the plural, and the plural number includes the singular, in each case, if the context so requires.

iii. The word "shall" is mandatory, the word "may" is permissive.

iv. The words "used" or "occupied" include the words "intended," "designed," "constructed," "altered," or "arranged" to be used or occupied.

v. The word "lot" includes the words "plot," "tract," or "parcel."

vi. The terms "standards," "regulations," and "requirements" are used to mandate a specific course of action or built outcome.

vii. Section headings are provided for ease of use and organization and shall not be interpreted as regulatory.

viii. Where a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and," " "either ... or," the conjunction shall be interpreted as follows:

ix. "And" indicates that all the connected items, conditions, provisions or events shall apply.

x. "Or" indicates that the connected items, conditions, provisions or events may apply singly or in any combination.

xi. "Either ... or" indicates that all the connected items, conditions, provisions or events shall apply singly but not in combination.

SECTION 1101.17 MINIMUM REQUIREMENTS

A. In their interpretation and application, the provisions of this Code shall be held to be minimum requirements (unless a maximum requirement is expressly provided) adopted for the promotion of the public health, safety, morals, and general welfare. Wherever the requirements of this Code are at variance with the requirements of any other lawfully adopted rules, regulations, codes, deed restrictions, or covenants, the most restrictive or that imposing the higher standards shall govern. Wherever special or unusual conditions or circumstances exist, or wherever there is an apparent safety hazard, the Planning and Zoning Board may prescribe additional requirements in order to promote and protect the health, safety, morals and general welfare of the city. The regulations contained in each district or zone herein shall be minimum regulations and shall apply uniformly to each class or kind of structure or land, except as hereinafter provided.

SECTION 1101.19 EFFECTS OF ANNEXATION ON ZONING

A. When a lot developed with an agricultural use or one (1) single-family dwelling is annexed into the City, it shall be classified as SR-Suburban Residential zone upon passage of the ordinance accepting the annexation unless otherwise designated by City Council upon acceptance of the annexation.

B. Any land within the City not designated or otherwise included within another zoning district shall be included in the SR-Suburban Residential zone.

C. When a lot owned by any public authority is annexed into the City via annexation, it shall be classified as an OS-Open Space/Schools zone upon adoption of the ordinance accepting the annexation unless otherwise specified by City Council upon acceptance of the annexation.

D. Annexed land may be incorporated into one or more zoning districts provided the applicant files a development plan satisfying the requirements of Chapter 1109.21that depicts the proposed zoning classification(s) for the annexed land.

SECTION 1101.21 PRIVATE PROVISIONS

A. The provisions of this Code are not intended to nullify, abolish or repeal any easement, covenant or other private agreement or restriction.

SECTION 1101.23 CONFLICTING PROVISIONS

A. In the case of any conflict or inconsistency between two or more provisions of this Code (e.g., the restrictions set forth in an overlay district versus the restrictions set forth in a base district) or any other City ordinance, the provision which imposes the greater or higher or more restrictive standard shall control.

SECTION 1101.25 DETERMINATION OF LAND USES NOT LISTED IN THIS CODE

A. It is recognized that this Code may require interpretation to assign all possible uses to individual zones or districts. Therefore, any use which is not specifically set forth in this Code shall be reviewed by the Planning and Zoning Administrator for consistency with the intent set forth in each district and for compatibility with use characteristics typical of uses permitted within those zones or districts. Based upon this review, the Director of Development shall determine the appropriate district or zone for any use which is not specifically set forth herein. In case of disagreement with the determination of the Director of Development in assigning a use to an appropriate district or zone, any aggrieved party may file an appeal with the Planning and Zoning Board.

SECTION 1101.27 SAVING PROVISION FOR PENDING ENFORCEMENT ACTIONS

A. Except as shall be expressly provided for in this Code, the adoption of this Code shall not:

i. nullify or make void any action pending under, or by virtue of, any prior zoning code or subdivision code;

ii. discontinue, nullify, void, abate, modify or alter any penalty accruing or about to accrue under, or by virtue of, any prior zoning code or subdivision code;

iii. affect the liability of any person, firm, or corporation under, or by virtue of, any prior zoning code or subdivision code;

iv. waive any right of the City under any section or provision of any prior zoning code or subdivision code; or,

v. vacate or annul any rights obtained by any person, firm, or corporation by lawful action of the City under, or by virtue of, any prior zoning code or subdivision code.

SECTION 1101.29

HOW TO NAVIGATE THIS CODE:

1. Step One: Locate your property and applicable district or zone on the Zoning Map, which can be found on the City of Reynoldsburg website at: www.reynoldsburg.gov.

2. Step Two: Locate the applicable district, zone or overlay regulations in Chapter 1103 below.

3. Step Three: Determine the use, building placement, parking, landscaping and signage regulations in the applicable district or zone in Chapter 1103 below.

4. Step Four: Determine if any common regulations apply in Chapter 1105.

5. Step Five: Determine if any nonconformities exist and how to address them in Chapter 1107.

6. Step Six: Determine if any approvals are necessary and how to apply for them in Chapter 1109.

7. Step Seven: Determine if any subdivision is necessary and how to address it in Chapter 1111.

8. Step Eight: Reference the Glossary for use and general terms in Chapter 1113.



1103 DISTRICTS AND ZONES

Districts and Zones

SECTION 1103.01 INTENT

The following districts and zones are hereby established for the regulation of land in the City of Reynoldsburg, Ohio. The districts and zones have been formulated to realize the general purpose as set forth in the preamble of Ordinance No. _____and the Comprehensive Plan, as may be amended from time to time. The specific purpose of each district and zone shall serve the regulatory basis for existing and future development within each district and zone.

SECTION 1103.03 COMPLIANCE WITH REGULATIONS

A. The regulations for each district and zone in this Code shall be minimum regulations and shall apply uniformly to each class or kind of structure or land, except as hereinafter provided or as otherwise granted by the Planning and Zoning Board.

B. No building, structure or land shall be used or occupied and no building or structure or part thereof shall be erected, constructed, reconstructed, moved or structurally altered except in conformity with all of the regulations herein specified for the district in which it is located.

C. No building or other structure shall be erected or altered:

   i. To provide for greater height or bulk;

   ii. To accommodate or house a greater number of families;

   iii. To occupy a greater percentage of lot area; or

   iv. To have narrower or smaller rear yards, front yards, side yards or other open spaces than herein required, or in any other manner be contrary to the provisions of this Code.

D. No yard or lot existing at the time of passage of this Code shall be reduced in dimension or area below the minimum requirements set forth herein. Yards or lots created after the effective date of this Code shall meet at least the minimum requirements set forth herein.

E. Notwithstanding anything to the contrary contained herein, any single lot of record existing on the effective date of this ordinance shall comply with the yard dimension requirements in effect at the time such lot was platted and/or created.

SECTION 1103.05 OFFICIAL SCHEDULE OF DISTRICT REGULATIONS ADOPTED

A. Development and use regulations and standards are included in each district and zone below.

B. Permitted Uses and Conditional Uses for each district and zone are set forth within each section. Permitted Uses shall include all Accessory Uses, as such term is defined within this Code, except as otherwise expressly set forth herein. Conditional Uses require the grant of a Conditional Use permit.


SECTION 1103.07 BUILDING TYPOLOGIES

The Building Typologies included in each district reflect various general forms of development contemplated for all new development within the City. For the alteration of existing structures, the alteration shall comply with the development standards applicable to the development typology that, in the determination of the Planning and Administrator is most similar to the existing structure.

SECTION 1103.09 DEVELOPMENT STANDARDS

Figure 1103.09~~A~~ below illustrates the key terms applicable to the development standards included for each development typology. These key terms are illustrated as follows:

FIGURE 1103.09: STANDARDS KEY TERMS



DISTRICTS AND ZONES

This Chapter is divided into four districts (the Olde Reynoldsburg Center, (ORD-C) the Olde Reynoldsburg Neighborhood (ORD-N), the Brice and East Main Street and the East Main Street Insight districts) and five zones. Districts are specific contiguous geographies with the city that have similar existing or desired development patterns. Districts may include numerous blocks of different uses and building types that form the character of each district. The regulations applied to each district respect the unique development pattern while promoting desired outcomes within. Zones are not all contiguous and are mapped across the city primarily based on existing and desired use patterns and distinguish between disparate uses without respect to a specific geographies.

REMOVED




TABLE 1103.10 DISTRICT AND ZONES MAP


LEGEND

SR	Suburban Residential Zone	ORD-C	Olde Reynoldsburg Commercial District
RM	Residential Medium Zone	ORD-N	Olde Reynoldsburg Neighborhood District
CC	Community Commercial Zone	EMD	East Main Street District
I	Innovation Zone	BMD	Brice and Main District
OS	Open Space / Schools Zone		

SECTION 1103.11 OLDE REYNOLDSBURG COMMERCIAL DISTRICT (ORD-C)



Image: Aerial view of the Olde Reynoldsburg Commercial District



Key for Diagrams

Lot Line Setback Line Buildable Area

A. INTENT

The primary intent of this district is to strengthen the mixed-use, pedestrian-oriented nature of the existing historic downtown. Historic buildings, facades, and public spaces should be maintained. Interesting and stimulating pedestrian environments should be a primary feature of the District. Sidewalk cafe seating is encouraged, ground-floor retail with large windows should be promoted, and pedestrians should feel safe and comfortable. New residential development is highly encouraged to help bolster and support the vibrancy of the downtown. This District includes properties with frontage on East Main Street and extending west over Blacklick Creek and including the current municipal buildings and campus.

B. ALLOWED BUILDING TYPES


The building types allowed in the ORD-C are limited to the following, which shall be placed on lots with minimum dimensions sufficient to accommodate the allowed building type and setback dimensions. See this Chapter 1103.27 (Building Typologies) for detailed design standards.


Allowed Building Types	
Large Flex Retail Building	Bed and Breakfast Building
Medium Flex Retail Building	School and Institutional Building
Small Flex Retail Building	Community Center Building
Detached Single-Family Building	Community Activity Center Building

C. BUILDING PLACEMENT

Build-to-Zone (BTZ)	E Main St Fronting	Commercial District	
Front	0'-15'	NA	A
Side Street, corner lot	0'-10'	NA	B
Setback			
Front	0' min	0' min	A
Side Street, corner lot	0' min	0' min	B
Side	0' min	0' min	C
Rear	0' min	0' min	D
Lot Coverage	NA	70%	
Building Form			
Primary Street built to BTZ	30% min	NA	E
Side Street, Corner Lot built to BTZ	30% min	NA	F
Lot Width	30' min	30' min	G
Lot Depth	NA	NA	H
Lot Frontage	30' min	30' min	

Not Applicable	NA
Not Permitted	NP





Key for Diagrams

Lot Line | Height Line | Buildable Area

Notes
All floors must have a primary ground-floor entrance facing the primary or side street.
Rear-facing buildings, loading docks, overhead doors, and other service entries are prohibited on primary street-facing facades.
Any buildings over 75' in width must be articulated with a demising line or designed to read as a series of buildings no wider than 75' each.

D. BUILDING FORM

Each proposed building in the ORD-C District shall comply with the following building form standards.

Height

The height of the buildings shall not exceed the following limits. Minimum and maximum heights are measured from average finished grade at the front setback line.

Height	E Main St Fronting	Commercial Neighborhood	
Building Maximum	5 stories, 60'	2 1/2 stories, 30'	J
Ancillary Building Max.	2 1/2 stories, 35'	2 stories, 24'	
First Floor Ceiling Height	12' min	9' min ~~clear~~	K
Upper Floor(s) Ceiling Height	8' min	8' min ~~clear~~	L

E. PARKING PLACEMENT

Off-street parking shall be located in compliance with the following setback standards. See this Chapter (Frontage Typologies) or applicability of frontage types associated with street-side parking.

Location (Distance from Property Line)	E Main St Fronting	Commercial Neighborhood	
Front Setback	20'	20' min	M
Side Setback	0'	0' min	N
Side Street Setback	5'	5' min	O
Rear Setback	0'	0' min	P

Required Spaces	
Ground Floor	
Uses < 3,000 sf	No off-street parking required
Uses =/ > 3,000 sf	1 space/400 sf
Upper Floors	
Residential uses	1 space/unit; .5 space/ studio
Other uses	1 space/450 ft

Notes		
Parking Drive Width	15’	Q
*Or as required by Fire Department		
On corner lots, primary parking drive shall not be located in primary street.		
Shared drives are encouraged between adjacent lots to minimize curb cuts along the street.		
Parking may be provided off-site within 1,300’ or as shared parking. Shared parking may count up to a 30% reduction in total parking required.		
Bicycle parking must be provided and in a secure environment and be ground mounted with a clear width of 32 inches and clear length of 84 inches. At least one bicycle space shall be provided for every ~~1,000~~ 10,000 square feet of gross floor area of the principle building.		
See Chapter 1105.01 for further parking regulations.		

F. FRONTAGE TYPES

See this Chapter 1103.31 (Frontage Type Standards) for detailed standards for each frontage type.

Frontage Type	Primary Street	Secondary Street	Reference
Shopfront	Allowed	Allowed	1103.31 (A)
Patio	Allowed	Allowed	1103.31 (B)
Yard	Allowed	Allowed	1103.31 (C)
Raised Yard	Allowed	Allowed	1103.31 (D)
Porch	Allowed	Allowed	1103.31(E)
Stoop	Allowed	Allowed	1103.31 (F)
Terrace	Allowed	Allowed	1103.31 (G)
Forecourt	Allowed	Allowed	1103.31 (H)
Streetwall	Allowed	Allowed	1103.31 (I)

G. ALLOWED OPEN SPACE TYPES

The open space types allowed in the ORD-C are limited to the following, which shall be placed on lots with minimum dimensions sufficient to accommodate the minimum open space type and setback dimensions. See Chapter 1103.29 (Open Space Typologies) for detailed illustrative standards.

Allowed Open Space Types	Reference
Greenway and Trail	1103.29 (A)
Park	1103.29 (F)
Nature	1103.29 (J)
Sport Field	1103.29 (G)

H. ALLOWED LAND USES AND PERMIT REQUIREMENTS

1. The land uses allowed by this Code are listed in Table 1103 A (Allowed Land Uses and Permit Requirements) below, together with the type of planning permit required for each use. Each land use listed in Table 1103 A (Allowed Land Uses and Permit Requirements) is defined in Chapter 1113 (Glossary of Terms

2. Establishment of an Allowable Use

A. Any one or more land uses allowed in Table 1103 A (Allowed Land Uses and Permit Requirements) may be established on any lot within the district, subject to the planning permit requirement listed in the Table, and in compliance with all applicable requirements of this Code.

b. Where a project on a single lot includes two or more of the land uses listed in the Table, the overall project will be subject to the highest permit level required by the Table for any individual use.

c. A land use that is not listed in Table 1103 A and is determined by the Director to not be included in the definition listed in Chapter 1113 A (Glossary of Terms), is not allowed, unless the Director finds that the proposed use is similar to, compatible with, and will not involve a greater intensity than a listed use and such use is consistent with the purposes of the zone, the Comprehensive Plan, and any applicable City plan.

TABLE 1103 A ALLOWED LAND USES AND PERMIT REQUIREMENTS		
Land Use Type	Permit Required by Zone	Specific Use Regulations
	ORD-C	
ANIMAL SERVICES		
Boarding/Kennel	C	
Grooming	P	
Veterinary	P	
COMMUNITY FACILITIES		
Community Facility - Activity Center	P	
Community Facility - Government Administration and Courts	P	
Community Facility - Outdoor Recreation	P	
Community Facility - Park	P	
Community Facility - Public Health Safety	P	
Community Facility - Trail	P	
CONGREGATION		
Event Center - Private Events and Conferences	P	
Event Center - Public Meetings and Conventions	P	
Mortuary	C	
Religious Assembly	P	
CULTURAL		
Library	P	
Live Theater	P	
Movie Theater	P	
Museum	P	
Visual Arts Center	P	

TABLE 1103 A ALLOWED LAND USES AND PERMIT REQUIREMENTS		
Land Use Type	Permit Required by Zone	Specific Use Regulations
	ORD-C	
DWELLING		
Dwelling - Assisted	P	
Dwelling - Attached Single-Family	P	
Dwelling - Group	P	
Dwelling - Multi-Unit Building	P	
Dwelling - Multi-Unit Building Complex	P	
Dwelling - Nursing	P	
Dwelling - Two-family	P	
FOOD AND BEVERAGE		
Bakery - Retail	P	
Beverage - Brewing and Distilling	P	Produces less than 15,000 barrels.
Beverage Sales - Liquor and Beer Sit Down/Bar Establishment	P	
Beverage Sales and Retail	P	
Food Sales - Small Format Grocery	P	See definition
Food Sales-Farm	P	

Deleted Dwelling - Developmental Disability from the table.

Allowable Use	P
Conditional Use	C

Add Food Service - Commercial Kitchen as a permitted land use.

TABLE 1103 A ALLOWED LAND USES AND PERMIT REQUIREMENTS

Land Use Type	Permit Required by District	Specific Use Regulations
	ORD-C	
Food Service - Fast Casual Restaurant	P	
Food Service - Full Service Restaurant	P	
EDUCATION		
School - College/ University	P	
School - Primary	P	
School - Secondary	P	
School - Trade	P	
HEALTH / WELLNESS		
Health and Wellness - Clinic	P	
Health and Wellness - Fitness Facility/Gym	P	
Health and Wellness - Massage	P	
Health and Wellness - Physical Therapy	P	
MANUFACTURING / PROCESS / INNOVATION		
Manufacturing - Artisan	P	
MEDICAL		
Medical Office	P	No overnight patients
Medical - Clinic	P	
Marijuana - Dispensary	C	

TABLE 1103 A ALLOWED LAND USES AND PERMIT REQUIREMENTS

Land Use Type	Permit Required by Zone	Specific Use Regulations
	ORD-C	
OFFICE		
Office - Corporate	P	
Office - Data Processing/ Call Center	C	
Office - Professional Services	P	
PERSONAL SERVICES		
Clothing Services - Dry Cleaning without drive thru	P	
Financial Services and Banking - without drive thru	P	
Personal Care and Beauty Services	P	
Tattoo/Piercing	P	
RECREATION		
Studio - Art	P	
Studio - Gymnastics/ martial arts	P	

Allowable Use	P
Conditional Use	C

TABLE 1103 A ALLOWED LAND USES AND PERMIT REQUIREMENTS		
Land Use Type	**Permit Required by Zone**	**Specific Use Regulations**
	ORD-C	
SALES AND EXHIBITION		
Antique Shop	P	80 percent of goods must be 30 years or older or have collectible value.
Auction Facility	P	Excludes livestock and motor vehicle auctions.
Gallery - Art	P	
Garden Center - Indoor and Outdoor	C	
Retail - Convenience without gasoline	P	
Retail - Large Format	P	
Retail - Medium Format	P	
Retail - Pharmacy without Drive-Thru	P	
Retail - Shopping Center - Enclosed	P	
Commercial Center - Outdoor - Small	P	
Commercial Center - Outdoor - Large	P	
Retail - Small Format	P	
TOURISM / VISITING		
Overnight Lodging - Bed and Breakfast	P	
Overnight Lodging - Boutique Hotel	P	Fewer than 30 rooms
Overnight Lodging - Hotel	P	
Overnight Lodging - Limited Service	P	
Overnight Lodging - Resort	P	

Allowable Use	P
Conditional Use	C

I. Design Guidelines for Olde Reynoldsburg Commercial District (ORD-C)

A. Purpose

The purpose of this section is to:

i. protect and enhance the Olde Reynoldsburg Commercial District's (ORD-C) unique aesthetic character;

ii. support high quality streets and public spaces;

iii. encourage architecture that blends harmoniously with the natural surroundings and neighboring development;

iv. safeguard property values and long-term economic assets; and

v. carefully preserve the character the District's historic character while permitting appropriate growth.

B. Intent and Applicability

These design guidelines shall apply to non-residential development in the ORD-N and ORD-C and are not intended to stifle innovative design or creativity. Instead, these design guidelines are intended to serve as the minimum standards applicable to non-residential development to ensure that new development and redevelopment satisfied the purposes of the Olde Reynoldsburg Districts as described herein. These design guidelines shall be applied by the Planning and Zoning Board in conjunction with its review of applications for Certificates of Appropriateness as described under Chapter 1109.19 hereof.

C. General Standards

i. ~~(1)~~ **Size, Mass and Scale:** The scale of buildings and accessory structures (including canopies) shall be appropriate to the scale of structures.

ii. ~~(2)~~ **Proportions of Bays and Openings:** All building bays, including porches, colonnades and porticos as appropriate, shall be square or vertical in proportion, unless the design merits a horizontally-proportioned opening. Wall openings, with the exception of transoms and storefronts, shall be square or vertical in proportion. The facade of a proposed building should draw upon the proportion and number of bays in surrounding buildings, as defined by windows, doors, and column spacing, to establish a compatible scale.

iii. ~~(3)~~ **Building Materials:** Building wall materials shall be combined on each facade only horizontally, unless the building is broken vertically by a change of plane, or a vertical architectural element. Heavier materials, such as masonry and stucco, shall be located below lighter materials, such as cement fiber or wood siding.

iv. ~~(4)~~ **Roof Forms:** Where pitched roofs exist, primary roofs shall have a minimum slope of 4:12, while ancillary roof slopes may be no less than 2:12.

v. ~~(5)~~ **Garages and Accessory Structures:** Attached garages, detached garages, and other accessory structures shall be subordinate in height, footprint, and proportion to the primary structure on the site, and shall be compatible with the principal structure in terms of roof form, materials, and color. Where a garage contains an accessory dwelling unit above, it may exceed the height of the primary structure.

vi. ~~(6)~~ **Trash, Mechanical, Utility and Service Equipment and Areas**

1. ~~i.~~ Loading docks, service areas, and trash disposal facilities (e.g., trash and recycling receptacles,compactors, dumpsters) shall be hidden or ~~ii.~~ screened from view of streets, parks, squares, or significant pedestrian spaces. Loading areas may be oriented toward adjoining developed properties that are zoned for nonresidential uses, if such loading areas are screened from view.
2. ~~iii.~~ Mechanical equipment, such as ventilation systems, commercial exhaust fans, rooftop terminations, commercial cooling equipment, heating and air conditioning units, TV antennas, and satellite dishes, shall be hidden or screened from view. Lattice, open brick enclosures, or vegetation can be used to conceal mechanical equipment. Screening material shall be properly maintained. If vegetation is used for screening, the mature size of the vegetation shall be considered so that equipment air flow will not be compromised.

vii. ~~(7)~~ **Colors:** Buildings and additional site elements — e.g., bollards, arbors, drive-thru canopies, sign posts — shall not be painted in a color or pattern that expresses corporate identify, to the extent that the paint color or pattern is not consistent with the design standards of the district. Fluorescent colors, such as ASHTO safety yellow, are also prohibited except where required by a public agency.

D. Specific Standards

i. ~~(1)~~ **Building Materials and Details.**

1. ~~i.~~ Building walls shall be finished in 1 or more (but not more than 3) of the following materials:
   (a) Wood;
   (b) Fiber cement board siding **smooth finish**

(c) Concrete masonry units with stucco (CBS);

(d) Reinforced concrete with stucco;

(e) Brick;

(f) Corrugated metal, which may be approved by the Planning and Zoning Administrator based on the surrounding context and location on the site; or

(g) Other materials as approved by the Zoning Administrator, based on visual compatibility with listed approved materials.

2. ~~ii.~~ Visible foundation walls and chimneys shall be finished in one of the following materials:

(a) Brick; or

(b) Stucco.

3. ~~iii.~~ Columns may be constructed of the following materials:

(a) Wood;

(b) Wood or fiber cement clad;

(c) Cast iron;

(d) Concrete with smooth stucco finish;

(e) Cast stone with smooth finish;

(f) Brick; or

(g) Perma-cast or other synthetic materials as approved by the Planning and Zoning Administrator, based on visual compatibility with listed approved materials.

4. ~~iv.~~ Railings and balustrades may be constructed of the following materials:

Building materials were listed twice (i-iv), deleted the duplicate text.

(a) Painted Wood;

(b) Wrought iron;

(c) Aluminum, PVC or other synthetic material as approved by the Planning and Zoning Administrator, based on visual compatibility with listed approved materials.

5. ~~viii.~~ Doors shall be made of wood, metal, glass, or fiberglass.

6. ~~ix.~~ Roofs with visible pitches shall be constructed of the following materials:

(a) 25-year architectural dimension shingles;

(b) Tile (clay, cement, natural or manufactured stone);

(c) Nonreflective pre-finished metal;

(d) Slate;

(e) Reflective metal such as copper; or

(f) Other similar metals as approved by the Planning and Zoning Administrator.

7. ~~x.~~ The following materials are prohibited:

(a) Exposed concrete masonry units;

(b) Vinyl Siding;

(c) Plastic shutters;

(d) Metal panels;

(e) Day-glo, luminescent, iridescent, neon or similar types of color finishes;

(f) Mirrored glass with a reflectivity of 20% or more; or

(g) Roofing;

1) Plastic or PVC roof tile; or

2) Nontraditional colors such as orange or purple.

ii. ~~(2)~~ Roof Forms

1. ~~i.~~ Permitted roof types include gabled, hipped, shed, barrel vaulted, flat, mono-pitch, and domed. Applied and partial (less than 3 sides) mansard roofs are permitted.
2. ~~ii.~~ Shed, flat, and mono-pitch roofs shall be concealed with parapets along the street frontage, except on porches, balconies, or building extensions.
3. ~~iii.~~ Downspouts and gutters should be galvanized steel, aluminum, or copper and shall match in materials and finish.
4. ~~iv.~~ Roof penetrations shall be hidden or painted to match the color of the roof.
5. ~~v.~~ Skylights must be flat to the pitch of the roof. They shall not be located on any sloped roof facing the primary frontage

iii. ~~(3)~~ Windows and Doors

1. ~~i.~~ Any commercial or mixed-use building elevation facing a street, waterway, or public space shall include a minimum of 40% of transparent fenestration (windows and doors) on the ground floor and 20% on upper floors. Apartment Houses shall conform to these requirements as much as possible, however the minimum percentage of transparent fenestration on the ground floor may be adjusted at the discretion of the Planning and Zoning Administrator. It shall not be reduced to lower than 30%.
2. ~~ii.~~ Proportion and Details
   (a) Windows shall not be flush with exterior wall treatments. Windows shall be provided with an architectural surround at the jambs and header, and a projecting sill.
   (b) Window openings may be grouped horizontally, but trim between windows shall be at least 3.5 inches wide. This does not apply to storefront windows.
   (c) Facades should have several window sizes with smaller ones above. This is particularly important when buildings rise more than 2 stories.
   (d) Thin mullions or muntins shall be required on windows larger than 2 feet in any direction, except for shopfronts. The depth of the mullion shall not be less than the width.


iv. ~~(4)~~ Architectural Details

1. ~~i.~~ Shutters: Shutters shall be sized and placed so as to equal the width that would be required to cover the window opening. Operable shutters are preferred.
2. ~~ii.~~ Column Bays: Columns and piers shall be spaced no farther apart than they are tall. Column bays shall be of equal and precise proportions.

SECTION 1103.13 OLDE REYNOLDSBURG NEIGHBORHOOD DISTRICT (ORD-N)



Image: Aerial view of the Olde Reynoldsburg Neighborhood District



Key for Diagrams

Lot Line | Setback Line | Buildable Area

A. INTENT

Because of its location adjacent to the Olde Reynoldsburg ~~Neighborhood~~ Commercial District (ORD-~~N~~ C), future development should support a more diverse range of housing options and should be well integrated with surrounding uses while allowing for more compact development to accommodate smaller household sizes, an aging population, and a growing number of households without children. Multi-unit buildings with common open spaces are encouraged where appropriate, Developments may include a range of housing options with different price points and styles including stacked flats, higher density single-family, row houses, and apartments. Reduced setbacks, improved streetscapes, and smaller blocks all contribute to improved walkabilty.

B. ALLOWED BUILDING TYPES


The building types allowed in the ORD-N are limited to the following, which shall be placed on lots with minimum dimensions sufficient to accommodate the minimum building type and setback dimensions. See Chapter 1103.27 (Building Types) for detailed design standards.


Allowed Buidling Types	
Detached Single-Family Building	Small Flex Retail Building
Attached Single-Family Building	Institutional Flex Building
Duplex Building	Community Center Building
Multi-Unit Building	ADU (Accessory Dwelling Unit)

C. BUILDING PLACEMENT

Setback		
Front	5’ min	A
Side Street, corner lot	5’ min	B
Side	5’ min	C
Side Townhome and Condos only	0’ min	
Rear	30’ min	D
Lot Coverage	70%	
Building Form		
Lot Width	35’ min	G
Lot Width Townhome and Condos only	23’ min	
Lot Depth	NA	H
Lot Frontage	35’ min	E
Lot Frontage Townhome and Condos only	23’ min	

Notes
All floors must have a primary ground-floor entrance facing the primary or side street.
Rear-facing buildings, loading docks, overhead doors, and other service entries are prohibited on primary street-facing facades.
Any buildings over 75’ in width must be articulated with a demising line or designed to read as a series of buildings no wider than 75’ each.





Key for Diagrams

Lot Line | Setback Line | Buildable Area

D. BUILDING FORM

Each proposed building in the ORD-N District shall comply with the following building form standards.

1. Encroachments into Setback

The following encroachments are allowed within the ORD-N District, subject to applicable frontage type standards. See this Chapter 1103.31 (Illustrative Frontage Typologies).

Location		
Front	5' max	I
Side	5' max	I
Side Street	5' max	I
Rear	0'	I

Notes

Canopies, Awnings, and balconies may encroach over the setback on the street sides and into the setback on the rear. Only balconies are allowed at the rear encroachment.

2. Height

35' max	J
2 1/2 stories max	J

Notes

See this Chapter (Illustrative Frontage Typologies) for descriptions and requirements.

E. PARKING PLACEMENT

Off-street parking shall be located in compliance with the following setback standards. See Chapter 1103.31 (Illustrative Frontage Typologies) for applicability of frontage types associated with street-side parking.

Location (Distance from Property Line)		
Front Setback	20' min	M
Side Setback	0' min	N
Side Street Setback	5' min	O
Rear Setback	5' min	P

Notes

Unless parking space is located in the driveway of a single-family or two-family dwelling.

F. FRONTAGE TYPES

See Chapter 1103.31 (Illustrative Frontage Typologies) for detailed standards for each frontage type.

Frontage Type	Primary Street	Secondary Street	Reference
Shopfront	Allowed	Allowed	1103.31 (A)
Patio	Allowed	Allowed	1103.31 (B)
Yard	Allowed	Allowed	1103.31 (C)
Raised Yard	Allowed	Allowed	1103.31 (D)
Porch	Allowed	Allowed	1103.31 (E)
Stoop	Allowed	Allowed	1103.31 (F)
Terrace	Allowed	Allowed	1103.31 (G)
Forecourt	Allowed	Allowed	1103.31 (H)
Streetwall	Allowed	Allowed	1103.31 (I)

G. ALLOWED OPEN SPACE TYPES

The open space types allowed in the ORD-N are limited to the following, which shall be placed on lots with minimum dimensions sufficient to accommodate the minimum open space type and setback dimensions. See Chapter 1103.29 (Open Space Typologies) for detailed standards

Allowed Open Space Types	Reference
Nature	1103.29 (J)
Greenway and Trail	1103.29 (A)
Square	1103.29 (C)
Green	1103.29 (D)
Passage	1103.29 (E)
Park	1103.29 (F)
Sport Field	1103.29 (G)
Pocket Park	1103.29 (I)
Pocket Plaza	1103.29 (H)

H. ALLOWED LAND USES AND PERMIT REQUIREMENTS

1. The land uses allowed by this Code are listed in Table 1103B (Allowed Land Uses and Permit Requirements) below, together with the type of planning permit required for each use. Each land use listed in Table 1103B (Allowed Land Uses and Permit Requirements) is defined in Chapter 1113 (Glossary of Terms).

2. Establishment of an Allowable Use

a. Any one or more land uses allowed in Table 1103B (Allowed Land Uses and Permit Requirements) may be established on any lot within the district, subject to the planning permit requirement listed in the Table, and in compliance with all applicable requirements of this Code.

b. Where a project on a single lot includes two or more of the land uses listed in the Table, the overall project will be subject to the highest permit level required by the Table for any individual use.

c. A land use that is not listed in Table 1103B and is determined by the Director to not be included in the definition listed in Chapter 1113 (Glossary of Terms), is not allowed, unless the Director finds that the proposed use is similar to, compatible with, and will not involve a greater intensity than a listed use and such use is consistent with the purposes of the zone, the Comprehensive Plan, and any applicable City plan.

TABLE 1103B ALLOWED LAND USES AND PERMIT REQUIREMENTS		
Land Use Type	Permit Required by Zone	Specific Use Regulations
	ORD-N	
ANIMAL SERVICES		
Veterinary	C	
CONGREGATION		
Event Center - Private Events and Conferences	C	
Religious Assembly	P	
CULTURAL		
Library	P	
Live Theater	C	
Museum	C	
Visual Arts Center	P	
DWELLING		
Dwelling - Assisted	P	
Dwelling - Attached Single-Family	P	
Dwelling - Detached Single-Family	P	
Dwelling - Group	P	
Dwelling - Multi-Unit Building	C	
Dwelling - Multi-Unit Building Complex	C	
Dwelling - Nursing	P	
Dwelling - Two-family	P	

Deleted Dwelling - Developmental Disability from the table.

TABLE 1103B ALLOWED LAND USES AND PERMIT REQUIREMENTS		
Land Use Type	Permit Required by Zone	Specific Use Regulations
	ORD-N	
FOOD AND BEVERAGE		
Bakery - Retail	P	
Beverage - Brewing and Distilling	C	Produces less than 15,000 barrels.
Food Sales - Farm Market	P	
Food Sales - Small Format Grocery	P	See definition
Food Service - Full Service Restaurant	C	
EDUCATION		
School - College/ University	C	
School - Primary	C	
School - Secondary	C	
School - Trade	C	
HEALTH / WELLNESS		
Health and Wellness - Clinic	C	
Health and Wellness - Fitness Facility/Gym	C	
Health and Wellness - Massage	P	
Health and Wellness - Physical Therapy	P	

Allowable Use	P
Conditional Use	C

TABLE 1103B ALLOWED LAND USES AND PERMIT REQUIREMENTS		
Land Use Type	Permit Required by Zone	Specific Use Regulations
	ORD-N	
MANUFACTURING / PROCESS / INNOVATION		
Manufacturing - Artisan	P	
MEDICAL		
Medical - Clinic	C	
Medical - Office	C	
Office - Professional Services	C	
PERSONAL SERVICES		
Personal Care and Beauty Services	C	
RECREATION		
Studio - Art	P	
Studio - Gymnastics/ martial arts	P	
RESIDENT AND CHILD CARE		
Child Day Care - Center	P	See 1105.13(H)
Child Day Care - In Home	P	See 1105.13(I)
SALES AND EXHIBITION		
Antique Shop	C	80 percent of goods must be 30 years or older or have collectible value.
Gallery - Art	P	
Retail - Boutique	P	
Garden Center	C	
TOURISM / VISITING		
Overnight Lodging - Bed and Breakfast	P	
Overnight Lodging - Boutique Hotel	C	Fewer than 30 rooms

Allowable Use	P
Conditional Use	C

I. Design Guidelines for Olde Reynoldsburg Neighborhood District (ORD-N)

A. Purpose

The purpose of this section is to:

i. protect and enhance the Olde Reynoldsburg Commercial District's (ORD-C) unique aesthetic character;

ii. support high quality streets and public spaces;

iii. encourage architecture that blends harmoniously with the natural surroundings and neighboring development;

iv. safeguard property values and long-term economic assets; and

v. carefully preserve the character the District's historic character while permitting appropriate growth.

B. Intent and Applicability

These design guidelines shall apply to non-residential development in the ORD-N and ORD-C and are not intended to stifle innovative design or creativity. Instead, these design guidelines are intended to serve as the minimum standards applicable to non-residential development to ensure that new development and redevelopment satisfied the purposes of the Olde Reynoldsburg Districts as described herein. These design guidelines shall be applied by the Planning and Zoning Board in conjunction with its review of applications for Certificates of Appropriateness as described under Chapter 1109.19 hereof.

C. General Standards

i. **Size, Mass and Scale:** The scale of buildings and accessory structures (including canopies) shall be appropriate to the scale of structures.

ii. **Proportions of Bays and Openings:** All building bays, including porches, colonnades and porticos as appropriate, shall be square or vertical in proportion, unless the design merits a horizontally-proportioned opening. Wall openings, with the exception of transoms and storefronts, shall be square or vertical in proportion. The facade of a proposed building should draw upon the proportion and number of bays in surrounding buildings, as defined by windows, doors, and column spacing, to establish a compatible scale.

iii. **Building Materials:** Building wall materials shall be combined on each facade only horizontally, unless the building is broken vertically by a change of plane, or a vertical architectural element. Heavier materials, such as masonry and stucco, shall be located below lighter materials, such as cement fiber or wood siding.

iv. **Roof Forms:** Where pitched roofs exist, primary roofs shall have a minimum slope of 4:12, while ancillary roof slopes may be no less than 2:12.

v. **Garages and Accessory Structures:** Attached garages, detached garages, and other accessory structures shall be subordinate in height, footprint, and proportion to the primary structure on the site, and shall be compatible with the principal structure in terms of roof form, materials, and color. Where a garage contains an accessory dwelling unit above, it may exceed the height of the primary structure.

vi. **Trash, Mechanical, Utility and Service Equipment and Areas**

1. Loading docks, service areas, and trash disposal facilities (e.g., trash and recycling receptacles, compactors, dumpsters) shall be hidden or screened from view of streets, parks, squares, or significant pedestrian spaces. Loading areas may be oriented toward adjoining developed properties that are zoned for nonresidential uses, if such loading areas are screened from view.
2. Mechanical equipment, such as ventilation systems, commercial exhaust fans, rooftop terminations, commercial cooling equipment, heating and air conditioning units, TV antennas, and satellite dishes, shall be hidden or screened from view. Lattice, open brick enclosures, or vegetation can be used to conceal mechanical equipment. Screening material shall be properly maintained. If vegetation is used for screening, the mature size of the vegetation shall be considered so that equipment air flow will not be compromised.

vii. **Colors:** Buildings and additional site elements — e.g., bollards, arbors, drive-thru canopies, sign posts — shall not be painted in a color or pattern that expresses corporate identify, to the extent that the paint color or pattern is not consistent with the design standards of the district. Fluorescent colors, such as ASHTO safety yellow, are also prohibited except where required by a public agency.

D. Specific Standards

i. Building Materials and Details.

1. Building walls shall be finished in 1 or more (but not more than 3) of the following materials:
   (a) Wood;
   (b) Fiber cement board siding, smooth finish;
   (c) Concrete masonry units

with stucco (CBS);

(d) Reinforced concrete with stucco;

(e) Brick;

(f) Corrugated metal, which may be approved by the Planning and Zoning Administrator based on the surrounding context and location on the site; or

(g) Other materials as approved by the Zoning Administrator, based on visual compatibility with listed approved materials.

2. Visible foundation walls and chimneys shall be finished in one of the following materials:

(a) Brick; or

(b) Stucco.

3. Columns may be constructed of the following materials:

(a) Wood;

(b) Wood or fiber cement clad;

(c) Cast iron;

(d) Concrete with smooth stucco finish;

(e) Cast stone with smooth finish;

(f) Brick; or

(g) Perma-cast or other synthetic materials as approved by the Planning and Zoning Administrator, based on visual compatibility with listed approved materials.

4. Railings and balustrades may be constructed of the following materials:

(a) Painted wood;

(b) Wrought iron; or

(c) Aluminum, PVC or other synthetic material as approved by the Planning and Zoning Administrator, based on visual compatibility with listed approved materials.

5. Doors shall be made of wood, metal, glass, or fiberglass.

6. Roofs with visible pitches shall be constructed of the following materials:

(a) 25-year architectural dimension shingles;

(b) Tile (clay, cement, natural or manufactured stone);

(c) Nonreflective pre-finished metal;

(d) Slate;

(e) Reflective metal such as copper; or

(f) Other similar metals as approved by the Planning and Zoning Administrator.

7. The following materials are prohibited:

(a) Exposed concrete masonry units;

(b) Vinyl Siding;

(c) Plastic shutters;

(d) Metal panels;

(e) Day-glo, luminescent, iridescent, neon or similar types of color finishes;

(f) Mirrored glass with a reflectivity of 20% or more; or

(g) Roofing;

1) Plastic or PVC roof tile;

or

2) Nontraditional colors such as orange or purple.

ii. Roof Forms

1. Permitted roof types include gabled, hipped, shed, barrel vaulted, flat, mono-pitch, and domed. Applied and partial (less than 3 sides) mansard roofs are permitted.
2. Shed, flat, and mono-pitch roofs shall be concealed with parapets along the street frontage, except on porches, balconies, or building extensions.
3. Downspouts and gutters should be galvanized steel, aluminum, or copper and shall match in materials and finish.
4. Roof penetrations shall be hidden or painted to match the color of the roof.
5. Skylights must be flat to the pitch of the roof. They shall not be located on any sloped roof facing the primary frontage.

iii. Windows and Doors

1. Any commercial or mixed-use building elevation facing a street, waterway, or public space shall include a minimum of 40% of transparent fenestration (windows and doors) on the ground floor and 20% on upper floors. Apartment Houses shall conform to these requirements as much as possible, however the minimum percentage of transparent fenestration on the ground floor may be adjusted at the discretion of the Planning and Zoning Administrator. It shall not be reduced to lower than 30%.

2. Proportion and Details

(a) Windows shall not be flush with exterior wall treatments. Windows shall be provided with an architectural surround at the jambs and header, and a projecting sill.

(b) Window openings may be grouped horizontally, but trim between windows shall be at least 3.5 inches wide. This does not apply to storefront windows.


(c) Facades should have several window sizes with smaller ones above. This is particularly important when buildings rise more than 2 stories.

(d) Thin mullions or muntins shall be required on windows larger than 2 feet in any direction, except for shopfronts. The depth of the mullion shall not be less than the width.

iv. Architectural Details

1. Shutters: Shutters shall be sized and placed so as to equal the width that would be required to cover the window opening. Operable shutters are preferred.
2. Column Bays: Columns and piers shall be spaced no farther apart than they are tall. Column bays shall be of equal and precise proportions.

SECTION 1103.15 BRICE & EAST MAIN STREET AND EAST MAIN STREET INSIGHT DISTRICTS



Example Development Pattern in Brice & East Main Street District



Example Development Pattern in East Main Street District

I. Purpose and Intent

Brice and East Main Street and the East Main Street Insight Districts are intended to create compact, mixed-use, walkable environments, remove regulatory barriers, and encourage the establishment of local enterprises (e.g. Main Street businesses, start-up makers and other platforms such as shared work spaces, community hubs, and markets). By creating this type of physical environment and reducing regulatory barriers in these two Insight Districts, investors and start-up businesses will be more likely to deploy capital. This will, in turn, enhance community character and allow existing businesses and residents to remain along with newer uses.

The Brice and Main Street Insight District is intended to be more of an urban, mixed-use zone or Transit oriented Development (TOD) that centers around a transportation hub or multi-modal transportation and leverages the area's proximity to major public transportation routes.

The East Main Street Insight District is intended to serve as a transportation corridor lined with compact, mixed-use, development and with standards to address the transition area where each corridor abuts adjoining neighborhoods.

Regulations found in the Insight Districts that are unique to both zones include:

- Transit supportive development standards: Walkways connecting streets to buildings and locating buildings or pedestrian plazas close to transit stops can set up development to accommodate future transit.
- On-site facilities for pedestrian, bike, and vehicular travel: Standards for bike parking and pedestrian access, particularly within 1/4 mile or not more than 1/2 mile of a transit stop.
- Adjusted regulations for nonconforming buildings and uses: Leaves the nonconforming section of the zoning code intact on nuisances but more lenient on improvements and adaptive re-use.
- Right-sized application fees: Fees are adjusted to reflect the policies of the community. If infill and suburban retrofit is a priority, fees in those environments should ~~are~~ be less.
- Adjust front setback regulations: Amend front setback regulations to specify setback ranges instead of just minimums.
- Reduced parking requirements for affordable housing: The reduction depends upon the urban/suburban context and public transportation access.
- Reduced minimum parking requirements: Requiring more parking than is necessary is a financial barrier to development, wastes site area for parking, and increases impervious surface.

II. Insight District Uses

The following uses are either permitted or conditional uses as indicated in the following table:

Allowable Use	P
Conditional Use	C

USES	BRICE AND MAIN DISTRICT (BMD)	EAST MAIN STREET DISTRICT (EMD)	SPECIFIC USE REGULATIONS
ANIMAL SERVICES			
Boarding/Kennel		C	
Shelter		C	
Veterinary	P	P	
COMMUNITY FACILITIES			
Community Facility - Activity Center	P	P	
Community Facility - Outdoor Recreation	P	P	
Community Facility - Park	P	P	
Community Facility - Public Health Safety	P	C	
Community Facility - Trail	P	P	
CONGREGATION			
Event Center - Private Events and Conferences	P	P	
Event Center - Public Meetings and Conventions	P	P	
Religious Assembly	P	P	
CULTURAL			
Library	P	P	
Live Theater	P	P	
Movie Theater	P	P	
Museum	P	P	
Visual Arts Center	P	P	
DWELLING			
Dwelling - Assisted		C	
Dwelling - Attached Single-Family	C	C	
Dwelling - Multi-Unit Building	C	C	
Dwelling - Multi-Unit Building Complex	C	C	

USES	BRICE AND MAIN DISTRICT (BMD)	EAST MAIN STREET DISTRICT (EMD)	SPECIFIC USE REGULATIONS
FOOD AND BEVERAGE			
Bakery - Retail	P	P	
Beverage - Brewing and Distilling	P	P	Produces less than 15,000 barrels.
Beverage Sales - Liquor and Beer Sit Down/Bar Establishment	P	P	
Beverage - Retail Sales	P	P	
Food Sales - Farm Market	P	P	
Food Sales - Large Format Grocery	P	P	At least 25,000 sq. ft. of gross floor area with at least 1,000 sq. ft. devoted to fresh produce
Food Sales - Small Format Grocery	P	P	5,000 to 25,000 sq. ft. of gross floor area with at least 500 sq. ft. devoted to fresh produce
Food Service - Commissary/Bakery	P	P	
Food Service - Deli	P	P	
Food Service - Fast Casual Restaurant	P	P	
Food Service - Full Service Restaurant	P	P	
Food Service - Quick Serve/Fast Food with Drive-Thru	C	C	See 1105.13(L)
Food Service - Quick Serve/Fast Food without Drive-Thru	P	P	
Food Service - Commercial Kitchen	P	P	
EDUCATION			
School - Child Day Care Center	C	C	
School - College/University	P	P	
School - Secondary	C	C	
School - Trade	C	C	
HEALTH / WELLNESS			
Health and Wellness - Clinic	P	P	
Health and Wellness - Fitness Facility/Gym	P	P	
Health and Wellness - Massage	P	P	
Health and Wellness - Physical Therapy	P	P	


USES	BRICE AND MAIN DISTRICT (BMD)	EAST MAIN STREET DISTRICT (EMD)	SPECIFIC USE REGULATIONS
MANUFACTURING / PROCESS / INNOVATION			
Manufacturing - Artisan	P	P	
Research Facility/Laboratory	P	P	
MEDICAL			
Medical - Clinic	P	P	
Medical - Emergency Services	P	P	
Medical - Full Service Hospital	P	P	
Marijuana - Dispensary	C	C	
Medical - Office	P	P	
Medical - Outpatient and Urgent Care	P	P	No overnight visits; ambulance services may not be provided
Medical - Psychiatric Facility - Standalone	C	C	
Medical - Standalone Emergency Services	C	C	
OFFICE			
Office - Corporate	P	P	
Office - Data Processing/Call Center	P	P	
Office - Professional Services	P	P	
PERSONAL SERVICES			
Clothing Services - Tailor	P	P	
Financial Services and Banking - with Drive-Thru	C	C	See 1105.13(L)
Financial Services and Banking - without Drive-Thru	P	P	
Personal Care and Beauty Services	P	P	
~~REPAIR SERVICES~~			
Vehicular Care Services - Minor - **with Drive-Thru**		C	See 1105.13(L)
Vehicular Care Services – Minor – without Drive-Thru		**C**	
RECREATION			
Indoor Recreation Enterprise	C	C	
Outdoor Recreation Enterprise	C		
Private Club	C	C	
Recreational Facility - Commercial	P	P	

USES	BRICE AND MAIN DISTRICT (BMD)	EAST MAIN STREET DISTRICT (EMD)	SPECIFIC USE REGULATIONS
Shooting Range - Indoor Only		C	
Studio - Art	P	P	
Studio - Gymnastics/martial arts	P	P	
SALES AND EXHIBITION			
Antique Shop	P	P	80 percent of goods must be 30 years or older or have collectible value.
Auction Facility		C	Excludes livestock and motor vehicle auctions.
Gallery - Art	P	P	
Garden Center - Indoor and Outdoor		C	
Retail - Convenience with gasoline		C	See 1105.13(K)
Retail - Convenience without gasoline		P	
Retail - Large Format		P	
Retail - Medium Format	P	P	
Retail - Pharmacy without Drive-Thru	P	P	
Retail - Pharmacy with Drive-Thru	C	C	
Retail - Shopping Center - Enclosed	P	P	See 1105.13(L)
Commercial Center - Outdoor - Small	P	P	
Commercial Center - Outdoor - Large	P	P	
Retail - Small Format	P	P	
TOURISM / VISITING			
Overnight Lodging - Bed and Breakfast	P	P	
Overnight Lodging - Boutique Hotel	P	P	Fewer than 30 rooms
Overnight Lodging - Hotel	P	P	
Overnight Lodging - Limited Service	P	P	
Overnight Lodging - Resort	P	P	
UTILITY FACILITIES			
Power Substation Facility		C	


III. Insight District Development Standards

The **Brice and Main District** includes the more urban attached typologies with off-street parking in a garage, driveway, or parking lot, in addition to instances of on-street, parallel parking.

A. Lot Dimensions and Setbacks



B. Lot Coverage




LOT DIMENSIONS	LOT SIZE (MIN./MAX SQ. FT.)	NA
	LOT WIDTH (MIN./MAX.)	NA
	LOT DEPTH (MIN. FT.)	NA
	LOT FRONTAGE (MIN. FT.)	NA
SETBACKS A	FRONT YARD SETBACK (MIN. FT.)	5 from ROW
A	FRONT YARD SETBACK (MAX. FT.)	20 feet from ROW*
B	SIDE YARD SETBACK (MIN. FT.)	10 from lot line; 10 feet between buildings
B	SIDE YARD SETBACK (MAX. FT.)	NA
B	SIDE YARD SETBACK (MIN./ MAX. AGGREGATE. FT.)	NA
	SIDE YARD SETBACK TOWNHOMES & CONDOS ONLY	0 feet
C	REAR YARD SETBACK (MIN. FT.)	10 feet from lot line; 10 feet between buildings
C	REAR YARD SETBACK (MAX. FT.)	NA

LOT COVERAGE/ OPEN SPACE A	LOT COVERAGE (MIN.)	50%
	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC	80%
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)	10%
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	100%
	OPEN SPACE (MIN.)	20%
	OPEN SPACE (MAX.)	30%
LANDSCAPE REVIEW	LANDSCAPE AND NATURAL BUFFERS	NA
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	12
	DENSITY (MAX. UNITS PER ACRE)	NA

Not Permitted	NP
Not Applicable	NA


*IF A MUNICIPAL LANDSCAPE EASEMENT EXISTS ON THE PARCEL, THEN THE MAXIMUM BUILDING SETBACK MAY BE INCREASED TO 45 FEET FROM THE RIGHT-OF-WAY.

C. Height and Parking



HEIGHT (A)	BUILDING HEIGHT (MIN. FT.)	22
	BUILDING HEIGHT (MAX. FT.)	75
ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	NP
	ADU HEIGHT (MAX. FT.)	NP
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	NP
PARKING LOCATION	LOCATION	Interior of the development or structured parking
SIGN REGULATIONS	PERMITTED SIGN TYPES	Refer to Section 1105.03 - Signs
DESIGN	DESIGN STANDARDS	Facade of natural materials similar in design, materials and color to majority of buildings in development.
	SITE PLAN STANDARDS	See Chapter 1109.17 and Supplemental Regulations below.

D. Frontage




ELEMENT	SHOPFRONT	(A)
	PATIO	(B)

Not Permitted	NP
Not Applicable	NA

III. Insight Zone Development Standards

The **East Main Street District** includes urban and some suburban typologies (Section IV Building Typologies) with off-street parking, driveway, or parking lot, in addition to instances of on-street, parallel parking.


A. Lot Dimensions and Setbacks



LOT DIMENSIONS	LOT SIZE (MIN./MAX SQ. FT.)	NA
	LOT WIDTH (MIN./MAX.)	NA
	LOT DEPTH (MIN. FT.)	NA
	LOT FRONTAGE (MIN. FT.)	NA
SETBACKS A	FRONT YARD SETBACK (MIN. FT.)	5 ft from ROW
A	FRONT YARD SETBACK (MAX. FT.)	20 ft from ROW*
B	SIDE YARD SETBACK (MIN. FT.)	5 ft from lot line; 10 feet between buildings
B	SIDE YARD SETBACK (MAX. FT.)	NA
B	SIDE YARD SETBACK (MIN. AGGREGATE. FT.)	20
	SIDE YARD SETBACK TOWNHOMES & CONDOS ONLY	0 feet
C	REAR YARD SETBACK (MIN. FT.)	30
C	REAR YARD SETBACK (MAX. FT.)	NA

If a municipal landscape easement exists on the parcel, then the maximum building setback may be increased to 45 feet from the right-of-way.


B. Lot Coverage



A	LOT COVERAGE (MIN.)	50%
LOT COVERAGE/ OPEN SPACE	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC	80%
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)	10%
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	70%
	OPEN SPACE (MIN.)	20%
	OPEN SPACE (MAX.)	30%
LANDSCAPE REVIEW	LANDSCAPE AND NATURAL BUFFERS	YES
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	8
	DENSITY (MAX. UNITS PER ACRE)	24


Not Permitted	NP
Not Applicable	NA

C. Height and Parking



HEIGHT (A)	BUILDING HEIGHT (MIN. FT.)	22
	BUILDING HEIGHT (MAX. FT.)	60
ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	NP
	ADU HEIGHT (MAX. FT.)	NP
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	NP
PARKING LOCATION	LOCATION	Rear or side yard, well-screened; private garages; structured parking
SIGN REGULATIONS	PERMITTED SIGN TYPES	Refer to Section 1105.03 - Signs
DESIGN	DESIGN STANDARDS	Facade of natural materials similar in design, materials and color to majority of buildings in development.
	SITE PLAN STANDARDS	See Chapter 1109.179 and Supplemental Regulations below.

D. Frontage



ELEMENT	SHOPFRONT	(A)
	PATIO	(B)

Not Permitted	NP
Not Applicable	NA

The following supplemental regulations shall apply to all development in the Brice and Main Street and East Main Street Insight Zones. The intent of these regulations is to promote the development of the City's auto-oriented corridors to allow for more residential development and access to employment opportunities. The standards and guidelines set forth herein are not intended to stifle innovative design. Instead, these regulations should serve as minimum standards and guidelines to ensure that new development and redevelopment advances the purposes described under this section.

IV. Transit Supportive Development

A. Enable bus stops, pullouts, shelters, and appropriate road geometry.

B. Retail, office, institutional buildings provide convenient access to transit:

   i. Walkways connecting streets to buildings

   ii. Bicycle Storage Requirements:

      1. Retail Buildings: Provide storage for 5% of regular building occupants, no fewer than 2 spaces per building.
      2. Office Buildings: Provide storage for 5% of peak visitors, no less than 4 spaces per building.
      3. Institutional Buildings: Provide storage for 5% of peak visitors, no less than 4 spaces per building.

   iii. At major transit stops:

      1. Buildings located within 20 feet or provide pedestrian plaza;
      2. Reasonably direct connection to buildings;
      3. Accessibility for disabled persons;
      4. Easement or dedication for shelter if transit provider requests;
      5. Lighting;
      6. Accommodations for seating or leaning;
      7. Bicycle facilities, including bike racks and areas for storing scooters.

V. Exceptions and Reductions in Parking Standards

A. There is no minimum number of required automobile parking spaces for uses within Brice and Main Street and East Main Street Insight Zones. The applicant may propose a parking standard that is different than the standard under 1105.01; Off-Street Parking and Loading for review and action by the Planning and Zoning Administrator.

   i. Site has a bus stop with frequent transit service located adjacent to it, and the site's frontage is improved with a bus stop waiting shelter, consistent with the standards of the applicable transit service provider: Allow up to a 20 percent reduction to the standard number of automobile parking spaces;

   ii. Site has dedicated parking spaces for carpool or vanpool vehicles: Allow up to a 10 percent reduction to the standard number of automobile parking spaces;

   iii. Site has dedicated parking spaces for motorcycles, scooters, or electric carts: Allow up to a 5 percent reduction to the number of automobile parking spaces.

   iv. Site has more than the minimum number of required bicycle parking spaces: Allow up to a 5 percent reduction to the number of automobile parking spaces.

VI. Lot Coverage Bonus

A. The Planning and Zoning Administrator, subject to review, may approve increases to the lot coverage standards as follows:

i. Lot coverage may increase by up to one-half square foot for every one square foot of proposed automobile parking area to be contained in a parking structure, either above or below leasable ground floor space (e.g., residential, commercial, or civic use), not to exceed a 20 percent increase in allowable coverage.

ii. Lot coverage may increase by up to one-half a square foot for every one square foot of proposed parking area paving that uses a City-approved porous or permeable paving material (i.e., allowing stormwater infiltration).

iii. Lot coverage may increase by up to one-half a square foot for every one square foot of City-approved water quality treatment area (e.g., vegetative swale or bio-filtration) to be provided on the subject site.

iv. In approving increases in lot coverage under subsections i-iii of this section, the City may require additional landscape buffering or screening, above that which is required by other provisions of this code, and may impose reasonable conditions of approval to ensure the ongoing maintenance of parking areas and surface water management facilities.

v. Notwithstanding the lot coverage increases authorized by this section, all other development standards of this chapter, and other applicable provisions of this Code, must be met.

SECTION 1103.17
SUBURBAN RESIDENTIAL ZONE (SR)

I. Purpose and Intent

A. The Suburban Residential (SR) Zone is intended to regulate all land in the city platted for medium-scale suburban single-unit residential development. The existing development pattern in the SR Zone is traditional single-family residential subdivisions with single-unit residential structures. The desired development pattern in the SR Zone is to accommodate multiple forms of single-family development, including attached single-family dwellings. New development in the SR Zone should also promote pedestrian connectivity and the retention of open space as an amenity. Where possible, new residential development should be connected to trail systems and within a half-mile walk from parks or significant open space.

II. Uses

A. The following uses are either permitted or conditional uses as indicated in the following chart:

DISTRICT USES	
PERMITTED USES:	• Community Facility - Park • Community Facility - Trail • Dwelling - Detached Single-family • Library • Residential Model Home • School - Primary • School - Secondary
CONDITIONAL USES:	• Child Day Care - Center (See 1105.13(H) • Child Day Care - In Home* • Community Facility - Activity Center • Community Facility - Outdoor Recreation • Community Facility - Public Health Safety • Dwelling - Assisted • Dwelling - Attached Single-Family • Dwelling - Group • Dwelling - Two Family • Golf Course • Private Club • Religious Assembly • Studio - Art • Studio - Gymnastics/martial arts • Visual Arts Center

Deleted Dwelling - Developmental Disability from the table.

** Subject to Home Occupation Regulations (see 1105.13(I))*

III. Development Standards

The Suburban Residential Zone includes the traditional suburban single-family detached and attached typologies with off-street parking in a garage, driveway, or parking space.

LOT DIMENSIONS	LOT SIZE (MIN. SQ. FT.)	NA
	LOT SIZE (MAX. SQ. FT.)	NA
	LOT WIDTH (MIN. FT.)	50
	LOT WIDTH (MAX. FT.)	NA
	LOT WIDTH TOWNHOMES & CONDOS ONLY (MIN. FT.)	~~23~~ 21
	LOT DEPTH (MIN. FT.)	100
	LOT DEPTH TOWNHOMES & CONDOS ONLY (MIN. FT.)	75
	LOT FRONTAGE (MIN. FT.)	50
	LOT FRONTAGE TOWNHOMES & CONDOS ONLY (MIN. FT.)	~~23~~ 21
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	NA
	DENSITY (MAX. UNITS PER ACRE)	NA
SETBACKS	FRONT YARD SETBACK (MIN. FT.)	20
	FRONT YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. FT.)	5
	SIDE YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK TOWNHOMES & CONDOS ONLY (MIN. FT.)	0
	SIDE YARD SETBACK (MIN. AGGREGATE. FT.)	NA
	SIDE YARD SETBACK (MAX. AGGREGATE FT.)	NA
	REAR YARD SETBACK (MIN. FT.)	30
	REAR YARD SETBACK TOWNHOMES & CONDOS ONLY (MIN, FT.)	20
	REAR YARD SETBACK (MAX. FT.)	NA
HEIGHT	BUILDING HEIGHT (MIN. FT.)	NA
	BUILDING HEIGHT (MAX. FT.)	35

LOT COVERAGE/ OPEN SPACE	LOT COVERAGE (MIN.)	NA
	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC	60%
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)*	10%
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	NA
	OPEN SPACE (MIN.)	NA
	OPEN SPACE (MAX.)	NA

*DETENTION PONDS INCLUDED IF DESIGNED AS AN AMENITY AND COMMUNITY FEATURE. (I.E. FENCING, LANDSCAPING, NATURAL FEEL)

ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	~~Rear yard, 3 feet from all lot lines, 10 feet from house~~ See Section 1105.05
	ADU	See Section 1105.05
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	15
PARKING LOCATION	LOCATION	Driveway leading to private attached or detached garage; no front yard parking
SIGN REGULATIONS	PERMITTED SIGN TYPES	Refer to Section 1105.03 - SIgns
DESIGN	DESIGN STANDARDS	Single-family building types; For garage requirements, please see Section 1105.05 & 1105.06.
	SITE PLAN STANDARDS	For subdivision requirements, see Chapter 1111

Not Permitted	NP
Not Applicable	NA

SECTION 1103.19
RESIDENTIAL MEDIUM ZONE (RM)

I. Purpose and Intent

A. The purpose of the Residential Medium (RM) Zone is to complement single-family residential development through the introduction of a more diverse range of housing options, including two-family buildings, townhomes, row houses, and apartments. Future development in the RM Zones should be well integrated with surrounding uses while allowing for more compact development to accommodate growth.

II. Uses

A. The flowing uses are either permitted or conditional uses as indicated in the following chart:

DISTRICT USES	
PERMITTED USES:	• Community Facility - Activity Center • Community Facility - Outdoor Recreation • Community Facility - Park • Community Facility - Public Health Safety • Community Facility - Trail • Dwelling - Attached Single-Family • Dwelling - Detached Single-family • Dwelling - Multi-Unit Building • Dwelling - Multi-Unit Building Complex • Dwelling - Two-family • Library • Dwelling - Nursing • School - Primary • School - Secondary
CONDITIONAL USES:	• Child Day Care - In Home* • Dwelling - Assisted • Dwelling - Group • Overnight Lodging - Bed and Breakfast

Deleted Dwelling - Developmental Disability from the table.

** **Subject to Home Occupation Regulations (see 1105.13(I))***

III. Development Standards

The Residential Medium Zone includes the traditional suburban single-family detached, attached, two-family, townhouse, and apartment building typologies with off-street parking in a garage, driveway, or parking space.

LOT DIMENSIONS	LOT SIZE (MIN. SQ. FT.)	NA
	LOT SIZE (MAX. SQ. FT.)	NA
	LOT WIDTH (MIN. FT.)	50
	LOT WIDTH (MAX. FT.)	NA
	LOT WIDTH TOWNHOMES & CONDOS ONLY (MIN. FT.)	~~23~~ 21
	LOT DEPTH (MIN. FT.)	100
	LOT DEPTH TOWNHOMES & CONDOS ONLY (MIN. FT.)	75
	LOT FRONTAGE (MIN. FT.)	50
	LOT FRONTAGE TOWNHOMES & CONDOS ONLY (MIN. FT.)	~~23~~ 21
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	NA
	DENSITY (MAX. UNITS PER ACRE)	24
SETBACKS	FRONT YARD SETBACK (MIN. FT.)	20
	FRONT YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. FT.)	8
	SIDE YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK TOWNHOMES & CONDOS ONLY (MIN. FT.)	0
	SIDE YARD SETBACK (MIN. AGGREGATE. FT.)	20
	SIDE YARD SETBACK TOWNHOMES & CONDOS ONLY (MIN. AGGREGATE. FT.)	NA
	SIDE YARD SETBACK (MAX. AGGREGATE FT.)	NA
	SIDE YARD SETBACK TOWNHOMES & CONDOS ONLY (MAX. AGGREGATE FT.)	NA
	REAR YARD SETBACK (MIN. FT.)	30
	REAR YARD SETBACK (MAX. FT.)	NA
	REAR YARD SETBACK TOWNHOMES & CONDOS ONLY (MIN. FT.)	20
HEIGHT	BUILDING HEIGHT (MIN. FT.)	NA
	BUILDING HEIGHT (MAX. FT.)	50

Not Permitted	NP
Not Applicable	NA

LOT COVERAGE/ OPEN SPACE	LOT COVERAGE (MIN.)	NA
	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC	70%
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)*	10%
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	NA
	OPEN SPACE (MIN.)	NA
	OPEN SPACE (MAX.)	NA

*DETENTION PONDS INCLUDED IF DESIGNED AS AN AMENITY AND COMMUNITY FEATURE. (I.E. FENCING, LANDSCAPING, NATURAL FEEL)

Not Permitted	NP
Not Applicable	NA

ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	**See Section 1105.05** ~~Same as primary~~
	ADU	See Section 1105.05
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	20
PARKING LOCATION	LOCATION	Driveway leading to private attached or detached garage; rear yard
SIGN REGULATIONS	PERMITTED SIGN TYPES	~~Temporary signs only; monument sign for each frontage~~ **Refer to Section 1105.03 - Signs**
DESIGN	DESIGN STANDARDS	Single-unit attached and detached building types; For garage requirements, please see Section 1105.05 & 1105.06
	SITE PLAN STANDARDS	See site plan review, Chapter 1109.1~~79~~
LANDSCAPE REVIEW	LANDSCAPE AND NATURAL BUFFERS	**See Section 1105.07 - Landscaping and Buffering** NA

SECTION 1103.21
COMMUNITY COMMERCIAL ZONE (CC)

I. Purpose and Intent

A. The Community Commercial (CC) Zone is intended to promote development patterns and businesses that are consistent with larger retail and office-users, including companies with a workforce residing throughout the region that is seeking the convenience of access from heavily-traveled corridors. Existing development in the CC Zone is comprised of traditional large lot retail development with surface parking. Future development patterns in the CC Zone should accommodate changes in retail and transportation, including smaller lots and smaller format retail uses.

II. Uses

A. The following uses are either permitted or conditional uses as indicated in the following chart:

DISTRICT USES	
PERMITTED USES:	• Adult Day Care • Adult Oriented Businesses (Subject to Section 795.02 of Codified Ordinances) • Antique Shop (See definition) • Bakery - Retail • Beverage - Brewing and Distilling (See definition) • Boarding/Kennel • Child Day Care - In Home (See 1105.13(I)) • Clothing Services - Dry Cleaning with drive thru • Clothing Services - Dry Cleaning without drive thru • Clothing Services - Tailor • Community Facility - Park • Community Facility - Trail • Event Center - Private Events and Conferences • Event Center - Public Meetings and Conventions • Financial Services and Banking - with drive thru (See 1105.13(L)) • Financial Services and Banking - without drive thru • Food Sales - Farm Market • Food Sales - Small Format Grocery • Food Sales - Large Format Grocery • Food Service – Commercial Kitchen • Food Service - Commissary/Bakery • Food Service - Deli • Food Service - Fast Casual Restaurant • Food Service - Full Service Restaurant • Food Service - Quick Serve/Fast Food Without Drive Thru • Food Service - Quick Serve/Fast Food With Drive Thru (See 1105.13(L)) • Gallery - Art • Health and Wellness - Clinic • Health and Wellness - Fitness Facility/Gym • Health and Wellness - Massage • Health and Wellness - Physical Therapy • Indoor Recreation Enterprise • Library • Live Theater • Manufacturing - Artisan • Medical – Clinic • Medical – Emergency Services • Medical – Full Service Hospital • Medical Office • Medical – Outpatient and Urgent Care

DISTRICT USES (CONT.)	
PERMITTED USES:	• Medical - Psychiatric Facility - Standalone • Medical – Standalone Emergency Services • Meeting Facility • Movie Theater • Museum • Office – Corporate • Office - Data Processing/Call Center • Office - Professional Services • Outdoor Recreation Enterprise • Overnight Lodging - Boutique Hotel • Personal Care and Beauty Services • Religious Assembly • Retail - Small Format • Retail - Medium Format • Retail Large Format • Retail - Extra Large Format • Overnight Lodging - Bed and Breakfast (See definition) • ~~Retail - Medium Format~~ • Retail - Pharmacy without Drive-Thru • Retail - Pharmacy with Drive-Thru (See 1105.13(L)) • Commercial Center - Outdoor - Small • Commercial Center - Outdoor - Large • School - Secondary • School - Primary • Shelter • Studio - Art • Studio - Gymnastics/Martial arts • Veterinary • Visual Arts Center
CONDITIONAL USES:	• Auction Facility • Beverage Sales - Liquor and Beer Sit Down/Bar Establishment • Beverage Sales - Liquor Store • Child Day Care - Center (See 1105.13(H)) • Community Facility - Activity Center • Community Facility - Outdoor Recreation • Community Facility - Public Health Safety • Dwelling - Assisted • Dwelling Group • Dwelling - Multi-Unit Building • Dwelling - Multi-Unit Building Complex • Dwelling – Nursing

Add Retail-Shopping Center - Enclosed

DISTRICT USES (CONT.)	
CONDITIONAL USES:	• Dwelling - Two-Family • Marijuana - Dispensary • Mortuary • Overnight Lodging - Hotel • Private Club • Research Facility and Laboratory • Retail - Convenience with gasoline (See 1105.13(K)) • Retail - Convenience without gasoline • Retail – Vape Shop/Smoke Shop • Shooting Range - Indoor • Storage - Self-Store (See 1105.13(F)) • Storage - Vehicular and Boat • ~~Vehicular Care Services – Major~~ • Vehicular Care Services – Minor - without Drive-Thru • Vehicular Care Services – Minor - with Drive-Thru (See 1105.13(L)) • ~~Vehicle Care Services – Washes~~ • Vehicular Sales - Automobiles • Vehicular Sales - Motorcycles • Vehicular Sales - Boats • Vehicular Sales - Recreational Vehicles

Deleted Dwelling - Developmental Disability from the table.

III. Development Standards

The Community Commercial Zone includes small and medium flex buildings, retail/large format, retail large restaurant building typologies, and off street parking.

LOT DIMENSIONS	LOT SIZE (MIN. SQ. FT.)	NA
	LOT SIZE (MAX. SQ. FT.)	NA
	LOT WIDTH (MIN. FT.)	80
	LOT WIDTH (MAX. FT.)	NA
	LOT DEPTH (MIN. FT.)	NA
	LOT FRONTAGE (MIN. FT.)	80
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	NA
	DENSITY (MAX. UNITS PER ACRE)	NA
SETBACKS	FRONT YARD SETBACK (MIN. FT.)	10
	FRONT YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. FT.) (EACH SIDE)	10
	SIDE YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. AGGREGATE. FT.)	20
	SIDE YARD SETBACK (MAX. AGGREGATE FT.)	NA
	REAR YARD SETBACK (MIN. FT.)	**10** ~~20~~
	REAR YARD SETBACK (MAX. FT.)	NA
HEIGHT	BUILDING HEIGHT (MIN. FT.)	NA
	BUILDING HEIGHT (MAX. FT.)	45
LOT COVERAGE/ OPEN SPACE	LOT COVERAGE (MIN.)	NA
	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC.	70%
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)*	10%
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	70%
	OPEN SPACE (MIN.)	NA
	OPEN SPACE (MAX.)	NA

*DETENTION PONDS INCLUDED IF DESIGNED AS AN AMENITY AND COMMUNITY FEATURE (I.E. FENCING, LANDSCAPING, NATURAL FEEL)

ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	NP
	ADU HEIGHT (MAX. FT.)	NP
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	NP
PARKING LOCATION	LOCATION	Front, side, or rear yard well-screened
SIGN REGULATIONS	PERMITTED SIGN TYPES	**Refer to Section 1105.03 - Signs** ~~Commercial uses only (see Section 1105.03)~~
DESIGN	DESIGN STANDARDS	Small to Medium Commercial Building Types; Natural Materials or Hardie Panel on front and side facades
	SITE PLAN STANDARDS	**See site plan review, Chapter 1109.17** ~~NA~~
LANDSCAPE REVIEW	LANDSCAPE AND NATURAL BUFFERS	**See Section 1105.07 - Landscaping and Buffering** ~~NA~~

Not Permitted	NP
Not Applicable	NA

SECTION 1103.23
INNOVATION ZONE (I)

I. Purpose and Intent

A. Innovation (I) Zone incorporates a mix of industrial and office uses that will facilitate the creation of economic centers that will serve Reynoldsburg and surrounding communities. The existing development pattern in the I Zone is traditional, auto-oriented retail and commercial development. The desired development pattern includes the construction of signature industrial/flex buildings to facilitate access to I-70 and I-270. New construction should be well-designed and site plans should incorporate attractive landscaping, streetscape elements and signage. Pedestrian crossing should be incorporated throughout the zone.

II. Uses

A. The following uses are either permitted or conditional uses as indicated in the following chart:

DISTRICT USES	
PERMITTED USES:	• Air Transportation Services • Auction Facility(See definition) • Beverage - Brewing and Distilling (See definition) • Beverage - Distribution • Beverage - Non-Alcoholic Production • Community Facility - Activity Center • Community Facility - Government Administration and Courts • Community Facility - Outdoor Recreation • Community Facility - Park • Community Facility - Public Health Safety • Community Facility - Trail • Event Center - Private Events and Conferences • Event Center - Public Meetings and Conventions • Financial Services and Banking -with Drive-Thru (See 1105.13(L)) • Financial Services and Banking without Drive-Thru • Food Service - Commissary/Bakery • Food Service - Processing • Food Service – Production • Forestry • Garden Center - Indoor and Outdoor • Health and Wellness - Clinic • Health and Wellness - Fitness Facility/Gym • Library • Manufacturing - Artisan • Manufacturing - Heavy • Manufacturing - Light • Medical – Clinic • Medical – Emergency Services • Medical – Full Service Hospital • Medical - Office • Medical - Outpatient and Urgent Care • Medical - Psychiatric Facility - Standalone • Medical – Standalone Emergency Services • Museum • Office - Corporate • Office - Data Processing/Call Center

DISTRICT USES (CONT.)	
PERMITTED USES:	• Office - Professional Services • Plant Cultivation • Printing and Publishing • Research Facility/Laboratory • School - College/University • School - Trade • Shelter • Studio - Art • Studio - Gymnastics/martial arts • Vehicle Care Services - Washes • Veterinary • Visual Arts Center • Warehouse - Large Format • Warehouse - Small Format
CONDITIONAL USES:	• Child Day Care - Center (See 1105.13(H)) • Community Facility - Detention and Corrections • Food Sales - Farm Market • Indoor Recreation Enterprise • Junk Storage and Sales • Marijuana - Dispensary • Marijuana Facility - Cultivation & Processing • Mineral Extraction/Processing • Outdoor Recreation Enterprise • Outdoor Processing - Agriculture • Outdoor Processing - Composting • Outdoor Processing - Concrete and Asphalt • Power Generation Facility • Power Substation Facility • Private Club • School - Primary • School – Secondary • Shooting Range - Indoor • Storage - Commercial Gasses

III. Development Standards

The Innovation Zone includes office, industrial, and warehouse typologies with on-street and off-street parking.

LOT DIMENSIONS	LOT SIZE (MIN. SQ. FT.)	NA
	LOT SIZE (MAX. SQ. FT.)	NA
	LOT WIDTH (MIN. FT.)	~~200~~ 80
	LOT WIDTH (MAX. FT.)	NA
	LOT DEPTH (MIN. FT.)	150
	LOT FRONTAGE (MIN. FT.)	80
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	NA
	DENSITY (MAX. UNITS PER ACRE)	NA
SETBACKS	FRONT YARD SETBACK (MIN. FT.)	10
	FRONT YARD SETBACK (MAX. FT.)	~~20~~ NA
	SIDE YARD SETBACK (MIN. FT.) (EACH SIDE)	20
	SIDE YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. AGGREGATE. FT.)	40
	SIDE YARD SETBACK (MAX. AGGREGATE FT.)	NA
	REAR YARD SETBACK (MIN. FT.)	40
	REAR YARD SETBACK (~~MIN~~ MAX FT.)	NA
HEIGHT	BUILDING HEIGHT (MIN. FT.)	35
	BUILDING HEIGHT (MAX. FT.)	75
LOT COVERAGE/ OPEN SPACE	LOT COVERAGE (MIN.)	NA
	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC.	~~70%~~ 80%
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)*	NA
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	NA
	OPEN SPACE (MIN.)	NA
	OPEN SPACE (MAX.)	NA

*DETENTION PONDS INCLUDED IF DESIGNED AS AN AMENITY AND COMMUNITY FEATURE. (I.E. FENCING, LANDSCAPING, NATURAL FEEL)

ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	Side or Rear Yards
	ADU HEIGHT (MAX. FT.)	NP ~~NA~~
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	35
PARKING LOCATION	LOCATION	Front or side yards, well-screened
SIGN REGULATIONS	PERMITTED SIGN TYPES	**Refer to Section 1105.03 - Signs** ~~Any two: Wall; Monument, Awning~~
DESIGN	DESIGN STANDARDS	Natural materials on front facade
	SITE PLAN STANDARDS	See site plan review, Chapter 1109.17 ~~NA~~
LANDSCAPE REVIEW	LANDSCAPE AND NATURAL BUFFERS	**See Section 1105.07 - Landscaping and Buffering** ~~NA~~

Not Permitted	NP
Not Applicable	NA

SECTION 1103.25
OPEN SPACE/SCHOOLS ZONE (OS)

I. Purpose and Intent

A. The purpose of the Open Space/Schools (OS) Zone is to promote the health and well-being of the city's residents. Desired forms of development and open space preservation in these zones includes golf courses, ball fields, playgrounds, natural passive areas, and neighborhood pocket parks. Trails originating in these zones should serve as gateways to the city's key destinations, including Olde Reynoldsburg and other entertainment and dining epicenters. Institutional uses such as schools are also encouraged in these zones and will help to promote the growth and development of the city's school age population by providing access to adjacent open space opportunities.

II. Uses

A. The following uses are either permitted or conditional uses as indicated in the following chart:

DISTRICT USES	
PERMITTED USES:	• Camping • Community Facility - Activity Center • Community Facility - Government Administration and Courts • Community Facility - Outdoor Recreation • Community Facility - Park • Community Facility - Public Health Safety • Community Facility - Trail • Cultural • Event Center - Public Meetings and Conventions • Golf Course • Health and Wellness - Fitness Facility/Gym • Library • Museum • Plant Cultivation • Religious Assembly • School - College/University • School - Primary • School - Secondary • School - Trade • Visual Arts Center
CONDITIONAL USES:	• Cemetery • Forestry

III. Development Standards

The Open Space/Schools Zone includes primary schools and community activity center typologies with off-street parking.

LOT DIMENSIONS	LOT SIZE (MIN. SQ. FT.)	NA
	LOT SIZE (MAX. SQ. FT.)	NA
	LOT WIDTH (MIN. FT.)	NA
	LOT WIDTH (MAX. FT.)	NA
	LOT DEPTH (MIN. FT.)	NA
	LOT FRONTAGE (MIN. FT.)	NA
DENSITY (MULTI-UNIT RESIDENTIAL)	DENSITY (MIN. UNITS PER ACRE)	NA
	DENSITY (MAX. UNITS PER ACRE)	NA
SETBACKS	FRONT YARD SETBACK (MIN. FT.)	NA
	FRONT YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. FT.)	NA
	SIDE YARD SETBACK (MAX. FT.)	NA
	SIDE YARD SETBACK (MIN. AGGREGATE. FT.)	20 feet from any residential structure
	SIDE YARD SETBACK (MAX. AGGREGATE FT.)	NA
	REAR YARD SETBACK (MIN. FT.)	30 feet from any residential structure
	REAR YARD SETBACK (MIN. FT.)	NA
HEIGHT	BUILDING HEIGHT (MIN. FT.)	NA
	BUILDING HEIGHT (MAX. FT.)	NA
LOT COVERAGE/ OPEN SPACE	LOT COVERAGE (MIN.)	NA
	LOT COVERAGE (MAX.) - INCLUDING IMPERVIOUS SFC	NA
	CREDIT FOR PERVIOUS OR OTHER COMMON GREEN SPACE UP TO 10% (MAX.)*	NA
	LOT COVERAGE (MAX.) - NOT INCLUDING ALL IMPERVIOUS SURFACES	NA
	OPEN SPACE (MIN.)	NA
	OPEN SPACE (MAX.)	NA

*DETENTION PONDS INCLUDED IF DESIGNED AS AN AMENITY AND COMMUNITY FEATURE. (I.E. FENCING, LANDSCAPING, NATURAL FEEL)

ACCESSORY STRUCTURE DIMENSIONS	ACCESSORY BUILDING LOCATION	NA
	ADU HEIGHT (MAX. FT.)	NP
	ACCESSORY BUILDING HEIGHT (MAX. FT.)	NA
PARKING LOCATION	LOCATION	Any yard, well-screened
SIGN REGULATIONS	PERMITTED SIGN TYPES	**Refer to Section 1105.03 - Signs** ~~Any two: Wall; Monument; Awning~~
DESIGN	DESIGN STANDARDS	Single-family building types; Natural materials or Hardie Plank on front and side facades
	SITE PLAN STANDARDS	**See site plan review, Chapter 1109.17** ~~NA~~
LANDSCAPE REVIEW	LANDSCAPE AND NATURAL BUFFERS	**See Section 1105.07 - Landscaping and Buffering** ~~NA~~

Not Permitted	NP
Not Applicable	NA

SECTION 1103.27 BUILDING TYPOLOGIES

The below-listed building typologies are the building typologies contemplated for new development in the districts and zones described below. New buildings and alterations to existing buildings shall be reviewed in accordance with Chapter 1103.07 hereof.


BUILDING TYPOLOGIES	OLDE REYNOLDSBURG COMMERCIAL DISTRICT	OLDE REYNOLDSBURG NEIGHBORHOOD DISTRICT	BRICE AND MAIN DISTRICT (BMD)	EAST MAIN STREET DISTRICT (EMD)
DETACHED SINGLE-FAMILY BUILDING	X	X		
ATTACHED SINGLE-FAMILY BUILDING		X	X	
DUPLEX BUILDING		X		
MULTI-UNIT BUILDING		X		X
MULTI-UNIT COMPLEX			X	X
SMALL FLEX RETAIL BUILDING	X	X	X	X
MEDIUM FLEX RETAIL BUILDING	X		X	X
LARGE FLEX RETAIL BUILDING	X		X	
INSTITUTIONAL FLEX BUILDING		X		X
BED AND BREAKFAST BUILDING	X			
SCHOOL AND INSTITUTIONAL BUILDING	X			
COMMUNITY CENTER BUILDING	X	X		
OFFICE BUILDING			X	X
OFFICE-CORPORATE BUILDING				
RETAIL LARGE FORMAT BUILDING				
INDUSTRIAL BUILDING				
WAREHOUSE BUILDING				
PRIMARY SCHOOL BUILDING				
COMMUNITY ACTIVITY CENTER BUILDING	X			
EVENT CENTER BUILDING				

SUBURBAN RESIDENTIAL ZONE (SR)	RESIDENTIAL MEDIUM ZONE (RM)	COMMUNITY COMMERCIAL ZONE (CC)	INNOVATION ZONE (I)	OPEN SPACE/ SCHOOLS ZONE (OS)
X	X			
X	X			
	X			
		X		
		X		
		X		
	X			X
	X		X	
		X		
		X	X	
		X		
			X	
			X	
				X
				X
		X		X

A. ATTACHED SINGLE-FAMILY BUILDING

The below illustrations of each development typology are for illustrative purposes only and are intended to supplement the regulations applicable to each zone and district.

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description


A structure with common walls on either side and no units below or above. Garage access is typically from a rear alley or shared parking area. A small side or rear yard is provided for each unit as private open space.



Image: Attached Single-Family Building

B. DETACHED SINGLE-FAMILY BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description


A small detached structure with small side and street setbacks. Garage access is typically from the street, but garages are clearly subordinate to the principal structure.



Image: Detached Single-Family Building

C. DUPLEX BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A detached structure with two units that is massed as a single structure. Setbacks can range from small to large and units are typically side-by side, but may be stacked.






Image: Duplex Building

D. MULTI-UNIT BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building with multiple residential units that front on an interior corridor and have their main access from the primary street. Units can be next to each other (side-by-side units), or stacked on top of each other (top and bottom units).






Image: Multi-Unit Building

E. MULTI-UNIT COMPLEX

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A collection of multi-unit buildings on adjoining pieces of land, generally owned by one entity. The buildings often share common grounds and amenities, such as pools, parking areas, and a community clubhouse, used as leasing offices for the community.






Image: Multi-Unit Complex Building

F. SMALL FLEX RETAIL BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description


Consists of attached or detached structures ranging from one to three stories. Structures can include single or mixed uses. Parking is located in the rear or side of the building and typically accessed from a rear alley when possible.



Image: Small Flex Retail Building

G. MEDIUM FLEX RETAIL BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description


Consists of attached or detached structures ranging from one to three stories. Structures can include single or mixed uses. Parking is located in the rear or side of the building and typically accessed from a rear alley when possible.



Image: Medium Flex Retail Building

H. LARGE FLEX RETAIL BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description


Consists of attached or detached structures that can include single or mixed-uses. Parking is located in the rear of the building and, where possible, accessed from a rear alley.



Image: Large Flex Retail Building

I. INSTITUTIONAL FLEX BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building that can house uses of an institutional nature (i.e. government building, library, post office, etc.) with parking on the same lot and the main access from the primary street.






Image: Institutional Flex Building

J. BED AND BREAKFAST BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A residential structure providing limited overnight lodging and meals for guests.







Image: Bed and Breakfast Building

K. SCHOOL AND INSTITUTIONAL BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

An institution or place for instruction or education, such as kindergarten; elementary, middle, or junior high school, and high school.






Image: School and Institutional Building

L. COMMUNITY CENTER BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description


Usually a public building where members of a community tend to gather for group activities, social support, public information, and other purposes. It can be open for the whole community or specialized groups (e.g. senior center) and can include both indoor and outdoor recreational facilities.



Image: Community Center Building

M. OFFICE BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building used primarily for conducting the affairs of multiple business, professional, service, industry, government, or like activity, which may include ancillary services for office workers with parking typically found on the same lot and the main access form the primary street.






Image: Office Building

N. OFFICE-CORPORATE BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building used primarily for conducting the affairs of a single business, professional, service, industry, government, or like activity, which may include ancillary services for office workers with parking typically found on the same lot and the main access form the primary street.






Image: Office-Corporate Building

O. RETAIL LARGE FORMAT BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A single-use, typically large single-story commercial building primarily accessed by automobile with parking on the same lot with a combination of parking in the front, side, or rear yards.






Image: Retail Large Format Building

P. INDUSTRIAL BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building that houses manufacturing activity that uses moderate amounts of partially processed materials to produce items of relatively high value per unit weight. Facilities for loading and unloading are typically located in the side or rear yard with employee and visitor parking in the rear yard.






Image: Industrial Building

Q. WAREHOUSE BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building for storing goods with facilities for loading and unloading that are typically located in the side or rear yard with employee and visitor parking in the rear yard.







Image: Warehouse Building

R. PRIMARY SCHOOL BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building designed to provide learning spaces and learning environments for the teaching of students from about four to eleven years old under the direction of teachers. The building has limited parking for staff and includes both outdoor and indoor recreational activity.






Image: Primary School Building

S. COMMUNITY ACTIVITY CENTER BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

Usually a public building housing space for indoor recreational activity as well as exterior space for sports and recreation.






Image: Community Activity Center Building

T. EVENT CENTER BUILDING

1. Typical Lot Configuration



Note: image is illustrative, not regulatory.

2. Description

A building designed to house special events, including weddings, private parties, and receptions.






Image: Event Center Building

SECTION 1103.29 OPEN SPACE TYPOLOGIES

The following Open Space Typologies cover land that is intended to be undeveloped within the Olde Reynoldsburg District (ORD Commercial and ORD Neighborhood), consistent with the goals of the Comprehensive Plan.

A. GREENWAY AND TRAIL

1. Typical Lot Configuration




2. Description

Greenways are primarily linear open spaces that connect other types of open spaces as part of a larger open space system. They typically include a path or trail as a primary feature. The greenway and trail open space is most effect when connecting to another open space type.

B. PLAZA

1. Typical Lot Configuration




2. Description

Plazas are spaces available for civic purposes and commercial activities intended to add to the vibrancy of streets and neighborhoods. Building frontages typically define the edges of these spaces. The landscape consists of primarily hardscape. If trees are included, they are formally arranged and of appropriate scale to the space.

C. SQUARE

1. Typical Lot Configuration




2. Description

Squares are medium scale formal open spaces designed to serve as gathering spaces in prominent commercial, civic and mixed-use settings. Squares are typically rectilinear and framed on all sides by streets. They are typically designed with a combination of both hardscape and landscape areas and contain amenities including, but not limited to benches and seating areas, planting areas, walking paths, gazebos or pavilions, fountains, and public art.

D. GREEN

1. Typical Lot Configuration




2. Description

Greens are medium-scale, informal open spaces designed to provide for active or passive recreation in neighborhood settings, including some landscape areas and is generally for those who live within walking distance.

E. PASSAGE

1. Typical Lot Configuration




2. Description

A passage is an informal or formal gathering space that serves equally as a pedestrian connector between other gathering places or between streetscapes. Passages are near the middle of a block, providing easy walking access through the block. A passage provides additional frontage opportunities for the shops and/or houses along its edges.

F. PARK

1. Typical Lot Configuration




2. Description

Parks are larger-scale, typically informal open spaces designed to provide a variety of active and passive recreational opportunities to the general public. Parks may include natural areas. These open spaces may have a variety of forms, with edges defined by streets, neighborhoods, or natural features. Landscaping may be required as deemed appropriate by the Review Authority.

G. SPORT FIELD

1. Typical Lot Configuration




2. Description

A Sports Field typology is a space or series of open spaces designed for sports activities. Sports fields often accommodate several individual sports games at the same time and may feature a concession area and seating for spectators. Due to the larger amounts of people attracted to this type, sports fields are located to maintain compatibility with adjacent neighborhoods. Landscaping may be required as deemed appropriate by the Review Authority.

H. POCKET PLAZA

1. Typical Lot Configuration




2. Description

Pocket plazas are small-scale, primarily hardscaped open spaces designed to provide opportunities for impromptu gathering and resting areas for passersby and for those who live or work in adjacent buildings or nearby destinations. Pocket plazas are typically designed as an extension from the public sidewalk, but clearly delineated as a separate space using features including, but not limited to landscaping and/or seating walls. Pocket Plazas are typically located along highly trafficked streets and in commercial areas with frequent pedestrian activity.

I. POCKET PARK

1. Typical Lot Configuration




2. Description

Pocket parks are small-scale, primarily landscaped open spaces designed to provide opportunities for neighborhood gathering and typically passive recreation, generally for those who live within walking distance. Pocket parks are typically located in residential neighborhood settings. Landscaping may be required as deemed appropriate by the Review Authority.

J. NATURE

1. Typical Lot Configuration



2. Description


Areas that are to remain undeveloped and that generate their physical character through their natural topography, trees, and plants. This open space type is preserved from any development.

SECTION 1103.31 FRONTAGE TYPOLOGIES

The following Frontage Typologies cover the area between the building façade and the front lot line or right-of-way and intended to ensure projects that establish or reinforce the appropriate frontage character within Olde Reynoldsburg District (ORD Commercial and ORD Neighborhood), consistent with the goals of the Comprehensive Plan.

A. SHOPFRONT

1. Typical Lot Configuration




2. Description

The shopfront is a traditional ground floor frontage treatment designed for active commercial uses (typically retail and dining) and a high degree of pedestrian activity between the public sidewalk and commercial spaces. A shopfront treatment includes one or more commercial tenant storefronts consisting of large windows and a direct tenant entrance from the sidewalk, typically at sidewalk grade. Storefront characteristics typically include prominent entrances, primarily composed of glass, and tenant signage. If not located in a zero lot line condition (immediately behind the sidewalk), the intervening front setback may be paved as an extension of the sidewalk streetscape to the building façade. All or portions of the setback may be designated for use as outdoor seating or dining/bar space. The setback may also include landscaping, either at grade with the sidewalk along the building foundation, or in raised beds or planters.

B. PATIO

1. Typical Lot Configuration




2. Description

The patio frontage is used primarily to provide outdoor seating associated with ground floor dining uses within a building. The patio is a hardscaped area that may be located to the front or side of a building between the building and sidewalk.

C. YARD

1. Typical Lot Configuration




2. Description

The yard is a typical landscape setback which may consist of open lawn, landscape beds, or some combination of the two. It may contain hardscape elements as a secondary feature and may be edged by a low fence or masonry wall. Yards are typically at the same or similar grade as the adjacent sidewalk and include a front walk connecting the public sidewalk to the main entrance of a building (see Raised Yard as a variation). This is the common frontage treatment for houses and other neighborhood-scale residential buildings, and is typically combined with other a porch or stoop building frontage. A yard may also be used for flex building types designed for any combination of uses.

D. RAISED YARD

1. Typical Lot Configuration




2. Description

The Raised Yard Frontage Type is a variation of the front yard. It generally represents an historic residential lot character in which the front yard is elevated above the sidewalk, often in a sloped condition and sometimes with a masonry retaining wall (often composed of dry-laid limestone) at the sidewalk edge, or some combination of the two. The raised yard is often a continuous frontage condition for multiple adjacent lots. Front walks connecting the public sidewalk to the main building entrance are typically terraced with a set of steps at or near the public sidewalk and a second set of steps at the building façade, often at a front porch or stoop (see Porch and Stoop Frontage Types). The raised yard differs from the Terrace Frontage type in that buildings are typically set back farther from the street and the yard primarily consists of turf lawn or landscaping.

E. PORCH

1. Typical Lot Configuration




2. Description

Common frontage type for residential building types. Porches should be an extension of the internal living space.

F. STOOP

1. Typical Lot Configuration




2. Description

Entry landing for buildings that have elevated first floors to secure privacy for first floor windows. Stoops may have perimeter railings and walls. Stoops can be covered or uncovered and can be located anywhere along the building face.

G. TERRACE

1. Typical Lot Configuration




2. Description

In the Terrace Frontage Type, the main facade is at or near the property line with an elevated terrace providing public circulation along the facade. This Type can be used to provide at-grade access while accommodating a grade change and is frequently used together with a shopfront. Frequent steps up to the terrace are necessary to avoid dead walls and maximize access. A terrace treatment differs from the Raised Yard Frontage type in that the building is typically located closer
to the sidewalk and the terraced setback is architecturally integrated with the building façade, consisting of more hardscape materials. Raised planters may be incorporated as part of a terrace frontage.

H. FORECOURT

1. Typical Lot Configuration




2. Description

The forecourt frontage treatment allows for a portion of a building façade to be set farther back from the street, creating a courtyard condition with street frontage. A forecourt condition may also be created through the composition of three separate buildings, oriented with the central building setback farther from the others. A forecourt may include open access to the public sidewalk with one or more entrances into the building, or may be fenced and elevated as a semi-private space, partially visible from the public realm. The forecourt area typically includes a combination of landscape and hardscape treatments, and may include outdoor amenities and seating areas associated with the building(s).

I. STREETWALL

1. Typical Lot Configuration



2. Description

The streetwall frontage is used to create a continuous and defined edge along parking lots where located in close proximity to a street and sidewalk. Streetwalls are typically low (at or below waist height of a passing pedestrian) and may be composed entirely of masonry, a combination of decorative metal fencing with masonry columns, raised planters, a landscape hedge treatment, or some combination of these. Masonry street walls are typically designed to coordinate with the principal building architecture and often are physically connected to the building façade. Street walls may be interrupted with a pedestrian walk connection to the public sidewalk. For new projects or redevelopment, street walls are intended for use along any portion of lot frontage in which side or rear parking is located adjacent to or near the public sidewalk, but are secondary to other frontage types associated with the principal building and should not dominate the entire lot frontage. Streetwalls are also an effective design approach to improve existing auto-oriented sites for which all or substantial portions of a primary frontage consist of parking.

1105 COMMON REGULATIONS

Common Regulations

SECTION 1105.01 OFF-STREET PARKING AND LOADING

A. Applicability. Except as otherwise provided herein, these regulations shall apply under the following circumstances:

i. The construction of a new building or structure;

ii. The substantial expansion of an existing building or structure;

iii. A change in the existing use to be conducted upon land or in a building or structure; and

iv. Whenever a building or use is changed in floor area, number of employees, number of dwelling units, seating capacity, or in a manner which otherwise creates a need for an increase in the number of parking or loading spaces, such spaces shall be provided for the entire increased use in conformance with the requirements of this article.

B. Parking Requirements in Olde Reynoldsburg Commercial District (ORD-C), Brice and Main District (BMD) and East Main District (EMD). Notwithstanding anything to the contrary contained herein, the parking requirements for any use conducted in the ORD-C, BMD, or EMD shall be determined based upon the applicable regulations set forth under Chapter 1105 hereof.

C. Supplemental Parking Regulations in Residential Districts. The provision of parking space, either open or enclosed, for the parking or storage of vehicles in a residential zoning district for residential uses shall be subject to the following:

i. Commercial Vehicles. Trucks having dual tires on one (1) or more axles, or having more than two (2) axles, designed for the transportation of cargo and including tractor-trucks, trailers, and semi-trailers, shall not be permitted on a lot or parked on a street or alley in a residential zoning district.

ii. Parking of Recreational Equipment. The parking of recreational equipment and vehicles, including but not limited to travel trailers, motor homes, pickup campers, folding tent trailers, boats or boat trailers, and other similar recreational equipment and vehicles, semi-trailers, travel trailers, or other trailers or motor homes shall not be permitted on any street within the City,

other than for the purpose of loading or unloading such equipment or vehicle. When located on property in a residential district for the purpose of loading or unloading, travel trailers, motor homes, boats or boat trailers, and other similar recreational vehicles shall not exceed a loading or unloading time of 48 consecutive hours. Residents shall be permitted to park a maximum of one (1) recreational vehicle on property located in a residential district if such vehicle is located in an enclosed structure OR all of the following requirements are satisfied for a vehicle parked or store outside of an enclosed structure::

1. Such recreational equipment and vehicles shall be stored or parked at least three (3) feet from any dedicated right-of-way, walkway and/or property line.
2. Not more than one (1) item of recreational equipment shall be permitted to be stored outside on any property used for a residential purpose. All recreational vehicles must be registered and licensed (if applicable) to the resident of the property on which the items are parked or stored. For the purposes of this chapter, a boat stored on a boat trailer shall be deemed one (1) piece of recreational equipment.
3. Under no circumstances shall any recreational vehicle or equipment be occupied or used for living, sleeping, housekeeping, storage or business purposes.
4. No such recreational vehicle shall be parked in any manner in which such vehicle may be deemed, in the professional opinion of the Planning and Zoning Administrator, to obstruct the view of traffic in a manner that endangers the safety of motorists or pedestrian.

D. Conversion of Use. No parking or loading space (including a residential garage) which is required by this Zoning Code shall be removed or converted to another use unless the parking or loading requirement is satisfied by the existence or construction of an additional parking or loading space conforming to this Zoning Code.

E. Required Parking and Loading Spaces.

i. Required Parking Spaces. Except as otherwise provided herein, the number of off-street parking spaces provided for a use shall not be less than set forth in the table identified as "Table 1105.01A: Required Parking Spaces." The number of parking and loading spaces required for a use shall be as determined by the Zoning Administrator in conformance with the provisions of this Zoning Code.

ii. Requirements for Unlisted Use. For a use for which off-street parking requirements have not been specifically stated in this Zoning Code, parking and loading facilities shall be provided as determined by the Zoning Administrator to be sufficient for the parking and loading needs of the proposed use and structures, giving consideration to the following criteria:

1. The number of off-street parking spaces required for a use listed in the table that is the most similar to the proposed use in terms of anticipated parking demand;
2. The floor area of the proposed use;
3. The anticipated number of employees and patrons; and
4. Any evidence submitted regarding the parking demand for the same use on similar existing sites.

iii. **Calculation for Certain Uses.** For uses for which required parking is based on number of dwelling units, floor area, seats, or beds, the number of required parking spaces shall be determined from drawings provided by the applicant and may be further confirmed by measurement of the actual built floor area. When calculation of required parking results in a fraction, then the fraction shall be rounded to the next higher whole number.

iv. **Calculation for Mixed-Uses.** For properties having mixed or multiple uses, the number of required parking spaces shall be the sum of those required for the various uses computed separately, except as otherwise provided.

F. Minimum Off-Street Parking Space Requirement Reductions.

i. **Minimum Off-Street Parking Space Reduction Standards.** The minimum number of off-street parking spaces required by Table 1105.01A may be reduced for a land use or land uses upon approval of an application demonstrating one or more of the off-street parking space reduction conditions set forth under Sections (F)(ii), F(v), F(vi), or F(vii) below; provided however, under no circumstances shall the cumulative reduction of minimum parking spaces exceed 30% of the minimum number of off-street parking spaces required for a land use.

ii. **Shared Parking Plan.** Where a mix of land uses on one or more properties or within one or more buildings can demonstrate parking utilization in staggered peak periods, a shared parking plan may be approved by the Planning and Zoning Administrator to the reduce the minimum number of required off-street parking spaces for the applicable land use(s). A shared parking plan for the reduction of off-street parking requirements may be submitted to the Planning and Zoning Administrator subject to the following requirements:

1. Shared parking plans must incorporate parking facilities located within five hundred feet (500 ft.) of the subject property or subject properties; and
2. To the greatest extent practicable, adjacent lots included in a shared parking plan shall be connected for vehicular passage and shall provide safe and efficient pedestrian access to all uses served by the parking facilities.

iii. **Review of Shared Parking Plan.** A decision pertaining to an application for a shared parking plan shall be based on the following factors:

1. The number of parking spaces otherwise required for the land uses that will share the parking facilities designated in the shared parking plan;
2. Documentation that the peak parking utilization for the land uses occurs at different days and/or times;
3. The demonstrated accessibility of the shared parking facilities; and
4. Such other relevant documentation as the applicant(s) may provide to the City in conjunction with a parking reduction application.

iv. **Effect of Approval of Shared Parking Plan.** When a shared parking plan application is approved, the modified number of required off-street parking spaces for the applicable land uses shall be the largest number of parking spaces needed for the applicable land uses during the most intensive time period of parking utilization as demonstrated by the evidence presented with the application.

v. **Auto-Share Parking Spaces.** The required minimum number of off-street parking spaces for a land use may be reduced by up to four (4) off-street parking spaces for each off-street parking space that is reserved for auto-share parking; provided however the satisfaction of this parking reduction condition may not result in an off-street parking space reduction in excess of 10%. Auto-share parking spaces shall be designed in a plan to be submitted for review by the Planning and Zoning Administrator; such plan must propose how the auto-share parking spaces will be reserved for auto-share parking.

vi. **Transit Proximity.** The required minimum number of off-street parking spaces for a land use or land uses may be reduced by up to 10% if more than 50% of the subject property is located within 1,200 feet of any public transit stop. If an existing transit stop is subsequently eliminated, any previously permitted parking reduction shall remain valid, provided that an active transit route remains within 1,200 feet of the development.

vii. **Bike Lockers and Shower Facilities.** The required minimum number of off-street parking spaces for a non-residential development may be reduced by 5% if such development contains shower and clothing and bike locker facilities for bicycle commuting employees. The required minimum number of off-street parking spaces for a multi-family development may be reduced by 5% if such development contains interior bicycle parking for residents. In each case, the reduction shall apply only to that portion of the minimum off-street parking requirement attributable to the employees or residents that have access to the shower and locker facilities. Removed space after section

viii. **Review and Revocation.** Upon the grant of a reduction in the minimum number of off-street parking spaces hereunder, the Planning and Zoning Administrator shall periodically review the land uses associated with any approval to determine compliance with such approval. If the Planning and Zoning Administrator determines upon review of any approved application that the terms of any approved plan are not being complied with, then the Planning and **Zoning** ~~zoning~~ Administrator may revoke such approval, and the applicable land use shall be required to satisfy the minimum off-street parking requirement otherwise set forth under Table 1105.01A hereof.

G. Parking and Loading Design Standards

i. **Location.** A parking space required for a dwelling unit shall be provided on the same lot as the dwelling unit. The standard size for a parking space installed in accordance with these provisions shall be 9' X 18.' A parking space required for a use other than a dwelling unit shall be located on the same lot as the use, except that some or all of such required spaces may be located on another lot within three hundred feet (300') of the use if authorized in the approval of the site plan. Parking or loading facilities shall not be permitted on the right-of-way of any publicly dedicated thoroughfare, except as provided by a public authority.

ii. **Setbacks.** Off-street parking and loading facilities, with the exception of driveways leading from the public right-of-way to aisles or spaces, shall be located as follows:

1. Required unenclosed parking spaces for Attached Single-Family, Detached Single-Family, Two-Family, and Multi-Unit Dwellings may be provided on paved areas within the front yard required for such structure. Parking shall not be permitted on unpaved areas;
2. No part of any parking lot shall be located closer than five feet (5') to a public right-of-way;
3. Parking may be located in the required front yard in any industrial district, but not closer than twenty feet (20') to a public right-of-way;

4. In any commercial district, parking shall not be located in the area between the frontage and the front setback. The area between the frontage and the front setback shall be improved as a grass and or planting area. Ingress and/or egress through this planting area shall be restricted to a driveway or driveways not to exceed thirty feet (30') in width. Under no circumstances will service roads and or driveways parallel to the right of way be permitted ~~the~~ **The** grass and/or planting area and driveways are to be made a part of the plot- grade-utility plan and are to be approved by the Service Director and City Engineer.

iii. Screening. Any parking lot which contains more than ten (10) parking spaces and which is located closer than fifty feet (50') to the lot line of any lot which is used for a dwelling, school, hospital, or other institution for human care shall be screened by a fence, wall, or hedge of acceptable design installed at each edge of the parking lot which faces the use noted above. Such fence, wall, or hedge shall be no less than four feet (4') nor more than six feet (6') in height and shall be maintained in good condition without any advertising thereon. The space between such fence, wall, or hedge and the lot line of the adjoining premises shall be landscaped with grass, hardy shrubs or evergreen ground cover and maintained in good condition.

iv. Access. Adequate ingress and egress from the public right-of-way and within the lot shall be provided for all parking and loading spaces. Access for all parking and loading facilities (except those required for Attached Single-Family, Detached Single-Family and Two-Family dwellings) shall be designed to permit any vehicle entering or leaving the premises to be traveling in a forward motion. Driveways shall be located to minimize conflict with vehicular and pedestrian traffic in the public right-of-way. Driveways and service roads shall not be located parallel to the right-of-way. Driveways for non-residential uses shall not exceed thirty feet (30') in width at the right-of-way line nor more than thirty feet (30') at the curb cut line of the street unless otherwise approved by the individual or administrative body reviewing the site plan for the subject property.

v. ADA Requirements. All parking facilities that require accessible parking spaces shall ensure that a portion of the total number of required parking spaces are specifically designated, located, and reserved for use by persons with physical disabilities, in accordance with the standards in the federal Americans with Disabilities Act (ADA). The following standards apply:

1. The closest parking spaces to the main entrance shall be devoted to the required accessible parking spaces; and
2. At least one accessible parking space shall be 12 feet (12') wide to accommodate an accessible van or paratransit. Moved table under Section 1105.01.G.vi

vi. Minimum Aisle Width. Minimum aisle width to access parking spaces shall be as follows:

1. Minimum Aisle Width (feet)

ANGLE OF PARKING	ONE-WAY	TWO-WAY
Parallel	13 ft.	20 ft.
Up to 50 degrees	13 ft.	22 ft.
50 up to 80 degrees	17 ft.	22 ft.
80 degrees or more	N/A	22 ft.

vii. Loading Spaces

1. Every building or lot used for non-residential purposes which customarily receives or distributes materials or services by motor vehicles shall provide sufficient space for all loading and service purposes. A loading space shall be provided as an area exclusive of required parking spaces, driveways, and aisles. Access to loading spaces shall be designed to prevent interference with the public right-of-way.
2. Number of Loading Spaces
   (a) Retail/Food Sales/Food Service and Other Similar Type Uses: One (1) space in excess of the first ten thousand (10,000) square feet of floor area plus one (1) space for each additional twenty thousand (20,000) square feet thereafter;
   (b) Office/Medical/Financial Services Type Uses: No loading space is required for the first ten thousand (10,000) square feet of floor area. One (1) loading space is required for ten thousand and one (10,001) square feet of floor area to twenty thousand (20,000) square feet of floor area. An additional loading space is required for each additional twenty thousand (20,000) square feet thereafter.
   (c) Other Uses: At the discretion of the Planning and Zoning Administrator.
3. Each loading space shall have minimum dimensions of twelve feet (12') in width, fifteen feet (15') in height and forty-five feet (45') in length for tandem trailers, or thirty feet (30') feet in length for two-axle trucks.

viii. Paving and Improvements

1. All required parking and loading facilities shall be paved with a durable, dust-free surface such as asphalt or concrete. Gravel is not a permitted surface.
2. Parking facilities shall be designed to direct surface water into an adequate storm drainage system. Drainage of surface water onto adjacent properties, walkways, or public streets is prohibited.
3. Paint lines shall be installed and maintained to mark the locations of all parking and loading spaces. Wheel blocks shall be installed for all parking spaces which abut unpaved areas of a lot.

ix. Lighting. Lighting may be installed and arranged as to direct the light away from adjoining properties and public rights-of-way.

H. Maintenance of Parking Lots Required. All paved areas shall be maintained free of holes, litter, trash, and other debris. Within thirty (30) days of the date on which a non-residential use of a lot is terminated, the owner shall install a barricade at all points of vehicular access in a manner approved by the Zoning Administrator.

I. **Reserved Parking Lot.** In conjunction with the site plan and design review, the applicable reviewing individual or administrative body may approve, upon request of the applicant and review of the site plan, construction of fewer parking spaces than required by Table 1105.01A for a proposed use and site development. In making such determination, the reviewing individual or administrative body shall nevertheless require that the additional area needed to accommodate the required number of parking spaces be reserved as landscaped open areas on the lot. The layout and design of the parking spaces, aisles, and drives of such reserved parking lot shall be indicated on the approved site plan and shall comply with provisions of this Zoning Code. The layout and design of the parking spaces, aisles, and drives of such reserved parking lot shall be indicated on the approved site plan and shall comply with provisions of this Zoning Code.

J. **Electric Vehicle (EV) Parking and Infrastructure.**

i. **Purpose.** To facilitate the transition to electric vehicles by requiring and regulating the provision of Electric Vehicle charging infrastructure in new and existing developments.

ii. **Applicability.**

1. All new off-street parking lots with 20 or more spaces.

iii. **Required Minimums.**

1. New Off-Street Parking:
   (a) 1 Electric Vehicle Supply Equipment (EVSE) Installed for 20 or more parking spaces.
2. Electric Vehicle Supply Equipment (EVSE) Installed spaces count toward total required parking.

iv. **Location and Design.**

1. Electric Vehicle spaces shall be located as close as feasible to building entrances or pedestrian access points.
2. Electric Vehicle Supply Equipment Installed spaces shall be marked with signage indicating they are for Electric Vehicle use only.
3. Electric Vehicle charging cords shall not interfere with pedestrian walkways or ADA access.
4. At least one Electric Vehicle Supply Equipment Installed space shall be ADA accessible in compliance with federal and state accessibility standards.
5. The charging station must be located a minimum of 10 feet from any property line, unless the adjacent property is a public right-of-way. In that case, the station must meet the minimum parking setback requirement adjacent to a right-of way.
6. All above-ground utility structures must be located outside any visibility triangles at intersections or driveways.

v. **Shared Use.** Public and shared parking facilities may satisfy Electric Vehicle requirements for multiple uses on the same or adjacent parcels, subject to cross-access agreements.

TABLE 1105.01A - REQUIRED PARKING SPACES	
USE	OFF-STREET PARKING SPACES REQUIRED
Dwelling - Attached Single-family	1 enclosed, 1 unenclosed
Dwelling - Detached Single-family	
Dwelling - Two-family	1 enclosed space and 1 unenclosed space per dwelling
Dwelling - Multi-Unit Building	Apartments - 1 per unit plus 1 per each 5 units to accommodate visitors
Dwelling - Multi-Unit Building Complex	
Dwelling - Assisted	1 per 8 beds plus 1 per employee based on the largest staff shift
Dwelling - Group	
Dwelling - Nursing	
Adult Day Care	1 per employee based on largest staff shift plus 10 for visitors
Child Day Care - Center	
Child Day Care - In Home	
Event Center – Private Events and Conferences	1 for each 4 seats in the main space
Event Center Public Meetings and Conventions	
Religious Assembly	
Beverage – Brewing and Distilling	1 for each 200 sq. ft. of floor area
Beverage – Distribution	
Beverage – Non-Alcoholic Production	
Food Service – Commissary/Bakery	
Food Service – Commercial Kitchen	
Food Service - Processing	
Food Service – Production	
Beverage Sales – Liquor and Beer Sit Down/Bar Establishment	1 for each 200 sq. ft. floor area
Food Service – Deli	
Food Service – Fast Causal Restaurant	
Food Service – Full Service Restaurant	
Food Service – Quick Serve/Fast Food with Drive Thru	
Food Service – Quick Serve/Fast Food Without Drive Thru	
Adult Oriented Businesses	1 for each 200 sq. ft. floor area

Deleted Dwelling - Developmental Disability from the table

TABLE 1105.01A - REQUIRED PARKING SPACES	
USE	OFF-STREET PARKING SPACES REQUIRED
Amusement Arcades	1 for each 200 sq. ft. of floor area
Antique Shop	
Auction Facility	
Bakery – Retail	
Beverage Sales – Liquor Store	
Clothing Services - Dry Cleaning with drive thru	
Clothing Services - Dry Cleaning without drive thru	
Clothing Services - Tailor	
Financial Services and Banking - with drive thru	
Financial Services and Banking - without drive thru	
Food Sales – Farm Market	
Gallery - Art	
Garden Center - Indoor and Outdoor	
Personal Care and Beauty Services	
Retail - Extra Large Format	1 for each 600 sq. ft. of floor area
Retail - Large Format	1 for each 200 sq. ft. of floor area
Retail - Medium Format	
Retail - Pharmacy without Drive-Thru	
Retail - Pharmacy with Drive-Thru	
Retail - Shopping Center - Enclosed	
Retail - Small Format	
Retail - Vape Shop/Smoke Shop	
Tattoo/Piercing Establishment	
Food Sales – Large Format Grocery	1 for each 300 sq. ft. of floor area
Food Sales – Small Format Grocery	
Commercial Center - Outdoor - Small	1 for each 300 sq. ft. of floor area
Commercial Center - Outdoor - Large	1 for each 450 sq. ft. of floor area
Retail - Convenience with gasoline	1 per each two dispensing stations plus 1 per each 200 sq. ft. retail floor area
Retail - Convenience without gasoline	

TABLE 1105.01A - REQUIRED PARKING SPACES	
USE	OFF-STREET PARKING SPACES REQUIRED
School – College/University	Determined by the Board but not less than 1 space per each 5 seats in the main assembly room or 1 space per each classroom
School – Primary	
School – Secondary	
School – Trade	
Boarding/Kennel	1 for each 200 sq. ft. of gross floor area
Health and Wellness – Clinic	
Health and Wellness – Fitness Facility/Gym	
Health and Wellness – Massage	
Health and Wellness – Physical Therapy	
Medical – Clinic	
Medical – Emergency Services	
Medical – Office	
Medical – Outpatient and Urgent Care	
Medical – Standalone Emergency Services	
Shelter	
Veterinary	
Medical – Full Service Hospital	1 per bed plus 1 per employee based on the largest staff shift
Medical – Psychiatric Facility - Standalone	
Library	1 for each 200 sq. ft. floor area
Live Theater	
Movie Theater	
Museum	
Visual Arts Center	
Manufacturing – Artisan	~~1 for each 200 sq. ft. floor area~~ 1 for each 1,000 sq. ft. of floor area
Manufacturing – Heavy	
Mineral Extraction/Processing	
Outdoor Processing – Agriculture	
Outdoor Processing – Composting	
Outdoor Processing – Concrete and Asphalt	
Research Facility/Laboratory	

TABLE 1105.01A - REQUIRED PARKING SPACES	
USE	OFF-STREET PARKING SPACES REQUIRED
Office - Corporate	1 for each 250 sq. ft. of floor area
Office - Data Processing/Call Center	
Office - Professional Services	
Printing and Publishing	
Equipment Repair	1 for each 500 sq. ft. of floor area
Vehicular Care Services - Major	
Vehicular Care Services - Minor	
Camping	1 for each 3 patrons or a plan that is acceptable to the Planning and Zoning Administrator
Community Facility - Outdoor Recreation	
Community Facility - Park	
Community Facility - Golf Course	
Outdoor Enterprise	
Indoor Enterprise	Club - 1 for each 100 sq. ft. floor area Recreation Facility - 1 for each 200 sq. ft. floor area
Private Club	
Shooting Range - Indoor Only	
Studio - Art	
Studio - Gymnastics/martial arts	
Community Facility - Activity Center	1 for each 200 sq.ft. of floor area
Community Facility - Detention and Corrections	
Community Facility - Government Administration and Courts	
Community Facility - Public Health Safety	

TABLE 1105.01A - REQUIRED PARKING SPACES	
USE	OFF-STREET PARKING SPACES REQUIRED
Overnight Lodging - Bed and Breakfast	1 per sleeping room or suite
Overnight Lodging - Boutique Hotel	
Overnight Lodging - Hotel	
Overnight Lodging - Limited Service	
Overnight Lodging - Resort	
Junk storage and sales	~~1 per 1,000 sq. ft. of gross building area~~ 1 space is required for every 1,000 sq. ft. of gross floor area for buildings up to 20,000 sq. ft. After the first 20,000 sq. ft. of building area, 1 space is required for every 5,000 sq. ft. of gross floor area for buildings between 20,001 sq. ft. to 120,000 sq. ft. After the 120,000 sq.ft. of building area,1 space is required for every 10,000 sq. ft. of gross floor area for buildings over 120,000 sq. ft.
Storage - Contractor	
Storage - Commercial Gases	
Storage - Self-Store	
Storage - Vehicular and Boat	
Warehouse - Large Format	
Warehouse - Small Format	
Air Transportation Services	1 for each 1,000 sq. ft. of sales area
Vehicle Care Services - Washes	2 per site
Vehicular Sales - Boats	1 per 1,000 sq. ft. of gross building area
Vehicular Sales - Automobiles	
Vehicular Sales - Motorcycles	
Vehicular Sales - Recreational Vehicles	
Mortuary	1 for each 50 sq. ft. floor space
Temporary Uses	As determined by the Planning and Zoning Administrator

SECTION 1105.03 SIGNS

TABLE 1105.03A PERMITTED PRINCIPAL SIGNS BY ZONE AND DISTRICT					
DISTRICT/ZONE	MONUMENT SIGN	PROJECTING SIGN	WALL SIGN	AWNING SIGN	ROOF SIGN
Olde Reynoldsburg Neighborhood District (ORD-N)	MU or NR				
Olde Reynoldsburg Commercial District (ORD-C)	X	X	X	X	X
Brice and Main Street District (BMD)	X	X	X	X	
East Main Street District (EMD)	X	X	X	X	
Community Commercial (CC)	X	X	X	X	
Residential Zones (SR and RM)	NE or NR	NR			
Innovation Zone (I)	X	X	X	X	
Sign Key: MU - Multi-Unit Development NR - Non-Residential Development, excluding home occupation NE - Neighborhood Entry Sign					

A. Purpose and Applicability. This section regulates the type, number, design, size, time of display, location, maintenance, and other characteristics of signs in order to: protect the public health, safety, and welfare in all zones and districts; promote clarity in sign communications; promote harmony between and among the physical characteristics of signs and the physical characteristics of surrounding land, structures, and other development features; and to promote attractive and orderly appearance in all districts. The provisions of this section shall apply to all existing signs, to all signs erected or installed after the effective date of this Zoning Code, and to any sign which replaces an existing sign or component thereof.

B. Zoning Sign Permits Required. Every sign, except those specifically exempted by the provisions of this section, shall only be erected or installed subsequent to and in conformance with the provisions of a zoning sign permit issued by the Planning and Zoning Administrator. The Planning and Zoning Administrator shall not be required to issue a zoning sign permit to any use or business that does not have a valid zoning certificate or that is otherwise not in compliance with the Zoning Code, Building Code or Property Maintenance Code. For the purposes of approving a sign in conformance with the Zoning Code, a zoning sign permit shall have the same effect as a zoning certificate.

C. Signs Requiring Permits

i. Signs in Zones and Districts. Signs shall be permitted in the respective districts as established in Table 1105.03A: Permitted Signs and as further provided in this section.

ii. Signs in Olde Reynoldsburg Districts. Subject to the approval of the Planning and Zoning Administrator or the Planning and Zoning Board, as applicable, in conjunction with the certificate of appropriateness process required under Section 1109.21, signs shall be permitted i n Olde Reynoldsburg Districts as established in Table 1105.03A and in conformity with the following specific provisions:

1. **Residential Signs – Olde Reynoldsburg Commercial District (ORD-C) and Olde Reynoldsburg Neighborhood District (ORD-N).** One (1) monument sign per entrance may be located on a lot or lots within a multi-dwelling unit development within the ORD-C or ORD-N. When located in the public right-of-way, all such signs shall be subject to a perpetual maintenance agreement and shall not be internally illuminated.
2. **Non-Residential Use or Mixed-Use Signs – ORD-C.** The following sign types shall be permitted to be displayed on structures or buildings utilized for non-residential or mixed-use purposes in conformity with the following specific provisions:

iii. Sign Lighting. The following types of lighting shall be permitted in the ORD-C: all exterior illuminated lighting types, except bulb surround (flashing or blinking), and neon colored signs.

iv. Changeable Copy Types. The following changeable copy types shall be permitted in the ORD-C: channel letters.

v. Principal Signs. A maximum of three (3) signs of any combination of the following sign types, with the exception of only permitting a monument sign to be one (1) of the three (3) permitted signs, shall be permitted per lot in the ORD-C in accordance with the following provisions:

1. Wall Sign. A wall sign may be erected on the wall of the building which most nearly parallels a street as determined by the Zoning Administrator. The total permitted area for any wall sign is two (2) square feet per lineal foot of building front facade or tenant space, as applicable. The total permitted wall sign area may be extended to areas of the building where a public entrance is located only. Any wall sign located in accordance with this subsection shall be attached parallel to the building wall, mounted on a raceway, or painted directly on a wall, provided no wall sign shall extend outward from the building wall more than twelve inches (12”). Where a building is located on a corner lot, ~~an~~ **one (1)** additional wall sign may be permitted on both front facade walls which parallel the intersecting streets **for a total of three (3) signs.** One front facade for corner lots can be utilized in calculating the maximum allowable sign square footage. Wall signs shall be composed of wood or metal frames with a face of wood, metal, polycarbonate, vinyl, acrylic or urethane materials.

2. **Projecting Sign.** A projecting sign constructed of wood, metal or urethane, including its mounting structure, may be mounted upon and be perpendicular to the wall of a building at a ninety (90) degree angle. The surface area of each face of such projecting sign shall be a maximum of six (6) square feet. It shall not project more than three feet (3') from the building façade, and shall not use a guy wire or angle iron support structure unless within the plane of the sign. A projecting sign shall be located no less than nine feet (9') above the sidewalk or ground level. Any applicant requesting a permit for a projecting sign which extends over a public right-of-way shall provide ~~for~~ a hold-harmless agreement with the City.
3. **Roof Sign.** Roof sign constructed of metal with a maximum surface area of eighty (80) square feet may be located on the roof of a principal structure located in the ORD-C. Such roof sign shall be setback a minimum of five feet (5') from the edge of the roof of the principal structure and may be illuminated with a direct light.
4. **Awning Signs.** A maximum of one (1) awning sign may be permitted in accordance with the provisions set forth under this subsection. All new awnings, or changes to awning colors shall be subject to a design and site plan review. Removal and replacement of awning materials that does not involve changes to the awning support structures shall be considered a sign face change. Changes to awning lettering that involve no material or color changes shall not require a zoning sign permit. Awning lettering may not exceed sixteen inches in height (16").
5. **Monument Sign.** One (1) monument sign with a base constructed of brick, stone, brick veneer or stone veneer may be installed in the ORD-C. The monument sign may be a maximum of six feet (6') in height with a maximum surface area of twenty-four (24) square feet. Any monument sign located in accordance with this subsection shall be setback a minimum of ten feet (10') from the front property line or easement line, as applicable.

vi. **Signs in Residential Zones (SR and RM Zoning Districts).** Subject to the approval of the Planning and Zoning Administrator or the Planning and Zoning Board, as applicable, in conjunction with the site plan and design review process required under Section 1109.17, signs shall be permitted in the SR and RM zones as established in Table 1105.03A and in conformity with the following specific provisions:

1. **Sign Lighting.** The following types of lighting shall be permitted in RM zones: exterior illuminated and gooseneck lighting. Sign lighting is not permitted in SR zones.
2. **Changeable Copy Types.** Changeable copy types are not permitted in SR and RM zones.
3. **Principal Sign Types.** The following sign types shall be permitted in the SR and RM zones in accordance with the following provisions:
4. **Neighborhood entry sign.** One (1) or more permanent ground signs may be located on a lot or lots within a subdivision or multi-family dwelling development. Any monument sign located in accordance with this subsection shall be set back a minimum of ten feet (10') from the property line, or easement line, as applicable. All such signs shall be subject to a perpetual maintenance agreement and shall not be internally illuminated.

5. **Flags.** Flags are permitted as a supplemental sign type in SR and RM zones.
6. **Real Estate Signs**. One (1) freestanding real estate sign per lot frontage is permitted on premises for individual lots or building until such lots are sold or rented in accordance with the following provisions:
   (a) Maximum Sign Face. Six (6) square feet.
   (b) Maximum Height. Five (5) feet.
   (c) Location Requirements. At least one foot from street right of way and at least five feet from side or rear lot lines.
   (d) Time Restrictions. Sold signs shall be removed within five (5) calendar days from closing on the sale of the subject property.
7. **Temporary Signs.** Temporary signs are permitted provided that any temporary sign may have a maximum area of two (2) square feet and may be located a maximum of three feet (3') above grade. Any temporary sign located in accordance with these provisions shall be constructed of vinyl with metal supports.

vii. **Signs in Commercial and Mixed-Use Zones. (BMD/EMD Districts, CC Zone, and Innovation Zone).** Subject to the approval of the Planning and Zoning Administrator ~~or the, as applicable,~~ in conjunction with the site plan and design review process required under Section 1109.17, signs shall be permitted in commercial and mixed-use zones as established in Table 1105.03A and in conformity with the following specific provisions:

1. **Wall sign.** Two (2) wall signs may be erected on the wall of the building which most nearly parallels a street as determined by the Zoning Administrator. The total permitted area for any wall sign is two (2) square feet per lineal foot of building front facade or tenant space, as applicable. The total permitted wall sign area may be extended to areas of the building where a public entrance is located only. Any wall sign located in accordance with this subsection shall be attached parallel to the building wall, mounted on a raceway, or painted directly on a wall, provided no wall sign shall extend outward from the building wall more than twelve inches (12"). Where a building is located on a corner lot, ~~an~~ **one (1)** additional wall sign may be permitted on both front facade walls which parallel the intersecting streets **for a total of three (3) signs.** One front facade for corner lots can be utilized in calculating the maximum allowable sign square footage. Wall signs shall be composed of wood or metal frames with a face of wood, metal, polycarbonate, vinyl, acrylic or urethane materials.
   a. One (1) Pickup sign is permitted for any use which utilizes pickup of goods from the existing business. The pickup sign should be located near the pickup area. To utilize this sign, a designated pickup area must be identified on the site.
2. **Projecting Sign.** One (1) projecting sign, including its mounting structure, may be mounted upon and be perpendicular to the wall of a building and shall not extend beyond any other dimension of the wall. It shall not project more than four feet (4') from the wall, and shall not use a guy wire or angle iron support structure unless within the plane of the sign. A projected sign shall be located no less than eight feet (8') above the sidewalk or ground level and no closer than six feet (6') to a street's pavement or curb. Any applicant requesting a permit for a projecting sign which extends over a public right-of-way shall provide ~~for~~ a hold-harmless agreement with the City.

3. Awnings. Awnings may be permitted in addition to or in lieu of a wall sign. Where awnings are used as the primary sign identification, the standards for wall signs shall apply. All new awnings, or changes to awning colors in the design review districts shall be subject to a certificate of appropriateness. Removal and replacement of awning materials that does not involve changes to the awning support structures shall be considered a sign face change. Changes to awning lettering that involve no material or color changes shall not require a zoning sign permit. Awning lettering may not exceed twelve inches (12") in height.

4. Monument Sign. One (1) monument sign with a base constructed of stone, brick, stone veneer or brick veneer may be installed in commercial or mixed-use zones. The monument sign may be a maximum of six feet (6') in height with a maximum surface area of twenty-four (24) square feet. Any monument sign located in accordance with this subsection shall be setback a minimum of ten feet (10') from the front property line or easement line, as applicable.

(a) Monument signs for parcels exceeding three (3) acres, and having two or more independent land uses, not accessory land uses to the principle land use; may have a monument sign identifying the complex name, along with one (1) additional monument sign at every point of ingress and egress location onto the overall development from the public right-of-way.

viii. Signs in Open Space/Schools Zone. Signs in the OS zone shall be subject to review and approval by the Planning and Zoning Administrator or the Planning and Zoning Board as applicable.

D. Supplemental Signs Non-Residential Districts. In addition to the above-listed principal sign types the following supplemental sign types are exempt from zoning sign permits and may be permitted in non-residential districts, as specified below, in accordance with the following provisions:

i. Banner Signs. In all non-residential districts a maximum of one (1) banner sign may be permitted in accordance with the provisions set forth under this subsection. Banner signs shall be a maximum of thirty-two (32) square feet and shall be located a maximum of eight feet (8') above grade. The display of banners shall be allowed for no more than forty-five (45) days per year.

ii. Flags. Flags are permitted as a supplemental sign type in all non-residential districts.

iii. Sandwich Board Signs. A maximum of one (1) sandwich board sign may be permitted in accordance with the provisions set forth under this subsection. Sandwich board signs shall have a maximum sign face area of six (6) square feet with a maximum board width of twenty-four inches (24") and a maximum board height of thirty-six inches (36"). Any sandwich board located in accordance with this subsection shall be constructed of wood and shall be displayed for a maximum of twelve (12) hours per day.

iv. Real Estate Signs. Any combination of free-standing, wall or window real estate signs may be located upon any non-residential property for a total of three (3) signs, provided that such signs do not exceed the permitted dimensions for the corresponding sign-type in the zoning district that is applicable to the subject property. Notwithstanding anything to the contrary contained herein, if freestanding signs are not permitted in the zoning district applicable to the subject property, then one free-standing sign not exceeding seven (7) feet in height with a maximum sign face of twenty (20) square feet may be located upon the subject property. All real estate signs located in accordance with this subsection shall be removed within five (5) calendar days from closing on the sale of the subject property.

v. Window Sign. The total square footage of all window signs may not exceed more than thirty percent (30%) of the total surface area of the window or windows on which such sign or signs are placed. Any object located within (3) three feet of the window pane that obstructs the interior view of any commercial building will be subject to all applicable window sign regulations. Any window sign located in accordance with this subsection shall be located on a window or windows on the front façade of the principal building.

vi. **Temporary Signs.** Temporary signs are permitted provided that any temporary sign may have a maximum area of two (2) square feet and may be located a maximum of three feet (3') above grade. Any temporary sign located in accordance with these provisions shall be constructed of vinyl with metal supports.

E. Generally Applicable Regulations for all Signs.

i. **Sign height.** The height of a sign shall be measured from the finished grade which shall be defined as that point where the grade line intersects the front wall of the building. The height of a sign may not be artificially increased beyond the permitted height by placement of the sign on an earth mound.

ii. **Sign setbacks.** Signs shall be located in conformity with the side and rear yard requirements of the applicable zone or district.

iii. **Sign colors.** No sign requiring a permit under the provisions of this chapter shall contain more than four (4) colors, including black and white. Where a corporate logo is used, the logo shall count as one of the four (4) colors. Where a multi-tenant sign is present, no individual sign face panel may contain more than four (4) colors.

iv. **Construction.** All signs shall be properly constructed and maintained to ensure that no safety hazard is created. All signs shall be built in conformity with the requirements of the Building Code and the procedures of the Building Division.

v. **Location.** Except as otherwise provided in this Zoning Code, no sign or any part of any sign shall be placed in, over or extend into any public right-of-way.

vi. **Lighting.** The level of illumination emitted or reflected from a sign shall not be so intense as to constitute a safety hazard to vehicular movement on any street from which the sign may be viewed, as determined by an average person. Illuminated signs shall be constructed and maintained so that the source of illumination is shielded or otherwise prevented from beaming directly onto adjacent lots or streets.

vii. **Concealment of Wires and Components.** Irrespective of the sign type permitted under this section, all wiring and components of such sign shall be concealed from public view.

viii. **Contractor Identification.** All signs shall be plainly marked with the name of the person or company that installed the sign.

ix. **Maintenance and Repair Required:**

1. The owner of a sign shall repair, support, clean, repaint, or perform any maintenance service necessary to maintain the reasonable and proper appearance and condition of the sign. Whenever the Planning and Zoning Administrator determines a sign to be in need of repair, support, cleaning, repainting or other maintenance, he/she may issue a notice to the sign owner to complete the needed repairs or maintenance.
2. All sign face panels shall be intact and free from cracks. No sign shall be permitted to exist without an intact face panel. Whenever the Planning and Zoning Administrator determines that a sign face is cracked or not intact, he/she may issue a notice to the sign owner to replace the sign face.
3. If the Planning and Zoning Administrator determines that the existing condition of the sign creates an immediate hazard to the public health, safety or welfare, he/she shall issue a

notice to the owner requiring the sign to be removed immediately.

F. Nonconforming Signs.

i. An existing sign that does not meet the requirements of this chapter shall be deemed a nonconforming sign.

ii. A nonconforming sign shall exist and be maintained in accordance with the following:

1. **For all signs, except Wall, Projecting and Awning signs:** The size and shape of the sign structure shall not be altered, except that sign face panels may be replaced.

2. **For Wall, Projecting, and Awning signs only: The size and shape of the sign structure – which includes the sign face, sign panels, and the sign cabinet – shall not be altered. Neither the width, nor the height, nor the square footage of the nonconforming sign shall be increased, and the replacement sign shall not exceed the width, height and square footage respectively of the existing nonconforming sign. All other components of the zoning code applicable to signage must be met.**

3. If damage occurs to a sign to the extent of sixty percent (60%) or more of either the structure or its replacement cost at the time of destruction, the sign shall be brought into compliance with the provisions of this Zoning Code.

iii. A nonconforming sign shall not be structurally relocated or replaced, unless the new sign is in compliance with this chapter.

G. Abandoned Signs and Sign Faces.

i. A sign or sign face shall be considered abandoned when:

1. The sign or sign face remains after the discontinuance of a use. A use is considered to be discontinued if it is closed to the public for at least ninety (90) consecutive days.

2. The sign or sign face is not maintained in accordance with the provisions of this chapter and the owner of the sign has not complied with notices to maintain the reasonable and proper appearance and condition of the sign.

ii. Whenever the Planning and Zoning Administrator determines that a sign has been abandoned as defined in this chapter, the right to maintain and use such a sign shall terminate immediately. Physical removal of a sign may be accomplished pursuant to the nuisance abatement procedures and ordinances of the City.

iii. Whenever the Planning and Zoning Administrator determines that a sign face is abandoned as defined in this chapter but the existing sign conforms to the Zoning Code, he/she may issue a notice to the sign owner to remove the abandoned panel and replace it with a blank. This shall not apply to signs maintained on lots that do not have any existing structure.

iv. Whenever the Planning and Zoning Administrator determines that a sign face in a multi-tenant sign is abandoned but other panels on the sign are not abandoned, he or she may issue a notice to the sign owner to remove the abandoned panel and replace it with a blank.

H. Special Sign Regulations for Gasoline Stations. Gasoline stations present several unique challenges for signage purposes due to industry-wide advertisement of the price of fuels for sale. In order to address these unique challenges, ground signs on lots with gasoline stations shall be permitted to incorporate electronic signage. Exempted ground signs of this type shall be subject to the following special regulations:

i. The electronic signage shall take up no more than one-third (1/3) of the sign area permitted by

this chapter.

ii. The electronic signage shall consist of a solid background with only one illuminated color per electronic panel.

iii. Such signs shall be subject to all other sign regulations of this chapter, and of the applicable zone or district.

SECTION 1105.05 ACCESSORY STRUCTURES

A. Generally Applicable Regulations for Accessory Uses and Accessory Structures. An accessory use or accessory structure shall be permitted in any district provided that:

i. It is incidental to and customarily found in connection with the main use or main building permitted in the district;

ii. It is subordinate to and serves the main use or building;

iii. It is subordinate to the main use or building in ground area, floor area, extent, and purpose;

iv. It is located on the same lot as the main building or main use which it serves; and

v. It contributes to the comfort, convenience, or necessity of occupants, business, or industry of the main use or main building served.

vi. Except as otherwise provided by this Zoning Code, a use or structure which is interpreted by the Planning and Zoning Administrator or by the Planning and Zoning Board to be an accessory use or accessory structure may only be established or constructed on a lot having a legally existing main use or main building.

vii. Except as otherwise provided in this Zoning Code, an accessory structure:

1. Shall not be located closer to any public right-of-way than the main building and shall not be located in the required front yard;
2. Shall not be located closer than three feet (3FT) to any rear lot line and not closer than three feet (3FT) to any side lot line **with the exception of Dwelling – Attached Single-Family land uses, which would have a zero foot (0 FT) side lot line setback;**
3. Shall not be located closer than ten feet (10FT) to a main building (applies only to sheds);
4. Shall not occupy more than twenty percent (20%) of the required rear yard;
5. In residential districts, the lot coverage of accessory structures shall not be more than fifty percent (50%) of the finished floor area of the main structure;
6. In commercial districts, open-sided accessory structures such as pergolas are permitted in the required front or side yard;
7. Except for accessory dwelling units, where permitted, shall not contain facilities for dwelling purposes; and
8. Shall not exceed fifteen feet (15FT) in height.

viii. For the purposes of this section, a storage building equal to or less than fifty square feet (50SF) i n area, not permanently attached to the ground, is not considered a structure. Only one **(1)**

(1) such storage building may be placed on a lot without a zoning certificate. Any additional buildings shall be considered accessory structures and subject to the provisions of this section. Storage buildings of this type shall be located behind the main structure and shall conform with the minimum lot line setbacks listed in this section.

ix. All accessory structures consistent with applicable floodplain regulations are permitted at the discretion of the Floodplain administrator

B. Accessory Dwelling Units

i. Except as otherwise provided by this Zoning Code, a use or structure which is interpreted by the Planning and Zoning Administrator or by the Planning and Zoning Board to be an accessory dwelling unit may only be established or constructed on a lot having a legally existing main use or main building.

ii. Except as otherwise provided in this Zoning Code, an Accessory Dwelling Unit:

1. Shall not be located any closer to any public right of way than the main building and shall not be located in the required front yard;
2. Shall follow the side yard setbacks set forth in the applicable zoning district for the primary dwelling unit;
3. Shall be no closer than 8 feet (8FT) from the rear lot line;
4. A detached ADU shall not be located closer than ten feet (10FT) to a main building;
5. Shall not occupy more than 20% of the required rear yard;
6. The ADU may be no larger than six hundred square feet (600SF) or 50% of the size of the primary dwelling unit whichever is less;
7. ADU's that are attached to the primary dwelling unit are not permitted to be located in a portion of the primary dwelling unit that encroaches a required yard setback;
8. Exterior finish materials must be compatible with existing primary dwelling unit;
9. Only one entrance is allowed and must be located on the primary façade facing the street.

C. Garage Standards

i. All garages in a residential district facing the street shall not be located more than eight (8) feet in front of the front façade of the structure.

ii. **In the Suburban Residential District Only.** No garage door or combination of garage doors facing the street shall occupy more than sixty percent (60%) of the width of the ground level façade.

D. Service Structures

i. Electrical transformers, generators, storage tanks, utility vaults and heating or cooling units which extend beyond the surface may be built in the rear and side yard.

ii. Service structures shall maintain a three (3) foot setback from all lot lines. With the exception of Dwelling – Attached Single-Family land uses, which would have a zero foot (0 FT) side lot line setback.

SECTION 1105.06 RESIDENTIAL DESIGN STANDARDS

A. Purpose and Intent. The following design standards are intended to enhance the character, aesthetics, and architectural consistency of residential development in the Suburban Residential (SR) and Residential Medium (RM) Districts.

B. Entry to Residential Buildings

i. Entries shall be visible from the front of the building and shall **be** connected to a paved driveway or sidewalk by a clearly delineated pedestrian walkway.

ii. At least two building materials should be used for exterior walls (excluding trim and cornices) on all building facades with road frontage.

C. Building Articulation and Openings

i. All dwellings must incorporate design features such as offsets, balconies, projections, recesses or covered entrances, windows, doors, window reveals, or similar elements to create horizontal and vertical relief and avoid box~~-life~~ **-like** forms.

ii. Incorporate at least three of the following features, consistent in design style, that provide articulation and design interest consistently throughout the project:

1. Decorative trim elements that add detail and articulation, such as door surrounds with at least a two-inch depth, decorative eave detailing, belt courses;
2. Pitched / variegated roof forms;
3. Roof overhangs at least 12 inches deep;
4. Variety in use of materials, especially at ground level stories, for detailing at porches / entry areas, paneling at bays or at special parts of the building;
5. Building base (typically bottom three feet) that is faced with a stone or brick material, or is delineated with a channel or projection; and/or
6. Railings with a design pattern and materials such as wood, metal, or stone which reinforces the architectural style of the building.

D. Garage Standards.

i. Side entry garages shall have windows on the front facing wall.

ii. Garages in a residential district facing the street shall not be located more than eight (8) feet in front of the front façade of the structure.

iii. For detached single-family only: No garage door or combination of garage doors facing the street shall occupy more than sixty percent (60%) of the width of the ground level façade.

E. Driveway Standards

i. Driveways shall be located at least 3 feet away from the property line unless the driveway is extended into the nearest front private or public right-of-way. For detached single-family and detached two-family only.

F. Building Orientation, Height, and Form

i. Divide massing of a structure by limiting building length, or designing buildings with two or more of the following special features to break up building bulk, including:

1. Horizontal and vertical setbacks and stepbacks (instead of a long flat wall);
2. Changes in roof form and height; and/or
3. Major full-height recesses (typically at least 10 feet deep) along the length of the building that successfully break the building into smaller discrete masses.

G. Architectural Design/Materials

i. Avoid combining structural and decorative characteristics from different architectural styles into a single building.

ii. Incorporate the surrounding architecture when building in an established neighborhood.

iii. Utilize durable, high-quality building materials that will last for the life of the building.

iv. Use exterior siding materials such as stucco, wood siding, masonry, tile, wood shingles, metal panels, and glass panels. Vinyl siding and other plastic materials may be used only in conjunction with other natural materials. Scored plywood (T1-11 or similar), corrugated metal, and cinderblock used for exterior cladding are not permitted.

H. Windows

i. Design window recesses, window trim, and other window elements to create architectural interest. Incorporate at least one of the following window features throughout the project:

1. Minimum depth of at least two inches from glass to exterior of trim;
2. Minimum depth of at least six inches from glass to wall edge around windows if there is no trim (this is only appropriate for certain architectural styles such as Spanish Revival or Modern); and/or
3. Decorative trim elements that add detail and articulation, such as window surrounds with at least a two-inch depth.

I. Remodeling and Additions.

i. Design remodeling projects and additions such that the exterior appearance of the building demonstrates design integrity in the following ways:

1. Use complementary materials for exterior facades;
2. Use window types that are similar in size, shape, and proportion of the windows on the original building and are characteristic for the architectural style; and/or
3. Use consistent roof materials and roof forms.

ii. Do not remove or cover high-quality original finish materials and ornamentation integral to the design integrity of the building.

See Attachment D

SECTION 1105.07 LANDSCAPING AND BUFFERING

A. Purpose and Intent. These standards are intended to establish landscaping regulations that:

i. Improve the aesthetic appearance of setback areas, common open space areas, public rights-of-way and off-street vehicular parking areas;

ii. Encourage the preservation of existing trees and natural features;

iii. Promote compatibility among different land uses;

B. Application. The Planning and Zoning Administrator may require a landscape plan and/or tree survey to be submitted in conjunction with any application for a zoning certificate, a variance, a conditional use permit, a similar use determination, a subdivision plat, or a site plan and design review approval. Such landscape plan and/or tree survey shall include the following:

i. The present location, size, and description of all existing major trees, with a designation of existing major trees sought to be removed. A major tree is a tree that is 18 inches (18") or greater at DBH (Diameter at Breast Height).

ii. The location, size and description of landscaping materials proposed to be placed on the lot in order to comply with this section.

iii. The location and size of any structures presently on the lot, and those proposed to be placed on the lot.

C. General Landscape Provisions.

i. When required by the Planning and Zoning Administrator, a landscape plan shall be approved in accordance with this chapter prior to granting a zoning certificate, a variance, a conditional use permit, a similar use determination, a subdivision plat, or a site plan and design review. A zoning certificate is not required for the addition of pervious surface including grass, mulched groundcover, other planted areas, and/or permeable or pervious pavers or paving that facilitates the infiltration of water into the soil.

ii. No landscaped area shall be used for display and/or storage purposes.

iii. The species, location and spacing of trees and shrubs planted in all public rights-of-way and on all sites shall be subject to approval by the Planning and Zoning Administrator.

iv. No Certificate of Occupancy shall be granted until all conditions herein have been met; however, in the event landscaping cannot be completed due to weather conditions, or peculiar conditions related to the development of the subject property such as conditions related to phased development, the applicant shall provide financial security, in a form acceptable to the City, in the amount of one hundred twenty-five percent (125%) of the cost of materials and installation of all remaining landscaping to be completed and an estimate of such costs in order to be eligible for a Certificate of Occupancy.

v. When phasing development upon a property, a proportionate share of landscaping acceptable to the City shall be installed and maintained with each phase based on the size of the proposed phase and shall be considered completed for the purposes of these regulations when such proportionate share of landscaping has been installed, unless special circumstances warrant the installation of a greater amount of landscaping with any phase.

vi. The developer and/or property owner shall be responsible for the installation and maintenance of all landscaping, buffering, perimeter treatment and screening improvements in a healthy condition. This provision shall also apply to single-family and two-family dwellings.

vii. Bare earth shall not be considered landscaping or a landscaped area for the purposes of meeting the landscape requirements herein. Land area shall be considered "covered" if it is used for growing grass, shrubs, trees, plants or flowers, or if covered by decorative rock, stone or wood chips, or otherwise landscaped as provided herein. This provision shall also apply to single-family and two-family dwellings.

viii. These landscaping provisions are not intended to require multiple or overlapping setbacks, buffers and perimeter treatments. When more than one (1) such standard applies, that standard which results in the higher landscaping or buffering requirement shall apply. Buffering and perimeter treatments may be located within the required setbacks and may be counted toward required open space except not as usable open space.

ix. Utility easements which conflict with required buffer yards, perimeter treatment, parkway or median standards may require an alternative design approach to address such conflicts.

D. Tree Preservation. Unless exempted in accordance with this subsection, all existing major trees shall be preserved. The Building Inspector may approve the cutting down, removal or destruction of a major tree/trees when the tree or trees interferes with the proper development of the lot, provided that the lot is the subject of an application for approval of a zoning certificate, development plan approval or variance, such application is approved and one of the following applies:

i. The tree or trees will be located within the public right of way.

ii. The subject property cannot be arranged in a manner to avoid removal of the tree or trees at the same time permitting the desirable and logical development of the lot.

iii. The tree/trees are located within the proposed driveway to service a single-family home, and such driveway cannot otherwise be relocated.

iv. The tree is damaged or diseased or can be proven to be of poor quality.

v. The tree/trees are an undesirable species in its present location.

TABLE 1105.07CA - CREDIT FOR EXISTING TREES (IN AGGREGATED INCHES)

CALIPER AT FOUR AND HALF FEET (4.5') ABOVE GROUND	MAXIMUM % OF SAME SPECIES NUMBER OF TREE CREDITS
20 total inches	4 (equal to 4 trees)
13 - 19 total inches	3 (equal to 3 trees)
8 - 12 total inches	2 (equal to 2 trees)
2 - 7 total inches	1 (equal to 1 trees)

moved to the correct location

E. Tree Replacement. Each existing major tree removed in accordance with subsection (d) above shall be replaced with one (1) tree, having a minimum caliper of two inches (2") as measured one foot (1') above ground level.

F. General Landscape Standards.

moved to the correct location

i. The following standards shall ensure that landscaping is used to improve the aesthetic quality of a development or site in addition to providing a functional purpose and year-round interest and/or screening.

ii. The size of landscape elements and materials shall meet minimum standards and be consistent with the size of the project and any existing streetscape. Minimum plant sizes are as follows:

MINIMUM PLANT SIZE	
PLANT TYPE	PLANT SIZE
Deciduous trees	Two inches (2") caliper, measured one foot (1') above ground
Ornamental trees	One and one half inches (1 1/2") caliper, measured one foot (1') above ground
Evergreen trees	Six feet (6') in height
Shrubs	Eighteen inches (18") in height or eighteen inches (18") spread, depending on growth characteristics

iii. Landscaping in parking areas, driveway entrances and intersections shall be designed to meet the minimum clear sight triangle as defined in the Zoning Code.

iv. Monoculture, or the extensive use of a single species of trees, shall be limited in order to minimize the potential for disease or pests to strike a particular species resulting in significant same-species loss. The following limits shall apply:

MAXIMUM USE OF SAME SPECIES	
NUMBER OF TREES ON SITE	MAXIMUM % OF SAME SPECIES
10-19	50%
20-39	33%
40-59	25%
Over 60	15%

moved to the correct location

v. Plant materials used in conformance with the provisions of this section shall conform to the specifications of the American Association of Nurserymen (AAN) for number one grade and shall have all wire and twine removed prior to planting. All trees shall be balled and burlapped or equivalent. Grass sod shall be clean and free of weeds and noxious pests or diseases. Plant materials which are known to be intolerant of the area in which they are proposed to be installed, or whose physical characteristics may be injurious to the public shall not be specified for use.

vi. If any trees or other plant materials die or become diseased and must be removed, the property owner shall be responsible for replacing all materials that were removed. In the event that existing preserved trees die or become diseased and must be removed; the replacement shall be based on the tree credits Table 1105.07A. If trees or shrubs are removed for convenience purposes, the property owner shall be responsible for replacing all removed materials elsewhere on the site. If adequate space is not available on the site, the replacement shall occur at a location approved by the City. Upon issuance of a citation, corrective action shall be completed within sixty (60) days unless the Development Director or designee determines that weather constraints require one additional sixty (60) day period. Failure to meet the requirements of this section shall constitute a violation of this Zoning Code and the penalty requirements shall apply.

vii. Trees and shrubs shall be planted so that at maturity they do not interfere with utility service lines and traffic safety. Trees planted near public sidewalks shall be installed in such a manner as to prevent physical damage to sidewalks, curbs, gutters, pedestrian ways, bike paths and other public improvements. A protective tree grate and vault shall be provided when trees are planted in paved areas such as plazas or sidewalks. This provision shall also apply to single-family and two-family dwellings.

viii. When an applicant presents that the placement of all trees and shrubs as required in this section would create an impractical landscape effect, a portion of the trees and shrubs may be located in alternative locations on the same site, subject to approval by the Development Director or designee.

ix. In no event shall a landscaped setback be less than six feet (6') in width, nor shall the width of the landscaped setback be inadequate to allow for the installation and healthy growing condition for the required amount of trees or shrubs.

x. In order to promote efficient irrigation and maintenance measures, berms shall not exceed a slope of three to one (3:1) and shall be graded to appear as smooth, rounded, naturalistic forms.

xi. To insure that landscape materials do not constitute a driving hazard, a clear "sight triangle" shall be observed at all street and access drive intersections. In the case of a city street intersection, the sight triangle shall consist of the area between points twenty feet (20') along both intersecting streets from their respective edge of pavements. Ground cover, perennials, shrubs and trees shall be permitted within the sight triangle provided that perennials and shrubs do not exceed a maximum height of eighteen inches (18") and tree trunks shall be devoid of limbs to a height of eight feet (8').

G. Street Tree Requirements. It shall be required in all zones and districts that applicants plant trees along public streets of their development. Trees shall be planted in such manner, type, quantity and locations as approved by the Planning and Zoning Administrator or the Planning and Zoning Board in conjunction with the site plan and design review process, as defined by the following conditions, and that any undeveloped street or existing street with undeveloped frontage shall conform to these requirements at the time of the development.

i. Trees planted shall be on the list of approved street trees maintained by the City of Reynoldsburg.

ii. The minimum spacing between this and other trees shall be 35 feet for large trees (mature height of fifty feet (50') or more), twenty-five feet (25') for medium trees (mature height of between thirty and fifty feet (30'-50') and fifteen feet (15') for small trees (range from ten to thirty feet (10'-30') at maturity).

iii. The maximum spacing between trees shall be forty-five feet (45') for large trees, thirty-five feet (35') for medium trees, and twenty-five feet (25') for small trees.

iv. The minimum distance between the tree and the edge of the street shall be two and one-half feet (2 ½') for a large tree, two feet (2') for medium tree and one and on-half feet (1 ½') for a small tree. In areas where a sidewalk exists or is proposed, the minimum distance between the tree trunk and both the edge of the street and the sidewalks shall be two feet (2') for a large tree, two feet (2') for a medium tree and one and one-half feet (1 ½') for a small tree, as defined in approved street tree list.

v. Trees shall be located so that a twenty-foot (20') sight triangle is maintained at street intersections.

vi. A small tree shall be used when planting under or within ten (10) lateral feet of overhead utility wires. A small or medium tree shall be used when planting within ten to twenty (10-20) lateral feet of overhead utility wires.

vii. At the time of platting, the developer shall develop a street tree plan that establishes the species and size of trees to be planted along the streets of the proposed subdivision.

viii. The developers shall be required to maintain all trees for a period of one (1) year after any installation and replace any tree which fails to survive or does not exhibit normal growth characteristics of health and vigor within such one (1) year period. Upon completion of a street tree planting, the landscape contractor shall contact the Department of Development for a preliminary inspection. The one-year guarantee period shall begin after the approval of the Department of Development. A final inspection shall be made at the end of the guarantee period. All trees not exhibiting a healthy, vigorous growing condition, as determined by the city's inspection, shall be promptly replaced at the expense of the developer. Upon replacement, the one-year guarantee period shall recommence for those materials having been replaced.

ix. All street trees along any one street shall be of the same species and variety to promote a continuous landscape treatment. A change in variety will only be permitted at intersections and other logical beginning and ending points.

x. The minimum trunk caliper measured one foot (1') above the ground for all street trees shall be no less than two inches (2").

H. Interior Lot Landscaping.

i. For all new construction or land development for which a building permit and/or a zoning certificate is required, trees shall be provided for within the structure-related property lot lines, equal to or in excess of the following total tree trunk diameters (as measured one foot (1') from the ground level) for the specified building ground coverage square footage or land area square footage, by building and/or land use type, as follows:

1. All residences and residential land uses, per dwelling unit, there must be planted one-half inch (1/2") in trunk diameter for everyone 3,000 square feet of lot size or fraction thereof, with a minimum of two inches (2") of total trunk diameter.
2. All commercial structures, including commercial-related parking, loading and trash storage areas, and all industrial, warehouse, and storage uses and their associated parking, loading, and trash storage areas:
   (a) Up to twenty thousand (20,000) square feet: one inch (1") trunk diameter for every two thousand (2,000) square feet or fraction thereof with a minimum of two inches (2") of total trunk diameter.
   (b) Twenty thousand and one to fifty thousand (20,001 - 50,000) square feet: a total trunk diameter of ten inches (10"), plus one-half inch (1/2") of trunk diameter for every two thousand (2,000) square feet over twenty thousand (20,000) square feet or fraction thereof.
   (c) Over fifty thousand (50,000) square feet: a total trunk diameter of twenty inches (20"), plus one inch (1") of trunk diameter for every four thousand (4,000) square feet over fifty thousand (50,000) square feet or fraction thereof.

Removed sections 1105.07.H.i.2.c.1, 1105.07.H.i.2.d, 1105.07.H.i.2.e, and 1105.07.H.i.2.f.

See Attachment Sheet (A)

ii. Existing healthy trees and shrubs shall be preserved and incorporated into the overall site and landscape design to the maximum extent practical as determined by the City. Existing trees may be credited toward minimum tree planting requirements as follows:
   1. Existing trees, which are preserved, may be credited toward the tree planting requirements of this section according to Table 1105.057A - Credit for Existing Trees. Tree credits shall be given as long as all other provisions and the intent of this Zoning Code are met. Fractional caliper measurements shall be attributed to the next lowest category.
   2. No credit shall be given for existing preserved trees that are:
      (a) Not located on the actual development site;
      (b) Not properly protected from damage during the construction process;
      (c) Prohibited species under the caliper size of thirteen inches (13") measured at four and one-half feet (4 ½') above the ground; or
      (d) Dead, dying, diseased, or infested with harmful insects.

iii. In order to apply for credit, existing trees must be protected during construction. All existing trees shall be protected by the placement of an orange construction fence around the perimeter of the tree/trees. In order to protect the root system of the existing trees, said fence shall be installed at a minimum radius from the trunk. The minimum shall be one foot (1') of radius per one inch (1") of caliper of the tree. (ex. On a six inches (6") diameter tree, the fence shall be placed a minimum of six feet (6') from the trunk of the tree.)

iv. No new tree plantings shall be required if existing trees to remain on the site after development, and the aggregate trunk sizes of such trees, meet or exceed the requirements as set forth above.

v. Any combination of existing and new trees may be used to meet the requirements of this section.

I. Property Buffer Requirements.

i. **Grass or Ground Cover Required.** Grass or ground cover shall be planted on all portions of the required buffer not occupied by other landscape material. Trees do not have to be equally spaced but may be grouped. All landscape requirements shall be met by the applicant if his/her property is contiguous to property fully developed prior to the passage of this chapter. A landscape plan meeting the requirements of this section shall be approved by the Planning and Zoning Board or the Planning and Zoning Administrator in conjunction with the site plan and design review process before the commencement of construction on the subject property.

TABLE 1105.075B: SUMMARY OF BUFFER REQUIREMENTS

ZONE OR DISTRICT REQUIRING BUFFER	ADJACENT ZONE OR DISTRICT TO REQUIRED TO PROVIDE BUFFER	BUFFER REQUIREMENTS
SR or RM	ORD-C, EMD, or BMD	• 10 foot (10') buffer along all common boundaries; • One (1) tree for every forty feet (40') of linear boundary or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
SR or RM	CC	• 15 foot (15') buffer along all common boundaries; • One (1) tree for every forty feet (40') of linear boundary or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
Any residential use in any zoning district	Any non-residential use in SR or RM	• 5 foot (5') buffer along all common boundaries; • One (1) tree for every fifty feet (50') of linear boundary or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
SR, RM, or residential use in other zoning district	I	• 15 foot (15') buffer along all common boundaries; • One (1) tree for every twenty feet (20') of linear boundary or fraction thereof; • Continuous ten foot (10') high planting, hedge, fence, wall, earth mound or combination thereof.
Any zone (except for Innovation)	Adjacent freeway or arterial	• Twenty feet (20') for residential zones and fifteen feet (15') for all other zones adjacent to a freeway or arterial • One (1) tree for each thirty feet (30') of linear boundary, or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
Any zone (except for Innovation) adjoining a railroad	Any property with a railroad	• Twenty feet (20') for residential zones and fifteen feet (15') for all other zones adjacent to railroad boundaries; • One (1) tree for each thirty feet (30') of linear boundary, or fraction thereof; • Continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.

moved to the correct location

ii. **Buffer Requirements.** When one zoning classification abuts another zoning classification, a minimum buffer zone shall be required as follows:

1. Any residential zone adjoining the EMD, BMD, or ORD-C; required buffer zone is ten feet (10') adjacent to all common boundaries except street frontage and shall include one (1) tree for each forty feet (40') of linear boundary, or fraction thereof, and a continuous six foot (6') high planting, hedge, fence, wall, earth mound, or combination thereof.
2. Any residential zone adjoining the CC required buffer zone is fifteen feet (15') adjacent to all common boundaries except street frontage and shall include one (1) tree for each forty feet (40') of linear boundary, or fraction thereof, and a continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
3. Any residential use adjoining a property located in a residential zone operating with a conditional use; required buffer zone is fifteen feet (15') adjacent to all common boundaries except street frontage and shall include one (1) tree for each forty feet of linear boundary, or fraction thereof, and a continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
4. Any residential zone or any residential use in any zoning classification adjoining an Innovation (I) District required buffer zone is twenty feet (20') adjacent to all common boundaries except street frontage and shall include one (1) tree for each twenty (20) feet of linear boundary, or fraction thereof, and a continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
5. Any zone adjoining a freeway or arterial street prohibiting driveways; required buffer zone is twenty feet (20') for residential zones and fifteen feet (15') for all other zones adjacent to a freeway or arterial and shall include one (1) tree for each thirty feet (30') of linear boundary, or fraction thereof, and a continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.
6. Any zone (except Innovation) adjoining a railroad; required buffer zone is twenty feet (20') for residential zones and fifteen feet (15') for all other zones adjacent to railroad boundaries and shall include one (1) tree for each thirty feet (30') of linear boundary, or fraction thereof, and a continuous six foot (6') high planting, hedge, fence, wall, earth mound or combination thereof.

J. Parking Area Landscaping Standards.

i. Parking lots containing more than six thousand (6,000) square feet of area or twenty (20) or more vehicular parking spaces, whichever is less, shall provide interior landscaping of the peninsular or island types of uncompacted, well-drained soil that contains a minimum of six inches (6") of top soil mix, as well as perimeter landscaping.

ii. For every ten (10) parking spaces or fraction thereof, the applicant shall provide not less than two hundred (200) square feet of interior landscaped parking lot areas containing at least one (1) tree with a minimum diameter of two inches (2") and four (4) shrubs.

iii. The minimum landscape area permitted shall be two hundred (200) square feet with a minimum planting width of ten feet (10').

iv. In order to encourage the required landscape areas to be properly dispersed, and to break up large expanses of parking, no individual landscape area shall be larger than five hundred (500) square feet in size in vehicular use areas less than thirty thousand (30,000) square feet and no individual landscape area shall be larger than two thousand (2,000) square feet in vehicular use areas over thirty thousand (30,000) square feet. Individual landscape areas larger than above are permitted as long as the additional area is in excess of the required minimum total.

v. All parking lots shall provide perimeter landscaping. Parking lots shall have perimeter landscaping of a minimum width of ten feet (10') exclusive of vehicle overhang. The perimeter landscaping shall consist of a continuous evergreen hedge, evergreen trees, earthen mound or a combination thereof as required to provide a continuous opaque screen, a minimum of thirty-six inches (36") in height, within one (1) year of installation. The perimeter landscape shall also contain a minimum of one (1) deciduous tree per fifty (50) linear feet of parking perimeter. **Required interior lot landscaping shall not be applied as parking lot area landscaping and vice-versa.**

vi. Parked vehicles may hang over the interior landscaped area no more than two and one-half feet (2 ½'). Concrete or other wheel stops shall be provided to ensure no greater overhang on the landscaped area. Where parked vehicles will overhang, a four-foot (4') minimum spacing shall be provided from the edge of pavement to all trees.

vii. Grass or ground cover shall be planted on all portions of the required landscaping area not occupied by other landscape material. Such material fulfills required interior or perimeter landscaping.

K. Screening and Landscaping for Service Structures.

i. In order to properly screen service structures from the main building and neighboring lots, the following screening requirements shall apply:

ii. Location of screening. Either a solid, opaque fence or wall or earth berm, or with a continuous planting of evergreen plant material shall enclose any service structure on all sides, unless such structure must be frequently accessed, in which case screening on all but one (1) side is required. The average height of the screening fence or wall or evergreen shall be one foot (1') more than the height of the enclosed structure but shall not exceed the maximum permitted height of fences and walls of the District.

iii. Mechanical equipment and service functions associated with a building shall, to the maximum extent feasible, be incorporated into the overall design theme of the building and the landscape so that these functions are out of view from public ways and adjacent properties while allowing convenient access.

iv. Plant material required for screening of service structures shall not count towards the fulfillment of other landscape requirements in this section. No interior landscaping shall be required within an area screened for service structures.

v. Curbs to protect plant material. Whenever plant material is placed around any trash disposal unit or waste collection unit which is emptied or removed mechanically on a regular basis, a curb to contain the placement of the container shall be provided adjacent to the plant material. The curbing shall be at least one foot (1') from the material and shall be designed to prevent possible damage to the plant material when the container is moved or emptied.

vi. Service structures shall be grouped together whenever possible.

vii. The provisions of this section shall not apply to service structures located on lots with single family and two-family dwellings, except that any generator located within six feet (6') of any lot line shall be screened in accordance with this section.

L. Natural Preservation Zones.

i. Applicability. Natural preservation zones are areas that protect both the aesthetic appearance and environmental significance including, but not limited to, woodlands, wetlands, ravines, flood plains, streams, lakes, ponds, and/or steep slopes and can provide effective buffers between different or same land uses. Such zones should be designated on the concerned property. It is the intent of this section to encourage the use of these preservation zones in new developments including single family subdivisions, multi family, commercial and industrial construction. It is the further intent of this section not to preclude and/or prevent development, but to protect and preserve environmentally significant areas by fostering the use of buffer zones that could be integrated within the development. Preservation zones shall be used in a manner to promote and protect the public safety, convenience, comfort, prosperity, and general welfare of the City.

ii. Determination of Preservation Zones.

1. Environmentally significant areas shall be required to have a preservation zone(s). (The natural resources maps A and B in the Reynoldsburg Planning Guide are guides in determining the environmentally significant areas. These maps shall be a guide in determining areas that shall be required to have preservation zones.)
2. However, this shall not preclude the Planning and Zoning Administrator or the Planning and Zoning Board from recommending and/or approving preservation zones in other areas that are considered to be environmentally significant. In determining preservation zones, the Planning and Zoning Administrator or the Planning and Zoning Board determines that the area needs to be protected from development and which could serve as a buffer between different or same uses.

iii. Approval of Preservation Zones. Preservation Zones shall be approved in accordance with the following procedures:

1. The Planning and Zoning Board shall have the authority to approve a preservation zone for a subdivision and/or a planned district. This approval shall occur during the preliminary plat stage and shall follow the procedures set out in Chapter 1111. The Planning and Zoning Administrator may recommend to the Planning and Zoning Board the location of a preservation zone.
2. Preservation zones shall become part of the final plat or final development plan for subdivisions by the Planning and Zoning Board and approved by Council. Preservation zones shall become part of the site plan that is part of the certificate of appropriateness approval.

iv. Protection of Preservation Zones.

1. Before any activity, clearing, and/or construction begins, the entire preservation zone shall be enclosed with at least three foot (3') high orange construction fencing to prevent any access to the area. Such fencing shall protect the root systems of vegetation within the preservation zone. The fencing can only be taken down for an individual lot when an occupancy permit has been issued for the structure on the concerned lot. The fencing shall remain on the undeveloped lots until occupancy permits are granted for each lot.

2. Said preservation zone shall not be disturbed any time before, during, or after said construction except for necessary access as approved by the Planning and Zoning Administrator.
3. No permanent or temporary structure, building, or fence shall ever be placed upon, in, or under said preservation zone.
4. Utilities and roadways in preservation zones may only be installed consistent with an Environmental Plan and/or Mitigation Plan.
5. No development, clearing, thinning, construction, or work shall be performed in the preservation zone except for necessary construction as deemed necessary by the Planning and Zoning Administrator. If a preservation zone is disturbed at any time (including but not limited to utility construction and/or easement, building or grading construction) by the developer, contractor, subcontractor, house builder, property owner, or a representative, such disturbances that occur shall be restored to an approved condition. Diseased trees and/or diseased vegetation may be removed with the approval of the Planning and Zoning Administrator. Obnoxious weeds and/or brush of less than one inch (1") caliper may be removed without destroying the integrity of the preservation zone.
6. No dirt, stones, wood, or debris shall be placed within the preservation zone.
7. Trees located in a preservation zone that have been pushed over, cut apart, blown over, or fallen due to aging and/or deterioration are the property owner's responsibility to remove from the preservation zone.
8. A utility company servicing and/or installing utilities in the designated preservation zone shall also be subject to these restrictions.
9. These restrictions shall be printed on the final plat, the final development plan, and/or site plan.
10. Drainage shall not be changed in a manner that will damage the preservation zone.
11. The developer shall notify all contractors, utility companies, and/or cable companies doing work in the concerned subdivision of the preservation zone requirements.

SECTION 1105.09 EXTERIOR LIGHTING

A. **Purpose and Applicability.** ~~T~~The purpose of this section is to ensure that all exterior site and building lighting shall not affect the reasonable use and enjoyment of adjacent properties but provide minimum levels to enhance safety of individuals and property. Lighting standards shall also protect the safety and operation of vehicles on the public rights-of-way from levels of illumination that are emitted or reflected from light sources of an intensity sufficiently to constitute a safety hazard to vehicular movement. Lighting standards shall apply to all lots except those developed with single family or two-family dwellings.

B. **Exterior Lighting Regulations.** Exterior site lighting shall be designed, located, constructed and maintained to minimize light and reflected light trespass and spill over off the subject property. Glare shall be minimized from all light sources.

i. The average horizontal illumination level on the ground shall not exceed three foot-candles (3FC). The light level along a property line adjacent to a residentially-zoned or used property shall not exceed an average intensity of one-half foot-candle (0.5FC).

ii. The height of parking lot lighting shall not exceed twenty feet (20') above grade and shall direct light downward, i.e. cut-off type fixtures. ~~in commercial and mixed-use districts and fifteen (15) feet in mulit-family or adjacent to residential districts.~~ In conjunction with a major site plan review, the Planning and Zoning Board or Administrator may require a lower standard based upon specific characteristics of the site.

iii. The height of light poles in loading areas and parking areas of semi-trailer trucks, tractor trucks, and similar vehicles in the I, Innovation zoning district only, shall not exceed thirty feet (30') above grade and shall direct light downwards, i.e. cut-off type fixtures. In conjunction with a major site plan review, the Planning and Zoning Board or Administrator may require a lower standard based upon specific characteristics of the site.

iv. The color of parking lot lighting poles and other lighting infrastructure shall match or complement the colors of the building's architecture, as approved by the Planning and Zoning Board.

v. For pedestrian areas, decorative low light fixtures shall be used and the height of the fixture shall not exceed fourteen feet (14') above grade.

vi. Exterior building illumination shall be from concealed sources. Strobe or flashing lights and exposed neon lights are not permitted. Lighting fixtures shall not generate excessive light levels, cause glare, or direct light beyond the facades onto neighboring property, streets, or the night sky. The maximum illumination of any vertical surface or angular roof surface shall not exceed four foot-candles (4FC).

vii. Security lighting shall be full, cut-off type fixtures, shielded and aimed so that illumination is directed to the designated areas with the lowest possible illumination level to effectively allow surveillance.

viii. Lighting fixtures used to illuminate the area below a freestanding canopy shall be recessed so that the lens cover is recessed or flush with the bottom surface (ceiling) of the canopy. However, indirect lighting may be used where a shielded source of light is beamed upward and then reflected down from the underside of the canopy.

C. Photometric Plan Requirements. For developments requiring site plan review, a photometric lighting plan shall be submitted and shall include:

i. Location and height of all proposed fixtures

ii. Type and wattage of lamps

iii. ISO-footcandle diagrams showing light levels at ground level, including property lines

iv. Fixture cut sheets demonstrating shielding and photometric distribution

D. Parking Lot Lighting.

i. Any parking lot containing ten (10) or more parking spaces, which is used during non-daylight hours, shall be illuminated during such hours to assist both motorists and pedestrians in avoiding accidents. Non-daylight hours are defined as sunset to sunrise.


ii. For aesthetic compatibility, light fixtures in parking lots shall be of the same or similar type and color.

iii. Light fixtures shall be placed in parking lot islands or solid bases to protect both lights and vehicles from possible damage.

SECTION 1105.11 FENCES AND SCREENING

TABLE 1105.11A FENCE MATERIALS								
SUMMARY OF PERMITTED FENCE MATERIALS								
DISTRICT/ZONE	LUMBER	VINYL	WROUGHT-IRON	STONE	PAINTED ALUMINUM	BRICK	CHAIN LINK	METAL
ORD-N	X	X	X	X	X	X		
ORD-C	X	X	X	X	X	X		
BMD	X	X	X	X	X	X		
EMD	X	X	X	X	X	X		
Community Commercial (CC)	X	X	X	X	X	X		
Residential Zones (SR and RM)	X	X	X	X	X	X		
Innovation Zone (I)	X	X	X	X	X	X		X
Open Space/Schools Zone (OS)	X	X	X	X	X	X		

INTERIOR LOTS



CORNER LOTS




TABLE 1105.11B FENCE HEIGHT, SETBACKS AND OPACITY						
SUMMARY OF FENCE HEIGHT, SETBACKS AND OPACITY						
	FRONT AND CORNER YARD FENCES			REAR AND SIDE YARD FENCES		
DISTRICT/ZONE	MAX. HEIGHT	MINIMUM SETBACK	MAXIMUM OPACITY	MAX. HEIGHT	MINIMUM SETBACK	MAXIMUM OPACITY
ORD-N	4 ft.	3 ft. from ROW	50%	6 ft.	0 ft. from property line	100%
ORD-C	4 ft.	3 ft. from ROW	50%	6 ft.	0 ft. from property line	100%
BMD	4 ft.	3 ft. from ROW	50%	8 ft.	0 ft. from property line	100%
EMD	4 ft.	3 ft. from ROW	50%	8 ft.	0 ft. from property line	100%
Community Commercial (CC)	4 ft.	3 ft. from ROW	50%	8 ft.	0 ft. from property line	100%
Residential Zones (SR and RM)	4 ft.	3 ft. from ROW	50%	6 ft.	0 ft. from property line	100%
Innovation Zone (I)	~~4~~ 8 ft.	3ft. from ROW	50%	10 ft.	0 ft from property line	100%
Open Space/Schools Zone (OS)	4 ft.	5 ft from ROW	50%	10 ft.	0 ft from property line	50%

A. Fences. The following regulations shall apply to the location and appearance of fences in the front, side, and rear yards of properties located in the City of Reynoldsburg.

i. Fences in Olde Reynoldsburg Commercial and Neighborhood Districts. The following regulations shall govern fences located upon properties in both the ORD-C and ORD-N:

1. **Front and Corner Yard Fences—Height.** Between the front setback line for structures and the front facade of the principal structure, fences shall be no higher than four feet (4FT).
2. **Front and Corner Yard Fences—Setback.** Front and corner yard fences shall be no closer to the right-of-way than three feet (3FT).
3. **Front and Corner Yard Fences—Opacity.** Front and corner yard fences shall be constructed of an open design, which is defined as at least fifty percent (50%) open. For picket fences, the distance between pickets shall be no less than the width of the pickets themselves.

4. **Rear and Side Yard Fences—Height.** Between the rear setback line or side setback line for structures and the rear façade or side of the principal structure, fences shall be no higher than six feet (6FT).
5. **Rear and Side Yard Fences—Setback.** Rear and side yard fences shall be placed on the property line of the subject property unless, at the discretion of the Planning and Zoning Administrator, there is articulable and substantial basis to permit an applicant to deviate.
6. **Rear and Side Yard Fences—Opacity.** Rear and side yard fences may be constructed of materials with a maximum opacity of 100%.
7. **Fence Materials.** Fences in the ORD-C and ORD-N districts shall be constructed of materials that match or compliment any existing structures on a lot. This includes but is not limited to, painted or treated lumber, vinyl, wrought iron, painted aluminum, brick, and stone. All lumber fences shall be constructed so that the finished boards hide the vertical and horizontal posts when viewed from adjacent lots unless the fence is constructed in such a manner that the finished look of both sides of the fence is the same.

ii. **Fences in Residential Districts.** The following regulations shall govern fences located upon properties in residential zoning districts:

1. **Front and Corner Yard Fences—Height.** Between the front setback line for structures and the front facade of the principal structure, fences shall be no higher than four feet (4FT).
2. **Front and Corner Yard Fences—Setback.** Front and corner yard fences shall be no closer to the right-of-way than three feet (3FT).
3. **Front and Corner Yard Fences—Opacity.** Front and corner yard fences shall be constructed of an open design, which is defined as at least fifty percent (50%) open. For picket fences, the distance between pickets shall be no less than the width of the pickets themselves.
4. **Rear and Side Yard Fences—Height.** Between the rear setback line or side setback line for structures and the rear façade or side of the principal structure, fences shall be no higher than six feet (6FT).
5. **Rear and Side Yard Fences—Setback**. Rear and side yard fences shall be placed on the property line of the subject property unless, at the discretion of the Planning and Zoning Administrator, there are substantial grounds to deviate.
6. **Rear and Side Yard Fences—Opacity.** Rear and side yard fences may be constructed of materials with a maximum opacity of 100%.
7. **Fence Materials.** Fences in residential districts shall be constructed of materials that match or compliment any existing structures on a lot. This includes but is not limited to, painted or treated lumber, vinyl, wrought iron, painted aluminum, brick, stone. All lumber fences shall be constructed so that the finished boards hide the vertical and horizontal posts when viewed from adjacent lots unless the fence is constructed in such a manner that the finished look of both sides of the fence is the same.

iii. **Fences in Commercial and Mixed-Use Zones and Districts.** The following regulations shall govern fences located upon properties in commercial and mixed-use zones and districts:

1. **Front and Corner Yard Fences—Height.** Between the front setback line for structures and the front facade of the principal structure, fences shall be no higher than four feet (4FT).
2. **Front and Corner Yard Fences—Setback.** Front and corner yard fences shall be no closer to the right-of-way than three feet (3FT).
3. **Front and Corner Yard Fences—Opacity.** Front and corner yard fences shall be constructed of an open design, which is defined as at least fifty percent (50%) open. For picket fences, the distance between pickets shall be no less than the width of the pickets themselves.
4. **Rear and Side Yard Fences—Height.** Between the rear setback line or side setback line for structures and the rear façade or side of the principal structure, fences shall be no higher than eight feet (8FT).
5. **Rear and Side Yard Fences—Setback.** Rear and side yard fences shall be placed on the property line of the subject property unless, at the discretion of the Planning and Zoning Administrator, there is articulable and substantial basis to permit an applicant to deviate.
6. **Rear and Side Yard Fences—Opacity.** Rear and side yard fences may be constructed of materials with a maximum opacity of 50%.
7. **Fence Materials.** Fences in the Commercial and Mixed-Use Zone Districts shall be constructed of materials that match or compliment any existing structures on a lot. This includes but is not limited to, painted or treated lumber, vinyl, wrought iron, painted aluminum, brick, and stone. All lumber fences shall be constructed so that the finished boards hide the vertical and horizontal posts when viewed from adjacent lots unless the fence is constructed in such a manner that the finished look of both sides of the fence is the same.

iv. **Fences in Innovation Zone.** The following regulations shall govern fences located upon properties in the Innovation Zone:

1. **Front and Corner Yard Fences—Height.** Between the front setback line for structures and the front facade of the principal structure, fences shall be no higher than ~~four~~ **eight** feet (**8** ~~4~~FT).
2. **Front and Corner Yard Fences—Setback.** Front and corner yard fences shall be no closer to the right-of-way than three feet (3FT).
3. **Front and Corner Yard Fences—Opacity.** Front and corner yard fences shall be constructed of an open design, which is defined as at least fifty percent (50%) open. For picket fences, the distance between pickets shall be no less than the width of the pickets themselves.
4. **Rear and Side Yard Fences—Height.** Between the rear setback line or side setback line for structures and the rear façade or side of the principal structure, fences shall be no higher than ten feet (10FT).
5. **Rear and Side Yard Fences—Setback.** Rear and side yard fences shall be placed on the property line of the subject property unless, at the discretion of the Planning and Zoning Administrator, there is articulable and substantial basis to permit an applicant to deviate.

6. **Rear and Side Yard Fences—Opacity.** Rear and side yard fences may be constructed of materials with a maximum opacity of 100%.
7. **Fence Materials.** Fences in the Innovation Zone shall be constructed of materials that match or compliment any existing structures on a lot. This includes but is not limited to, painted or treated lumber, vinyl, wrought iron, painted aluminum, brick, and stone. All lumber fences shall be constructed so that the finished boards hide the vertical and horizontal posts when viewed from adjacent lots unless the fence is constructed in such a manner that the finished look of both sides of the fence is the same. Metal, non-chain-link, fences are permitted in the Innovation Zone.
8. **Barb-Wire Fences—Innovation Zone.** Fences containing barbs may be erected as rear fences to secure properties in the Innovation Zone. The Planning and Zoning Administrator shall only grant a fence permit for a fence of this type after determining that the nature and location of the fence is not a danger to the public or intended to injury persons engaged in lawful activity.

v. **Fences in the Open Space/Schools Zone.** The following regulations shall govern fences located upon properties in the Open Space/Schools Zone:

1. **Front and Corner Yard Fences—Height.** Between the front setback line for structures and the front facade of the principal structure, fences shall be no higher than four feet (4FT).
2. **Front and Corner Yard Fences—Setback.** Front and corner yard fences shall be no closer to the right-of-way than five feet (5FT).
3. **Front and Corner Yard Fences—Opacity.** Front and corner yard fences shall be constructed of an open design, which is defined as at least fifty percent (50%) open. For picket fences, the distance between pickets shall be no less than the width of the pickets themselves.
4. **Rear and Side Yard Fences—Height.** Between the rear setback line or side setback line for structures and the rear façade or side of the principal structure, fences shall be no higher than ten feet (10FT).
5. **Rear and Side Yard Fences—Setback.** Rear and side yard fences shall be placed on the property line of the subject property unless, at the discretion of the Planning and Zoning Administrator, there is articulable and substantial basis to permit an applicant to deviate.
6. **Rear and Side Yard Fences—Opacity.** Rear and side yard fences may be constructed of materials with a maximum opacity of 50%.
7. **Fence Materials.** Fences in the Open Space/Schools Zone shall be constructed of materials that match or compliment any existing structures on a lot. This includes but is not limited to, painted or treated lumber, vinyl, wrought iron, painted aluminum, brick, and stone. All lumber fences shall be constructed so that the finished boards hide the vertical and horizontal posts when viewed from adjacent lots unless the fence is constructed in such a manner that the finished look of both sides of the fence is the same.

B. ~~C.~~ **Corner Lots.** In the case of a corner lot, one side will be designated as the primary front yard, i.e., the principal front of the building, and the second side will be designated as the secondary front yard. Setbacks in primary and secondary front yard shall be placed at least three (3) feet from the right-of-way.

C. **Service Fences.** Waste containers, air conditioning units, and electrical generators may be screened with fence materials allowable in the property's district and shall be considered decorative fences and not require a permit.

D. **Temporary Fences.** Temporary fences may be constructed without a permit for the following reasons:

i. As required due to an unsafe building, right-of-way or utility maintenance emergency.

ii. A construction fence in conjunction with a site that has active building permits.

iii. In conjunction with an approved temporary special land use permit or any special event approved through the Parks and Recreation Department. Temporary fences of this nature may only be maintained for the length of the approved permit or through the duration of the special event.

iv. Temporary horticultural fences are permitted as temporary fences within the area designated for rear fences. Temporary horticultural fences shall be of an open design, shall not exceed four feet (4FT) in height, and not enclose an area larger than five hundred square feet (500SF).

v. Temporary fences may be constructed of materials or in a manner not consistent with the provisions of this chapter, but shall not be constructed in a manner designed to cause a hazard to public safety.

vi. In the event a temporary fence exists for a period of thirty (30) days or more, and the Planning and Zoning Administrator determines that it is a hazard to public safety, the Planning and Zoning Administrator may require a fence permit or that the fence comply with any provision of this chapter.

E. **Generally Applicable Fence Regulations.**

i. All fences, unless specifically exempt by this chapter, shall require a fence permit from the Planning and Zoning Administrator. No fence shall be erected, constructed, altered, relocated or rebuilt prior to obtaining a fence permit. An existing fence that requires new vertical posts to be set shall be considered an altered fence, and subject to a new permit. Existing chainlink fences within the Suburban Residential zoning district may be repaired or replaced in their entirety provided that a zoning certificate is obtained and that the subject fence is placed in the same position and arrangement as the existing fence and otherwise meets the same or smaller dimensions. For the purposes of this chapter, a fence permit shall have the same effect as a zoning certificate in proving conformance with the Zoning Code.

ii. Fences shall only be constructed in conformance with the provisions of this chapter and of the fence permit issued by the Planning and Zoning Administrator.

iii. No fence shall be installed in a manner or location which obstructs or alters the drainage of the lot on which it is located or of any abutting lot. All fences that are constructed abutting or across drainage easements shall be subject to the following additional regulations:

1. Shadow box fences and fences of an open design, which is defined as at least fifty percent (50%) open will be the preferred fence styles. For picket fences, the distance between pickets shall be no less than the width of the pickets themselves.

2. Privacy fences shall provide a gap between the vertical boards and the ground of no less than two inches (2IN).

iv. Fences may be inspected for compliance with the provisions of this Zoning Code. If any fence is installed, erected, constructed or maintained in violation of any of the provisions of this chapter, the Planning and Zoning Administrator may notify the owner or lessee of the fence in question to repair or replace the fence so as to comply with this chapter or to remove it.

v. No fence shall be constructed of materials such as highway guardrails, corrugated metal, metal wire or plastic mesh, or other such materials that are not designed for use as fencing material or are not sufficiently weather resistant and durable.

vi. No fence shall be constructed which is electrically charged, includes any material which is potentially hazardous such as spikes or barbed wire, or is otherwise designed to injure except as provided for in this chapter.

vii. Chain-link fences may not be utilized as a means of support for wooden privacy fences.

SECTION 1105.13 SUPPLEMENTARY USE CONDITIONS

A. Temporary Land Use. The Planning and Zoning Administrator shall have the power to grant permits authorizing temporary special land uses for the following types of temporary events: tent sales, sidewalk sales, or seasonal sales of produce, plants, firewood, or Christmas trees.

i. Zoning Districts Where Permitted. Temporary special land uses for tent sales, sidewalk sales, or seasonal sales of produce, plants, firewood, or Christmas trees shall only be permitted in the Community Commercial Zone (CC), the Brice & East Main Street District (BMD) ~~and~~ , the East Main Street District (EMD), and the Olde Reynoldsburg Commercial District (ORD-C).

ii. Application and Fee. Every person, firm or corporation desiring to obtain a temporary special land use permit, as required by this section, shall file an application with the Planning and Zoning Administrator together with an application fee. The application for a temporary special land use permit shall be accompanied by plans and specifications as required by the Planning and Zoning Administrator. This includes but is not limited to, plans that show the following:

1. The shape, location, and dimensions of the lot, including the shape, size, location, and use of all buildings or other structures already on the lot, and the off-street parking layout.
2. The materials to be utilized in and the shape, size, and location of all buildings and structures to be erected or moved onto the lot, including all tents, tables, stands or display racks.
3. The anticipated automobile traffic flow to and from the lot and any adjacent thoroughfares, loss of off-street parking space, if any, as well as the anticipated flow of pedestrian traffic upon lot sidewalks.

iii. Time Limitations

1. A temporary special use permit for a tent or sidewalk sale shall be effective for no longer than seven (7) days. No more than three (3) temporary special land use permits for tent sales or sidewalk sales shall be issued for a given location within a single calendar year. Temporary special use permits for tent sales or sidewalk sales shall not be issued for any given location for consecutive time periods except in the Olde Reynoldsburg Commercial District, the Brice and East Main Street District, and the East Main Street District.

2. A temporary special land use permit for the sale of Christmas trees shall be effective for no longer than thirty (30) days. No more than one (1) temporary special land use permit for the sale of Christmas trees shall be issued for any given location within a single calendar year.
3. A temporary special use permit for seasonal sales of produce, plants, or firewood shall be effective for a period no longer than ninety (90) days. No more than one (1) temporary special land use permit for seasonal sales of produce, plants, or firewood shall be issued for any given location within a single calendar year.
4. The Planning and Zoning Administrator or the Planning and Zoning Board shall have the power to vary these periods and add other conditions to an approved permit as deemed necessary by the Planning and Zoning Administrator or the Board in order to further the goals and principles of the Zoning Code.

iv. **Regulations.** A temporary special use permit shall only be granted if the Planning and Zoning Administrator determines that the proposed use, including the erection of any temporary building or structure, will:

1. Provide adequate light and ventilation between buildings and structures.
2. Provide adequate automobile and pedestrian traffic flow.
3. Provide adequate off-street parking.
4. Will meet the intent of the Zoning Code or otherwise not interfere with the protection of public health, safety, and general welfare.
5. Not be incompatible with, or otherwise adversely affect, the physical character of the community and, in particular, the surrounding area within a distance of one thousand feet (1,000FT).
6. No temporary special use shall be permitted if it reduces the parking on a lot by greater than twenty-five percent (25%).

v. **Vacant Lots.** When the proposed temporary special use is to be conducted on an otherwise vacant or unused lot, the use shall comply with all applicable zoning regulations for the district.

vi. **Accessory Structures.** Tents and other temporary structures are subject to building permits and other regulation by the Building Division.

vii. **Variance.** The Planning and Zoning Administrator or the Planning and Zoning Board shall have the power to vary the time periods of and add other conditions to an approved permit as deemed necessary by the Planning and Zoning Administrator or the Planning and Zoning Board in order to further the intent of the Zoning Code or otherwise protect the public health, safety, and general welfare.

B. **Special Events and Community Activities.** The following regulations apply to the approval and operation of special events and community activities.

i. **Exceptions.** A temporary special land use permit shall not be required for special event or community activity permitted or organized through the Parks and Recreation Department or Public Safety Department.

ii. **Exceptions—Open Space Districts.** A temporary special land use permit shall not be required for a special event or community activity associated with a permitted semi-public use in Open Space/Schools District provided that the special event or festival meets the following conditions:

1. The special event or festival takes place entirely on the lot or parcel associated with the existing approved semi-public use.
2. The special event or festival is no longer than three (3) consecutive days and that there are no more than two (2) such events or festivals at a given location within a calendar year.

iii. Exceptions—Non-Profit or Charitable Organizations. A temporary special land use permit shall not be required for a special event or community activity conducted on a commercial parcel that is organized by a non-profit or charitable organization. No more than two (2) such events shall be conducted by the same organization at the same location within a calendar year, unless the Planning and Zoning Administrator, consultation with the Director of Parks and Recreation and Director of Public Service finds there's a substantial basis to grant an additional permit.

iv. Applicability. Except as otherwise provided herein, the Planning and Zoning Administrator may require temporary special land use permit for any other type of special event.

v. Accessory Structures. Tents and other temporary structures for festivals and special events are subject to building permits and other regulation by the Building Division.

C. Regulations Applicable to Swimming Pools, ~~Fish Ponds, and Water Parks.~~ A swimming pool, ~~fish pond, or water park~~ shall conform with all yard and setback requirements for accessory structures in the district in which it is located, as well as the following requirements.

i. Private Swimming Pool. A private swimming pool, where in-ground or above-ground shall be permitted in any commercial, mixed-use or residential district as an accessory use provided that it complies with the following conditions and requirements:

1. Use. The pool shall be intended and used solely for the enjoyment of the occupants of the main use of the lot on which it is located.
2. The pool, including any walks or paved areas or accessory structures (including decks) adjacent thereto, shall not be located closer than ten feet (10') to any lot line, shall not be closer than 10' from the ~~principle~~ principal structure, and shall not be closer to any frontage than a distance ten feet (10') greater than the setback required for a principal building. A pool is not permitted in the front yard or side front yard.
3. The area of the swimming pool, exclusive of decks, walks, and other appurtenances, shall not exceed ten percent (10%) of the area of the lot.
4. No lights, diving board, or other equipment or accessory shall project more than ten feet (10') above the average finished grade of the pool site.
5. In ground pools are required to have a fence around the pool or the property, minimum height of 4 feet with a locking gate. Above ground pools are required to have a fence around the pool or the property, minimum height of 4 feet with a locking gate or a removable ladder that is able to be locked up
6. A swimming pool shall be installed or constructed subsequent to and in conformance with the regulations of the Building Code and a permit issued by the Building Inspector. The Building Inspector shall not issue any permit for a swimming pool until he has submitted the application for a swimming pool to the Zoning Officer who shall determine compliance with the Zoning Code and issue a zoning certificate.

ii. **Community or Club Swimming Pool.** A community or club swimming pool means any pool constructed by an association of property owners or by a private club for use and enjoyment by members of the association or club and their families. Community and club swimming pools are permitted in any district, but shall comply with the following conditions and requirements:

1. A community or club swimming pool shall be intended and used solely for the enjoyment of the members, their families and guests, and guests of the association or club under whose ownership or jurisdiction the pool is operated.
2. A community or club swimming pool and accessory structures thereto, including the areas used by the bathers, shall not be closer than one hundred feet (100') to any lot line.
3. A community or club swimming pool and all of the area used by the bathers, including all adjacent deck areas, shall be so walled or fenced as to prevent uncontrolled access by children.

Deleted section 1105.13.C.iii

See Attachment Sheet (B)

D. Portable Temporary Storage Units. A zoning certificate shall be obtained from the Zoning Administrator prior to the placement of a portable temporary storage unit on a property when the unit will be on the property for a period of more than seven days. No more than one unit is permitted on a property at any given time, the duration of which shall not exceed a period of fourteen days total. The unit must be placed on a hard surface (not grass), and must be on the property for which it is being used. The use of these units shall be limited to no more than twice in any twelve month period. Permission to exceed these limitations may be granted by the Planning and Zoning Board. A portable temporary storage units is not permitted as a permanent accessory structure regardless of the proposed location of the unit on a parcel.

i. **Calamity exception**. If the portable temporary storage unit is being used to store personal property as a result of major calamity (e.g. fire, flood, or other event where there is significant property damage), the Planning and Zoning Board or Zoning Administrator may extend these time periods.

ii. **Approved construction project.** If the portable temporary storage unit is being used to store materials as part of an approved construction project, the portable temporary storage unit may remain onsite as long as there is a valid open building permit obtained through the City of Reynoldsburg.

E. Outdoor Storage. The following regulations shall apply to the approval and operation of outdoor storage as an accessory use:

i. Outdoor storage shall only be permitted in areas identified on the approved site plan. No such activity shall be located closer than fifty feet (50FT) to a residential zoning district boundary or road right-of-way abutting any residential zoning district or within ten feet (10FT) of any road right-of-way. Such activities shall not occupy any required parking area or driveway;

ii. Any outdoor storage area located closer than one hundred feet (100FT) to a residential district shall, if determined to be visible from such district, be screened by a landscape buffer strip or other means indicated on the approved site plan;

iii. Illumination of outdoor storage areas shall be designed to prevent glare or direct light from the illumination source into residential areas;

iv. Outdoor displays shall be maintained in a neat and orderly fashion. Waste material shall be

contained within a storage area completely surrounded by a gated masonry wall six feet (6FT) in height or other screening approved by the Board. Such screening shall be set back from residential districts at least six feet (6FT) and landscaped according to the approved site plan;

v. The site plan submitted with an application for a conditional use permit shall indicate the types of merchandise or materials to be stored, and, if applicable, any seasonal changes of merchandise or materials;

vi. Outdoor repair, preparation, cleaning, assembly, disassembly, or other similar activities shall not be permitted unless the nature and location of such activity is specifically identified in the application and approved by the Planning and Zoning Administrator or the Planning and Zoning Board.

F. Self-Store. The following regulations shall apply to the approval and operation of mini-storage facilities:

i. All storage shall be within an enclosed building unless the nature and location of outdoor storage has been specifically approved by the Board in conformance with the supplementary regulations for outdoor sales, storage, or display;

ii. Loading and unloading areas shall be paved and shall be located only as approved by the Board;

iii. A minimum of five (5) parking spaces shall be provided near the leasing office. Sufficient space shall be provided in the paved lanes serving the storage units to accommodate on-site movement of vehicles and the parking and loading/unloading of the trucks, vans, trailers, and automobiles of persons using the units;

iv. An on-site leasing office shall be provided;

v. Fencing of the perimeter shall be provided as determined by the Planning and Zoning Administrator or the Planning and Zoning Board in a manner which promotes security and presents an appropriate appearance to abutting properties;

vi. A landscaped yard of at least twenty-five feet (25FT) in width shall be provided along any lot line of the subject site which abuts a residential area. This area shall not be covered by buildings, parking or drives;

vii. Door openings facing residential areas shall not be permitted unless approved by the Planning and Zoning Administrator or the Planning and Zoning Board;

viii. Activities on the site shall be limited to the storage of property only. Other activities, such as the operation of tools, rummage sales, temporary residency, shall be prohibited unless specifically permitted by the Planning and Zoning Administrator or the Planning and Zoning Board;

ix. Hours of operation shall only be as approved by the Planning and Zoning Administrator or the Planning and Zoning Board after consideration of the impact of the proposed use upon the character, safety, and tranquility of the neighborhood.

G. Indoor Storage Facilities. The following regulations apply to the approval and operation of indoor storage facilities:

i. A minimum of twenty percent (20%) of the floor area of any structure proposed to be used as an indoor storage facility shall be used for other uses permitted within the respective zoning district, unless otherwise specifically approved by the Board on the approved site plan.

ii. All storage shall take place within an enclosed individual storage unit that is rented or leased on an individual basis. Storage shall be prohibited outside of the structure or within designated aisle areas with exception of vehicle and recreational vehicle storage areas clearly shown on the plan.

iii. A rental or leasing office shall be required to be located on-site.

iv. No more than one (1) external garage-door entrance shall be provided for each twenty (20) storage units within the structure.

v. A landscaped yard of at least twenty-five feet (25FT) in width shall be provided along any lot line of the subject site which abuts a residentially zoned property. A reduction of this buffer may be approved by the Board if alternate means of screening are provided and specifically approved on the site plan.

vi. Caretaker/residential units are prohibited.

vii. One (1) parking space shall be located on the site for each seventy-five (75) storage units, in addition to other required parking for all other uses on the site.

H. Childcare Centers. The following regulations shall apply to conditional use permits for childcare centers:

i. No zoning permit or conditional use permit for a childcare center shall be issued for a lot that is within one hundred fifty feet (150FT) of any lot or parcel with an approved gasoline station use, or which is likely to generate noxious fumes or vapor.

ii. All outdoor play areas shall meet the minimum requirements outlined by the State agency with oversight of childcare centers. No play area shall be located adjacent to a loading space, loading dock or other area where vehicles are likely to idle. No play area shall be constructed in a manner that allows children access to any electrical or telecommunications box/vault.

iii. No childcare center shall be permitted to operate between the hours of 7:00 p.m. and 6:00 a.m. the following morning unless specifically approved by the Planning and Zoning Administrator or the Planning and Zoning Board.

I. Home Occupations. The following regulations shall apply to the approval and operation of a home occupation as an accessory use in a dwelling:

i. No person who is not a permanent resident of the dwelling shall be employed in the home occupation;

ii. The home occupation shall be clearly incidental and subordinate to the dwelling use~~. No more than fifteen percent (15%) of the floor area of all buildings on the lot shall be used in the conduct of the home occupation.~~ , with a minimum permitted square footage of three-hundred square feet (300) or no more than thirty percent (30%) of the floor area of the principal building, whichever is greater.

iii. The home occupation shall only be conducted in the principal building on the parcel.

iv. There shall be no change in the outside appearance of the dwelling or lot, or other visible evidence of the conduct of the home occupation. No sign is permitted.

v. The home occupation shall not generate traffic in greater volumes than would normally be expected in a residential neighborhood.

vi. No equipment or process shall be used which creates noise, vibration, glare, fumes, odors, or electrical interference detectable to the normal senses off the lot. In the case of electrical

interference, no equipment or process shall be used which creates visual or audible interference in any radio or television receivers off the premises, or causes fluctuations in the line voltage off the premises.

vii. Prior to establishing a home occupation, the owner or occupant of the dwelling shall apply and receive approval for a zoning certificate from the Planning and Zoning Administrator.

J. Pawnbrokering, Bookmaking, Betting, Adult Oriented Businesses. The following requirements shall apply to the approval and operation of pawnbrokering, bookmaking, betting, scheme/game of chance, massage establishment, ~~body piercing establishment, tattoo establishment~~, adult bookstore, adult motion picture theater, adult video store: No such conditional use for these uses shall be conducted within one thousand feet (1,000FT) of the property line of any church, childcare center, public or private school, public library, public park lands, or any premises that sell or distribute alcoholic beverages.

K. Gasoline Stations. The following regulations shall apply to the approval and operation of gasoline stations:

i. Parking of employee vehicles, vehicles used in the operation of the business, vehicles awaiting servicing or return to customers after servicing, and vehicles held for disposal shall only be permitted in the locations approved on the site plan. Parking and storage of vehicles not related to the principal use of the site shall not be permitted.

ii. Vehicle sales, service, rental, or leasing shall not be permitted on the site unless specifically approved.

iii. Retail sales of products other than vehicular fuels shall be permitted only within an enclosed structure which shall comply with all provisions of the district, including requirements for parking. Outdoor display, storage, or sale of goods shall not be permitted on the site unless specifically approved in the conditional use permit and in conformance with the supplementary standards for outdoor display, storage, and sale.

iv. Temporary outdoor storage of discarded materials, vehicle parts, scrap and other waste prior to collection shall only be permitted within a storage area completely surrounded by a gated masonry wall six feet (6FT) in height or other screening approved by the Planning and Zoning Administrator or the Planning and Zoning Board. Such screening shall be set back from residential districts at least ten feet (10FT) and landscaped according to the approved site plan.

v. Fuel pumps and canopies shall conform to all requirements of this chapter with regard to height, setbacks, and signs.

vi. Air compressor pumps (e.g., for tire inflation) and other outdoor equipment shall be identified on the site plan and shall be located in a manner which minimizes noise impacts on residential areas.

vii. Curb cuts shall be limited to two (2) per site. On corner lots, curb cuts shall be limited to one (1) per street.

L. Drive-Thru Service. The following regulations shall apply to the approval and operation of drive-thru establishments:

i. Loudspeakers shall be located and designed, with volume and hours of operation controlled, in a manner to minimize noise impacts on nearby residential uses.

ii. Lanes required for vehicle access to and waiting for use of a drive-thru facility shall be designed to have sufficient length to accommodate the peak number of vehicles projected to use the facility at any one (1) time, to provide escape/abort lanes for vehicles desiring to leave the stacking lanes or to avoid disabled vehicles, and to minimize impacts on the use of other required parking or drives or on the use of abutting streets and hazards to pedestrians. The Planning and Zoning Administrator or Planning and Zoning Board, as applicable, may require a traffic study which documents the projected vehicular use of the proposed facilities and evidence of compliance with the provisions of this Zoning Code.

iii. The Planning and Zoning Administrator or Planning and Zoning Board, as applicable, may impose restrictions on the hours of operation in order to reduce inappropriate impacts on abutting uses and on street traffic and to ensure compatibility with normal vehicular activity in the district.

iv. The applicant shall so design the site plan or otherwise provide assurances as to reduce the impacts of lighting, litter, noise, and exhaust resulting from the facility, especially impacts on nearby residential uses.

M. Solar Panels and Solar Panel Arrays. The following regulations shall apply to the installation of solar panels and solar panel arrays:

i. Accessory Use. A solar panel or a solar panel array, in each case, whether freestanding or roof mounted, shall be classified as a permitted accessory use in all zoning districts in the city, subject to the regulations set forth herein. Any solar panel or solar panel array shall be installed in accordance with all applicable building and electrical codes. Except as otherwise, provided herein, solar panels and solar panel arrays shall be installed and located in accordance with the zoning regulations for the base zoning district in which such panels or arrays are to be installed. A zoning certificate is required for freestanding solar panels, ~~or~~ **roof** solar panel arrays,~~ only~~. **and roof solar shingles.**

ii. Roof mounted solar panels and solar panel arrays. Roof-mounted solar panels or solar arrays shall be located in accordance with the following regulations.

1. **Roof Line.** A roof-mounted solar panel or solar panel array shall not be located so that it extends beyond the roof line in any direction including above and beyond the roof peak.
2. **Roof Height Projection**. When located on a flat roof, solar panels or solar panel arrays shall not be project vertically more than ten feet from the surface of the flat roof. For purpose of this subsection, "flat roof" shall mean any roof that is less than seventeen (17) degrees or 2/12 pitch.
3. **Glare.** Roof mounted solar panels or solar panel arrays shall not be positioned so as to create glare on to adjacent roads, buildings, lots, or rights-of-way.

iii. Freestanding solar panels and solar panel arrays. Free-standing solar panels or solar arrays shall be located in accordance with the following regulations.

1. **Location**. Freestanding solar panels or solar panel arrays shall not be located in front of any principal building and shall not project past the width of the principal building.
2. **Height**. The maximum height for any freestanding solar panel or solar panel array shall be the maximum height of an accessory structure in the base zoning district in which the solar panel or solar panel array is located.

3. **Glare.** Freestanding solar panels or freestanding solar panel arrays shall be located so as not to create glare onto adjacent roads, buildings, lots, or rights-of-way.
4. **Lot Coverage.** The maximum lot coverage for any freestanding solar panel or freestanding solar panel array shall be ten percent (10%) of the total lot area with the lot coverage being determined based upon the area of the face of the solar panels.
5. **Screening.** All freestanding solar panels or freestanding solar panels with a ground storage battery shall secure such battery with a secure cover.
6. **Wind Resistance.** All freestanding solar panels and freestanding solar panel arrays shall be able to withstand velocities of no less than one -hundred and ten (110) miles per hour.

iv. **Site Plan.** Any application for a solar panel or solar panel array under this section shall be accompanied with a site plan depicting the following items:

1. The location of the panels or panel array;
2. The height of the panels or panel array;
3. For roof mounted panels and panel arrays, an overhead view of the roof identifying all vents, chimneys, or other appurtenances, including vertical objects (e.g. trees), that may affect the location of panels;
4. For freestanding panels and panel arrays, a calculation of the lot coverage of the panels or panel array;
5. An indication of whether any freestanding panel or panel array has a ground storage battery, and, if so, how such battery will be secured;
6. The manufacturer cut sheet for the model to be installed; and
7. Such other information as the Planning and Zoning Administrator may determined to be necessary to evaluate compliance with this section and with the Zoning Code.

v. **Decommissioning.** The Planning and Zoning Administrator shall be notified in writing by the owner of any previously permitted solar panel or solar panel array upon the permanent discontinuance of energy production, and panels and/or arrays shall be completely removed within nine (9) months of discontinuance of use and the affected area shall be fully restored to its preconstruction condition or better within three (3) months of the date of such removal.

N. **Licensed Marijuana Cultivation, Processing, and Dispensaries.** The following regulations shall apply to conditional use permits for any marijuana facility:

i. Any and all marijuana facilities in the City shall be licensed by the Department of Commerce and under Chapter 785 of the Codified Ordinances of the City of Reynoldsburg.

ii. Any and all other marijuana facilities in the City shall be licensed by the Division of Cannabis Control in accordance with Chapter 3780 of the Ohio Revised Code.

iii. No marijuana facility shall be located within a five hundred (500) feet radius of another such marijuana facility measured from the centerline of the front door of the establishment.

iv. No marijuana facility shall be located within a five hundred (500) feet radius of any public park, residential district, or school, as measured from the centerline of the front door of the establishment.

v. The exterior of any marijuana facility shall be properly screened such that activities, with the exception of administrative tasks, occurring within the facility cannot be observed from any

public right of way.

vi. Any marijuana facility shall not be permitted with any other use located on the same parcel of land or located within the same building.

O. Retail – Vape Shop/Smoke Shop. The following regulations shall apply to conditional use permits for any retail – vape shop/smoke shop facility:

i. No vape shop/smoke shop facility shall be located within a five hundred (500) feet radius of another such vape shop/smoke shop facility measured from the centerline of the front door of the establishment.

ii. No vape shop/smoke shop facility shall be located within a five hundred (500) feet radius of any public park, residential district, or school, as measured from the centerline of the front door of the establishment.

iii. Any vape shop/smoke shop facility shall not be permitted with any other use located on the same parcel of land or located within the same building.

P. Dwelling – Group. The following regulations shall apply to conditional use permits for any Dwelling-Group:

i. The site will be staffed 24 hours a day.

ii. No commercial activities will be conducted on the site.

iii. The land use will not be located within 500 feet of another parcel where an existing Dwelling – Group is located. This requirement is measured from the parcel boundary.

SECTION 1105.15 TELECOMMUNICATIONS FACILITIES

A. In recognition of the quasi-public nature of cellular and/or wireless telecommunication systems, it is the purpose of these regulations to: accommodate the need for cellular or wireless telecommunications towers and facilities for the provision of personal wireless/cellular services while regulating their location and number in the City; minimize adverse visual effects of telecommunication towers and support structures through proper siting, design, and screening; to minimize the adverse impacts that telecommunication facilities may have on the health, safety and welfare of the public; to avoid potential damage to adjacent properties from telecommunication tower and support failure; and to encourage the joint use of any new and existing telecommunication towers and support structures to minimize the number of such structures. The following requirements shall apply to conditional use permits for wireless telecommunication facilities:

B. Special Application Requirements. A site plan shall include the following:

i. The total area of the lot;

ii. The existing zoning of the site and all adjoining lots;

iii. All public and private right-of-way and easements located on the lot;

iv. The location of all existing buildings and structures on the lot; all buildings or structures and uses within five hundred feet (500FT) of the tower site; and the proposed location of the wireless/cellular communication tower and all wireless/cellular communication support structures

including dimensions, heights, and, where applicable, the gross floor areas;

v. The location and dimensions for all curb cuts, driving lanes, off-street parking spaces, grades, surfacing materials, drainage plans, illumination of the facility, and landscaping;

vi. The location of all proposed fences, screening and walls;

vii. Any other information as may be required by the Board.

viii. A report prepared by a licensed professional engineer documenting the height, design, proof of compliance with nationally accepted structural standards, and a description of the tower's capacity, which shall include the number and types of antennae it can accommodate.

ix. For the purpose of demonstrating the necessity for the erection of any new telecommunication tower, any applicant requesting permission to install a new tower shall provide evidence of written communication with all other wireless/cellular service providers who supply service within a one (1) mile radius of the proposed facility requesting use of the other providers' towers for collocation of the applicant's antennae. The contacted provider shall be requested to respond in writing to the inquiry within thirty (30) days. The applicant's letter(s) as well as the responses received shall be presented to the Board to demonstrate the need for a new tower.

x. The applicant shall also provide evidence of written communication with owners of nearby tall structures within a one (1) mile radius of the proposed tower site, asking permission to install the wireless/cellular antennae on those structures. Tall structures shall include, but not be limited to: smoke stacks, water towers, buildings over fifty feet (50FT) in height, other communication towers, and roadway light poles.

xi. The facility owner/operator shall present a maintenance plan demonstrating responsibility for the site.

xii. The applicant shall provide a copy of a permanent easement or appropriate leasehold estate providing for access to the tower site. The access to the tower sight must be maintained regardless of other development that may take place on the site.

xiii. The communication company must demonstrate proof to the City that the company is licensed by the Federal Communications Commission (FCC).

C. The following additional regulations shall apply to wireless telecommunications facilities:

i. Wireless or cellular telecommunication sites shall be located at least two hundred fifty feet (250FT) from any residential zoning district.

ii. The setback between the base of the tower or any guy wire anchors and any property line shall be located a distance which is at least forty percent (40%) of the tower's height or fifty feet (50FT), whichever is greater.

iii. The maximum height of a telecommunication tower shall be two hundred feet (200FT). The maximum height of the equipment building shall be thirty-five feet (35FT).

iv. Maximum size of an equipment building shall be seven hundred and fifty square feet (750SF).

v. The minimum lot size and area restriction shall be the same as permitted for any other use in the Innovation Zone.

vi. A security fence eight feet (8FT) in height with barbed wire around the top shall completely surround the tower, the equipment building and any guy wires.

vii. Towers and antennae shall be designed to withstand wind gusts of at least one hundred miles per hour (100MPH).

viii. The tower shall be painted in a non-contrasting gray or similar color to minimize its visibility, unless otherwise required by the Federal Communications Commission (FCC) or Federal Aviation Administration (FAA).

ix. No graphics advertising is permitted anywhere on the facility.

x. Buffer planting shall be located around the perimeter of the security fence as follows: An evergreen screen shall be planted that consists of either a hedge or evergreen trees that shall provide a minimum of seventy-five percent (75%) opacity year round.

xi. The tower shall not be artificially lighted except to assure safety or as required by the FAA.

xii. Warning signs shall be posted around the facility with an emergency telephone number of whom to contact in the event of an emergency.

xiii. The owner/operator of any telecommunications facility shall design such facility so that additional service providers may add their antennae, platforms, and associated hardware to the structure at a later date. The owner/operator shall negotiate in good faith with other providers for the collocation of other service providers' antennae at the facility, shall cooperate with the City in identifying other wireless/cellular service providers for the purpose of negotiating sublease agreements for collocation of other service providers' antennae at the facility, and shall not interfere or hinder service providers from utilizing the facility.

xiv. Where possible, an antenna or tower for use by a wireless/cellular service providers shall be attached to an existing structure or building. A new wireless communication facility shall not be erected if there is a technically suitable space for wireless communication facility available on an existing wireless communication tower or other suitable structure within the applicant's search area. The applicant must demonstrate that a technically suitable location is not reasonably available on an existing structure or that bona fide efforts to negotiate location on structures have been rejected.

xv. Any owner of a tower whose use will be discontinued shall submit a written report to the Planning and Zoning Administrator indicating the date on which such use shall cease. If at any time the use of the facility is discontinued for one hundred eighty (180) days (excluding any dormancy period between construction and the initial use of the facility), the Board may declare the facility abandoned. The tower owner and the owner of the property upon which the tower is located shall receive written instruction from the Board to either reactive the use within one hundred eighty (180) days or dismantle and remove the facility.

xvi. If reactivation does not occur within said period, the City may thereafter proceed to move the facility and assess the costs of removal to the owner, as well as certify those costs to the County Auditor as a lien against the property.

xvii. In addition to the foregoing requirements, the following standards, items A. through D., shall apply to wireless or cellular telecommunications facilities permitted on a property with an existing use:

1. The existing use on the property may be any permitted use or lawful nonconforming use in the Innovation Zone, and said use need not be affiliated with the wireless/cellular telecommunication provider.
2. The telecommunication facility shall be fully automated and unattended on a daily basis.
3. The vehicular access to the equipment building shall, whenever feasible, be provided along

the circulation driveways of the existing use.

4. Subsequent to approval of a conditional use permit for a telecommunication tower, the owner shall submit building permit applications to the City for any additional antennae proposed to be placed on the tower. A new zoning certificate will not be required, unless the Planning and Zoning Administrator determines that such additions do not conform with the approved conditional use permit.

SECTION 1105.17 CONVERSION OF DWELLING UNITS

A. In the SR, RM, and ORD-N, a structure may be converted to accommodate an increased number of dwelling units, provided that the proposed dwellings and lot conform with all requirements for new dwellings in the district, including the permitted number of dwellings, all yard and lot dimensions, floor area for each dwelling, and required parking spaces.

SECTION 1105.19 PERFORMANCE STANDARDS

A. Applicability. Every permitted use and conditional use permit shall conform to the performance standards in this chapter and to the laws and regulations of the State of Ohio and of the federal government. Any use permitted by this Zoning Code may be undertaken and maintained if acceptable measures and safeguards are employed to limit dangerous and objectionable elements to acceptable limits as established by the performance standards. Compliance with these standards shall be required during all times of operation of the approved activity or use.

B. Existing Use. An existing use which does not conform with these performance standards shall not be enlarged or remodeled if: the enlargement or remodeling will cause greater noncompliance with the performance standards which exist at the time of the proposed enlargement or remodeling; or if the nonconforming conditions are not brought into compliance as a result of or concurrently with the enlargement or remodeling.

C. Measurement Procedures. Methods and procedures for the determination of compliance with these performance standards shall conform to applicable methodologies prescribed by this Zoning Code or to applicable standard measurement procedures published by the American National Standards Institute, New York, N.Y., the Manufacturing Chemists' Association, Inc., Washington, D.C. and the United States Bureau of Mines, the National Fire Protection Association, the Ohio Environmental Protection Agency, and other recognized organizations whose standards are acceptable to the Zoning Official.

D. Studies to Demonstrate Compliance. When the Planning and Zoning Administrator or the Planning and Zoning Board determines that either the information provided by the property owner is not sufficient to determine compliance with the performance standards without providing additional studies or expert advice, or that the information provided by the owner is of such nature, complexity, or quantity that the Planning and Zoning Administrator or the Board is not able to make a determination of compliance without additional studies or expert advice, then the Planning and Zoning Administrator shall advise the owner that such studies or advice are required. The Planning and Zoning Administrator and the Board may accept the required studies prepared by qualified professionals

engaged by the owner or the owner shall deposit funds with the City as required to pay for such studies or expert advice.

E. Control of Objectionable Processes and Operations. The Planning and Zoning Administrator or Planning and Zoning Board, prior to the issuance of a zoning certificate, may require the submission of statements and plans indicating the manner in which dangerous and objectionable elements, including those described in the following performance standards, involved in processing and in equipment operations are to be eliminated or reduced to acceptable limits and tolerances.

F. Performance Standards. The following performance standards shall be applicable to the operation of any use permitted under this Zoning Code.

i. **Fire Hazards.** Any activity involving the use or storage of flammable or explosive materials shall be protected by adequate fire-fighting and fire suppression equipment and by such safety devices as are normally used in the handling of any such material. Such hazards shall be kept removed from adjacent activities to a distance which is compatible with the potential danger involved.

ii. **Radioactivity or Electrical Disturbance.** No activity shall emit dangerous radioactivity at any point or electrical disturbance adversely affecting the operation at any point of any equipment other than that of the creator of such disturbance.

iii. **Noise and Vibration.** All activities shall comply with the provisions of Section 509.11 of the Code of Ordinances and all other regulations of the City relating to noise and vibration.

iv. **Smoke Emission.** Smoke shall not be emitted with a density greater than No. 1 on the Ringelmann Chart as issued by the U. S. Bureau of Mines except for flow-off periods of ten minutes duration of one per hour when a density of not more than No. 2 is permitted.

v. **Odors.** No malodorous gas or matter which is offensive or produces a public nuisance or hazard on any adjoining lot shall be permitted.

vi. **Air Pollution.** No pollution of air by fly-ash, dust, vapor or other substance which is harmful to health, animals, vegetation or other property, or which can cause excessive soiling shall be permitted.

vii. **Glare.** No direct or reflected glare which is visible from any lot outside any Industrial District or from any public street, road or highway shall be permitted.

viii. **Erosion.** No erosion, by either wind or water carrying objectionable substance onto neighboring properties shall be permitted.

ix. **Water Pollution.** Pollution of water shall be subject to the requirements and regulations established by the State Water Pollution Control Board.

x. **Toxic or Noxious Matter.** No use, operation, or activity shall emit or discharge toxic or noxious matter in any form, particularly as identified on the USEPA Extremely Hazardous Substances List, which may be detrimental to the public health, safety or general welfare or which may endanger the natural environment. Provisions for the proper storage, use, and disposal of hazardous and/or toxic materials shall conform to the standards and requirements for such materials established by the USEPA and OEPA.

SECTION 1105.21 COMMERCIAL DESIGN STANDARDS

A. **Purpose.** The design standards in this section are intended to:

i. Promote a visually appealing built environment with human-scale design.
ii. Reinforce the identity and character of mixed-use centers and corridors.
iii. Encourage architectural variety while maintaining a unified streetscape.
iv. Ensure that new development complements surrounding structures and the public realm.

B. **Applicability.** These standards shall apply to all new construction, and the expansion of an existing structure of Community Commercial (CC), Brice and Main Street District, (BMD) and the East Main Street District (EMD).

C. **Street Orientation.**

i. All buildings shall have a primary façade and functional entrance oriented toward the primary public street or plaza.
ii. Buildings located on corners shall address both the primary and secondary streets through façade articulation.

D. **Transparency Requirements.**

i. Ground floor façades along primary streets must have a minimum of 20% transparency (clear, non-reflective glass).

E. **Blank Walls.**

i. No street-facing façade shall contain a blank wall.
ii. Architectural features or landscaping shall be used to break up large walls.

F. **Entries.**

i. Primary entries shall be clearly identifiable with architectural detailing, awnings, or recesses.

G. **Façade Articulation.** Façades longer than 30 feet must include at least one of the following:

i. Wall plane projections/recesses (minimum 12 inches)
ii. Material or color changes
iii. Vertical bays or pilasters
iv. Variation in roof height

H. **Material Requirements.**

i. Acceptable materials include:
    1. Brick (clay or cast)
    2. Stone or cast stone or synthetic stone
    3. Wood or fiber-cement siding

4. Architectural metal panels
5. Glass
6. Stucco (cementitious)
7. Decorative tile
8. Natural wood elements
9. Other materials as approved by the Zoning and Planning Administrator, based on visual commutability with listed approved materials.

I. Prohibited Materials.

i. Vinyl siding (except as an accent material)
ii. Mirrored or opaque glass
iii. Unfinished concrete block

J. Roof Design.

i. All roof designs are permitted.
ii. Flat Roofs
    1. Flat roofs must include parapets or a pronounced cornice line.
    2. Mechanical equipment shall be screened by the parapet and not visible from the street.
iii. Pitched Roofs
    1. Minimum slope: 4:12

K. Building Lighting.

i. Accent lighting may highlight architectural features but must be fully shielded to prevent light trespassing, glare and light pollution.

SECTION 1105.23 PROPERTY WITHOUT DIRECT STREET FRONTAGE

A. Purpose and Intent. The purpose of this section is to regulate the subdivision and redevelopment of landlocked parcels in order to:

i. Ensure safe and functional access for – residents, customers, employees, and emergency services.
ii. Prevent traffic congestion and circulation issues within developments.
iii. Promote economic development and property utilization while maintaining access to essential infrastructure.
iv. Require public or private street connections when necessary for safe and efficient site access.

B. General Access Standards.

i. No new parcel shall be created unless it has legal access to a public or private street.

ii. Access to landlocked parcels may be established through:

1. A recorded easement sufficient to engineering requirements for two-way traffic.
2. A shared access driveway with adjacent properties sufficient to engineering's requirements.
3. A new private street or service road meeting engineering standards.

C. **Minimum Street Frontage for Subdivision.**

i. If a parcel is subdivided without direct frontage, a cross-access agreement with an adjacent property is required.

D. ~~CI.~~ **Private Streets and Shared Access Drives.**

i. Private streets serving commercial developments must include:

1. A minimum pavement width that meets engineering standards.
2. Legal agreements for maintenance and repair among benefiting properties.
3. Compliance with Section 1111.15, Standards.

ii. **Shared access drives must:**

1. Meet engineering's design standards for traffic.
2. Have clear directional signage and striping to ensure visibility and traffic flow.
3. Connect to at least one public street or service road.

E. ~~CII.~~ **Cross-Access Requirements.**

i. All redevelopments on landlocked parcels must provide a cross-access driveway to adjacent commercial properties, unless infeasible due to:

1. Significant grade changes or environmental constraints.
2. Incompatible land uses that prevent safe shared access.

ii. Where feasible, sites should incorporate a service road or access lane to reduce curb cuts on primary streets.

F. ~~CIII.~~ **Parking and Loading Access.**

i. Shared parking arrangements must be recorded in a cross-easement agreement or a reciprocal easement agreement when access is shared between parcels.

ii. Loading zones and service areas must be accessible from a private street, service road, or dedicated access lane, and not require backing movements onto public roads. Except for the ORD-C & ORD-N commercial land uses.

G. ~~CIV.~~ **Exclusion.**

i. This section does not apply to new residential subdivision of lots.

SECTION 1105.25 TEMPORARY STORAGE CONTAINERS ON CONSTRUCTION AND RENOVATION SITES

A. **Purpose.** To permit the temporary use of storage containers for securing materials and equipment during active construction or renovation, while protecting public safety, minimizing visual impacts, and ensuring timely removal.

B. **Applicability.** Storage containers are permitted only in association with the following:

i. An active construction or renovation project with a valid building permit;
ii. As an Accessory Dwelling Unit (ADU), meeting all residential design standards and ADU requirements;
iii. A construction job site trailer, with an active construction or renovation project with a valid building permit.

C. **Standards.**

i. Permit and Duration
   1. Containers must be included in an approved building permit or a separate temporary use permit.
   2. Storage containers are permitted only for the duration of active construction activity.
   3. Extensions beyond the permitted construction period require approval of a temporary use extension by the Zoning Administrator.

ii. Location.
   1. Containers must be placed on the same lot as the construction or renovation project.
   2. Containers shall not be placed within public rights-of-way, required landscape areas, sidewalks, fire lanes, or designated parking spaces without specific approval.
   3. Containers must comply with required setbacks unless otherwise authorized.

iii. Size and Quantity.
   1. The number and size of containers shall be appropriate to the scale of the construction or renovation project and subject to review by the Zoning Administrator.
   2. For single-family residential construction or renovation, no more than one container, not exceeding 320 square feet in area, shall be permitted unless otherwise approved.

iv. Appearance and Maintenance:
   1. Containers shall be maintained in good condition, free of graffiti, peeling paint, or visible damage.
   2. Only identification signage (maximum 6 square feet per side) is permitted.

v. Prohibited Use as Permanent or Accessory Structures.
   1. Storage containers shall not be used as a permanent structure, accessory structure, or storage building on any property.
   2. Storage containers shall not be used for storage purposes on vacant lots or properties without active construction or renovation.
   3. Storage containers shall not be converted for occupancy, commercial operations, or any other use not directly related to construction or renovation activities under an active permit, with the exception of an Accessory Dwelling Unit (ADU) meeting all residential design standards and ADU requirements.

vi. Exceptions. The Zoning Administrator may approve administrative modifications to these standards in cases of unusual site conditions, large-scale development projects, or for the protection of public health, safety, or welfare.



1107 NON-CONFORMITIES

Whole Section changed, see Attachment Sheet (C) for the original.

Non-Conformities

SECTION 1107.01 PURPOSE OF NONCONFORMITIES

A. This section's regulations are intended to minimize governmental takings of private property rights resulting from the enactment of new land use regulations by permitting certain legal nonconforming uses, lots, and structures to continue to exist.

SECTION 1107.03 UNLAWFUL LOTS, USES, AND STRUCTURES, GENERALLY

A. This chapter does not allow for the perpetuation of uses or structures that were unlawfully established or constructed. Such uses or structures are not "legally nonconforming," but instead remain "unlawful," and are subject to all of the provisions of this Code and any other applicable law. Likewise, this chapter does not legitimize unlawful subdivisions of property.

SECTION 1107.05 LEGAL NONCONFORMING STATUS ATTACHED TO THE LAND

A. The status of a use as a legal nonconforming use shall run with the land and be independent of the identity of the property owner and of the structure in which the nonconforming use is conducted. The status of a structure as a legal nonconforming structure shall run with the land and be independent of the identity of the property owner and of the use conducted within, around, or on such structure.

SECTION 1107.07 UNDERSIZED OR OVERSIZED LOTS

A. Undersized or Oversized Lots Definition. An undersized or oversized lot is any lot that was legally created prior to the enactment of this Zoning Code and has dimensions that do not comply with the minimum or maximum lot area, lot frontage, lot width, and/or lot depth standards required by this Zoning Code.

B. Undersized or Oversized Lots Continuance. An undersized or oversized lot shall be permitted to support structures that are legally situated or were legally situated at their time of erection, provided that the structure is not determined by the City to pose an immediate risk to public safety. An undersized or oversized lot shall be permitted to be put to use by any legal land use, provided that the lot has sufficient frontage on a public street to provide emergency response access that is appropriate for the proposed use, and shall be permitted to continue to be put to use by a legal nonconforming use, subject to the regulations of Section 1107.09 "Nonconforming Uses."

SECTION 1107.09 NONCONFORMING USES

A. **Legal Nonconforming Uses Definition.** For the purposes of this section, a legal nonconforming use shall be any use of a particular lot that fulfills one (1) of the following:

i. The use of that lot was a permitted land use by the previously effective Zoning Code, either by right or as Conditional Use, and was appropriately permitted by the City, but that use of land is no longer a permitted land use in the district in which it is located by this Zoning Code; or

ii. The use of land was deemed a legal nonconforming use by the previously effective Zoning Code, but that use of land is no longer a permitted land use in the district in which it is located by this Zoning Code.

B. **Abandonment of Use.** Whenever a nonconforming use has been discontinued for a period of six (6) months, it shall be considered abandoned, and any subsequent use shall conform to the regulations of this Zoning Code.

C. **Nonconforming Uses Burden of Proof.** When ambiguity exists, it shall be the burden of the property owner to prove to the City that a particular land use on their property, which does not conform to the standards of this Zoning Code, was put into use on a date in which such land use was a permitted use under a former Zoning Code and that such land use has not since been intentionally abandoned.

D. **Nonconforming Uses Continuance.** A legal nonconforming use shall be permitted to continue, provided that all of the following conditions are met:

i. The legal nonconforming use was not considered intentionally abandoned on the effective date of this Zoning Cod or at any point thereafter;

ii. The legal nonconforming use continues to occur on the same lot as was previously occupied by such land use, and the legal nonconforming use is not expanded to another lot;

iii. The specific nature of the legal nonconforming use is not changed, or the specific nature of the legal nonconforming use is changed in a manner consistent with Section 1107.09 (E) "Change of Legal Nonconforming Use"; and

iv. The legal nonconforming use is not expanded in its intensity, including hours of operation, average number of working hours per week, capacity for customers, and footprint of the lot area dedicated to the use, except where specifically permitted by the following subsection, Section 1107.09 (F) "Expansion of Nonconforming Uses."

E. **Change of Legal Nonconforming Uses.** No change to the specifications of a legal nonconforming use shall be permitted where such a change, according to the City, may result in an increased risk to public safety.

F. **Expansion of Nonconforming Uses.** A legal nonconforming use shall not be expanded in its intensity, including in its hours of operation, average number of working hours per week, capacity for customers, and footprint of the lot area dedicated to the use, except that a nonconforming use shall be permitted to expand into a portion of the lot or structure that was manifestly arranged for such use while such legal nonconforming use was a conforming use of the land and was not abandoned, and such expansion shall permit a proportional increase in customer capacity and working hours.

SECTION 1107.11 NONCONFORMING STRUCTURES

A. **Legal Nonconforming Structures Definition.** For the purposes of this chapter, a legal nonconforming structure is any structure that was existing and lawful as of the date of adoption of this Zoning Code, or in the case of amendment to this Zoning Code, then at the time of such amendment, and which does not now conform to the provisions of this Zoning Code or amendment thereto with respect to setback, height, building footprint or lot coverage, impervious coverage percentage, building type, or architectural design standards.

B. **Legal Nonconforming Structures Continuance.**

i. A legal nonconforming structure shall be permitted to continue existing, provided that all of the following conditions are met:

1. The legal nonconforming structure does not pose an immediate risk to the public safety, as determined by the City;
2. The legal nonconforming structure is not reconstructed, repaired, or expanded, except according to the provisions described in this section.

ii. All existing portions of a legal nonconforming structure may be put to use, provided that such use is not illegal and provided that such use does not violate this Zoning Code, including use specific standards, and does not violate any other City, County, State, or Federal statute.

C. **Reconstruction or Repair of a Legal Nonconforming Structure.** The reconstruction, repair, or maintenance of a legal nonconforming structure shall be permitted to occur, provided that the nonconforming feature is not enlarged, increased, or extended more than 50 % of the structure's then fair market value; that no new nonconforming feature is created; and that reconstruction or repair occurs within six (6) months of the legal nonconforming structure's disrepair, destruction, or demolition. If reconstruction, repair, or maintenance does not occur within six (6) months, a written request for extension may be submitted to a designee of the Development Department.

D. **Expansion of a Legal Nonconforming Structure.** A legal nonconforming structure may be expanded or reduced, provided that the expansion or reduction does not intensify the nonconforming nature of the structure and does not result in any additional nonconforming feature. For example, a structure that is legally nonconforming because it has a lesser front setback than required by this Zoning Code in the district in which it is located may be expanded, provided that the expansion does not occur within the required front yard setback and does not violate any other structure focused provision, including height limits, building footprint limits, impervious coverage limits, minimum setbacks from lot lines, or design standards.

SECTION 1107.13 OTHER NONCONFORMITIES

A. **Nonconforming Signs Regulated Elsewhere.** Nonconforming signs are regulated by Section 1105.03 "Nonconforming Signs."

B. **Nonconforming Parking.**

i. Any nonconforming parking behavior, including the parking of vehicles on areas of a lot where prohibited by the standards in this Zoning Code, shall be considered an immediate violation of this Zoning Code.

ii. Any nonconforming impervious surface coverage caused in part by parking areas shall be regulated as a parking area infrastructure nonconformity according to the subsection below.

iii. All nonconforming parking area infrastructure on a lot, such as not providing the correct number of bicycle parking spaces or electric vehicle charging stations or building a number of parking spaces in excess of parking maximums, shall be permitted to continue, provided that such nonconformities are brought into conformity during any of the following occurrences:

1. The complete reconstruction of the principal structure on the lot, or the piecemeal reconstruction of such entire structure over the course of two (2) years or less; or
2. A net increase in vehicle parking area on the lot.



1109 ADMINISTRATION AND PROCEDURES

Administration and Procedures

SECTION 1109.01 REVIEW AND APPROVALS SUMMARY

A. This Chapter sets forth the powers and duties of the Planning and Zoning Administrator and the Planning and Zoning Board relative to the administration and enforcement of this Zoning Code.

B. The following table summarizes the applications and role of each of the administrative, quasi-judicial, quasi-legislative, and legislative reviews set forth in this Title and the responsible reviewing party:

TABLE 1109.01A

APPLICATION TYPE	ZONING ADMINISTRATOR	PLANNING AND ZONING BOARD (PZB)	COUNCIL
ZONING CERTIFICATES			
Application Submitted To:	X		
Decision By:	A		
Appeal To:		QJ	
VARIANCES			
Application Submitted To:	X		
Decision By:		QJF	
Appeal To:			
CONDITIONAL USES			
Application Submitted To:	X		
Decision By:	A	QJF (optional)	
Appeal To:			

TABLE 1109.01A			
APPLICATION TYPE	ZONING ADMINISTRATOR	PLANNING AND ZONING BOARD (PZB)	COUNCIL
SIMILAR USE DETERMINATION			
Application Submitted To:	X		
Decision By:		QJ	
Appeal To:			QJ
SITE PLAN REVIEW AND DESIGN REVIEW			
Application Submitted To:	X		
Decision By:	A Standard Plan	QJ Major Plan	
Appeal To:			
ZONING TEXT AND MAP AMENDMENT			
Application Submitted To:	X		X
Decision By:	A	QL	LS
Appeal To:			

KEY	
A	Administrative Decision
QJ	Quasi-Judicial Decision
QJF	Quasi-Judicial Decision-Final Appealable Decision
QL	Quasi-Legislative Decision
LS	Legislative Decision
X	Responsible for Application Intake and Determination of Completeness

SECTION 1109.03 PLANNING AND ZONING ADMINISTRATOR

A. Unless otherwise directed by the Director of Development, the Planning and Zoning Administrator shall have the following responsibilities and powers:

i. Enforce the provisions of this Code and interpret the meaning and application of its provisions;

ii. Receive, review and make determinations on applications for zoning certificates;

iii. Issue zoning certificates as provided by this Code and keep a record of same with notations of special conditions involved;

iv. Review and process standard site and design plans pursuant to the provisions of this Code;

v. Make determinations on whether violations of this Code exist, determine the nature and extent thereof, and notify the owner in writing pursuant to the procedures in this Code;

vi. Conduct inspections of buildings and uses of land to determine compliance or noncompliance with this Code;

vii. Review, process, and approve or deny applications for conditional use permits pursuant to the provisions of this Code.

viii. Maintain permanent and current records required by this Code, including, but not limited to, the Zoning Map, zoning certificates, inspection documents and records of all variances, amendments and Conditional Uses, which shall be made available for use of the Council and Planning and Zoning Board and the public;

ix. Determine the existence of any violations of this Code and enforce this Code;

x. Revoke a Zoning Certificate or approval issued contrary to this Code or based on a false statement or misrepresentation on the application;

xi. Administer the Flood Plain regulations set forth under Chapter 1103 of this Code; and

xii. Such other administrative duties as specifically granted to them from time to time by the Mayor or the Director of Development

SECTION 1109.05 PLANNING AND ZONING BOARD

A. The City of Reynoldsburg Planning and Zoning Board is established and organized in accordance with Section 7.01, Article VII of the Charter.

B. The Planning and Zoning Board shall have the following powers and duties under this Code and in furtherance of the Charter:

i. Initiate advisable Zoning Map changes, or changes to the test of the Code where the same will promote the best interest of the public in general through recommendation to the City Council;

ii. Review all proposed amendments to this Code, whether map amendment or text amendment;

iii. Review plats and subdivision regulations in accordance with Chapter 1111;

iv. Review and approve or deny approval of certificates of appropriateness, as provided in Chapter 1109.19 hereof;

v. Review of site plans in accordance with Chapter 1109.17 hereof;

vi. Establish such reasonable conditions, regulations, and standards in the approval of a district change, site plan and design approval, certificate of appropriateness, or other official action as necessary to ensure a project complies with the purpose and intent of this Code and of the ordinances of the City;

vii. Exercise any powers, duties or functions provided to municipal planning Boards by state law that do not otherwise conflict with City Council's ordinances or resolutions, this Code or the Charter; and

viii. Such other official action consistent with the powers, duties, or authorities of the Board as set forth by the provisions of the Charter, this Code, or assigned by City Council.

ix. To permit exceptions to and variances from the provisions of this Code, as provided in Chapter 1109.11 thereof;

x. To authorize or deny a conditional use permit where the Planning and Zoning Administrator has forwarded an application to the PZB for review;

xi. To authorize the operation of a similar use through the similar use determination process set forth under Chapter 1109.~~17~~5 hereof;

xii. To establish such reasonable conditions, regulations, and standards in the approval of a conditional use, variance or exception, or other official action as necessary to ensure that the design, construction, and operation of the use or structures subject to such approval are carried out consistent with the purpose and intent of this Code and of the ordinances of the city;

xiii. To make interpretations, upon request of the Planning and Zoning Administrator or upon appeal from any property owner of the city, of the meaning and application of the provisions and illustrations of this Code and of the Zoning Map of the city including:

1. Determination of the exact boundary lines of districts or zones;
2. Determination of the meanings of the permitted uses and conditional uses as listed in the districts or zones;
3. Determination of the rules applicable to the filing of applications, review procedures, and permit issuances; provided however, the PZB shall not make such interpretations as the City Attorney may determine should be a matter of legislative action by City Council;

xiv. To grant or deny a zoning certificate when the question of the issuance of such certificate is referred to it by the Planning and Zoning Administrator, or when the provisions of this Zoning Code indicate that the Board shall consider such question;

xv. To overrule or amend any official action of the Planning and Zoning Administrator when an applicant makes an appeal for such relief and when the Board determines that such action has been contrary to the intent and spirit of this Code. For such purpose, the Board may make null and void any zoning certificate issued or any action taken by the Planning and Zoning Administrator by notifying the Planning and Zoning Administrator and the principal interested party or parties in writing;

xvi. To hear appeals from the Property Maintenance Code as provided for in that code; and

xvii. Such other official action consistent with the powers, duties, or authorities of the Board as set forth by the provisions of the Charter this Code or assigned by City Council.

C. In furtherance of its duties and powers under this Code and the Charter, the Planning and Zoning Board shall operate in accordance with the following procedures:

i. Four (4) members present shall constitute a quorum of the Planning Board.

ii. All actions taken by the Planning and Zoning Board shall be initiated by motion and shall be recorded in the minutes.

iii. The Planning and Zoning Board shall keep minutes of its proceedings showing the vote of each member upon each application or questions, or, if a member is absent or fails to vote, the minutes shall indicate such fact.

iv. Four (4) affirmative votes shall be required for the adoption of any motion.

SECTION 1109.07 APPLICATIONS

A. All requests for a decision or approval under this Code begins with the property owner or agent thereof filing an application with the Planning and Zoning Administrator on forms provided from time to time.

B. A complete application shall include all required submissions and the payment in full of all applicable fees, which shall be proposed from time-to-time by the Mayor and approved by Council.

C. The Planning and Zoning Administrator will determine whether an application is complete and is ready to be processed. In some instances, an additional application may be deemed necessary by the Planning and Zoning Administrator and, if so, an application will not be deemed to be complete unless and until the all applications are submitted and reviewed and determined to be in accordance with all submittal requirements. The applicant will be notified in writing of any deficiencies in the completeness of the application and shall have 30 days from the date thereof to complete the application or the application will be deemed null and void.

D. If a decision on the application is to be made by someone other than the Planning and Zoning Administrator, then the complete application shall be forwarded to the appropriate body for review in accordance with this Code.

E. Unless otherwise prescribed by this Code or requested by the applicant, the applicable decision-making body or administrator shall render a decision on all applications within sixty (60) days from the original hearing.

F. The Planning and Zoning Administrator, in consultation with the Director of Development, Planning and Zoning Board, or any additional City staff shall publish application procedures and additional requirements in a document to be known as the Development Handbook, which shall be incorporated here by reference. The Planning and Zoning Administrator shall make the most current version of this document available to the public in a manner that is easily accessible.

G. In the interest of timely and efficient administration of the provisions of this Code, applicants may submit, and the Board may take action upon, concurrent applications for conditional uses, similar use determinations, variances, and other matters on which the Board is granted authority by this Code. All

such concurrent applications shall be submitted in conformance with the applicable provisions of this Code. The Board shall not take such concurrent action if it determines that such concurrent action is not in the best interest of the city.

H. Unless otherwise prescribed by this code or requested by the applicant, the Board shall render a decision on all applications within sixty (60) days from the original hearing.

I. At staff's discretion, a presubmittal meeting can be required.

SECTION 1109.09 ZONING CERTIFICATE

A. The submission and review of zoning certificates shall be conducted in accordance with the provisions set forth hereunder.

B. No use of land, building or structure and no construction or alteration of an existing use, building, or structure shall commence until a zoning certificate is issued by the Planning and Zoning Administrator certifying that the intended use of the premises has been documented, reviewed, and approved in conformance with the provisions of this Zoning Code. **This includes changes of the name and/or ownership of a business.** A zoning certificate shall only be issued by the Planning and Zoning Administrator subsequent to completion of all procedures and approvals required by this Code. The Planning and Zoning Administrator shall not be required to issue a zoning certificate where the subject property is not in compliance with the Zoning Code, Building Code, or Property Maintenance Code.

C. Except as otherwise provided in this code, a zoning certificate shall be required before:

i. **Locating, erecting, constructing, reconstructing, altering or moving any building/structure, including accessory structures such as a sign or fence;**

ii. **Occupying or using land or a building or changing the use of land or of a building in whole or in part for a different use;**

iii. **Changing a nonconforming use to a different use of extending or expanding a nonconforming use or structure.**

iv. **Where a non-conforming use has been discontinued, meaning the structures containing the use has remained vacant, unoccupied, unused or has ceased the daily activities or operations which had occurred for a period of 6 or more continuous months, the non-conforming use shall be permanently terminated. Please refer to Section 1107 for additional information on Non-Conformities.**

D. An application for a zoning certificate shall be submitted to the Planning and Zoning Administrator and shall include, a plan or plans drawn to scale, showing:

i. The dimensions and the shape of the lot to be used or built upon;

ii. The sizes and locations of existing structures and uses on the lot;

iii. The dimensions and locations of proposed structures and uses;

iv. The heights of existing and proposed structures;

v. A statement detailing the proposed use, which will be signed by the applicant; and

vi. Such other documentation as may be necessary to determine conformance with the provisions of this Code.

E. When the Planning and Zoning Administrator determines that an application for a zoning certificate does not comply with the provisions or intent of this Code, or that an application does not provide sufficient information to determine compliance with this Code, then the Planning and Zoning Administrator shall deny the application and shall not issue a zoning certificate.

F. The Planning and Zoning Administrator may refer zoning certificates to the Planning and Zoning Board for review.

G. Within fourteen (14) days of the Planning and Zoning Administrator's denial of a zoning certificate, the application may file a written appeal with the PZB. Any applicant who does not file an appeal within (14) days of the date of denial by the Planning and Zoning Administrator shall forfeit their right to appeal the Planning and Zoning Administrator's decision.

SECTION 1109.11 VARIANCES

A. The provisions set forth hereunder shall apply to the review and grant of variances under this Code.

B. An applicant seeking a variance shall submit a written request for variance on forms provided by the Planning Zoning Administrator together with the applicable fee. In addition to information relating to the subject property and the applicant, the request for a variance shall include the following information:

i. The name, address, and telephone number of the property owner (s) and owner's agent(s);

ii. The legal description, address, tax district and parcel number of the property;

iii. A description of the nature of the variance requested and a statement demonstrating the extent to which the requested variance conforms to the standards for variance in this Code;

iv. A statement of hardship; and

v. Such other information and exhibits as may be appropriate to establish the facts of the appeal and the grounds for relief.

C. Before approving or denying a request, the PZB shall hold at least one public hearing on the matter. The PZB shall cause notice of the hearing to be made to the public by seven (7) days advance publication, in a newspaper of general circulation in the City, of the place, time, date and the nature of the variance applied for. The PZB shall also cause the subject property to be posted with a notice of hearing at least seven (7) days prior to the day of the hearing. The notice of hearing shall state thereon the nature of the request and the time and place of the public hearing.

D. No variance from the strict application of the provisions of this Code shall be granted unless the PZB makes specific findings of fact, based on the evidence presented to it, which support conclusions that

the variance conforms to the following standards:

i. The variance is in accord with the general purpose and intent of the regulations imposed by this Code in the district in which it is located, and shall not be injurious to the area or otherwise detrimental to the public welfare.

ii. The variance will not permit the establishment of any use which is not otherwise listed as a permitted use or a conditional use in the zone or district in which the subject property is situated.

iii. There exist special circumstances or conditions, fully described in the findings, applicable to the land or structures for which the variance is sought, which are peculiar to such land or structures and which do not apply generally to land or structures in the area, and which are such that the strict application of the provisions of this Code would deprive the property owner of the reasonable use of such land or structures. ~~There must be a deprivation of the beneficial use of land, as opposed to mere loss in value as justification for the variance.~~

iv. **There is a deprivation of the beneficial use of land, as opposed to mere loss in value as justification for the variance.**

v. There is proof of hardship or practical difficulty created by the strict application of this Code, beyond simply a showing that greater profit will result if the variance is granted. Economic hardship is not grounds for the variance. Furthermore, the hardship complained of is not self-created nor is it established on this basis by one who purchased with or without knowledge of the restrictions. The hardship results from the application of this Code and is suffered directly by the property in question.

vi. The variance is necessary for the reasonable use of the land or building, and the variance as granted is the minimum variance that will accomplish this purpose.

vii. The variance will not impair an adequate supply of light and air to adjacent property, substantially increase the congestion in the public streets, increase the danger of fire, endanger the public safety, or substantially diminish or impair property values of the adjacent area.

viii. The variance will not confer on the property owner any special privilege that is unduly denied by this Code to other land, structures, or buildings in the same district.

ix. No nonconforming use of neighboring land or structures in the same district and no permitted or nonconforming use of land or structures in other districts are considered as grounds for approval of the variance.

x. The variance is not a matter of convenience when other remedies are available within the provisions of this Code.

E. In granting any variance, the PZB shall establish such conditions as are necessary to secure substantially the objectives of this Code. Any violation of such conditions and safeguards, when they have been made a part of the terms under which the variance has been granted, shall be deemed a violation of this Code.

F. No action of the PZB granting a variance shall be valid for a period longer than twelve (12) months from the date of such action unless the zoning certificate is obtained within such period, and the erection or alteration of a structure is started or the use is commenced within such period, provided however, notwithstanding anything to the contrary herein, such twelve (12) month period may be extended by the Planning and Zoning Administrator upon the demonstration by the applicant that any delay in the commencement of the erection or alteration of a structure is the result of factors beyond

the control of the applicant, in which case, the Planning and Zoning Administrator may elect to grant an extension of up to six (6) months.

G. The PZB shall not accept a new application for a variance that has been previously denied within twelve (12) months of denial.

SECTION 1109.13 CONDITIONAL USES

A. Reviews of applications for conditional uses shall be conducted by the Planning and Zoning Administrator in accordance with the provisions set forth under this section; provided however, if, the Planning and Zoning Administrator determines in his or her professional opinion that an application warrants public review, then the Planning and Zoning Administrator shall forward such application to the PZB for review. The intent of the procedure for authorizing a conditional use is to set forth the development standards and criteria for locating and developing conditional uses in harmony with the character of the surrounding area, conditions of development and with regard to appropriate laws.

B. In addition to such standard information regarding the subject property and the applicant, the application for a conditional use shall contain the following:

i. Description of the zoning district and existing uses of adjacent lots;

ii. A statement of the conditional use for which the application is submitted,

iii. Including a description of the activities proposed on the subject property, the goods and services sold or provided, hours of operation, anticipated number of employees, nature and volume of delivery activity, and other information which will assist the PZB with understanding the nature of the proposed use and its potential impacts;

iv. A plan of the proposed site and improvements showing the proposed location of all structures, parking and loading areas, streets and traffic accesses, open spaces, refuse and service areas, utilities, signs, yards, landscaping, and other relevant features;

v. A narrative statement describing the compatibility of the proposed use with the existing uses of adjacent lots and with the Land Use Plan, including an evaluation of the effects on adjoining lots of such elements as traffic circulation, noise, glare, odor, fumes, vibration, and storm water, and any measures proposed to mitigate such effects;

vi. A narrative addressing each of the applicable criteria set forth in the standards and requirements for all conditional uses set forth below and, as applicable, the supplementary requirements for special uses set forth under the applicable district or zone regulations.

vii. Such other information as the PZB deems necessary to make a determination of the compliance of the proposed use with the applicable standards and regulations. Such additional information may include, but shall not be limited to:

1. Traffic impact analysis;
2. Storm water impact analysis; and/or
3. Utility impact analysis.

C. When review of an application for a conditional use permit is forwarded by the Planning and Zoning Administrator to the PZB, before approving or denying a request for a conditional use, the PZB shall hold at least one public hearing on the matter. The PZB shall cause notice of the hearing to be made in accordance with its standard process for providing notice of a hearing. The notice of hearing shall state thereon the nature of the request and the time and place of the public hearing.

D. Upon reviewing an application for a conditional use, the Planning and Zoning Administrator or the PZB, as applicable, shall consider whether the application provides adequate evidence that the proposed conditional use is consistent with the following standards:

i. The proposed use shall be in harmony with the existing or intended character of the zone or district and nearby affected zones and districts and shall not change the essential character of the zones and districts;

ii. The proposed use shall not adversely affect the use of adjacent property;

iii. The proposed use shall not adversely affect the health, safety, morals, or welfare of persons residing or working in the neighborhood;

iv. The proposed use shall be served adequately by public facilities and services such as, but not limited to, roads, police and fire protection, storm water facilities, water, sanitary sewer, and schools;

v. The proposed use shall not impose a traffic impact upon the public right-of-way significantly different from that anticipated from permitted uses of the zone or district;

vi. The proposed use shall be in accord with the general and specific objectives, and the purpose and intent of this Zoning Code and the Land Use Plan and any other plans and ordinances of the City;

vii. The proposed use complies with the applicable specific provisions and standards of this Code;

viii. The proposed use shall be found to meet the definition and intent of a use specifically listed as a conditional use in the zone or district in which the subject property is situated.

E. After review of the application and any additional information presented by the applicant, the Planning and Zoning Administrator or the PZB, as applicable, shall take action to:

i. Approval the conditional use, based upon findings of compliance with the standards and requirements of this Code and subject to conditions to ensure compliance with this Code; or

ii. Deny the conditional use, upon finding that the application does not comply with the provisions of this Code

F. In approving a conditional use, the Planning and Zoning Administrator or the PZB, as applicable, may impose such conditions as deemed necessary to protect the public welfare, preserve the purpose and intent of this Code, to protect the character of the surrounding properties and neighborhood affected by the proposed use, and to mitigate the special impacts of the use. Such conditions may include, but shall not be limited to:

i. Locations, setbacks, and configurations of structures and of uses of interior and exterior space;

ii. Screening comprised of landscaping, walls, fencing or other materials or construction;

iii. Access points and traffic management provisions, including those impacting vehicular and pedestrian access, and the locations and design of parking facilities;

iv. Noise control measures, including those regulating loudspeakers or irregular vehicular or equipment noise;

v. Other features of construction, including but not limited to paving and parking, signs, and landscaping;

vi. Hours and method of operation;

vii. Maintenance of the site, structures, and landscaping;

viii. Means of controlling glare, vibration, odors, dust, smoke, hazardous materials, refuse matter, water-carried waste, and storm water; and

ix. A time limit for operation of the use, if temporary operation is determined to be a typical characteristic of the proposed use or otherwise appropriate given unique circumstances of the proposed use.

G. Subsequent to approval by the Planning and Zoning Administrator or the PZB, and compliance with all applicable conditions of such approval and of this Zoning Code, the Planning and Zoning Administrator shall issue a zoning certificate stating the conditional use and all conditions of its approval.

H. Approval of a conditional use shall be void upon the occurrence of any or all of the following:

i. The applicant fails to commence construction of the structure in which the approved conditional use is to be conducted within one (1) year of the date of approval;

ii. The applicant fails to commence the operation of the conditional use within six (6) months of the date of the approval, where such use is to be conducted in an existing structure; and/or

iii. The conditional use is operated in a manner which violates any condition of the approval.

I. The Planning and Zoning Administrator shall review all approved conditional use permit applications six (6) months after final action to determine if the approved use is in operation and otherwise in compliance with all conditions of approval. Upon such six (6) month review the Planning Zoning Administrator shall proceed in accordance with the circumstances outlined below:

i. If the Planning and Zoning Administrator finds the conditional use to be in operation and in compliance with the conditions of approval, the Planning and Zoning Administrator shall notify the PZB of such compliance.

ii. If the Planning and Zoning Administrator finds that construction has not begun, the Planning and Zoning Administrator shall record that information for an additional six (6) month review, and shall notify the of such inaction.

iii. If the Planning and Zoning Administrator finds a use in an existing structure or building not to be in operation, the permit and zoning certificate shall be deemed revoked and the Planning and Zoning Administrator shall notify the applicant of such revocation as well as the PZB. Upon such revocation, the applicant shall have the right to appeal that decision of the Planning and Zoning Administrator to the PZB and request the PZB allow up to one (1) additional six (6) month period to begin operation following the administrative appeal procedure.

J. Whenever the Planning and Zoning Administrator determines that a conditional use is being operated

in a manner that violates any condition of the use's approved permit, the permit and zoning certificate shall be considered revoked. The Planning and Zoning Administrator shall notify the permit holder as such, who shall immediately discontinue operation of the use:

i. If this determination is made in conjunction with the six (6) month review procedure for an approved permit, the Planning and Zoning Administrator shall also notify the PZB. The applicant shall have the right to appeal this determination of the Planning and Zoning Administrator to the PZB following the administrative appeal procedure. Upon appeal, the PZB shall (a) approve upholding the revocation, (b) overturn the revocation and reapprove the conditional use permit or (c) overturn the revocation and modify of the conditions of approval.

ii. If this determination is made at any other time, the Planning and Zoning Administrator shall notify the PZB. The applicant shall have the right to appeal this determination of the Planning and Zoning Administrator following the normal administrative appeal procedure. Upon appeal, the PZB shall have the power to uphold the revocation or reapprove the permit.

K. If this determination is made in conjunction with the six (6) month review procedure for an approved permit, the Planning and Zoning Administrator shall also notify the PZB. The applicant shall have the right to appeal this determination of the Planning and Zoning Administrator to the PZB following the administrative appeal procedure. Upon appeal, the PZB shall (a) approve upholding the revocation, (b) overturn the revocation and reapprove the conditional use permit or (c) overturn the revocation and modify of the conditions of approval.

L. The conditions of an approved conditional use permit may be amended upon request of the permit holder. Any amendment proceeding shall be conducted in accordance with the procedures, requirements, and standards applicable to review of a new conditional use permit.

M. Subsequent to disapproval of an application for a conditional use permit, a period of at least one (1) year shall elapse before another application for the same conditional use at the location may be considered by the Planning and Zoning Administrator or the PZB.

N. Appeals of decisions of the Planning and Zoning Administrator may be taken to the PZB pursuant to the procedures set forth under Chapter 1109.23 hereof. Appeals of decisions of the PZB may be taken to the Franklin County Court of Common Pleas as allowed by Ohio Revised Code Chapter 2506.

SECTION 1109.15 SIMILAR USE DETERMINATION

A. When an application for a zoning certificate is submitted for a use which, in the opinion of the Planning Administrator, is not listed as a permitted use or a conditional use in any district, then the Planning Administrator shall refuse to issue a zoning certificate.

B. When a particular use is not specifically listed in this Zoning Code and it is unclear whether the use is permitted, the provisions established in this Section allow the Planning and Zoning Administrator, by formal action, to determine whether or not a proposed use is similar to a permitted or conditionally permitted use and whether such proposed use may be permitted in a particular Zoning District.

C. **Approving Authority.** The Planning and Zoning Administrator shall be the designated Approving Authority for Similar Use Determinations.

D. **Approval Findings.** In determining "similarity," the Approving Authority shall make all of the following findings:

i. Such use is not listed in any other zone or district as a permitted use;

ii. Such use has characteristics and impacts consistent with those of one (1) or more of the permitted uses in the district; and such use has characteristics and impacts more consistent with those of the permitted uses of the zone or district than with the permitted uses of any other district;

iii. The establishment of such use in the zone or district will not significantly alter the nature of the district;

iv. Such use does not create dangers to health and safety and does not create offensive noise, vibration, dust, heat, smoke, odor, glare, traffic, or other objectionable impacts or influences to an extent greater than normally resulting from permitted uses listed in the zone or district; and

v. Such use does not typically require site conditions or features, building bulk or mass, parking lots or spaces, or other requirements dissimilar from permitted uses; and the typical development of site and buildings for such use is compatible with those required for permitted uses and can be constructed in conformance with the standard regulations for height, lot dimensions, setbacks, and other provisions of the zone or district.

E. A similar use may be heard by the PZB in accordance with the notice provisions applicable to a conditional use if, in the professional opinion of the Planning and Zoning Administrator, such determination warrants review by the adjudicative body.

F. Based upon the application of the foregoing factors, the PZB shall determine whether a proposed use should be or should not be determined to be a similar use for the district or zone. Appeals of any similar use determination shall be heard by City Council in accordance with the appeals provisions set forth under Chapter 1109.25~~3~~ hereof.

G. Following the approval of any similar use determination, the Planning and Zoning Administrator shall conduct the six (6) month review applicable to conditional uses and make such determinations and reports as provided for under Chapter 1109.15~~3~~(J) hereof.

H. Within fourteen (14) days of the PZB's denial of a similar use determination, the applicant may file a written appeal with City Council. Any applicant who does not file an appeal within fourteen (14) days of the date of denial by the PZB shall have waived such right to appeal, and the decision of the PZB shall become final.

SECTION 1109.17 SITE PLAN AND DESIGN REVIEW

SITE PLAN AND DESIGN REVIEW	WHEN APPLICABLE….
Minor Site Plan and Design Review	Any non-residential development, or site improvement which involves under five thousand square feet (5,000SF) of surface area, structure and/or building, other than a fence or accessory structure.
Major Site Plan and Design Review	Any development, which involves more than five thousand square feet (5,000SF) of surface area, structure and/or building; Any development impacting or adjacent to an environmentally sensitive feature; Any development which in the professional opinion of the Planning and Zoning Administrator, warrants public review.

A. Applicability. Except as otherwise provided herein or elsewhere in this Zoning Code, minor site plan and design review or major site plan and design review is required in accordance with the provisions contained herein. The Planning and Zoning Administrator shall conduct minor site plan and design review. The Planning and Zoning Administrator shall conduct major site plan and design review for all zoning districts except for ORD-C and ORD-N. The Planning and Zoning Board shall conduct major site plan and design review for all projects located in the ORD-C and ORD-N districts. Any project triggering a major site plan may be required to combine all parcels on which the project is located.

B. Minor Site Plan and Design Review. Minor site plan and design review shall be required for any non-residential development or site improvement which involves under five thousand square feet (5,000 SF) of surface area, structure and/or building other than a fence or accessory structure.

C. Minor Site Plan and Design Review—Application. An application for minor site plan and design plan review shall be submitted to the Planning and Zoning Administrator and shall include the following information:

i. A vicinity map showing the location of the proposed development in relationship to the surrounding area including major thoroughfares.

ii. A site plan illustrating the following:

1. Shall be signed and sealed by a professional engineer, architect, or landscape architect registered with the State of Ohio.
2. Each sheet shall contain a title block with the name of the project and the address of the project.
3. The dimensions of property lines, parcel dimensions and adjoining rights-of-way.

4. The current zoning of the parcel and all adjacent parcels.
5. The location of proposed buildings and structures.
6. The location of existing water bodies, streams, drainage ditches, stands of trees and other pertinent features within one hundred fifty feet (150 ft.) of the proposed development.
7. Setbacks and building separations shall be noted in accordance with zoning requirements.
8. A landscape ~~concept~~ plan, including approximate location of all new landscape material and plantings, that addresses the applicable district requirements.
9. A transportation and parking plan, including location and number of all parking and loading spaces and location of all proposed walkways and bike/pedestrian access points, that addresses the applicable district requirements.

iii. An architectural plan, including exterior building materials, colors, and lighting features, that addresses the applicable district requirements; and

iv. Such other information as the Planning and Zoning Administrator or Planning and Zoning Board may require so as to carry out the full intent of the Zoning Code. Any applicant requesting review of a major site and design plan shall submit to the Planning and Zoning Administrator an application form and as many copies of the required materials as may be required by the Planning and Zoning Administrator or the Planning and Zoning Board. The Board shall act upon the application for major site and design plan review based upon the adopted regulations, standards, and design guidelines of the City.

D. Minor Site Plan and Design Review—Review and Approval or Denial. Any applicant requesting minor site plan and design review shall submit to the Planning and Zoning Administrator an application form and as many copies of the required materials as the Planning and Zoning Administrator may require. Within thirty (30) days of filing a complete application, the Planning and Zoning Administrator shall act upon the application for minor site plan and design review based upon the applicable district regulations, and other applicable regulations, standards, and design guidelines of the City. If the Planning and Zoning Administrator determines that the proposed development complies with the applicable standards of the applicable districts, then, the Planning and Zoning Administrator shall issue a zoning certificate. If the Planning and Zoning Administrator determines that the proposed development does not comply with the applicable standards of the applicable district, then the Planning and Zoning Administrator shall deny the application and state the reasons for such denial in writing.

E. Major Site Plan and Design Review. Major site plan review shall be required for the following forms of development in any district:

i. Any development, which involves more than five thousand square feet (5,000SF) of surface area, structure and/or building;

ii. A development impacting or adjacent to an environmentally sensitive feature; or

iii. A development which in the professional opinion of the Planning and Zoning Administrator, warrants public review.

F. Major Site Plan and Design Review—Application. An application for major site plan and design review shall be submitted to the Planning and Zoning Administrator and shall include the following information:

i. All materials required for minor site plan and design review as set forth above;

ii. A basic utility plan;

iii. Where applicable an engineers staff report will be conducted by the City Engineer, where further recommendations could be made. The cost for any engineering study or report prepared by and/or for the City shall be assumed by the Applicant as part of the cost of the application;

iv. Where required a plot-grade utility plan shall be submitted to the Director of Development for PZB review and approval subsequent to and in conformance with an approved site plan;

v. Such other information as the Planning and Zoning Administrator or Planning and Zoning Board may require so as to carry out the full intent of the Zoning Code. Any applicant requesting review of a major site and design plan shall submit to the Planning and Zoning Administrator an application form and as many copies of the required materials as may be required by the Planning and Zoning Administrator or the Planning and Zoning Board. The Board shall act upon the application for major site and design plan review based upon the adopted regulations, standards, and design guidelines of the City.

G. Site Plan and Design Review—Conditions. In accordance with the site plan and design review procedures contained in this chapter, the Planning and Zoning Administrator or the Planning and Zoning Board, as applicable, may place such reasonable conditions on the approval of a site plan that may be required to address the standards for review set forth herein or are otherwise consistent with the purpose and intent of this Zoning Code.

H. Approved Site Plan—Modifications. The Director of Development or his or her designee, may approve such adjustments to an approved site plan as are required for engineering purposes such as proper function of utilities or to accommodate soil conditions. Such adjustments shall meet the following conditions:

i. The adjustment is required in order to ensure the life-safety, proper function of the site utilities or building, or to comply with the regulations of a State or Federal agency;

ii. The adjustment is as minimal as possible to correct the engineering issue;

iii. The adjustment does not increase the impervious surface on the subject property by more than10% as compared to the impervious surfaces contemplated on the approved site plan or in response to a public safety concern initiated by the fire department or law enforcement agency with jurisdiction.

iv. The adjustment shall not be used to add any additional uses or tenants;

v. The adjustment does not increase the number of curb cuts on a public street; and

vi. The adjustment does not violate any specific condition of the approved site plan.

I. Approved Site Plan—Amendment. Any amendment to an approved site and design plan shall be considered by the applicable approving body based on the standards applicable to such amendment; provided however, any amendment that in the direction of the Planning and Zoning Administrator constitutes a minor amendment may be reviewed and approved by the Planning and Zoning Administrator even if such amendment pertains to a major site and design plan.

J. Site Plan—Appeals. The Planning and Zoning Board shall hear all appeals of individuals who are directly affected by a decision of the Planning Board or Planning and Zoning Administrator when such

appeal is properly and timely filed as required by this chapter. An applicant refused such certificate shall appeal in writing to the PZB within thirty (30) days of the date of refusal by the applicable decision-making body. The PZB shall set a date for a hearing on the appeal and render a decision on the appeal within thirty (30) days of the receipt of such written request.

SECTION 1109.19 CERTIFICATE OF APPROPRIATENESS—OLDE REYNOLDSBURG DISTRICTS

A. Certificate of Appropriateness (COA). A certificate of appropriateness must be obtained prior to commencing new construction or any exterior remodeling, reconstruction or other exterior building modifications of non-residential structures located within the Olde Reynoldsburg Districts. The Planning and Zoning Administrator shall not issue a zoning certificate prior to the Planning and Zoning Board review and approval of a certificate of appropriateness in accordance with the provisions of this chapter. The Planning and Zoning Administrator shall review all zoning certificate applications for projects within the design review districts exempted from a COA by this section or any other section of this Zoning Code, for compliance with the standards of Section design guidelines adopted by the Planning and Zoning Board or City Council. If in the professional opinion of the Planning and Zoning Administrator, the proposed project does not meet those standards or design guidelines, a certificate of appropriateness from the Planning and Zoning Board shall be required.

B. Application for COA. All applications and attachments for a COA shall be made to the Planning and Zoning Administrator at least twenty-one (21) days prior to a regularly scheduled meeting of the Planning Board.

C. Exception to COA. A certificate of appropriateness shall not be required in the case of customary building maintenance activities that do not alter the building material types or exterior colors.

D. COA Review. The Planning and Zoning Board shall review an application for a COA to determine if proposed new construction or alteration to an existing non-residential structure promotes, preserves and enhances the overall architectural character and integrity of the Olde Reynoldsburg Neighborhood District or Olde Reynoldsburg Commercial District, as applicable, and to endeavor to assure that the proposed structure or alteration would not be at variance with existing non-residential structures within such district. In considering the new construction or alteration, the Planning and Zoning Board shall evaluate the application based whether the proposal:

i. Enhances the attractiveness and desirability of the district;

ii. Encourages the orderly and harmonious development in a manner in keeping with the overall character of the district.

iii. Improves residential amenities in any adjoining residential neighborhood.

iv. Enhances and protects the public and private investment in the value of all land and improvements within the district.

v. Satisfies the applicable guidelines set forth under Chapter 1103; and

vi. Overall effects of the project or development on the appearance and environment of the district.

E. **Time for Decision on COA.** The Planning and Zoning Board shall render a decision on all applications within sixty (60) days from the original hearing of the Planning Board unless additional time is requested by the applicant. Upon approval by the Planning and Zoning Board, the Planning and Zoning Administrator shall issue a COA to the applicant.

F. **Other Land Use Approvals.** An application for a COA in which the design under consideration would require a variance granted by the Planning and Zoning Board or a site plan and design review by the Planning and Zoning Board prior to construction shall not be considered until a final determination has been made on all required variances or site plan and design reviews. If during the course of a review, the PZB determines that a zoning variance or other approval will be required in order to implement the proposal under consideration, it shall suspend further action on the application until such time as the additional approval has been heard and approved by the PZB or the application has been amended to eliminate the need for such additional approval.

G. **Appeal of COA.** The PZB shall hear all appeals of individuals who are directly affected by a decision of the Planning Board when such appeal is properly and timely filed as required by this chapter. An applicant refused such certificate shall appeal in writing to PZB within thirty (30) days of the date of refusal by the Planning and Zoning Board. The PZB shall set a date for a hearing on the appeal and render a decision on the appeal within thirty (30) days of the receipt of such written request. A resolution stating the decision of PZB shall be introduced and passed at the next regular meeting following the hearing.

SECTION 1109.21 ZONING MAP (REZONING) AND TEXT AMENDMENTS

A. In conformance with the provisions of the City Charter, ordinances or resolutions establishing, amending, revising, changing, or repealing zoning districts, uses, regulations, or other provisions of this Zoning Code shall be initiated by a member of Council.

~~B. Any person having an interest in property in the City may petition City Council to initiate such ordinance or resolution by making an application to the Planning and Zoning Administrator. The Planning and Zoning Administrator shall review the application for compliance with the provisions of this chapter and forward it to the Clerk of Council.~~

B. The PZB may recommend amendments, revisions, changes, or repeals of zoning districts, uses, regulations, or other provisions of this Zoning Code. When the PZB makes an advisory recommendation to City Council, the application requirements and fees shall not apply.

C. When a person or persons having an interest in a lot or lots in the City petitions City Council for an amendment to the Zoning Code which involves changing the zoning district assigned to the lot(s), then such petition shall be made in the following form which shall be known as the development plan, unless such requirements are waived by City Council:

i. Correct legal description of the lot(s);

ii. The names and addresses of the owners of lot(s) contiguous or directly across the street from the subject lot(s);

iii. Existing topography at two-foot (2 ft.) contour intervals of the subject lot(s) and extending at least three hundred feet (300 ft.) outside of the proposed lot, including lot lines, easements, street rights- of-way, existing structures, trees and landscaping features thereon;

iv. The proposed vehicular and pedestrian traffic patterns;

v. The location of all existing and all proposed structures;

vi. The proposed assignment of use and subdivision of land including private land and common land;

vii. Preliminary plans of all structure types;

viii. Deed restrictions and protective covenants;

ix. A schedule for construction;

x. Utilities impact study;

xi. Drainage impact study; and

xii. Such other relevant information as City Council may require to determine the propriety of initiating the ordinance for district change.

D. In conformance with the Charter, subsequent to initiation by a member of Council of an ordinance or resolution establishing, amending, revising, changing, or repealing zoning districts, uses, regulations, or other provisions of this Zoning Code, the presiding officer of Council shall, immediately after the first reading and initial public hearing of the ordinance or resolution, set a date for a public hearing before the Planning and Zoning Board, to be held not earlier than fifteen (15) days after the first reading.

E. Immediately after the first read and initial public hearing before Council, a copy of the ordinance or resolution establishing, amending, revising, changing, or repealing zoning districts, uses, regulations, or other provisions of this Zoning Code and, if applicable, the development plan, shall be referred to the Planning and Zoning Board. The Planning and Zoning Board shall recommend such conditions or amendments with respect to the ordinance or resolution and, if applicable, the development plan, as it deems reasonable and necessary. Within thirty (30) days of referral, the Planning and Zoning Board shall return to the Clerk of Council the written recommendations of a majority of the members of the Planning and Zoning Board.

F. The Planning and Zoning Board and City Council shall give consideration to the following standards in making recommendations and taking action with regard to proposed district changes:

i. The compatibility of the proposed zoning district and the features of the proposed development plan with the characteristics of the site and of the surrounding areas;

ii. The potential impacts of the proposed uses of the district in terms of traffic, storm water, utility demand, noise, and other impacts;

iii. The impacts of the proposed district and development plan on the health, safety, welfare, and morals of the community; and

iv. The compatibility of the proposed district and development plan with a comprehensive plan, or any area plans, to surrounding zoning districts, and to existing and planned land uses.

G. At the next meeting of Council subsequent to receiving the recommendations of the Board, the ordinance or resolution shall be given its second reading.

H. Council may adopt, deny, or adopt with modifications the recommendations of the Planning and Zoning Board. A development plan, along with any conditions or amendments to the petition, shall, upon adoption by Council, become part of the district change and shall be deemed incorporated by reference into legislation amending the district. The development plan, conditions, and amendments shall bind any future development or use of the subject lots.

I. A concurring vote of at least three fourths (¾) of the membership of Council shall be necessary to pass any zoning ordinance or resolution which differs from the written recommendations of the Planning Board, but in no event shall an ordinance or resolution be considered as having passed unless it receives at least a majority vote of the members of Council. Any petition for zoning ordinance or resolution filed under subsection 1109.21(d) that does not receive the required number of votes for approval shall be deemed to have been denied.

J. After a proposed district change is denied by City Council, at least twelve (12) months shall elapse before another petition for a district change for the same lot(s) to the same district can be considered.

K. The development is intended to show that the proposed use is consistent with the comprehensive plan and the proposed zoning district change and is not intended to replace the major site plan, variance or conditional use process.

L. An extension of the time limit may be approved by the Planning and Zoning Board. Such approval shall be given upon a finding of evidence of reasonable effort toward the accomplishment of the original development plan within the time limit, and that such extension is not in conflict with the general health, safety and welfare of the public or the development standards of this Code.

M. When Council reviews an ordinance proposing one or more zoning district changes, whether initiated by Council or an applicant, notice shall be published pursuant to Section 4.11(a) of the Charter of the City of Reynoldsburg. The Planning and Zoning Board shall also cause the subject property to be posted with a notice of hearing at least seven (7) days prior to the day of the hearing. The notice of hearing shall state thereon the nature of the request and the time and place of the public hearing.

SECTION 1109.23 APPEALS

A. Any person directly affected by the decision of the Planning and Zoning Admistrator or a notice or order issued under this Zoning Code shall have the right to appeal to the PZB, provided that a written application for appeal is filed within fourteen (14) days after the day the decision, notice or order was served. An application for appeal shall be based on a claim that the true intent of this code or the rules legally adopted thereunder have been incorrectly interpreted or the provisions of this code do not fully apply.

B. Unless otherwise provided in this Code, an applicant refused such approval, exception, certificate or variance shall appeal in writing to Council within thirty (30) days of the date of refusal by the PZB. The Council shall set a date for a hearing on the appeal and render a decision on the appeal within thirty (30) days of the receipt of such written request. A resolution stating the decision of Council shall be introduced and passed at the next regular meeting following the hearing.

SECTION 1109.25 DURATION OF CERTIFICATES, PERMITS, APPROVALS

A. Unless otherwise provided in Code, all zoning certificates, permits or other approvals granted by the Planning and Zoning Administrator, or the Planning and Zoning Board, shall be valid for a period of one (1) year from date of approval by the Planning and Zoning Board or date of issue by the Planning and Zoning Administrator.

B. Once a building permit is secured, a zoning certificate, permit or other approval shall be considered to expire when that building permit expires.

C. Within that period, that applicant must complete the following for the proposed improvement:

i. If required, submit a subsequent zoning application;

ii. If required, secure a building permit; and

iii. If no other permits are required, construct the proposed improvement.

D. Any application that is incomplete or otherwise un-issued by the Planning and Zoning Administrator shall expire one(1) year from the date of application.

E. One (1) additional period of six (6) months may be granted by the Planning and Zoning Administrator upon finding that unique circumstances warrant the additional time and that the conditions upon which approval was granted have not changed.

SECTION 1109.27 VIOLATIONS; REMEDIES

In the event of a violation of any provision of this code, or imminent threat thereof, the City, or the owner of contiguous or neighboring property who would be especially damaged by such violation, in addition to any other remedies provided by law, may institute a suit for injunction to prevent or terminate such violation. The City may file for a judgment for damages if the violation is deemed to have caused damages to the City.

A. Notice of Violation. Whenever the Planning and Zoning Administrator, or her or his designee, determines there are reasonable grounds to believe that there is a violation of any provisions or requirements set forth in this Zoning Code, the Administrator or designee may issue a notice setting

forth the alleged violations and advising the owner or person having a charge that such violations must be corrected.

B. Content of Notice of Violation. All notices of violation shall do the following:

i. All notices of violation shall be in writing and shall be served on the owner, operator, occupant, or any person from whom action, forbearance or compliance is required.

ii. All notices of violation shall identify the sections of this Zoning Code to which the order applies.

iii. All notices of violation shall provide a description of the property, dwelling, dwelling unit, multiple dwelling, business building or premises where the violations are alleged to exist or to have been committed; and/or a description of the violation. Such description of property may include, but is not limited to, the address where the violation exists.

iv. All notices of violation shall specify a reasonable time for compliance with the order. Such reasonable time may vary depending upon the nature of the violation.

v. All notices of violation shall advise the owner or person being charged that if the order is not complied with by the specified date of compliance the administrator may initiate a civil and/or criminal complaint against the owner or person having the charge.

C. Service of Notice of Violation. A Notice of Violation shall be served upon the owner, operator, occupant, or any person from whom action, forbearance, or compliance is required. Such notice shall be served by any one (1) of the following methods:

i. Personal service; or,

ii. Certified Mail service; or,

iii. Residence service.

If the methods prescribed by in (i)-(iii) are ineffective, service may be effectuated by publication in a newspaper of general circulation in the City; or, if service is returned marked as having been refused or unclaimed, service may be effectuated by Regular Mail service to an address that is reasonably believed to be:

iv. A place of residence of the owner or operator; or

v. A location at which the owner or operator regularly receives mail.

For any owner, operator, or occupant that is a business registered with the Ohio Secretary of State, service may, in addition to the above, be effectuated by Certified Mail service on the statutory agent of the business.

When the Notice of Violation has been properly serviced, the order shall be effective as to anyone having any interests in the premises whether recorded or not at the time the order was issued and shall be effective against any subsequent owner of the premises as long as the violation exists and there remains a city record of the order in a public file maintained by the director.

Written or oral acknowledgement by the owner of a receipt of a notice of violation shall be evidence that the owner received the notice of violation. An appeal of the notice of violation to the PZB by the owner pursuant shall constitute evidence of written acknowledgement by the owner of service of notice of violation.

D. Civil Penalties.

i. In addition to any other remedy or penalty provided in the Section, any owner of property who fails to comply with a Notice of Violation issued under this Section by the date specified in the notice shall incur a civil penalty of $1,000.00 for each calendar day thereafter that an owner, operator, or occupant fails to comply with the Notice of Violation.

ii. The administrator shall provide notice to the owner prior to the assessment of a civil penalty. Such notice shall state the date on which the assessment of a civil penalty will commence and shall be served on the owner as provided in this Section.

iii. The administrator must document the noncompliance for each day for which civil penalty is to be assessed against an owner under Section. Such documentation may include periodic, but not necessarily daily, photographic evidence of non-compliance demonstrating the continued existence of the condition of the premises for which the Notice of Violation was issued.

iv. The Administrator shall also document that prior to the issuance of the notice of civil penalty that the Administrator personally conferred or attempted to confer with the owner of the premises in an effort to establish a reasonable period of time for the owner to comply.

v. The City, through the Administrator, may file a civil action in a court of competent jurisdiction seeking a court order to recover any accumulated civil penalties.

vi. Any accumulation of civil penalties under this Section shall be stayed pending an appeal of the Notice of Violation to the PZB until the PZB issues its decision on appeal.

vii. This section shall apply to any Condominium Association under Chapter 5311 of the Ohio Revised Code as the owner and/or operator of common areas under the control of the Condominium Association.

E. Additional Penalties.

i. In addition to any other civil penalties provided for by this Code, any owner, operator, or occupant of a premises found in violation of this Chapter who fails to comply with the written Notice of Violation as provided in this Chapter is guilty of an unclassified misdemeanor, which is punishable by a fine of up to one thousand dollars ($1,000.00) each calendar day the offender fails to comply with the notice of violation.

ii. A separate offense shall be deemed committed for each and every day during or upon which such illegal location, erection, construction, reconstruction, enlargement, change, maintenance, or use occurs or continues. It shall not be necessary for a separate complaint to be filed for each calendar day such violation persists.

iii. On a second or subsequent offense occurring within two (2) years of a prior offense, any owner, operator, or occupant of a premises found in violation of this Chapter who fails to comply with the written notice provided herein is guilty of an unclassified misdemeanor punishable by up to sixty (60) days in jail and a fine of up to one thousand dollars ($1,000.00) each calendar day the offender fails to comply with the notice of violation.

This page intentionally left blank.



1111

SUBDIVISION REGULATION

Subdivision Regulations

SECTION 1111.01 VARIANCES

A. In cases where it is deemed that hardships, topography or other factual deterrent condition prevail, variations and exceptions from the dimensional standards and improvement requirements as set forth in the Subdivision Regulations may be recommended by the Planning and Zoning Board, but must be approved by Council

SECTION 1111.03 APPROVAL OF SUBDIVISION WITHOUT PLAT

A. Notwithstanding any other provisions of the Subdivision Regulations, a proposed division of a parcel of land along an existing public street, whether the parcel to be divided fronts on the street or has access to it by private right of way or private driveway, not involving more than five lots after the original tract has been completely subdivided, may be submitted to the Planning and Zoning Board for approval without plat. If the Planning and Zoning Administrator, acting on behalf of the Planning and Zoning Board, is satisfied that the proposed subdivision complies with all applicable platting, subdividing or zoning regulations, they shall approve the proposed subdivision and, on presentation of a conveyance of the parcel, shall stamp the same "approved by the Planning and Zoning Board; no plat required." The Planning and Zoning Administrator may require the submission of a sketch and such other information as is pertinent to determining compliance with this section. No building, structure or land shall be used or occupied and no building or structure or part thereof shall be erected, constructed, reconstructed, moved or structurally altered except in conformity with all of the regulations herein specified for the district in which it is located.

SECTION 1111.05 PRELIMINARY PLAT

A. Sketch may be Submitted for Suggestions. The owner of land who desires to subdivide it shall submit a sketch of the plat to the Planning and Zoning Board for its comments and suggestions. The owner can then make such corrections and changes as agreed upon before preparing and submitting his preliminary plat for consideration.

B. Copies of Preliminary Plat To Be Submitted. The owner of land who desires to subdivide it shall submit eleven (11) copies of a preliminary plat along with eleven (11) copies of a general layout of all site improvements to be installed on the entire tract of land to be developed even if the owner or developer only intends to initially develop only a part of the tract, to the Planning and Zoning Board twenty-one (21) days prior to a regular meeting of the Board. A copy of the general layout of all site improvements attached to a copy of the plat shall be in the possession of each member of the Planning and Zoning Board for a minimum period of seven (7) days before consideration for approval.

C. Fees. A fee shall be paid at the time of submission of the preliminary plat as stated in this Code.

D. Contents of Preliminary Plat

i. The preliminary plat shall contain the following, and be prepared by a licensed professional engineer in the State of Ohio:

1. The scale, with a minimum of one inch to equal one hundred feet;
2. The proposed name of the subdivision;
3. Key map showing location within the City;
4. Names and addresses of owners, developers and the surveyor who made the plat;
5. Date;
6. North point; and
7. Legal description of parcel being subdivided.

ii. The following existing conditions shall be shown on the plat:

1. Boundary lines and approximate acreage included matching the provided legal description;
2. Locations, widths and names of all existing or previously platted streets or alleys, and proposed thoroughfare locations as shown on the official City Thoroughfare Plan, railroad and utility rights of way, parks and public open spaces, permanent buildings and structures, all section and corporation lines within or adjacent to the tract;
3. Existing sewers, water mains, culverts and other underground facilities within the tract, indicating pipe sizes, elevations and grades, if readily available, and locations, if known or available;
4. Boundary lines of adjacent tracts of unsubdivided and subdivided land;
5. Existing zoning restrictions;
6. Existing contours, with intervals of five feet where the slope is greater than ten percent and not more than two feet where the slope is less than ten percent;
7. Drainage channels, wooded areas, water courses and other significant physical features;
8. Existing and proposed easements.

iii. All elevations on the preliminary plat shall be based on NAVD (North American Vertical Datum) 1988 datum.

iv. The following proposed conditions shall be shown:

1. Layout of streets and right-of-way widths;
2. Layout, numbers and dimensions of lots including total square footage;
3. Parcels of land intended to be dedicated or temporarily reserved for public use;
4. Building setback lines shown graphically with dimensions;
5. Indication of any lot on which a use other than residential is proposed by the owner;
6. Names of new streets which shall not duplicate names of any existing dedicated street within the County and/or its incorporated areas;
7. New streets which are extensions of or in alignment with existing streets which shall bear the names of the existing streets of which they are extensions or with which they are in alignment;
8. Bearings and dimensions of lot, parcel, and right-of-way boundaries; and
9. Proposed landscaping, if any.

v. All new streets shall be named in the following manner and shall be subject to the approval of the Planning and Zoning Board:

GENERAL DIRECTION	OVER 1,000 FEET IN LENGTH	UNDER 1,000 FEET IN LENGTH
North and south	Streets	Places
East and west	Avenues	Courts
Diagonal	Roads	Ways
Curving	Drives	Circles

vi. The general layout of all site improvements attached to the preliminary plat shall be for the entire tract of property even if the owner or developer only intends to initially develop a part of the entire tract and such general layout is to provide for the extension of improvements to the boundary of the proposed subdivision to serve adjoining land.

E. Approval of Preliminary Plat. When a plat is filed with the Planning and Zoning Board, the Planning and Zoning Administrator shall examine it to determine whether or not it complies with the requirements of Section 1111.01(A) through (D). The Planning and Zoning Administrator shall then refer the plat to the City Engineer. If the plat does not meet the requirements, the Planning and Zoning Administrator shall return it to the owner who shall revise and refile it, and additional fees may apply. If the plat meets the requirements, the Planning and Zoning Administrator shall lay it before the Planning and Zoning Board at its next meeting. The shall thereupon examine it and approve it or conditionally approve it within thirty (30) days if it is satisfied that it complies, or will comply after minor changes, in all respects with this chapter. The approval or the conditions of approval of the Planning and Zoning Board will be indicated in writing on two (2) copies of the preliminary plat which will be returned to the owner and surveyor. The remaining four (4) copies bearing the notation of approval shall remain on file, available to the public. The approval of a preliminary plat shall be effective for a maximum period of twelve months, unless extended by the Planning and Zoning Board.

SECTION 1111.07 FINAL PLAT

A. The general layout of all site improvements attached to the preliminary plat shall be for the entire tract of property even if the owner or developer only intends to initially develop a part of the entire tract and such general layout is to provide for the extension of improvements to the boundary of the proposed subdivision to serve adjoining land.

SECTION 1111.09 ADDITIONAL REQUIRED INFORMATION

A. A final plat shall contain the following additional information, and be prepared and sealed by a licensed professional engineer in the State.

i. Boundary of plat based on an accurate traverse with angular and lineal dimensions;

ii. True angle and distance to the nearest street intersection, accurately described on the plat;

iii. Municipal, township, county or section lines accurately tied to the lines of all chord dimensions;

iv. Radii, internal angles, points of curvature, tangent bearings and lengths of all chord dimensions;

v. All lot numbers and lines with accurate dimensions in feet and hundredths and bearings in degrees and minutes;

vi. Accurate location of all monuments, which shall be composed and/or located as follows:

1. Be composed of a durable material;
2. Be a minimum length of thirty inches (30IN);
3. Of a minimum cross-section area of material of two tenths square inches (one inch (1IN) in diameter);
4. Be identified with a durable marker bearing the Surveyor's Ohio Registration number and/or name or company name;
5. Be detectable with conventional instruments for finding ferrous or magnetic objects;
6. Placed with the top at the existing grade elevation.
7. One such monument shall be placed at each extreme corner of the subdivision. All lots must be marked with steel pins, and such pins must be in place after a building is completed. The Building Official shall confirm that lot pins are in place on the final occupancy permit.

vii. Exact location, width and name of all streets or other public ways; and

viii. Known easements, accurately located and stating the purpose for which they are intended. Easements may be added or revised on the final plat after final plat approval. Easements added to the final plat or revised on the final plat require the approval of the City Engineer and the Director of Public Service and said approvals are to be entered on the final plat. The owner or developer shall offer an easement for television cable and television cable equipment within the easement(s) shown on the final plat. The easement shall be granted at no expense to the television cable owner/operator, if the cable operator installs the necessary television cable and television cable equipment in the utility trench during the time the trench is open for the installation of other utilities. Otherwise, the owner, developer or City may revoke the offer of an easement.

B. A final plat shall also contain:

i. A certificate by a registered professional land surveyor that the plat represents a completed survey and that the monuments shown exist as located or will be set following construction and that all dimensional and geodetic details are correct.

ii. Notarized certification by the owner or owners of the adoption of the plat and the dedication by them to public use of the streets and other public areas shown on the plat. The signatures of the owner(s) are required prior to the obtaining of any City Official's signature on the plat. No property shall extend to the center of a right of way.

iii. Proper form for the approval of the Planning and Zoning Board with space for the signature of the Chairman.

iv. Space for approval by signature of the City Engineer and Director of Public Service.

v. Proper form for approval and acceptance by Council, showing ordinance number and provisions for signature by the Clerk of Council.

vi. Space for approval, by signature of the City Engineer and Director of Public Service, of easements added to or revised on the final plat.

vii. Space for transfer by the County Auditor and recording by the County Recorder. A statement of the expiration date of the City approval shall be placed just ahead of the space provided for the County Auditor's signature.

viii. A topographic survey prepared by an Ohio registered professional surveyor using the North American Vertical Datum of 1988 (NAVD88) reflecting flood way, floodway fringe, base flood elevations and property lines of the plat under consideration for development.

C. Copies to be filed with Clerk. One (1) copy of the final plat showing all approvals and the date and place of recording shall be supplied by the owner to the Clerk of Council.

D. Copies to be filed with Clerk. One (1) copy of the final plat showing all approvals and the date and place of recording shall be supplied by the owner to the Clerk of Council.

i. The subdivider shall not transfer any lot, parcel or tract of a proposed subdivision, until approval is received of the final plat.

ii. The subdivider shall not proceed with any construction work on any lot until approval is received of the final plat and compliance is made with all other provisions of the Subdivision Regulations, unless it is for the exact purpose of building model units. The subdivider may be granted a building permit for not more than two units, in the case of single family detached housing and not more than one building of eight units or less, in the case of townhouse for sale or condominium housing, providing the following conditions have been met:

1. Proof of ownership of that portion of subdivision to be used for models;
2. The proposed models have legal frontage on an existing public roadway, water and sanitary sewer;
3. Insurances have been granted to the City in the form of bond, escrow funds, letters of credit or other assurances the City deems necessary to insure installation of improvements;
4. Occupancy permit shall not be issued until Section 1111.09 has been complied with.

E. Transfer of Lot Contrary to Plat Prohibited. The owner of the subdivision shall make no conveyance of any lot smaller in width or area than indicated on the plat, except for the purpose of increasing the area of another lo**t.**

F. Project Representation by Engineer During Installation of Improvements. All construction work and materials used in connection with public improvements and storm water management in the area platted shall conform to City specifications and requirements of the City Engineer. The City Engineer shall provide the owner or developer with project representation at the expense of the owner or developer during installation of the improvements.

G. Bond Letter of Credit for Improvements: Deposit and Insurance

i. Before approval of the final plat, the owner or developer shall agree in writing that prior to the beginning of construction of any street, private roadway, public improvement and storm water management infrastructure the owner or developer shall provide a bond, certified check or an irrevocable letter of credit from a solvent bank doing business in Franklin, Licking or Fairfield Counties, Ohio, guaranteeing the completion of said improvement(s) within one (1) year from the date of agreement or such time as may be agreed to by Council. The bond, check or irrevocable letter of credit shall be in an amount equal to the estimated cost of constructing said improvement(s), as approved by the City Engineer. A maintenance bond, certified check or an irrevocable letter of credit in the amount of five percent (5%) of the estimated construction costs shall be provided for a maintenance period of one (1) year beginning with the date of acceptance of the said improvement(s) by the Director of Public Service and City Engineer.

ii. The owner or developer shall prior to construction, deposit with the Director of Public Service and with the approval of the City Engineer a sum of money as prescribed by the Director of Public Service and the City Engineer to defray the cost of inspection and the engineering services provided and any expenses incurred by the City due to the installation of the improvements and review of the plat and plans. Fees for the review of plats and plans shall be calculated by the owner or developer, to be verified by the City using the fee schedules as provided by the Director of Public Service. These and other documents detailing the development process can be obtained from the Public Service Department. For inspections the owner or developer shall deposit with the Public Service Department a sum of money based on an approved cost of construction schedule, and be approved by the City Engineer. Should the amount of such deposit be insufficient to cover the cost thereof, the owner or developer shall immediately upon request of the City deposit a sum of money acceptable to the City Engineer and the Director of Public Service. Upon completion and acceptance of the improvements, any unexpended balance shall be refunded to the owner or developer.

iii. The subdivider shall hold the City harmless for any claims for damages of every nature arising or growing out of the construction of such improvements, and shall defend at his cost and expense, each suit or action brought against the City by reason thereof, until the improvement has been accepted by the City and the developer notified in writing within thirty days. The subdivider shall furnish proof to the City, prior to the time of commencing construction of possession of Comprehensive General Liability Insurance, naming the City of Reynoldsburg as an additional insured. These Certificates of Insurance shall contain a provision that coverage afforded in the policies will not be canceled unless at least thirty days prior written notice has been given to the City. Limits on bodily injury shall not be less than five hundred thousand dollars ($500,000) for

personal injury to any one person and a total of not less than one million dollars ($1,000,000) each accident. Limits on property damage shall be not less than two hundred thousand dollars ($200,000) per occurrence, or five hundred thousand dollars ($500,000) aggregate for each accident. Umbrella Excess Liability Insurance to extend existing policies to the required limits will be accepted.

iv. If any violation of or noncompliance with, any of the provisions and stipulations of this chapter occurs, the City shall have the right to stop the work without delay and utilize the bond, certified check or an irrevocable letter of credit for the completion of the improvement or use the certified check or proceeds thereof for such purpose.

H. Modification, Alteration, Amendment or Vacation, In Whole or In Part Of Plat After Approval. No modification, alteration, amendment, or vacation, in whole or in part, of a final plat except for the addition of appropriate easements as approved by the City Engineer shall be made in or to a final plat approved by Council under the provisions of this chapter or another political subdivision prior to annexation unless such modification, alteration, amendment, or vacation, in whole or in part, is first submitted to and accepted by the Service Director, is recommended by the Planning and Zoning Board, and Council approves such modification, alteration, amendment, or vacation, in whole or in part, by ordinance. If the modified, altered, amended, or vacated, in whole or in part, final plat is approved by Council, the owner shall file and record the plat with the County Recorder within sixty days. If the final plat has already been recorded then the owner shall file and record the ordinance and an authenticating affidavit executed by the Clerk of Council with the County Recorder within sixty days, wherein the modified, altered, amended, or vacated, in whole or in part, plat shall be indexed or cross-referenced with the original plat. If the plat is not filed with the County Recorder within sixty days, the modification, alteration, amendment, or vacation, in whole or in part, is void and is of no effect.

SECTION 1111.11 REQUIRED IMPROVEMENTS

A. Improvements to be Paid for By Subdivider

i. The owner of land who desires to subdivide it shall provide and pay the entire cost of improvements to such land as follows:

1. Before the construction of any building, street improvements shall consist of grading the right of way for full width; construction of permanent curbing and roadway; construction of drainage structures and appurtenances. Two roof drain openings shall be provided in the curb for each lot;
2. Sanitary sewers, including manholes, services and all appurtenances;
3. Water distribution system, including mains, services, valves, fire hydrants and all appurtenances;
4. Curbs and sidewalks on existing streets as determined by the City Engineer; Storm sewers, including manholes, inlets and all appurtenances.

ii. All phases of the improvement shall be approved by the City Engineer and shall be constructed in accordance with City specifications.

iii. The City may require other improvements not listed in this section, if they are deemed necessary by the City Engineer for the protection of public health, safety or welfare.

iv. The City shall require a plot-grade-utility-plan approval for all residential subdivisions in accordance with the provisions of Chapter 1109.17.

B. Inspection During Installation

i. The construction of all improvements shall be inspected by the City Engineer at the time of installation. Under no circumstances are such installations to be made without an inspector on the job. The City Engineer shall be notified three days before any construction work is begun.

ii. If any violation of, or noncompliance with, any of the provisions of this chapter occurs, the City shall withhold the issuance of the occupancy permit until the violation or noncompliance is corrected.

C. Construction Drawings; Dimensions; Revision

i. All construction drawings for improvements shall be on a horizontal scale of one inch to fifty feet and vertical scale of one inch to five feet. The sheet size shall be twenty-two inches by thirty-six inches.

ii. Upon approval and acceptance of all improvements, the original construction drawings for the improvements shall be revised to reflect the actual construction. All drawings including the master grade plan or reproductions thereof on tracing cloth shall become the property of the City and shall be on file in the office of the City Engineer.

D. Service Roads

i. Service Roads Authorized. When it is determined by the City Engineer that the roadways provided in the Subdivision Regulations are not satisfactory for the needs of special circumstances, additional roadways, designated "service roads," may be prescribed by the City Engineer. These service roads will be shown on the plat of a subdivision in such locations as are determined by the City Engineer, subject to plat approval as provided by the Subdivision Regulations.

ii. Service Road Right of Way. When it is determined that service roads may be included in a subdivision plat, the right of way for the road shall be no less than thirty-two feet in width and shall be dedicated to public use in the same manner as prescribed in the Subdivision Regulations for all other public roads.

iii. Service Road Specifications. Service roads shall be constructed of materials and to design section as shown on the revised standard construction drawing File R-23A as presently constituted and as hereafter amended on file with the City Engineer.

iv. Sidewalks Not Required. No sidewalks or other provision for traffic, other than motor vehicular traffic, shall be required in conjunction with the construction of any service road.

SECTION 1111.13 STREET LIGHTS

A. Design and Layout. The design and layout for the street lighting, the underground wiring and other pertinent equipment to be used shall be designed by a registered engineer, and approved by the City Engineer.

i. All energy lines leading to the light standard shall be underground in new developing subdivisions.

ii. All street lighting designs are to be coordinated with the supplier of electric energy. Two drawings for each street lighting layout shall be submitted to the supplier of electric energy for record purposes.

iii. Street lights using poles and light assemblies as shown on standard drawings R-46 and R-47, respectively, are to be installed with not less than 160 feet spacing nor more than 240 feet spacing. Street lights using the alternate residential luminaire and pedestal pole, as shown on standard drawing R-46A, are to be installed with not less than 125 feet spacing nor more than 160 feet spacing. Street lights shall be installed alternating on opposite sides of the street.

iv. The alternate residential luminaire and pedestal pole detail, as shown on standard drawing R-46A, shall be used in all residential areas. The pole detail and light assembly (commonly referred to as a "cobra light"), as shown on standard drawing R-46 and R-47, respectively, shall be used in all commercial corridors, unless otherwise approved by Council through adoption of streetscape standards or other such action to permit consideration of alternative styles, or as may otherwise be approved by any other Board of Commission having jurisdiction to approve or permit the use of alternative styles as part of its review of an overall design concept.

v. The drawings are specification sheets for street light standards, luminaries, mercury vapor lamps and pedestal termination points and will be available at the Director's office.

vi. All connections to supplier of electric energy secondary service locations shall be made by supplier.

B. Lights to Be Installed. Any person, firm or corporation desiring final acceptance of a street, shall, before final acceptance is granted, have the street lights installed and ready for use.

C. Maintenance of Lighting Is Responsibility of City. It shall be the responsibility of the City to secure the energy for lighting and to maintain the installations.

D. Damages to distribution system. Any contractor or agent for the developer, while in the process of installing street lights, who damages the distribution system of an electric energy supplier shall be liable for such damages and for any other cost as a result of such damages, and the energy supplier may charge and receive payment for such damages from the party responsible.

E. Completion Bond Required. If conditions are such that street lights cannot be installed prior to the acceptance of the streets upon which street lights are to be installed as required in Section 1111.13, the person, firm or corporation requesting acceptance of such streets shall deposit with the City Auditor an amount of cash or collectable funds, or a performance bond in form satisfactory to the City Attorney equal to one and one-half times the estimated cost of the installation of street lights as security for the installation of such lights, which installation shall be completed within six months of the date of deposit of such funds or bond. Failure on the part of such person, firm or corporation to complete the installation within six months shall be cause for the Public Service Director to order installation by such other contractor as he may choose and cause the cost of installation to be paid from the funds or bonds so deposited. That portion of such funds not used for the installation shall be returned to the depositor at the completion and acceptance by the City of the street lighting installation.

F. Easement for Energy Lines to Light Standards. The developer shall provide the necessary easement for street lighting. The City Engineer will coordinate with the developer, where necessary, the easement leading to the electric lighting standard so that lighting may be properly spaced.

SECTION 1111.15 STANDARDS

A. Street Standards

i. Street Design. Streets shall be dedicated to public use by the owner. Minor residential streets shall be so designed as to discourage their use by nonlocal traffic. Except where necessitated by local conditions, dead-end streets and cul-de-sacs will not be approved in residential districts. Dead-end alleys are prohibited in all districts. Easements for utilities must be provided along side or rear lot lines where possible. Street rights of way shall have the following minimum widths:

1. Major arterial, which include Federal, State and County roads which are main arteries of access to the City: one hundred (100FT); an additional width of forty-five feet (45FT) shall be provided to accommodate a service drive wherever lots are to face a primary road;
2. Minor arterial, which are next in importance as avenues of access between sections of the City as opposed to commercial traffic and nonlocal traffic: eighty feet (80FT);
3. Neighborhood collector, which are within a new subdivision: sixty feet (60FT);
4. Minor residential, which are completely residential in nature: fifty feet (50FT);
5. Alleys: twenty feet (20FT);
6. Easements: as required.

ii. Minimum Pavement Widths. Minimum pavement widths shall be as follows:

1. Major arterial: variable as conditions may require;
2. Minor arterial: thirty-six feet (36FT);
3. Neighborhood collector: thirty-two feet (32FT);
4. Minor residential: twenty-six feet (26FT);
5. Alleys: eighteen feet (18FT);
6. Service drives: twenty feet (20FT);
7. Sidewalks: minimum four feet (4FT) along non-arterial and minimum width along arterial streets to be as approved by the City Engineer, in accordance with the provisions of Section 909.02.

iii. Maximum Grades. The maximum grades shall be:

1. Major arterial: four percent (4%);
2. Minor arterial: five percent (5%);
3. Neighborhood collector, minor residential streets and alleys: six percent (6%)

iv. Minimum Grade. The minimum grade for any street shall be one-half of one percent at the gutter, unless otherwise approved by the City Engineer. Street intersections shall be rounded by radii not less than twenty feet (20FT) at the curbline.

v. Standards. All street construction and specifications for materials shall be in conformity with standards required by the City as published by the City Engineer.

vi. Plans. The plans must bear the approval of the City Engineer, Director of Public Service, Superintendent of Water/Wastewater, Superintendent of Streets, and Fire Chief. Places shall be provided for their signatures.

B. Private Roadways

i. As used in this section "private roadway" means any passageway designed for use by motor powered vehicles, upon property owned by one or more persons, firms or corporations where such passageway serves in excess of four dwelling units.

ii. All proposed private roadways and their pavement widths shall be shown on the preliminary and final plats filed in accordance with these Subdivision Regulations. In addition, a document indicating the responsible party for maintenance shall also be provided.

iii. All private roadways shall be improved with a hard surface of concrete, asphalt or other similar products or combination of products. The construction and specification for materials for private roadways shall conform with standards provided by the City standards as published by the City Engineer.

iv. The minimum pavement width for private roadways shall be twenty-six feet (26FT) and the maximum grade shall be six percent (6%), however, the minimum grade for private roadways shall be one- half of one percent at the gutter, unless otherwise approved by the City Engineer.

v. Every private roadway ending in a dead end or at a cul-de-sac circle shall have a minimum pavement width as approved by the Planning and Zoning Board to assure access to the area for fire equipment and to facilitate the turning of vehicular traffic. In approving such minimum pavement widths the Planning and Zoning Board shall consider whether such cul-de-sac or turn-around will be used for parking vehicles.

vi. The plans must bear the approval of the City Engineer, Director of Public Service, Superintendent of Water/Wastewater, Superintendent of Streets, and Fire Chief. Places shall be provided for their signatures.

C. Sanitary Sewers

i. Plans and profiles of sanitary sewers shall be submitted to the Director of Public Service. All grades, pipe sizes, manholes and other appurtenances shall be shown and installation and materials shall be in conformity with City standards as published by the City Engineer.

ii. Sanitary sewer plans must bear the approval of the Director of Public Service and the City Engineer and the Superintendent of Water/Wastewater. Places shall be provided for their signatures.

D. Water Distribution

i. Plans of the proposed water distribution system shall be submitted to the Director of Public Service. All plans must show pipe sizes, locations of valves, fire hydrants and other appurtenances. Installation and materials shall be in conformity with City standards as published by the City Engineer.

ii. Water distribution system plans, if not incorporated as part of the street improvement plans, must bear the approval of the City Engineer, Director of Public Service, Superintendent of Water/Wastewater, Superintendent of Streets, and Fire Chief. Places shall be provided for their signatures.

E. Storm Sewer System

i. Proposed storm sewers, including grades, pipe sizes, manholes, inlets and appurtenances may be shown on the street improvement plans. Installation and materials shall be in conformity with City standards published by the City Engineer.

ii. The owner or developer shall follow the recommendations of the City Engineer with regard to the proper method and direction of drainage and storm water following review of the proposed plan of such drainage as submitted by the subdivider or his engineer. A storm water management report shall be submitted to the City Engineer for review in conjunction with drainage plans.

iii. The storm sewer plans, if not incorporated as part of the street improvement plans, must bear the approval of the City Engineer, Director of Public Service, Superintendent of Water/Wastewater, Superintendent of Streets, and Floodplain Administrator. Place shall be provided for their signature.

F. Lots and Blocks

i. Every lot shall abut on a dedicated street. Double frontage lots shall be avoided. At the intersection of two streets, property line corners shall be rounded by an arc with a minimum radius of ten feet (10FT). Size, shape and orientation of residential lots shall be appropriate to the location of the proposed subdivision and for the types of development contemplated and in conformity with the Zoning Code, with proper regard given yard areas, setback lines, etc. Excessive depth in relation to length shall be avoided. A proportion of two to one depth to frontage shall be normal and depths in excess of three times the lot width are not recommended. Side lines of lots shall be approximately at right angles or radial to the street line. Corner lots shall have extra width sufficient to permit maintenance on both front and sides of lot. The maximum length of blocks may not exceed eighteen hundred feet (1,800FT) except where topographic conditions require longer blocks, nor shall they be less than four hundred feet (400FT) in length. Wherever blocks are longer than nine hundred feet (900FT), crosswalks or crosswalk easements not less than ten feet (10FT) in width may be required near the center of the block, and Council may require that a sidewalk be constructed in accordance with City standards for sidewalk construction. The width of a block shall normally be sufficient to allow two tiers of lots of appropriate depth except where double and reverse frontage lots are allowed. Where frontage on a primary street is involved, the long dimension of the block shall front thereon in order to minimize access intersections.

ii. Where either sanitary sewer or water service is not available, lots shall have a minimum frontage of seventy-five feet (75FT) and a minimum area of ten thousand square feet (10,000SF). Where neither sanitary sewer nor water service is available, lots shall have a minimum frontage of one hundred feet (100FT) and a minimum area of twenty thousand square feet (20,000SF).

G. Drainage

i. The Planning and Zoning Board shall not approve any subdivision having inadequate storm drainage or other physical drainage impairment as determined by the City Engineer. In areas known to be subject to periodic floods, such drainage improvements must be made as to satisfy the Director of Public Service and the City Engineer in order that the health and welfare of the people will be protected.

ii. No natural drainage course shall be altered and no fill, buildings or structures shall be placed in it unless provisions are made for the flow of water in a manner satisfactory to the City Engineer. An easement shall be provided on both sides of any existing important surface drainage course adequate for the purpose of protecting, widening, deepening, enclosing or otherwise improving such stream for drainage purposes.

iii. A master grade plan shall be prepared for all subdivisions and shall be presented to the for review and approval by the City Engineer. The grading plan shall show the existing topography, the proposed street grades and the proposed storm sewers with pipe sizes and grades. It shall also show the proposed elevation at each lot corner, the proposed finish grades at the house and shall delineate the method of rear yard drainage by showing proposed swales and direction of surface slope by arrows. The grading plan shall follow the standards as established for such grading by the City Engineer.

iv. Wherever possible, with exceptions being made where the topography of an area does not permit such grading practice, lots shall be graded from the rear lot line to the street. Where a lot abuts directly on two streets, the grade shall be from the corner of the lot which is diagonally opposite to the corner of the two streets on which the lot abuts. This section is included in order to reduce the amount of water standing in yards to a minimum. Therefore, where it is not possible to grade a lot in the prescribed manner, the owner or developer shall provide for the adequate drainage of any and all low areas and tie such drainage into and make it a part of the storm sewer system of the development and the City as directed by the City Engineer, with approval of such drainage subject to inspection by the City Engineer along with the inspection of other storm sewer installations.

v. The Planning and Zoning Board shall not approve the final plat of any development or subdivision over which it has jurisdiction without certification from the Director of Public Service and the City Engineer that such development or subdivision has been designed to be in full compliance with the design requirements contained in the Stormwater Management Policy and Design Manual.

vi. There is hereby adopted, and incorporated by reference as if set out at length herein, for the purpose of establishing rules and regulations for the design, construction, or alteration, the Stormwater Management Policy and Design Manual as hereafter amended in the most recent edition published by City Engineer.

H. Public Use Areas

i. Ten percent (10%) of the area of each residential subdivision, exclusive of streets, shall be allocated for recreational uses. When a proposed subdivision contains an area described as a proposed public building site, park, playground or other public area, that area shall be dedicated on the plat to the City, another public agency, or reserved for acquisition by the City within a period of five (5) years by purchase or other means.

ii. Where required, the developer and the City shall work out an arrangement for parks and recreational facilities.

iii. Proposed large scale neighborhood unit developments and similar unusual developments may require the reservation or dedication of such additional areas or sites of a character, extent and location suitable for the needs of the community facilities created by such particular developments where deemed necessary by the Planning and Zoning Board.

iv. Natural features of beauty such as trees, brooks, topography and views shall be preserved whenever possible in designing any subdivision.

I. Underground and Electric Telephone Lines

i. The term "subdivision" as used in this section refers only to residential subdivisions of more than eleven (11) lots platted subsequent to July 1, 1967.

ii. Unless the subdivision has been exempted from the requirements of this section, as provided in subsection (e) hereof, all telephone and electric distribution wires, conduits, and cables therein shall be installed underground, except as necessary to bring service to the subdivision, and except for existing overhead facilities and any rearrangement, improvement or addition thereto.

iii. The preliminary plan with respect to the subdivision shall be submitted to the City Engineer and to the electric and telephone utility companies which will provide service to the subdivision for their recommendations with respect to the width and location of easements for electric and telephone distribution cables and related facilities. The recommendations of the City Engineer and such utility companies shall be submitted to the Planning and Zoning Board by the owner of the subdivision together with the plat of the subdivision. Prior to signing the plat of the subdivision, the Planning and Zoning Board shall determine that adequate easements are provided for all utility services, including underground electric and telephone distribution wires, conduits, cables, gas pipelines, sewer and water lines. The owner of the subdivision shall, at the time the plat of the subdivision is submitted for approval, present such evidence as the Planning and Zoning Board deems necessary to ensure that the owner shall makes or has made provision for all utility services, including underground electric and telephone distribution wires, conduits, cables, gas pipelines, sewer and water lines in accordance with this section, adequate for the anticipated needs of the subdivision.

iv. The construction of all underground facilities shall meet the minimum requirements of any code approved by the Public Utilities Commission of Ohio.

v. If, in the opinion of the owner of any subdivision or a portion thereof, or any interested utility company, the installation of underground facilities is economically or physically unfeasible, such owner or utility company may apply to the Planning and Zoning Board for exemption of the subdivision or portion thereof from the requirements of this section, stating in the application for exemption the reasons thereof or, and submitting therewith such exhibits, documents and data as may be necessary to substantiate the request. The Planning and Zoning Board shall hold a hearing, at which the applicant and any other interested person may appear, at its regularly scheduled meeting, after the submission of an application for exemption. Notice of the hearing shall be given by certified mail by the applicant, at the applicant's expense, to each interested utility and owner no less than seven (7) days prior to such hearing. If the Planning and Zoning Board denies the application following the notice and hearing, the applicant may file a written

appeal therefrom with the Clerk of Council, stating the reasons therefor, within thirty (30) days following the announcement of such decision by the Planning and Zoning Board. Such appeal shall be placed on the agenda for the next regularly scheduled meeting of Council following the filing thereof with the Clerk and shall be heard at such meeting. Council may, by resolution, reverse or affirm, wholly or in part, or may modify the decision of the Planning and Zoning Board.

J. Separability. If any court of competent jurisdiction determines that any clause, section or portion of Section 1111.15(I) is invalid or unconstitutional, such finding shall in no way affect the validity of unconstitutionality of the balance of Section 1111.15(I).

K. Erosion and Sediment Control

i. An erosion and sediment control plan shall be prepared for all developments covered by this regulation which disturb one or more acres of land.

1. The erosion and sediment control plan shall conform to any and all standards defined in the Ohio Environmental Protection Agency authorization for storm water discharges associated with construction activity under the current National Pollutant Discharge Elimination System (NPDES) permit, and all revisions and amendments thereto. The Notice of Intent, as well as a copy of the Storm Water Pollution Prevent Plan (SWP3) shall be provided to the city as part of the erosion and sediment control plan submittal.
2. The SWP3 shall be prepared by a professional experienced in the design and implementation of erosion and sedimentation controls and shall address all phases of construction. The SWP3 shall incorporate, at a minimum, all of "Part III, Section G" SWP3 requirements of the current NPDES permit, and all revisions and amendments thereto.

L. Utility and Traffic Studies. Utility and traffic studies may be required by the City Engineer to facilitate proper master or large-scale planning of the City's infrastructure prior to the submission of public or private construction plans. Fees for review of such traffic or utility studies shall be established and updated from time to time.

This page intentionally left blank.



1113 GLOSSARY OF TERMS

Glossary of Terms

A.

Accessory Dwelling Unit (ADU). An accessory dwelling unit (ADU) is a smaller, secondary home on the same lot as a primary dwelling. ADUs are independently habitable and provide the basic requirements of shelter, heating, cooking, and sanitation. ADUs can be detached structures or attached to the primary structure. One ADU is permitted per lot. ADUs are subject to all applicable regulations in section 1105.05 of this code.

Accessory Structure. A building or structure that is subordinate to the principal building or structure upon the same lot and serving a purpose customarily incidental to the principal structure.

Accessory Use. A use that is subordinate to the principal use of the land and serving a purpose customarily incidental to the principal use or structure.

Adult Booth. Any area of an adult oriented business set off from the remainder of such establishment by one or more walls or other dividers or partitions and used to show, play, or otherwise demonstrate any adult materials or to view any live performance that is distinguished or characterized by an emphasis on the exposure, depiction, or description of specified anatomical areas or the conduct or simulation of specified sexual activities.

Adult Day Care. A licensed facility for the daytime care of an adult with a mental or cognitive impairment.

Adult Entertainment. See Section 795.02, Codified Ordinances of the City of Reynoldsburg.

Adult material. Any of the following, whether new or used:

A. Books, magazines, periodicals, or other printed matter, or digitally stored materials that are distinguished or characterized by an emphasis on the exposure, depiction, or description of specified anatomical areas or the conduct or simulation of specified sexual activities.

B. Films, motion pictures, video or audio cassettes, slides, computer displays, or other visual representations or recordings of any kind that are distinguished or characterized by an emphasis on the exposure, depiction, or description of specified anatomical areas or the conduct or simulation of specified sexual activities.

C. Instrument, novelties, devices, or paraphernalia that are designed for use in connection with specified sexual activities, or that depict or describe specified anatomical areas.

Advertising structure. Any outdoor display for the purpose of advertisement, notice or announcement located apart from the premises or product referred to in the display.

Agriculture. Farming; ranching; aquaculture; algaculture meaning the farming of algae; apiculture and related apicultural activities, production of honey, beeswax, honeycomb, and other related products; horticulture; viticulture, winemaking, and related activities; animal husbandry, including, but not limited to, the care and raising of livestock, equine, and fur-bearing animals; poultry husbandry and the production of poultry and poultry products; dairy production; the production of field crops, tobacco, fruits, vegetables, nursery stock, ornamental shrubs, ornamental trees, flowers, sod, or mushrooms; timber; pasturage; any combination of the foregoing; the processing, drying, storage, and marketing of agricultural products when those activities are conducted in conjunction with, but are secondary to, such husbandry or production.

Aisle. That part of an off-street parking or loading area which provides vehicular access to parking or loading spaces, exclusive of driveways.

Alterations, structural. Any change in the supporting members of a building such as bearing walls, columns, beams or girders.

Antique Shop. Any premises used for the sale or trading of articles of which 80 percent (80%) or more are over thirty (30) years old or have collectible value. Antique shop does not include a thrift or second-hand store.

Applicant. Any Person or authorized agent of a Person, that applies for a Zoning Permit, Certificate of Appropriateness, Map Amendment or other land use process or approval pursuant to this chapter.

Application. The process by which an Applicant submits a request to be granted any land use approval or land use approvals under the provisions of this chapter. An Application includes all attachments to the form promulgated by the city from time to time, as well as all verbal statements and representations made by the Applicant throughout the review process.

Auction facility. A building, area, or areas within a building used for the public sale of goods, wares, merchandise, or equipment to the highest bidder. This definition excludes therefrom an auction, the principal purpose of which is the sale of livestock or motor vehicles.

Awning. A shelter projecting from and supported by the exterior wall of a building constructed of non-rigid materials on a supporting framework.

Awning, Back-lit. Any awning, fixed or retractable, which incorporates any transparent or translucent material in its covering and is illuminated by a light source placed behind the covering.

Awning, Fixed. A fixed structure supported by a frame or bracketing extending outward from the wall of a building which does not retract or roll up and is constructed to provide shade or shelter.

Awning, Retractable. A structure fastened to the wall of a building which, in a closed or rolled up position, does not extend beyond 8 inches from the face of the building and, when extended, is constructed to provide shade or shelter.

Awning Sign. A non-illuminated sign affixed flat to the surface of an awning (known as the base material) or which does extend vertically or horizontally beyond the limits of such an awning.

B.

Bakery-Retail. An establishment primarily engaged in the retail sale of baked products for consumption off site. The products may be prepared either on or off site. Such use may include incidental food service. A bakery shall be considered a general retail use.

Banner. A temporary sign composed of light weight material not enclosed in a rigid frame, secured or mounted so as to allow movement of the sign caused by the movement of the atmosphere. Includes those used to announce open houses, grand openings, make special announcements, or communicate events.

Basement. A story all or partly underground but having at least one-half (1/2) of its height below the average level of the adjoining ground.

Berm. A mound of earth, higher than the surrounding grade, used for screening or buffering, definition of space, noise attenuation and/or decoration in landscaping.

Beverage – Brewing and Distilling. An establishment where beer, malt beverages or spirits are made on the premises and then sold or distributed, and which produces less than 15,000 barrels (~465,000 gallons) per year. The brewer may sell to a retailer or directly to a customer.

Beverage – Distribution. A facility where beverages are received and/or stored for delivery to the ultimate customer at remote locations.

Beverage - Non-Alcoholic Production. A facility that manufactures and distributes non-alcoholic beverages, such as soft drinks, to other distributors or retailers.

Beverage Sales - Liquor and Beer Sit Down/Bar Establishment. An area primarily devoted to the serving of alcoholic beverages and in which the service of food is only incidental to the consumption of such beverages.

Beverage Sales - Liquor Store. Any business selling general alcoholic beverages, also known as sale of distilled spirits or hard liquor, and may include wine and beer sales, for off-premises consumption.

Block. A parcel of land which is bound by other lots, streets, highways, railroad rights-of-way, parks or open space, undeveloped land, water courses or bodies of water, channels or a combination thereof.

Boarding / Kennel. Any structure or premises on which five (5) or more dogs or cats over three (3) months of age are housed, bred, boarded, or trained overnight.

Buffer. The promotion of separation and compatibility between land uses of different intensities within or adjacent to a development, or along roadways or other public areas through the use of setbacks, natural vegetation, berms, fences, walls or a combination thereof. The term "buffer" may also be used to describe the method(s) used to promote compatibility such as a landscape buffer.

Buffer Yard. Area intended to provide buffering between land uses of different intensities or along public rights-of-way.

Building. A structure enclosed with exterior walls used or intended for the support, enclosure, shelter, or protection of persons, animals, chattels, or property.

Building, Accessory. See "Accessory Structure".

Building Code. Part Thirteen of the Codified Ordinances of the City of Reynoldsburg, Ohio.

Building Frontage. The side, or facade, of a building closest to and most nearly parallel to an abutting street.

Building Frontage, Primary. A building frontage that abuts a street listed as a primary street.

Building Frontage, Secondary. A building frontage that abuts an alley or street not listed as a primary street.

Building, Height. The vertical distance measured from the average elevation of the proposed finished grade at the front of the building to the highest point of the coping of a flat roof, to the deck line of mansard roofs, and the mean height between eaves and ridge for gable, hip and gambrel roofs.

Building, Main. A building in which is conducted the main use of the lot on which the building is located.

Building Materials and Hardware (Retail). An establishment for the retailing, wholesaling or rental of building supplies or construction equipment. This use classification includes lumberyards, home improvement sales and services, tool and equipment sales or rental establishments.

Building, Rear. The wall or plane opposite the primary building frontage. For a building on a corner lot, the building rear is the wall or plane opposite the wall or plane containing the principal building entrance.

Build-To-Line. The point from a primary or secondary street where the front of the building is to be located.

Business Sign. A sign containing product advertisements or other detailed information about the operation of a business. Specifically, such sign is one which contains brand names of goods sold or services rendered on the premises, a listing of numerous specific types of goods or services, prices or special sale information, telephone number or other similar information. A business sign may also include items permitted on an identification sign.

Building, Temporary. A building located on a lot for a limited duration.

C.

Camping. Any parcel or tract of land under the control of any person, organization, or governmental entity wherein sites are offered for the use of the public or members of any organization for the establishment of temporary living sites for two or more recreational vehicles, tents or camping units.

Canopy. A permanent or temporary structure other than an awning or marquee, attached to a building over an entrance and carried by a frame supported by the ground or sidewalk, extending from the entrance to or over the public sidewalk for the purpose of providing shade or shelter to pedestrians walking from the sidewalk to the building's entrance.

Cemetery. Land used or intended to be used for the burial of the human dead and dedicated as a cemetery for such purposes.

Certificate of Appropriateness. A certificate issued by the Planning and Zoning Administrator stating that the proposed modification to a structure complies with the provisions of Chapter 1109.19.

Changeable Copy Sign (Automatic). A sign or portion thereof on which the copy changes automatically or animation is displayed through electrical or electronic means (e.g., time and temperature units and message centers); considered a business sign.

Changeable Copy Sign (Manual). A sign or portion thereof on which copy is changed manually through placement of letters or symbols on a sign panel; considered a business sign.

Channel. A natural or artificial watercourse of perceptible extent, with bed and banks to confine and conduct continuously or periodically flowing water.

Charter. The charter of the City, the same as may be amended from time to time.

Child Care, Type A. A permanent residence in which child care or publicly funded childcare is provided for seven (7) to twelve (12) children at one time or a permanent residence of the administrator in which childcare is provided to four (4) to twelve (12) children at one time if four (4) or more children at one time are under the age of two (2).

Child Care Center, Type B. A permanent residence of the provider in which child care is provided for one to six (6) children at one time in which no more than three (3) children are under the age of two (2) at one time.

Child care – in home. A private home licensed by the state of Ohio in which more than six (6) but not more than twelve (12) minor children are given are and supervision for periods of less than twenty-four (24) hours a day, unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage, or adoption.

Child day care – center. Any place operated by a person, society, agency, corporation, institution, or any other group that is licensed by the state of Ohio wherein twelve (12) or more children under 17 years of age who are not related to the facility operator and whose parents or guardians are not residents in the same house and with such person, society, agency, corporation, or institution responsible for the control and care of children enrolled therein.

City. The City of Reynoldsburg, Ohio, a municipal corporation, acting by and through its City Council.

City Attorney. The elected Law Director of the City.

City Council. The elected members of the City Council of the City.

City Engineer. The City Engineer of the City.

Clerk of Council. The Clerk of the City Council.

Clothing Services – Dry Cleaning with Drive Thru. An establishment or business maintained for the pickup and delivery of dry cleaning and/or laundry via a counter or drive-through without the maintenance or operation of any laundry or dry-cleaning equipment or machinery on the premises.

Clothing Services - Dry Cleaning without Drive Thru. An establishment or business maintained for the pickup and delivery of dry cleaning and/or laundry via a counter without the maintenance or operation of any laundry or dry-cleaning equipment or machinery on the premises. Drive-through pick-up or delivery is not permitted.

Clothing Services - Tailor. An establishment or place of business primarily engaged in the provision of frequent or recurrent services related to the alteration or hand-made creation of clothing.

Code. The Code of Ordinances of the City.

Commercial Center - Outdoor - Small. A group of commercial establishments planned, constructed, and managed as a total entity shopping center with customer and employee parking provided on-site, provision for goods delivery separate from customer access, aesthetic considerations, whereby access to individual shops requires outdoor access from a shared sidewalk or road. For centers that are 9,500 square feet or less.

Commercial Center - Outdoor - Large. A group of commercial establishments planned, constructed, and managed as a total entity shopping center with customer and employee parking provided on-site, provision for goods delivery separate from customer access, aesthetic considerations, whereby access to individual shops requires outdoor access from a shared sidewalk or road. For centers that are 9,501 square feet or more.

Common Area. Land in any development held in common or single ownership that is not reserved for the exclusive use or benefit of an individual tenant or owner.

Community Activity. An activity that is open to the general public and sponsored by a public, private, nonprofit or religious organization that is educational, cultural, or recreational in nature.

Community Facility. Existing, planned and proposed parks, playgrounds, schools and other public lands and buildings located within the City.

Community Facility – Activity Center. A building or other enclosed structure open to residents of a subdivision or the general public, which is owned and operated by a private entity, a public agency, or a nonprofit organization, and that is used predominantly for cultural, educational, recreational, or social purposes.

Community Facility - Detention and Corrections. A facility for the detention, confinement, treatment or rehabilitation of per- sons arrested or convicted for the violation of civil or criminal law. Such facilities include an adult detention center, juvenile delinquency center, jail, and prison. These facilities house prisoners who are in the custody of city/county/ law enforcement and the facilities are typically government owned.

Community Facility - Government Administration and Courts. A facility devoted to the operations of the City, County or State, but not including detention and corrections.

Community Facility - Outdoor Recreation. Non-commercial recreation premises consisting of woodlands, water courses, and fields used for active recreational activities that do not require modifying the existing setting, including but not limited to, paintball, laser tag, and orienteering.

Community Facility – Park. A natural or landscaped area, buildings, or structures, provided by a unit of government, to meet the active or passive recreational needs of people.

Community Facility - Public Health Safety. Facilities operated by public agencies including fire stations, other fire prevention and firefighting facilities, police and sheriff substations and headquarters, including interim incarceration facilities.

Community Facility – Trail. A public path exclusively for pedestrians and bicycles, but not including a sidewalk or street.

Comprehensive Plan. A plan, or any portion thereof, adopted by the Planning and Zoning Board and Council of the City showing the general location and extent of present and proposed physical facilities including housing, industrial and commercial uses, major thoroughfares, parks, schools and other community facilities. This plan establishes the goals, objectives and policies of the community.

Conditional Use. A special use that allows the Planning and Zoning Board to review and place conditions on development standards such as location, design, size, density, operation, intensity of use, generation of traffic and traffic movement, processes and equipment employed, and the amount and kinds of public facilities and services required. These conditions ensure that each proposed use is consistent with the intent and objectives of the particular district in which it is to be located, and protects adjacent properties and the general health, safety and welfare of the public.

Conditional Use Permit. A permit issued by the Planning and Zoning Administrator upon approval by the Planning and Zoning Administrator or the Board of Zoning and Building Appeals, as applicable, to allow a use designated as such in the applicable district or overlay.

Council. The Council of the City.

County. Collectively, as applicable, any of Franklin, Fairfield or Licking Counties in Ohio.

County Recorder. The office of official land records for the County.

Curb Cut. A location, approved by the City, at which vehicular access is permitted from the traveled portion of a public street to or from a private driveway. Such location may involve or require the alteration or cutting of the curb abutting the street pavement to allow for at-grade vehicular movement onto the street pavement.

D.

Deed. A written instrument for the conveyance of real property from one person to another.

Deciduous. A plant with foliage that is shed annually.

Deck. An uncovered platform or floor, supported above the ground and open to the sky. If the deck is attached to the principal structure, the principal structure's side yard setbacks and rear yard setbacks will apply. If the deck is freestanding and not attached to the principal structure, it will be considered an accessory structure and will need to meet all accessory structure standards.

Density. A unit of measurement; the number of dwelling units per acre of land.

A. Gross density. The number of dwelling units per acre of the total land to be developed.

B. Net density. The number of dwelling units per acre of land when the acreage involved includes only the land devoted to residential uses.

Developer. Any person, subdivider, partnership, owner or corporation or duly authorized agent who constructs or contracts to construct improvements on subdivided land.

Development. The improvement of a tract or parcel of land, which results in an alteration of land or vegetation.

Development Agreement. An agreement between a Developer and the City and which contains the following components:

A. Summary and Affidavit;

B. Preliminary Development Plan;

C. Final Development Plan;

D. Restrictive Covenants; and

E. Attachments.

Development Director. The Development Director of the City of Reynoldsburg as defined in the Administrative Code. All references to the Development Director may be construed as referring to the Development Director or his/her designee.

Development Plan. Reports, applications, maps, technical drawings, illustrations, and other matter describing the intended use and construction of improvements of land, particularly relating to a request for amendment of a zoning district or for creation of a planned unit development.

Directional Sign. On-premise sign used to direct vehicles to parking areas or indicate points of entry or exit for a facility or off-street parking lot. Such signs may contain information such as “Lot A”, “Green Lot”, “in”, “enter”, “entrance”, “out”, “exit”, “do not enter” or similar directives. Such signs shall not include any business information other than the business logo and/or name.

District. A section of the City for which zoning regulations governing the use of land and buildings, the height of buildings, the sizes of yards and the intensity of uses are uniform. Boundaries of the districts are shown on the Official Zoning Map.

Drainage Features and Improvements. Natural features of land or designed features of land, buildings, and other improvements, including storm sewers, natural and manmade watercourses, swales, yard drains, catch basins, curbs, retention facilities, and other features affecting the flow of storm water or designed to direct or manage the flow of storm water.

Driveway. A paved way providing access from a street or other means of access to the subject premises.

Drive-Thru. A building or portion thereof that, by design, permits customers to receive goods or services while remaining in a motor vehicle.

Dwelling. Any building or portion thereof designed or used exclusively as the residence or sleeping place of one or more persons, but not including a tent, cabin, trailer or mobile home, boarding or rooming house or hotel.

Dwelling, Assisted. A residential facility for elderly persons (age 60 or older) and their spouses, or for persons having such disabilities as to require assistance with daily living tasks, as suggested by their physician. The facility contains four or more dwelling units and/or rooming units, and provides, through on-site personnel, such exclusive resident services as meal preparation, laundry services and room cleaning.

Dwelling – Attached Single-Family. A dwelling unit that is attached to one or more dwelling units, each with independent exterior access and each with no less than two exterior walls. This type of dwelling includes condominiums and townhouses.

Dwelling – Detached Single-Family. A building designed for or occupied by one family or housekeeping unit.

~~Dwelling – Developmental Disability. A dwelling devoted to two or more persons who have a physical or mental impairment or handicap, or both, that substantially limits one or more major life activities, such as caring for oneself, performing manual tasks, walking, seeing, hearing, speaking, learning, breathing, or working. A physical or mental impairment may include orthopedic, visual, speech, or hearing impairments, Alzheimer's disease, presenile dementia, cerebral palsy, epilepsy, muscular dystrophy, multiple sclerosis, cancer, heart disease, diabetes, mental retardation, autism, or emotional illness~~

Dwelling Floor Area. The sum of the gross horizontal inside dimension areas of the floors of a dwelling, including stairways, halls, and closets, but not including basements, porches, garages, breeze ways, utility rooms, laundry areas, or carports.

Dwelling, Group. A residential facility providing accommodations and personal care services for one (1) to five (5) unrelated persons and licensed as a residential facility that meets the criteria specified in Ohio Revised Code section 5119.34 (B)(1)(b).

Dwelling, Mobile Home. Any non-self-propelled vehicle so designed, constructed, reconstructed or added to by means of accessories in such manner as will permit the use and occupancy thereof for human habitation when connected to utilities, whether resting on wheels, jacks, blocks or other temporary foundation and used or so constructed as to permit its being used as a conveyance upon the public streets and highways and exceeding a gross weight of 4,500 pounds and an overall length of thirty (30) feet.

Dwelling, Multi-Unit Building. A building containing three or more dwelling units.

Dwelling, Multi-Unit Building Complex. A site containing two or more multi-unit buildings situated in relation to one another, which may include common facilities such as a clubhouse and/or swimming pool and common parking areas.

Dwelling, Nursing. A facility operated and dedicated to the care of persons who cannot care for their own needs either partially or totally. This term includes nursing homes, skilled nursing facilities, convalescent homes, special care facilities (e.g., Alzheimer Unit), assisted living facilities, adult day care facilities, independent living units such as patio homes, and other similar facilities.

Dwelling - Two-Family. A building on a single lot containing two dwelling units, each of which is totally separated from the other by an unpierced wall extending from ground to roof or an unpierced ceiling and floor extending from exterior wall to exterior wall, except for a common stairwell exterior to both dwelling units.

Dwelling Unit. One or more rooms, designed, occupied or intended for occupancy as a separate living quarter, with cooking, sleeping and sanitary facilities provided within the dwelling unit for the exclusive use of a single household maintaining a household.

E.

Easement. A right granted by a written instrument from one owner of land to another for use of a specified portion of the grantor's real property for a specific purpose or purposes as set forth in an easement agreement.

Easement Area. The particularly described area of exclusive or non-exclusive legal interest in, on, under, over or through a portion of a parcel of land or appurtenance thereto.

Educational/Public Service sign. A sign designed to provide information on school or public events, community recognition and/or promotes information about good health and safety.

Electric Vehicle (EV). A motor vehicle that uses one or more electric motors for propulsion. Onboard batteries provide electricity for propulsion, which can be charged using Electric Vehicle Supply Equipment.

Electric Vehicle Supply Equipment (EVSE Installed). Are parking spaces reserved for Electric Vehicles (EV) and provide dedicated panel capacity, conduit, and EVSE installed.

Emergency. A reasonably unforeseen occurrence with a potential to endanger personal safety or health, or cause substantial damage to property, that calls for immediate action.

Engineer. Any engineer licensed by the State of Ohio State Board of Registration for Professional Engineers.

Equipment Repair. Establishments primarily engaged in the provision of repair services to individuals and households, rather than businesses, but excluding automotive and equipment repair use types. Typical uses include appliance, electronic, computer, or bicycle/scooter repair shops.

Essential Public Services and Utilities. The erection, construction, alteration or maintenance, by public utilities or municipal or other governmental agencies, of underground gas, electrical, water transmission or distribution systems, collection, communication, supply or disposal systems or sites, including poles, wires, mains, drains, sewers, pipes, traffic signals, hydrants or other similar equipment and accessories in connection therewith which are reasonably necessary for the furnishing of adequate service by such public utilities
or municipal or other governmental agencies or for the public health or safety of general welfare, but not including buildings.

Event Center – Private Events and Conferences. A commercial event center used to host private events and conferences such as weddings and other personal events, but not including funerals, and private business or industry conferences.

Event Center – Public Meetings and Conventions. A public event center used to host events and conferences such as trade shows, conferences, and other public events.

Evergreen. A plant with foliage that persists and remains green year-round.

F.

Façade. A side of the exterior of a building (exclusively of permitted encroachments), especially the front, but also sometimes the sides and rear.

Fee. A charge, as required by this Zoning Code, paid by an applicant or other person, for the purpose of paying some or all of the costs incurred by the City in processing and reviewing requests for zoning amendments, site plans, zoning permits, and other administrative activities relating to zoning.

Fence. A structure, hedge or other landscape material positioned up to or on top of the property line, easement line, right-of-way, or setback line, as applicable for the purpose of separating properties, or for screening, enclosing, and/or protecting the property within its perimeter.

Fence, decorative. A fence, hedge or other landscaping material used for decorative purposes only and not intended for use as an enclosure, barrier, or means of protection or confinement. Decorative fences shall not be site obscuring.

Financial Services and Banking – with Drive-Thru. A facility including provisions for the conduct of banking services directly to the occupants of motor vehicles for the custody, loan, or exchange of money; for the extension of credit; and for facilitating the transmission of funds. Does not include standalone ATM.

Financial Services and Banking - without Drive-Thru. A freestanding building without a drive-up window, for the custody, loan, or exchange of money; for the extension of credit; and for facilitating the transmission of funds.

Finished Grade. The average level of the finished surface of the ground adjacent to the exterior walls of a building.

Fire Pit. An aboveground structure together with a seating area, installed, constructed and designed for the setting of small-scale fires in accordance with the regulations applicable to the subject property upon which such structure and seating area are located.

Flood plain. Land under and along a watercourse which is subject to inundation by a 100-year flood, as determined by the Federal Emergency Management Agency (FEMA) or other source determined acceptable to the city.

Flood, Regional. Large floods which have previously occurred or which may be expected to occur on a particular stream because of like physical characteristics. The regional flood generally has an average frequency of the 100-year recurrence interval flood.

Floodway. That portion of the flood plain, including the channel, which is reasonably required to convey the regional flood waters. Floods of less frequent recurrence are usually contained completely within the floodway.

Floodway Fringe. That portion of the flood plain, excluding the floodway, where development may be allowed under certain restrictions.

Floor. That part of a room or story which forms its lower, horizontal enclosing surface.

Floor area, gross. The total square feet of all main and accessory buildings which are enclosed, measured from the exterior building face or from the centerline of common walls separating building units.

Food Sales - Farm Market. Retail sales of agricultural products and items grown or produced in and around the City.

Food Sales - Large Format Grocery. A retail establishment which primarily sells food, but also may sell other convenience and household goods, and which occupies at least 25,000 square feet of gross floor area. At least 1,000 square feet of a large format grocery shall be devoted to the sale of fresh produce at all times.

Food Sales - Small Format Grocery. A retail establishment which primarily sells food, but also may sell other convenience and household goods, and which occupies at least 500 square feet but not more than 25,000 square feet of gross floor area. At least 10 percent of a small format grocery shall be devoted to the sale of fresh produce at all times.

Food Service - Commissary/Bakery. A facility that produces food and baked goods for distribution or sale to restaurants and retail bakeries. Any on-site **and/or** direct-to-consumer sales are ~~only for consumption off the premises.~~ **prohibited. This specifically excludes Food Service – Commercial Kitchen.**

Food Service – Commercial Kitchen. A commercial food facility in which goods are processed or otherwise prepared for off-site sale or consumption. Facilities may operate as a shared facility where multiple individual or businesses lease shared space or may be used by a single operator. This use classification includes catering, as well as ghost kitchen, where customers are served exclusively by delivery and pick-up based on phone and online ordering. No customer dining is provided on the premises. Does not include eating establishments where customers are served from a walk-up ordering counter for either on- or off-premises consumption and establishments where most customers are served food at a table for on-premises consumption. This listing also excludes commercial kitchens that are incidental and accessory to the primary use.

Food Service – Deli. An establishment where food is sold for consumption off- premises and no counters or tables for on- premises consumption of food are provided, but excludes groceries and supermarkets.

Food Service - Fast Casual Restaurant. An establishment where food is preparing and purveying food on a full-service basis where customers order at the counter and where their prepared food is either delivered to them or carried by them to a table for on-premises consumption or carried out for off-premises consumption.

Food Service - Full Service Restaurant. An establishment maintained, operated, and/or advertised or held out to the public as a place where food and beverage are served to the public on demand from a menu during stated business hours, served in and on reusable containers and dinner- ware, to be consumed on the premises primarily inside the building at tables, booths, or counters, with chairs, benches, or stools. This use may include incidental delivery service using no more than two delivery vehicles.

Food Service – Processing. Manufacturing establishments processing foods for human consumption and certain related products. Includes: (1) bakery products, sugar and confectionery products (except facilities that produce goods only for on-site sales with no wider distribution; (2) dairy products processing; (3) fats and oil products (not including rendering plants); (4) fruit and vegetable canning, preserving, and related processing; (5) grain mill products and by-products; (6) meat, poultry, and seafood canning, curing, and byproduct processing (not including facilities that also slaughter animals); and (7) miscellaneous food preparation from raw products, including catering services that are independent from food stores or restaurants.

Food Service – Production. Manufacturing establishments producing foods for human consumption and certain related products. Includes rendering plants and animal slaughterhouses.

Food Service - Quick Serve/Fast Food with Drive Thru. An establishment engaged primarily in the business of preparing food and purveying it on a self-serve or semi self-serve basis. Customer orders and/or service may be by means of a walk-up counter or window designed to accommodate vehicular traffic. Consumption may be either on or off the premises.

Food Service - Quick Serve/Fast Food without Drive Thru. An establishment engaged primarily in the business of preparing food and purveying it on a self-serve or semi self-serve basis. Customer orders and/or service may be by means of a walk-up counter. Consumption may be either on or off the premises.

Forestry. Facilities, activities, or equipment used to plant, raise, manage, harvest, and remove trees on private land. The term includes site preparation, fertilization, pest control, and wildlife management.

Freestanding Sign. A sign which is not attached to a building and which is either attached directly to the ground or elevated on a supporting structure attached to the ground.

Freestanding solar panel. A solar panel or an array of solar panels that is not attached to a structure and is mounted on a structure that is attached to the ground.

Frontage. The principal elevation of a building, which is most often the elevation that abuts a street. In the context of the location of any building typology described under the Zoning Code, frontage means the street or right-of-way type that a building is permitted to abut.

G.

Gable. The triangular section of wall at the end of a pitched roof, occupying the space between the two slopes of the roof, or the whole end wall of a building or wing having a pitched roof.

Gallery – art. An establishment engaged in the sale, loan, or display of art books, paintings, sculpture, or other works of art. This clarification does not include libraries, museums, or non-commercial art galleries.

Garage, Private. An accessory building or part of a principal building used for the storage of motor vehicles as an accessory use and in which no business or industry connected directly or indirectly with the repair or servicing of such motor vehicles is carried on.

Garden center – indoor and outdoor. A place of business where retail and wholesale products and produce are sold to the consumer. These centers, which may include a nursery and/or greenhouse, import most of the items sold, and may include plants, nursery products and stock, potting soil, hardware, power equipment and machinery, hoes, rakes, shovels, and other garden and farm variety tools and utensils.

Golf Course. A tract of land laid out with at least nine holes for playing a game of golf and improved with tees, greens, fairways, and hazards. A golf course includes a clubhouse and shelters as accessory uses.

Gasoline Station. See "Retail – Convenience with gasoline".

Grade. The elevation of land surrounding a structure or the slope of a road, in each case expressed as a percentage.

Ground Sign. A display sign supported by uprights or braces in or upon the ground surface.

H.

Health and Wellness – Clinic. An establishment where patients who are not lodged overnight are admitted for examination and treatment by a group of physicians practicing medicine together.

Health and Wellness – Fitness Facility/Gym. Any fitness center, gymnasium, health, studio fitness center and athletic club, which may include any of the following: aerobics instruction, exercise machines, sauna, spa or hot tub facilities; indoor tennis, handball, racquetball and other indoor athletic amenities and events.

Health and Wellness – Massage. A private establishment that provides therapeutic or medical massage of a non-sexual nature provided by a licensed practitioner.

Health and Wellness - Physical therapy. An outpatient office establishment that provides physical rehabilitation or occupational therapy for individuals with an injury or disability.

Height or Above Ground Level. When referring to a tower or other structure, the distance measured from

the finished grade at the base of the tower/structure to the highest point on the tower or other structure, including the base pad and any antenna.

Home Occupation. An occupation conducted in a dwelling unit, provided that no ~~more than one~~ person **who is not a permanent resident of the dwelling shall be employed in the home occupation.** ~~other than members of the family residing on the premises shall be engaged in such occupation.~~ The use of the dwelling unit for the home occupation shall be clearly incidental and subordinate to its use for residential purposes by its occupants, and not more than thirty ~~five~~ percent (30~~5~~%) of floor area of the dwelling unit shall be used in the conduct of the home occupation. There shall be no change in the outside appearance of the building or premises, or other visible evidence of the conduct of such home occupation ~~other than one sign, not exceeding four square feet in area, non-illuminated, and mounted flat against the wall of the principal building.~~ No traffic shall be generated by the conduct of such home occupation and any need for parking generated by the conduct of such home occupation shall meet the off-street parking requirements as specified in this Zoning Ordinance, and shall not be located in a required front yard.

Homeowners Association (HOA) or Property Owners Association (POA). An incorporated, non-profit organization established by a developer, subdivider or an association of property owners whose membership shall consist of individual property owners within a subdivision.

Household. A person living alone or two (2) or more persons living together as a single housekeeping unit as distinguished from two or more persons living together in any congregate or group housing. For purposes of these Regulations, the following shall create a rebuttable presumption that the group is not a single housekeeping unit:

A. Keyed lock(s) on any interior door(s) to prevent access to any area of the dwelling unit with sleeping accommodations;

B. Members of the group have separate leases, or sub-leases and/or make separate rent payments to a landlord; or

C. The group significantly reforms over the course of a twelve (12) month period by losing and/or gaining members.

I.

Identification Sign. A sign identifying or naming a business institution, residential development or other use. Specifically, such sign may indicate the name, owner, or manager and address of an existing building, business or other use, including the general type of goods sold or services rendered, but without a listing of numerous specific goods or services and without reference to brand names, prices, "sales" or telephone numbers.

Illuminated Sign. Any sign illuminated by electricity, gas or other artificial light including reflecting or phosphorescent light.

Improvements. Any additions to the natural state of the land which increases its value or utility, including pavements, curbs, gutters, sidewalks, crosswalks, water mains, sanitary and storm sewers, landscaping and other appropriate facilities or plantings.

A. "Site improvements" means the improvements made to the land outside the exterior limits of a structure or structures.

B. "Public improvements" means all improvements financed entirely or in part by public funds or which have been dedicated to public use by plat, easement or deed of transfer.

C. "Final Plat Improvements" mean those improvements set forth in the final plan submitted to and approved by the City in accordance with these regulations.

D. "Drainage Improvements" means those improvements determined by the City Engineer to be necessary to facilitate satisfactory drainage in accordance with these regulations, including but not limited to underground pipe, inlets, catch basics, ditches, and/or retention basins.

Independent Living, Age-Restricted. A private development comprised of individual dwelling units designed for occupancy by individuals who are over a threshold age, which is typically fifty-five (55) years old.

Indoor Recreation Enterprise. Any business which is operated as a recreational enterprise, either publicly or privately owned, for profit. Examples include, but are not limited to, arcades, bowling alleys, theaters, etc.

Indoor Storage Facility. Climate-controlled storage within an enclosed structure containing separate, individual, and private storage spaces of varying sizes leased or rented on an individual basis for varying periods of time, with no unit having direct external access, but being served by common indoor access aisles.

Information Window/Wall Sign. Window or wall signage bearing only information about entry and exit, business hours, authorized service representative information and/ or discount, credit systems accepted in that establishment (e.g. American Express, MasterCard, Visa, Golden Buckeye Card, etc.), and business directives (e.g. no soliciting, no firearms, etc.).

Institutional/Government Offices. A building or location that provides for community meetings and/or activities including, but not limited to, City Hall, Township Hall, school administration building, recreation center (public or private), property listed on the National Register of Historic Places, Chamber of Commerce building, Arts Council building, library, or other public buildings owned or operated by the City.

J.

Junk. Old or scrap copper, brass, rope, gas, trash, waste, batteries, paper or rubber, junked, dismantled or wrecked, automobiles or parts thereof, iron, steel and other old or scrap ferrous or nonferrous materials.

Junk Storage and Sales. Any lot, land, or structure, or part thereof, used primarily for the collection, storage and sale of waste paper, rags, scrap metal or discarded material, or for the collecting, dismantling, storage and salvaging of machinery or vehicles not in operating condition, and for the sale of parts thereof.

K.

No definitions.

L.

Landscaped Area. An area with plants, trees, natural turf or other vegetation planted in accordance with a landscape plan.

Landscaping. Physical improvements consisting of plants, shaped earth, walls and fences, rocks, and other related features, typically installed to beautify a premises and/or to screen negative impacts or protect certain uses from one another.

Land Use Plan. The long-range plan for the desirable use of land in an area as adopted by the Planning Zoning Board and City Council; one purpose of the Plan, among other purposes, is to serve as a guide in future development and zoning for the community.

Library. A public facility for the use, but not sale, of literary, musical, artistic, or reference materials.

Live Plantings. Trees, shrubs and organic ground cover which are in healthy condition.

Live Theater. A structure used for dramatic, operatic, or other live performance, for admission to which entrance money is received.

Loading Space, Off-Street. Space logically and conveniently located for bulk pickups and deliveries, scaled to delivery vehicles expected to be used, and accessible to such vehicles when required off-street parking spaces are filled. Required off-street loading space is not to be included as off-street parking space in computation of required off-street parking space. All off-street loading spaces shall be located totally outside of any street or alley right of way.

Logo (or trademark). A letter or group of letters (usually stylized) or a symbol or symbols that represent a word, group of words, or business name. Usually used as part of a business identification scheme that is meant to identify goods, products, services or a business entity itself.

Lot. A portion of a subdivision or other parcel of land intended as a unit for transfer of ownership and/or for building purposes or development, having fixed boundaries and designated on a plat or survey together with the required open spaces and having frontage on a public street or a private street.

Lot Coverage. The ratio of enclosed ground floor area of all buildings and structures on a lot to the horizontally projected area of the lot, expressed as a percentage.

Lot Line Adjustment. A process that is used to change property lines of existing parcels for the purpose of combining two (2) or more adjacent parcels into one (1) parcel, alter and/or correct the boundary between two (2) or more parcels, or reconfigure the shape of parcels, without creating any additional parcels.

Lot Measurements. The method of measurement for a lot under this chapter, which shall be conducted as follows:

A. Depth means the distance between the mid-points of straight lines connecting the foremost points of the side lot lines in front and the rearmost points of the side lot lines in the rear.

B. Width means the distance between straight lines connecting front and rear lot lines at each side of the lot, measured at the minimum required building setback line.

Lot, Minimum Area of. The area of a lot is computed exclusive of any portion of the right of way of any public or private street.

Lot of Record. A lot which is part of a subdivision recorded in the office of the County Recorder, or a lot or parcel described by metes and bounds, the description of which has been so recorded.

Lot Types. Means, as follows:

A. "Corner lot" means a lot located at the intersection of two or more streets. A lot abutting on a curved street or streets shall be considered a corner lot if straight lines drawn from the foremost points of the side lot lines to the foremost point of the lot meet at an interior angle of less than 135 degrees.

B. "Interior lot" means a lot with only one frontage on a street.

C. "Through lot" means a lot other than a corner lot with frontage on more than one street. Through lots abutting two streets may be referred to as double frontage lots.

D. "Reversed frontage lot" means a lot on which frontage is at right angles to the general pattern in the area. A reversed frontage lot may also be a corner lot.

M.

Maintenance bond. An agreement by a subdivider or developer with the City, for a percentage of the established construction cost, used as a guarantee against any deficiencies which might develop between commencement of a development by a subdivider or developer and formal acceptance of dedication by City Council.

Major Thoroughfare Plan. The portion of comprehensive plan adopted by the City Planning and Zoning Board indicating the general location recommended for arterial, collector and local thoroughfares within the appropriate jurisdiction.

Manufactured Home. Any non-self propelled vehicle transportable in one or more sections which, in the traveling mode, is 8 body feet or more in width or 40 body feet or more in length, or, when erected on site, is 320 or more square feet, and which is built on a permanent chassis and designed to be used as a dwelling unit with or without a permanent foundation when connected to the required utilities, and includes the plumbing, heating, air conditioning, and electrical systems contained therein, and which bears a label certifying that it is built in compliance with Federal Manufactured Housing Construction and Safety Standards.

Manufactured Home Park. Any tract of land upon which three or more manufactured homes are located for residential use, either free of charge or for revenue purposes, including any roadway, building, structure, vehicle, or enclosure used or intended to be used as a part of the facilities of such park.

Manufacturing – Artisan. An establishment, not exceeding 3,000 square feet of floor area, for the preparation, display, and sale of individually crafted artwork, jewelry, furniture, sculpture, pottery, leathercraft, hand-woven articles, and related items. Odors, fumes or excess noise may not be produced at the facility.

Manufacturing – Heavy. Any use in which the major activity is the treatment, processing, rebuilding, repairing, or bulk storage of material, products, or items, and where the finished product is not acquired by the ultimate user on the premises and produces any externally perceptible noise, fumes, odors, vibrations, or outdoor storage.

Manufacturing, Light. Manufacturing establishments engaged in and undertaking the assembly, fabrication and conversion of already processed raw materials into products, the production of which does not cause excessive noise, odor or other similar impacts on surrounding land uses

Marquee. A permanent structure fastened entirely to the building and projecting from the wall above an entrance and extending over the street right-of-way to provide shelter for automobile passenger loading and unloading entrance.

Marquee sign. A display sign attached to or hung from and supported by the building and extending beyond the building wall or front facade.

Medical - Clinic. A facility other than a hospital, emergency room or urgent care where medical, mental health, surgical and other personal health services are provided on an outpatient basis. Examples of these uses include: offices for physicians, dentists, chiropractors, or other health care professionals; outpatient care facilities; urgent care facilities; and other allied health services. These facilities may also include incidental medical laboratories. Patients are not provided with room and board and are not kept overnight on the premises. Medical Services and medical clinics include medical and dental laboratories incidental to the medical office use.

Medical – Emergency Services. A 24-hour outpatient facility, operated by a hospital or health organization, and staffed by doctors and nurses that provides immediate emergency care services similar to what would be expected in a hospital. Urgent care facilities are not considered emergency care facilities.

Medical – Full Service Hospital. An institution in which sick or injured persons are provided medical care and assistance and, in the course of same, may be housed overnight, fed and provided nursing and related services. Hospital shall comprise any related, accessory facilities such as laboratories, outpatient departments, training facilities, food service facilities, central service facilities and staff offices which are integral parts of the principal hospital facility.

Medical – Office. A building used exclusively by physicians, dentists, and similar personnel for the treatment and examination of patients solely on an outpatient basis, provided that no over- night patients shall be kept on the premises.

Medical - Outpatient and Urgent Care. Outpatient-only medical services that apply to medical issues whereby a patient requires more immediate attention or care than can be provided by an appointment with a family doctor or general practitioner. Emergency ambulance services may not be provided.

Medical - Psychiatric Facility – Standalone. An establishment where human patients who may or may not be lodged overnight are admitted for examination and treatment by a group of professionals licensed by the state of Ohio to treat mental health issues or addiction.

Medical - Standalone Emergency Services. Stand-alone emergency medical facilities, which provide emergency services, including basic imaging and laboratory services that may be an off-campus emergency center associated with a hospital, or a non-affiliated, licensed medical care provider.

Marijuana Facility - Cultivation. Any entity that has been issued a certificate of operation by the Ohio Department of Commerce to grow, harvest, package, and transport marijuana as permitted under R.C. Chapters 3780 and 3796.

Marijuana Facility - Dispensary. Any entity licensed pursuant to R.C. §§ 3796.04, 3796.10, and/or 3780.15, and any rules promulgated thereunder to sell marijuana.

Marijuana Facility - Processing. Any entity in the business of obtaining marijuana from one or more licensed cultivators, processing marijuana from one or more licensed cultivators, delivering and/or selling marijuana to one or more licensed retail dispensaries, and licensed under Ohio Revised Code Section 3796.19 and/or 3780.14.

Meeting Facility. Facilities typically accommodating groups of students in multiple instructional spaces. Examples of these facilities include: individual and group instruction and training in the arts; production rehearsal; photography, and the processing of photographs produced only by users of the studio facilities; martial arts training studios; gymnastics instruction, and aerobics and gymnastics studios with no other fitness facilities or equipment. This definition also includes production studios for individual musicians, painters, sculptors, photographers, and other artists.

Mineral Extraction / Processing. The exploration for or extraction of surface or subterranean compounds and materials; this includes oil and gas exploration and production, and the mining of metallic and nonmetallic minerals, sand, gravel, and rock.

Mini-Storage Facility. A building consisting of individual, self-contained spaces that are leased or owned for the storage of business goods, household goods, or contractor supplies.

Minor Subdivision. A proposed division of a parcel of land along an existing public street, not involving the opening, widening or extension of any street or road, and involving no more than five lots after the original tract has been completely subdivided, that may be submitted to the authority having approving jurisdiction of plats under the provisions of R.C. 711.05, 711.09 or 711.10 for approval without plat.

Mobile Home Park. Any site, or tract of land under single ownership, upon which three or more mobile homes used for habitation are parked, either free of charge or for revenue purposes; including any roadway, building, structure, vehicle or enclosure used or intended for use as a part

Mobile Home. Any non-self-propelled vehicle so designed, constructed, reconstructed, or added to by means of accessories in such manner as will permit the use and occupancy thereof for human habitation, when connected to utilities, whether resting on wheels, jacks, blocks, or other temporary foundation and used or so construed as to permit its being used as a conveyance upon the public streets and highways and exceeding a gross weight of four thousand five hundred (4,500) pounds and an overall length of thirty (30) feet, and not in compliance with the Federal Manufactured Housing Construction and Safety Standards Act of 1974.

Mobile home subdivision. A subdivision as defined in this section in which three or more mobile homes used for habitation are parked, including any roadway, building, structure, vehicle or enclosure used or intended for use therein.

Monuments. Permanent concrete or iron markers used to establish definitely all lines of the plat of a subdivision, including all lot comers, boundary line comers and points of change in street alignment.

Monument Sign. A sign, with one or two (2) sides, attached to a permanent foundation or fastened to a base, and not attached or dependent upon any structure, pole, post or similar

Mortuary. A building or part thereof used for human funeral services. Such building may contain space and facilities for (a) embalming and the performance of other services used in the preparation of the dead for burial; (b) the performance of autopsies and other surgical procedures; (c) the storage of caskets, funeral urns, and other related funeral supplies; (d) the storage of funeral vehicles; and (e) facilities for cremation. Where a mortuary is permitted, a mortuary chapel shall also be permitted.

Motor Vehicle. A vehicle which is designed and manufactured to be self-propelling or self-moving upon the public street or highway. More specifically, as referred to in this ordinance, it includes: automobiles, trucks, tractors and scooters and motorcycles.

Movie Theater. A specialized theater for showing movies or motion pictures. The primary structural difference between a theater and a movie theater is the projection screen. However, many movie theaters can easily be adapted for stage performances and many stages have folding screens for movie projections. Although screen shapes are mostly rectangular, they come in a variety of shapes. Also, some special-purpose multimedia movie theaters use multiple screens, one on each wall face, or the entire ceiling surface, which are sometimes curved or geodesic in shape.

Multi-Family (2-4 Units). A building designed for two families, or housekeeping units, living independently of each other in separate dwelling units.

Multi-Family. A building or portion thereof designed for or occupied by five (5) or more families, or housekeeping units, living independently of each other in separate dwelling units which are accessible by interior hallways. This type of dwelling unit excludes a hotel.

Multi-Family Rental Office/Management Site. A residential apartment structure, permitted in multi-family residential districts, that is used by an apartment owner, employee or realtor to demonstrate construction and to display built-in amenities to prospective apartment tenants and to promote the rental or lease of apartment units. The rental office may be staffed and furnished.

Museum. A room or building for exhibiting, or an institution in charge of, a collection of books, or artistic, historical, or scientific objects.

N.

New Business. A commercial enterprise that is started for the purpose of making a profit, that also generates a profit from a new product or service. This also applies to non-profits that are organized and operated for a collective public or social benefit. This includes a change of ownership and/or renaming of businesses.

Nonconformities. A building, structure or use of land existing at the time of enactment of this Zoning Ordinance which does not conform to the regulations of the district or zone in which it is situated.

O.

Office – Corporate. An establishment primarily engaged in providing internal office administration services as opposed to customer service in a single building or a campus setting; for example, the headquarters, regional offices or the administrative offices for a corporation. Generally, the majority of the traffic generated from corporate offices comes from employees and not the general public.

Office - Data processing / Call Center. A facility containing equipment for telecommunications or data processing/storage including switches, routers, operation centers, and other infrastructure critical for telecommunication companies, internet servers, data firms, fiber-optic cable, and other technology providers.

Office – Professional Services. Professional offices including: accounting, auditing and bookkeeping services; advertising agencies; architectural, engineering, planning, and surveying services; attorneys; counseling services; court reporting services; data processing and computer services; detective agencies and similar services; educational, scientific, and research organizations; employment, stenographic, secretarial, and word processing services; government offices including agency and administrative office facilities; management, public relations, and consulting services; photography and commercial art studios; writers and artists offices outside the home. Does not include medical offices or offices that are incidental and accessory to an- other business or sales activity that is the principal use. Incidental offices that are customarily accessory to another use are allowed as part of an approved principal use.

Office - Professional Services – Tarot Card Reading/Palm Reader/Fortune Teller/Psychic. A business or individual providing services involving the prediction of future events, insight into personal issues, or spiritual guidance through means such as tarot card reading, palmistry, astrology, clairvoyance, mediumship, or similar methods. This definition does not include licensed counseling services, religious institutions, or medical or psychological services.

Official Zoning Map. The Official Zoning Map of the City of Reynoldsburg, as the same may be amended from time to time in accordance with this Zoning Ordinance.

Off-Premises Sign. Any sign unrelated to a business or profession conducted or to a commodity or services sold or offered upon the premises where such sign is located.

On-Premises Sign. Any sign related to a business or profession conducted, or a commodity or service sold or offered upon the premises where such sign is located.

Opacity. The degree or extent that light is obscured. 100% opacity meaning fully obscured, 0% meaning fully transparent.

Open/Closed Sign. A window or wall sign bearing only information indicating if the business is open or closed. This does not include the hours of operation. Signs that include both the open/closed information and the hours of operation shall be deemed to be an information sign.

Open Space. An area of land that is intended and used for environmental, scenic, or recreational purposes and which may include lawns, landscaping, walkways, active and passive recreation areas, playgrounds, fountains, swimming pools, and wooded areas. Open space shall not be deemed to include paved areas such as roads, driveways, or parking lots, and shall not be deemed to include spaces required for minimum yards. That portion of a natural or man-made water body which shall be interpreted as open space shall be determined by the Planning and Zoning Board.

Ornamental Tree. A deciduous tree planted primarily for its ornamental value or for screening and which will typically be smaller than a shade tree.

Outdoor Recreation Enterprise. Any business which is operated as a recreational enterprise, either publicly or privately owned, for profit. Examples include but are not limited to horse stables, fisheries, wilderness preserves, golf course, mini-golf courses, amusement parks and campgrounds.

Outdoor Processing – Agriculture. Activities involving a variety of operations on crops or livestock which may generate dust, noise, odors, pollutants, or visual impacts that could adversely affect adjacent properties. These uses include but are not limited to slaughterhouses, mills, canneries, and milk processing plants.

Outdoor Processing – Composting. An establishment for the processing of organic waste in a controlled environment to produce a stable fertilizing product by microbiologically degrading organic matter under aerobic conditions.

Outdoor Processing - Concrete and Asphalt. An industrial facility used for the production of asphalt or concrete, or asphalt or concrete products, used in building or construction, and includes facilities for the administration or management of the business, the stockpiling of bulk materials used in the production process or of finished products manufactured on the premises and the storage and maintenance of required equipment, but does not include the retail sale of finished asphalt or concrete products.

Outdoor Storage. The keeping of property in an open area of a lot for the purpose of sales, storage, or display.

Overnight Lodging – Bed and Breakfast. An owner-occupied residential single-family, detached structure wherein lodging and breakfast only are provided to transient guests for compensation.

Overnight Lodging – Boutique Hotel. A small-scale hotel in a historic structure, or a structure with façade made of a high-quality material such as wood, brick, masonry, tile, stone, granite, limestone, or another natural material, that has fewer than thirty (30) rooms. Rooms must be accessed from an interior hallway.

Overnight Lodging – Hotel. A place of transient occupancy which includes any structure consisting of one or more buildings containing any combination of more than five (5) guestrooms that are each approved by the Chief Building Official and the fire chief as meeting the requirements for transient sleeping rooms, or as having features of such sleeping rooms and dwelling units within the same room, and such structure is specifically constructed, kept, used, maintained, advertised, and held out to the public to be a place where transient sleeping accommodations are offered for pay to persons. “Hotel” does not include agricultural labor camps, apartment houses, apartments or other similar places of permanent personal residence, lodging houses, rooming houses, or hospital or college dormitories.

Overnight Lodging – Resort. A group or groups of buildings containing more than five dwelling units and/or guest rooms and providing outdoor recreational activities that may include golf, horseback riding, swimming, shuffle- board, tennis and similar activities. A resort may furnish services customarily furnished by a hotel, including a restaurant, cocktail lounge, and convention facilities.

Owner. Any individual, firm, association, syndicate, co-partnership, corporation, trust, or other legal entity having sufficient proprietary interest in real property to commence and maintain proceedings with respect to any land use approval sough hereunder.

Overlay. An area depicted on the official zoning map, within which, through super-imposition of a special designation, certain regulations and requirements apply in addition to those of the base zoning districts to which such designation is added.

P.

Pad. A building site prepared by artificial means, including grading, excavation or filling, or any combination thereof.

Panel Sign. A sign which is mounted, attached, painted, or displayed on a sign panel.

Parapet Wall. A low wall barrier at the edge of a roof or structure which may serve to prevent falls over the edge or serve as a stylistic feature.

Parcel. A division of real property contained in a single legal description that is recorded in the official land records of the Recorder's office.

Park. See "Community Facility - Park".

Parking Area or Structure. An off-street area or structure for required parking or loading spaces, including driveways, access ways, aisles, parking and maneuvering space necessary for the parking or loading areas.

Parking Space, Off-Street. An area adequate for parking an automobile with room for opening doors on both sides, together with properly related access to a public street or alley and maneuvering room, but shall be located totally outside of any street or alley right of way.

Patio. An outdoor seating area, covered or uncovered, constructed, installed and located upon a property in accordance with all local and state laws and regulations, including this zoning ordinance, applicable to the subject property upon which such seating area is located.

Pedestrian Amenity. Elements of individual developments that directly affect the quality and character of the public domain.

Pedestrian Zone. An area between a main building and a public street utilized for pedestrian access and amenities.

Perimeter Treatment Plan. A plan designed for the installation and perpetual maintenance of improvements intended to provide visual and noise protection for the outer edges of developments which border arterial or major collector streets. Said plan shall include materials, techniques and sizes of buffering treatments such as landscaping, fencing, screen walls, berms, or a combination thereof sufficient to provide adequate buffering. The perimeter treatment plan may be incorporated into the landscape plan.

Performance Bond or Surety Bond. An agreement by a subdivider or developer with the City for the amount of the estimated construction cost guaranteeing the completion of physical improvements according to plans and specifications within the time prescribed by the subdivider's agreement.

Person. Any firm, association, organization, limited partnership, general partnership, trust, company or corporation as well as any natural person.

Personal Care and Beauty Services. Any enterprise conducted for gain which primarily offers services to the general public such as shoe repair, watch repair, barber shops, beauty parlors and similar activities. These uses may also include accessory retail sales of products related to the services provided.

Pet Grooming. An establishment to which owners of domestic pets bring such pets for grooming services, including nail clipping, bathing, haircuts and related services; provided however, such establishment shall not keep animals overnight or offer general veterinary services.

Planned Development or Planned Unit Development. An area of land in which a variety of housing types and subordinate commercial and industrial facilities are accommodated in a preplanned environment under more flexible standards, such as lot sizes and setbacks, then those restrictions that would normally apply under these regulations. The procedure for approval of such development contains requirements in additional to those of the standard subdivision, such as building design principles and landscaping plans.

Planning and Zoning Administrator. The public official of the City of Reynoldsburg designated to administer and enforce this Zoning Ordinance.

Plant Cultivation. The production of crops, fruit trees, nursery stock, truck garden products, or similar plant materials outside of structures such as greenhouses.

Planting Area. Any area utilized for landscape material installation having a minimum area of fifty (50) square feet.

Plants. Living vegetation. Artificial plants are not included in this definition.

Plat. The map, drawing or chart on which the developer's plan of subdivision is presented to the City Planning and Zoning Board for approval and, after such approval, to the County Recorder for recording.

Plat, final. The final map, drawing or chart made by a surveyor registered in the State of Ohio, and supplementary information, based upon the approved preliminary plat, in which the subdivider's plan is presented to the City Planning and Zoning Board for a recommendation, and then to City Council for approval and which, if approved, will be certified and submitted to the County Recorder.

Plat, preliminary. The preliminary map, drawing or chart, and supplementary information, on which the layout and design of a proposed subdivision is submitted to the City Planning and Zoning Board for consideration and tentative approval.

Plot-Grade-Utility Plan. Drawings and other documents describing the approved grading, drainage features and improvements, vehicular facilities, utilities, and other improvements for a development.

Political Sign. Signs having reference to a political official, candidate, question, issue or opinion.

Portable Sign. A sign which is designed to be moved and is not permanently attached to any part of a building or to the ground.

Power Generation Facility. A facility that converts one or more energy sources, including but not limited to water power, fossil fuels, nuclear power, or solar power, into electrical energy or steam. A power generation plant may also perform either or both of the following: (a) operation of a transmission system that conveys the energy or steam from the generation facility to a power distribution system; (b) operation of a distribution system that conveys energy or steam from the generation facility or the transmission system to final consumers.

Power Substation Facility. An assemblage of equipment for purposes other than generation or utilization, through which electric energy in bulk is passed for the purposes of switching or modifying its characteristics to meet the needs of the general public, provided that in residence districts an electric substation shall not include rotating equipment, storage of materials, trucks or repair facilities, housing of repair crews, or office or place of business.

Primary Street. A primary street as referred to in this section includes Main Street, Brice Road, and Livingston Avenue.

Printing and Publishing. Any business publishing of newspapers, magazines, brochures, business cards and similar activities either for profit or nonprofit.

Private Club. A building or portion thereof or premises owned or operated by a person for a social, literary, political, educational or recreational purpose primarily for the exclusive use of members and their guests.

Private Swimming Pool. Any structure that contains water over 24 inches (610 mm) in depth and which is used, or intended to be used, for swimming or recreational use and which is available only to the family and guests of the property owner. This includes inground, aboveground, portable and inflatable swimming pools, hot tubs and spas.

Professional Office. A building or portion of a building wherein services are performed involving predominately administrative, professional or clerical operations.

Projecting Sign. A display sign which is attached directly to the building wall and which extends more than fifteen (15) inches from the face of the wall.

Public Access Easement. An easement granted to the public for all the purposes for which a public sidewalk may be used, including but not limited to, pedestrian and travel.

Public Service Facility. The erection, construction, alteration, operation or maintenance of buildings, power plants or substations, water treatment plants or pumping station, sewage disposal or pumping plants, and other similar public service structures by a public utility, by a railroad, whether publicly or privately owned, or by a municipal or other governmental agency, including the furnishing of electrical, gas, rail transport, communication, public or private water and sewage service.

Public Street. A public right-of-way used for vehicular traffic that is permanently maintained by the City of Reynoldsburg, by the State of Ohio, or by the federal government.

Public Swimming Pool. Any outdoor structure, chamber, or tank containing a body of water for swimming, diving, recreational use, or sanctioned event that is intended to be used collectively for swimming, diving, recreational use, or sanctioned event and is operated by any person whether as the owner, lessee, operator, licensee, or concessionaire, regardless of whether or not a fee is charged for use.

Public Uses. Public parks, schools, and administrative, cultural, and service buildings, not including public land or buildings devoted solely to the storage or maintenance of equipment and material.

Public Way. An alley, avenue, boulevard, bridge, channel, ditch, easement, expressway, freeway, highway, land, parkway, right of way, road, sidewalk, street, subway, tunnel, viaduct, walk, bicycle path or other ways in which the general public or a public entity have a right, or which are dedicated whether improved or not.

Q.

No definitions.

R.

R.C. The Ohio Revised Code.

Real Estate/Model Home Sign. A temporary sign promoting the development, construction, rental, sale or lease of property.

Recreation Facility, Commercial. Recreation facilities open to the public, established and operated for a profit, such as commercial golf courses, golf driving ranges, swimming pools, ice skating rinks, riding stables, race tracks, carnivals, and similar commercial enterprises.

Recreation Facility, Institutional. Recreation-type facilities open to the public, established and operated for a profit and offering a learning environment. Such activities may include but are not limited to gymnastics, karate studio, exercise/gym facility, ceramics, photography and similar commercial enterprises.

Recreation Facility, Noncommercial. Any business which is operated as a recreational enterprise, either publicly or privately owned, for nonprofit. Examples include, but are not limited to: fishing areas, parks, archery ranges, etc.

Recreational Vehicle. A vehicle type unit primarily designed as temporary living quarters for recreation, camping, or travel use only, which either has its own motive power or is mounted on or drawn by another vehicle. The basic entities are: boat, travel trailer, camping trailer, truck camper, and motor home.

Redevelopment. The increase of a developed property or building gross floor area or combination thereof by more than fifty percent (50%) over a seven year period.

Religious Assembly. A permanently located church, cathedral, synagogue, temple, mosque, or other place dedicated to religious worship. As part of its functions it may include the following incidental and subordinate uses subject to applicable federal, state and local regulations: offices, residences for clergy, religious instruction, educational institutions, private and special schools, day care centers, emergency shelters, and community and recreational activities.

Research Facility / Laboratory. A facility primarily for medical, optical, orthotic, prosthetic, or dental laboratory services, photographic, analytical, or testing services and/or engaged in the research, development and controlled production of high technology electronic, industrial or scientific products or commodities for sale.

Reservation. Any reservation of public land made by a developer in accordance with the provisions of these regulations.

Residential (Upper Floor). Where permitted, dwelling units located on a floor other than the ground floor.

~~Residential Care and Congregate Residential. An establishment operated for the purpose of providing special care or rehabilitation to the occupants, as defined in R.C. 5119.341 and 5123.19, including the following: Assisted living; Developmental disability dwelling; Elderly Care; Life Care or Continuing Care Services; Mental Health or Substance Abuse; and Nursing care~~

Residential Model Home. A residential structure, permitted in all residential districts that is used by a licensed home builder/developer, real estate workers or realtor to demonstrate construction, display built-in amenities and color selection charts to prospective home buyers and promote the sale or lease of housing units. The model home may be staffed and furnished. (Ord. 25-97. Passed 6-12-97 :)

Restricted Open Space. Open space within any subdivision that is restricted from further development in accordance with a deed restriction or similar restrictive covenant.

Retail – Convenience with gasoline. A facility associated with the sale of gasoline products that also offers for sale prepackaged food items and tangible consumer goods, primarily for self- service by the consumer. Hot beverages, fountain-type beverages, and pastries may be included in the food items offered for sale.

Retail – Convenience without gasoline. A small retail establishment, usually located within or associated with another use, that offers for sale convenience goods, such as prepackaged food items, tobacco, periodicals, and other household goods.

Retail - Extra Large Format. A retail establishment containing consumer goods that exceeds 50,000 square feet.

Retail – Large format. A retail establishment containing consumer goods that ~~exceeds~~ **is** 20,000 **to 50,000** square feet.

Retail – Medium format. A retail establishment containing consumer goods that is between 5,000 and 20,000 square feet.

Retail – Vape Shop/Smoke Shop. A retail establishment primarily engaged in the sale of tobacco products, electronic nicotine delivery systems (ENDS) such as e-cigarettes or vape pens, cigars, hookahs, pipes, smoking accessories, and related paraphernalia. This use may also include the on-site sampling of tobacco or vapor products, where permitted by law. This definition does not include licensed medical or recreational marijuana dispensaries or general retail establishments where tobacco or vape products are incidental to the primary business.

Retail – Pharmacy without Drive-Thru. A business substantially devoted only to the sale of pharmaceutical items, supplies, and equipment such as prescription drugs.

Retail – Pharmacy with Drive-Thru. A business substantially devoted only to the sale of pharmaceutical items, supplies, and equipment such as prescription drugs. This includes provisions for the conduct of pharmaceutical services served directly to the occupants of motor vehicles.

Retail – Shopping center – enclosed. A group of commercial establishments planned, constructed, and managed as a total entity shopping center with customer and employee parking provided on-site, provision for goods delivery separated from customer access, aesthetic considerations, and protection from the elements.

Retail – Small format. A retail establishment containing consumer goods that is no greater than 5,000 square feet.

Right-of-Way. A strip of land taken or dedicated for use as a public or private way. In addition to the roadway, it normally incorporates the curbs, lawn strips, sidewalks, lighting and drainage facilities, and may include special features (required by the topography or treatment) such as grade separation, landscaped area, viaducts and bridges.

Road. See "Street".

Routine Maintenance. Work that is planned and performed on a routine basis to maintain and preserve the condition of the building or site including but not limited to painting, addition of awnings, roof repair, parking rehabilitation, and window replacement and treatment.

S.

School – College / University. A post-secondary institution for higher learning that grants associate or bachelor's degrees and may also have research facilities and/or professional schools that grant master and doctoral degrees. This may also include community colleges that grant associate or bachelor's degrees or certificates of completion in business or technical fields.

School – Primary. A public, private, or parochial school offering instruction at the elementary school level in the branches of learning and study required to be taught in schools within the state.

School – Secondary. A public, private, or parochial school offering instruction at the junior, and/or senior high school levels in the branches of learning and study required to be taught in the public schools within the state.

School – Trade. A school established to provide for the teaching of industrial, clerical, managerial, or artistic skills. This definition applies to schools that are owned and operated privately for profit and that do not offer a complete educational curriculum.

Screening. Improvements such as landscaping and fencing, or the intentional arrangement and location of uses, structures, and open spaces in a manner intended to mitigate or conceal negative impacts of one use upon another or to improve the appearance of the use.

Seat. For purposes of determining the number of off-street parking spaces for certain uses, the number of seats is the number of seating· units installed or indicated, or each twenty-four (24) lineal inches of benches, pews or space for loose chairs.

Semi-Nude. A state of dress or undress in which clothing covers no more than the human genitals, anus, and areolae of the female breast, as well as portions of the body covered by supporting straps or devices or by other minor accessory apparel such as hats, gloves, and socks.

Semi-Public Uses. Places of worship, Sunday schools, parochial schools, colleges, hospitals, and other institutions of an educational, religious, charitable, or philanthropic nature.

Service Director. The Director of Public Service of the City of Reynoldsburg, as defined by the Administrative Code or City Charter.

Setback. A line established by these regulations and/or Zoning Ordinance or resolution, generally parallel with and measured from the front lot line, defining the limits of a front yard in which no building or structure may be located above ground, except as may be provided in such Codes.

Setback Line. A line established by the Zoning Ordinance generally parallel with and measured from the lot line, defining the limits of a yard in which no building, other than accessory building, or structure may be located above ground, except as may be provided in such Zoning Ordinance.

Sewage and Water Facilities. Sewage collection and/or water distribution systems provided or franchised by a public authority.

Sewage Disposal System, Group. An approved sewage disposal system which provides for the combined collection and disposal of sewage from a group of residential, commercial, or industrial buildings.

Sewage Disposal System, On-Site. A septic tank installation on an individual lot which utilizes an anaerobic bacteriological process for the elimination of solid wastes and provides for the proper and safe disposal of the effluent, subject to approval of health and sanitation officials having jurisdiction.

Sewers, Central or Group. An approved sewage disposal system which provides a collection network and disposal system and central sewage treatment facility for a single development, community or region.

Sewers, On-Site. A septic tank or similar installation on an individual lot which utilizes an aerobic bacteriological process or equally satisfactory process for the elimination of sewage and provides for the proper and safe disposal of the effluent, subject to the approval of health and sanitation officials having jurisdiction.

Shade Tree. A deciduous tree planted primarily for its high crown of foliage or overhead canopy and which typically reaches a height of at least forty (40) feet.

Shed. A storage structure constructed and located upon a property in accordance with the regulations applicable to the subject property the purpose of which is for the storage of yard equipment, recreational equipment or other consumer goods to be utilized by the residents of the subject property upon which such structure is located.

Shelter. A facility used to house or contain stray, homeless, abandoned, or unwanted animals and that is owned, operated, or maintained by an established humane society, animal welfare society, society for the prevention of cruelty to animals, or other nonprofit organization devoted to the welfare, protection, and humane treatment of animals.

Shooting Range – Indoor. A building open to the general public wherein the shooting of firearms is permitted for the practice of marksmanship, except indoor shooting galleries maintained or operated by any police department which is not available to the general public.

Shrub. That area which the City requires maintenance in order to preserve the sight distance and safety of motorists, pedestrians and bicyclists by requiring an unobstructed line of sight necessary for most drivers stopped at an intersection to see an approaching vehicle to avoid a collision. Further information is provided in Section 1105.07.

Sidewalk. That portion of the road right of way outside the roadway, which is improved for the use of pedestrian traffic.

Sight triangle. A triangle at an intersection, formed by the two roads or rights-of-way and a third line, which must be kept clear of obstructions such as hedges so that people in one road can see cars approaching on the other.

Sign. Any display, figure, painting, placard, poster, drawing, letter, word, symbol, number, or any combination of these or any other device visible, with or without verbiage, which can be seen from the right-of-way and is designed to inform or attract the attention of persons not on the premises on which the sign or street graphic is located. Used to convey a message, advertise, inform or direct attention to a person, institution, organization, activity, place, object or product.

Sign Area. The entire area within a single continuous perimeter enclosing the extreme limits of writing, representation, emblem, or any figure or similar character together with any frame or other material or color forming an integral part of the display or used to differentiate such sign from the background against which it is placed; excluding the necessary supports or uprights on which such sign is places. The area of a sign having more than one display shall be computed as the total of the exposed exterior display surface area.

Sign, Bulletin Board. A structure containing a surface upon which is displayed the name of a religious institution, school or library, auditorium, stadium, athletic field or area of similar use for the announcement of services or activities to be held therein.

Sign, Construction. A sign indicating the names of architects, engineers, contractors and similar persons involved in the design and construction of a structure or project.

Sign Face. The surface of the sign upon, against or through which the message of the sign is exhibited.

Sign, Flashing. Any illuminated sign on which the artificial light or any part thereof has conspicuous or intermittent variation in intensity or color.

Sign, Governmental. A sign erected at the side of or above roads to give instructions or provide information to road users.

Sign Height. The vertical distance from the uppermost point used in measuring the area of the sign to the crown of the road on which the property fronts.

Sign, Moving. Any sign which in part or total, rotates, revolves or otherwise is in motion.

Sign, Name Plate. A sign designating only the name and address or the name and professional occupation and address of a person or persons residing in or occupying space in such building or premises.

Sign Panel. A structural object or portion of a structural object designed to form a distinct background area or frame for the display of a sign's information.

Sign, Painted Bulletin. An advertising structure on which advertising design is painted and posted, and which may incorporate the use of cutouts and/or other embellishments.

Sign, Poster Panel. An advertising structure measuring not more than twelve (12) feet by twenty-five (25) feet overall on which posters are displayed.

Sign, Promotional. A temporary sign, the function of which is to announce a special event.

Sign, Roof. Any sign which is erected over the roof or parapet above the roofline and/or receives any or all its support from the roof structure.

Sign Structure. The supports, uprights, bracing or framework for signs.

Sign, Warning. Any sign indicating danger or a situation which is potentially dangerous.

Site Plan. A drawing and other documents, subject to review and approval by the City, describing the planned improvements of a lot. A site plan is one of the following types:

A. **Major Site Plan.** A plan review required for any development that meets the requirements on Section 1109.17, and which is subject to review and approval by the Planning and Zoning Administrator, City staff, or the Planning and Zoning Board;

B. **Minor Site Plan.** A plan review required for any development which does not qualify for a major site plan review and consists of an improvement other than a single family dwelling, two-family dwelling, or a dwelling within a planned development, and which is subject to review and approval by the Planning and Zoning Administrator and other City staff; or

C. **Residential Site Plan.** A plan review required for a single family dwelling, two-family dwelling, or a dwelling within a planned development, and which may be approved by the Planning and Zoning Administrator. (Also see Section 1109.17)

Site Obscuring Structure. Opaque or having such qualities as to constitute a complete visual barrier to persons outside the perimeter of the site obscuring object. A fence, which partially obscures a site, shall not be considered site obscuring if it has maintained at least 40% transparency.

Skirting. The rigid physical attachments to a mobile home designed and intended to completely screen, shelter, and protect such mobile home's base and entire area between the floor surface and the ground, which includes, but not limited to, all electrical and plumbing conduits, insulation material, and undercarriage.

Solar Panel. A solar photovoltaic panel, solar hot air or hot water panel collector device, or other type of energy system which relies upon solar radiation as a source for the generation of electricity or transfer of stored heat.

Solar Panel Array. An integrated assembly of solar panels with a support structure or foundation and other components.

Sold Sign. A temporary sign announcing that a property has been sold, leased or is no longer available.

Special Event. A temporary outdoor use of land for the purposes of a gathering, including but not limited to a fair, festival, celebration, or fundraiser.

Specified Sexual Activities. Any of the following activities , the fondling or other intentional touching of human genitals, pubic region, buttocks, anus, or female breasts; or Sex acts, normal or perverted, actual or simulated, including intercourse, oral copulation, or sodomy; masturbation, actual or simulated; or Human genitals in a state of sexual stimulation, arousal or tumescence; or excretory functions as part of or in connection with any of the activities set forth above.

Stacking Space. Area where cars are permitted to wait in a resting state to access a use, or at a traffic signal or sign.

Storage – commercial gases. Any establishment whereby the primary activity is, or necessitates, the storage of compressed gasses.

Storage – Contractor. An unenclosed portion of the lot or parcel upon which a construction contractor maintains its principal office or a permanent business office. Designation of the lot or parcel as a contractor's storage yard would allow this area to be used to store and maintain construction equipment and other materials customarily used in the trade carried on by the construction con- tractor.

Storage – Self-Store. A building or group of buildings designed and used solely for the purpose of leasing interior space for the storage of personal property, household items and the inventory of commercial businesses where storage units are individually leased or rented and where access to storage units is infrequent. Outdoor storage and the storage of junk, explosives, flammable materials and other noxious or dangerous materials are specifically prohibited.

Storage – vehicular and boat. An enclosed or outdoor facility used solely for the storage of land-, air-, or water-based vehicles.

Storm Water Design Manual. The most current copy of the "Storm Water Design Manual", which provides guidelines for developing proper and adequate storm water collection and disposal facilities will be on file in the office of the City Engineer. The Storm Water Design Manual is that manual prepared by the Mid-Ohio Regional Planning Commission.

Story. That portion of a building other than a cellar included between the surface of any floor and the surface of the floor above it or if there is not floor above it, then the space between the floor and the ceiling next above it. A basement shall be counted as a story if it is used for living quarters or if two-thirds of its volume is above the average finished grade of the adjoining ground. See also, "Basement".

Street. The full width between property lines bounding every public way of whatever nature, with a part thereof to be used for vehicular traffic and designated as follows:

A. "Alley" means minor ways used primarily for vehicular service access to the back or side of properties abutting on other streets.

B. "Arterial street" means a highway primarily for through traffic, carrying heavy loads and large volume of traffic, usually on a continuous route.

C. "Collector street" means a thoroughfare, whether within a residential, industrial, commercial or other type of development, which carries traffic from local streets to arterial highways, including principal entrance streets of residential developments and primary circulation routes within such development.

D. "Cul-de-sac" means a local street of relatively short length with one end open to traffic and the other end terminating in a vehicular turnaround.

E. "Dead-end street" means a street or a portion of a street with only one vehicular traffic outlet.

F. "Expressway" or "freeway" means a thoroughfare which carries relatively large volumes of traffic at a relatively high speed over long distances. Expressways are usually multi-lane highways for through traffic with all crossroads separated in grade and with full control of access.

G. "Half-street" means a street or a portion of a street with only one-half of the width paved and having proper right of way. Usual access at edge of subdivision where the centerline is also the plat boundary

H. "Local street" means a street primarily for providing access to residential, commercial or other abutting property.

I. "Loop street" means a type of local street, each end of which terminates at an intersection with the same arterial or collector street, and whose principal radius points of the 180 degree system of turns are not more than 1,000 feet from such arterial or collector street, nor normally more than 600 feet from each other.

J. "Major arterial street" or "principal arterial street" means a throughway which carries through traffic, usually intra-city, on a continuous route. Major arterial streets will have no curb parking and will have no curb parking and will use of marginal access roads, including limited access highways.

K. "Marginal access streets" means a local street parallel and adjacent to an arterial highway, providing access to abutting properties and protection from the major street or arterial highway.

L. "Minor arterial street" means a throughway which carries crosstown traffic from several neighborhoods, thereby servicing several residential collector streets.

M. "Service Drive" means a public street generally parallel and contiguous to a main traveled way, primarily designed to promote safety by eliminating promiscuous ingress and egress to the right-of-way, and providing safe and orderly points of access at fairly uniformly-spaced intervals. Would not be a Service Drive if parking spaces are located directly off of a road.

The comprehensive plan gives additional guidance on street classification and definitions.

Street Tree. A tree planted in close proximity to a street in order to provide canopy over the street to provide shade and soften the street environment.

Structure. Anything constructed or erected, the use of which requires location on the ground, or attachment to something having a fixed location on the ground.

Structured Parking. Structured parking means a building or structure consisting of one or more levels for parking motor vehicles as the primary use of the building or structure. Where Structured Parking is permitted, the building shall be subject to the height and setback requirements of other buildings in the district.

Studio – Art. Work space for one or more artists or artisans, including the accessory sale of art produced on the premises, or gallery space.

Studio – Gymnastics/martial arts. A space used for physical indoor exercise which is offered in a class or organized format for activities such as gymnastics, martial arts, dance, aerobics, pilates, or circuit training.

Subdivider. Any individual, owner, developer, firm, association, syndicate, co-partnership, corporation, trust or any other legal entity commencing proceedings under these regulations as an applicant to affect a subdivision of land hereunder for himself or for another.

Subdivision.

A. The division of any parcel of land shown as a unit or as contiguous units on or before January 1, 1976 into two or more parcels, sites or lots, any one of which is less than five acres for the purposes, whether immediate or future, of transfer of ownership, provided, however, that the division or partition of land into parcels of more than five acres not involving any new streets or easement of access, and the sale or exchange of parcels between adjoining lot owners, where such sale or exchange does not create additional building sites, shall be exempted; or

B. "Commercial Subdivision" means the improvement of one or more parcels of land for commercial structures or groups of structures involving the division or allocation of land for the opening, widening or extension of any street or streets, except private streets serving industrial structures; the division or allocation of land as open spaces for common use by owners, occupants or lease holders or as easements for the extension and maintenance of public sewer, water, storm drainage or other public facilities; or

C. "Industrial Subdivision" means the improvement of one or more parcels of land for industrial structures or groups of structures involving the division or allocation of land for the opening, widening or extension of any street or streets, except private streets serving industrial structures; the division or allocation of land as open spaces for common use by owners, occupants or lease holders or as easements for the extension and maintenance of public sewer, water, storm drainage or other public facilities; or

D. "Minor Subdivision". See "Minor Subdivision".

Subdivision Regulations. The Subdivision Regulations of the City of Reynoldsburg, Chapter 1111 of Part Eleven, Land Use and Subdivision Regulations, of the Codified Ordinances of Reynoldsburg.

Swimming Pool. A body of water of artificial construction, used for swimming or recreational bathing, which is over eighteen inches (18") in depth at any point, and has more than one hundred (100) square feet of area on the water surface when filled to capacity, and including the bottom and sides of the pool, and the equipment appurtenances thereof.

T.

Tattoo/Piercing Establishment. A place, as defined by the Ohio Revised Code or the Ohio Administrative Code, where tattoo or body piercing services are provided.

Temporary Sign. A display sign, banner or other advertising device constructed of cloth, canvas, fabric or other light temporary material with or without a structural frame, intended for a limited period of display, including decorative displays for holidays or public demonstrations.

Temporary Special Land Use. A temporary use of land for a set amount of time, permitted in conjunction with the display or the display and sales of merchandise, goods, or materials.

Temporary Use. A temporary use of land for a set amount of time, permitted in conjunction with the display or the display and sales of merchandise, goods, or materials.

Tenants-in-Common. That form of real property ownership described in R.C. 5302.19, as the same may be amended from time to time.

Thoroughfare. See "Street".

Thoroughfare Plan. A plan, adopted by City Council, which shows general locations and extent of existing, planned, and proposed streets and other transportation facilities of the City.

Tract. A continuous expanse of land.

Traditional or Natural Materials. Consists of clay bricks (full or thin set, if thin set, corners must have full brick appearance), stone, cultured stone (samples must be provided), wood or fiber cement board siding.

Tree. A large woody plant having one (1) or several self-supporting stems or trunks and numerous branches and which may be deciduous or evergreen.

Tree Lawn. A small area, often planted with trees and grass, between a street and the sidewalk of that street.

U.

Unit of a Building or Building Unit. A space occupying a portion of a building, containing an entrance from the building exterior, and separated from other such spaces by a party wall or walls.

Use. The specific purposes for which land or a building is designated, arranged, intended or for which it is or may be occupied or maintained.

Use, Accessory. A use located on the same lot with, and of a nature customarily incidental and subordinate to, the main use. Examples include: a parking lot for a commercial or industrial business; administrative and sales offices for an industrial plant; or a home occupation.

Use, Main. A use which is the dominant or principal activity or use of a lot.

Use, Permitted. A use which is permitted by right in a district, as listed on Table 1103.01A or as otherwise permitted by right in this Code, provided that such use shall comply with all provisions of this Code.

Use, Prohibited. A use which is not identified in this Zoning Code as either a permitted use or a conditional use.

Use, Similar. A use which is not identified in this Code as a permitted use or a conditional use in any district, but which is determined by action of the Planning and Zoning Board and City Council to be a use sufficiently like or compatible with other uses in a district as to be allowed as a conditional use in that district.

V.

Variance. An adjustment to the development standards of the zoning regulations, that does not apply to use or required density that is reviewed and approved, modified, or denied by the Planning and Zoning Board after at least one public hearing.

Vehicular Care Services – Major. General repair, rebuilding, or reconditioning of engines, motor vehicles, or trailers, including body work, framework, welding, and major painting service.

Vehicular Care Services – Minor. The replacement of any part or repair of any part that does not require removal of the engine head or pan, engine transmission or differential; incidental body and fender work, minor painting and upholstering service. Above stated is applied to passenger automobiles and trucks not in excess of 7,000 pounds gross weight.

Vehicle Care Services – Washes. The use of a site for washing and cleaning of passenger vehicles, recreational vehicles, or other light duty equipment.

Vehicle Rental Facility. A facility primarily engaged in the short-term rental or leasing of automobiles, light trucks, vans, trailers, or similar vehicles or equipment. Such facilities may include customer service offices, vehicle and trailer storage areas, minor maintenance activities related to the rental fleet, and associated parking. This use does not include the sale of vehicles as a principal use or heavy vehicle storage or repair.

Vehicular Sales – Automobiles. The use of any building or portion thereof, or other premises or portion thereof, for the display, sale, rental, or lease of new motor vehicles, or used motor vehicles as an ancillary use of a lot, and any warranty repair work and other repair service conducted as an accessory use.

Vehicular Sales – Boats. The use of any building or portion thereof, or other premises or portion thereof, for the display, sale, rental, or lease of new boats or watercraft, or used boats or watercraft as an ancillary use of a lot, and any warranty repair work and other repair service conducted as an accessory use.

Vehicular Sales – Motorcycles. The use of any building or portion thereof, or other premises or portion thereof, for the display, sale, rental, or lease of new motorbikes or motorcycles, or used motorbikes or motorcycles as an ancillary use of a lot, and any warranty repair work and other repair service conducted as an accessory use.

Vehicular Sales - Recreational Vehicles. The use of any building or portion thereof, or other premises or portion thereof, for the display, sale, rental, or lease of new recreational vehicles or campers, or used recreational vehicles or campers as an ancillary use of a lot, and any warranty repair work and other repair service conducted as an accessory use.

Vehicular Sign. A sign mounted upon, painted upon, or otherwise erected on a trailer, truck, automobile or other vehicle parked or placed so that the signs thereon are visible from a public street or right of way.

Veterinary. A structure or premises utilized for the diagnosis and treatment of ill and injured animals and the short-term boarding incidental to the clinical use. A veterinary clinic cannot be implicitly interpreted as a kennel.

Vicinity Map. A drawing located on the plat which sets forth by dimensions or other means, the relationship of the proposed subdivision or use to other nearby developments or landmarks and community facilities and services within the general area in order to better locate and orient the area in question.

Visual Arts Center. A facility open to the public that is devoted to the visual arts.

W

Walkway. A public or private way, four (4) feet or more in width, for pedestrian use only, whether along the side of a road or not.

Wall, of a building. An external, vertical surface enclosing a portion of a building.

Wall, front. That wall of a building which most nearly parallels the front lot line of the lot on which the building is located or, for the purpose of locating a wall sign on a space within a multi-occupant building, that wall which is declared by the Planning Administrator to be the front wall, generally that wall which faces a common, central parking lot or drive.

Wall Sign. A display sign which is painted on or attached directly to the building wall and which extends not more than fifteen inches from the face of the wall.

Warehouse – large format. An enclosed storage facility which is used to store goods or parts, or for any part of the shipping process, that is greater than 50,000 square feet and includes cross-dock facilities.

Warehouse – small format. An enclosed storage facility which is used to store goods or parts, or for any part of the shipping process, that is under 50,000 square feet and does not include cross-dock facilities.

Warehousing, Public. A person or business whose primary purpose and profit motive is the receiving, storing and shipping of merchandise or commodities for one or more unrelated persons or businesses.

Weed. Any ground cover or shrub which is typically not installed for the purposes of landscaping; which is not typically propagated by the horticultural or nursery trades; or which presents a particularly noxious allergenic or growth characteristic.

Wholesale and Distribution. An establishment that engages in the sale of goods, merchandise and commodities for resale by the purchaser.

Window Sign. A sign painted, attached or affixed to the interior or exterior surface of windows or doors of a building or suspended on the inside or outside of the windows or doors.

Working day. The days occurring Monday through Friday, excluding legal holidays. The time within which an act is required by law to be done shall be computed by excluding the first and including the last day; except that when the last day falls on the weekend or a legal holiday, the act may be done on the next succeeding day that is not the weekend or a legal holiday. ·

Y.

Yard. A required open space other than a court unoccupied and unobstructed by any structure or portion of a structure above the general ground level of the graded lot upward; provided accessories, ornaments and furniture may be permitted in any yard, subject to height limitations and requirements limiting obstruction of visibility.

Yard, front. A yard extending between side lot lines across the front of a lot and from the front lot line to the front of the principal building.

Yard, rear. A yard extending between side lot lines across the rear of the lot and from the rear lot line to the rear of the principal building.

Yard, side. A yard extending from the principal building to the side lot line on both sides of the principal building between the lines establishing the front and rear yards.

Z.

Zoning Certificate. A document issued by the Zoning Inspector authorizing the occupancy or use of a building or structure or the actual use of lots or lands in accordance with the previously issued zoning permit.

Zoning District or District. An area depicted on the official zoning map comprised of properties and land uses that are otherwise intended to reflect the comprehensive plan.

Zoning Code. The part of the Codified Ordinances of the City of Reynoldsburg known and referred to as the City of Reynoldsburg Planning and Zoning Code, as it may be amended from time to time.

Zoning Permit. A document issued by the Planning and Zoning Administrator authorizing the use of lots, structures, uses of land and structures, and the characteristics of the uses.

A. **Terms Applicable to Landscape Requirements**

Crown Spread. The distance measured across the greatest diameter of the above ground portions of a plant.

Decorative Walls and Fences. Barriers constructed of wood, masonry or other appropriate material.

Developed Area. That a portion of a plot or parcel of land upon which a building, structure, pavement, landscaped material or other improvements, excluding public rights-of-way, have been placed.

Diameter at Breast Height (DBH). The diameter of the tree as measured at four and a half (4½) feet above grade. If a tree splits into multiple trunks below 4½ feet above grade, the trunk is measured at its most narrow point below the split.

Earth Mounds. Earthen physical barriers which block or screen a view, which have vegetation capable of preventing erosion, and have a maximum permitted slope of three feet horizontal to one vertical (3:1) where mounds are to be mowed.

Ground Cover. Landscape materials such as natural mulch or low growing plants installed in such a manner so as to form a continuous cover over the ground.

Interior Landscaping. The use of landscape materials within the boundaries of the parcel, exclusive of the perimeter landscaping.

Landscape Buffer. Landscape materials installed between certain land uses [i.e. (1) between multifamily and single-family uses, (2) between any residential and commercial uses, and (3) between any manufacturing and residential or commercial use], between thoroughfares and land uses, and between thoroughfares and off-street parking in order to reduce glare, unsightly views, and noise.

Landscape Material. Materials such as, but not limited to, living trees, shrubs, vines, lawn grasses, ground cover, landscape water features and non-living, durable material commonly used in landscaping, including, but not limited to, rocks, pebbles, sand, decorative walls and fences, earthen mounds, but excluding pavements or surfaces for

Native Plant Species. A plant species, other than noxious weeds, that are indigenous to the area and usually do not need human intervention to grow or reproduce.

New Structure. Any structure newly constructed or erected, except for fences, decks, signs, trash enclosures, swimming pools, playground equipment and accessory structures under 250 sq. ft., which requires location on the ground. Additions to, alterations to and/or reconstruction of an existing structure or building shall not be considered a new structure.

Opacity. The required percent of visual screening from adjacent properties in a vertical plane extending from the established grade to a required height.

Service Structures. Equipment or elements providing service to a building or a site including but not limited to loading docks, storage tanks, trash containers or receptacles, electrical transformers, utility vaults which extend above the surface, cooling towers, and heating and cooling units.

Shrub. A perennial plant which has persistent multiple woody stems from a common root and differing from a tree by ·its low stature and habit of branching from the base.

Substantial Expansion. When an existing structure or vehicular access area is expanded, altered, or enlarged where such expansion, alteration, or enlargement exceeds twenty-five (25) percent of the area of the existing structure or vehicular access area.

Tree. Any self-supporting, woody perennial plant which normally grows to an overall height of at least fifteen (15) feet.

Tree, Deciduous. Trees which normally shed their leaves in the fall.

Tree, Large. Any tree which normally attains a mature height equal to or greater than forty (40) feet.

Tree Lawn. That part of the street right of way not covered by sidewalk, bike path or other paving, lying between the sidewalk and street.

Tree, Major. An existing living tree with a DBH of at least eighteen (18) inches.

Tree, Measurement. The diameter in inches of a tree trunk measured six (6) inches above grade for trees equal to or less than six (6) inches in diameter or measured at DBH for trees larger than six (6) inches in diameter.

Tree, Medium. Any tree which normally attains a mature height greater than twenty-five (25) feet and less than forty (40) feet.

Tree, Small. Any tree which normally attains a mature height greater than fifteen (15) feet and less than twenty-five (25) feet.

Tree, Standard. A tree planted with a trunk caliper (diameter) of at least one and 3/4 (1¾) inches measured 6" above grade.

Vehicle Encroachment. Any protrusion of a vehicle outside of a parking space, display area, storage area, access way, or access aisle into a landscape area.

Vehicular Use Area. Any paved surface area, excepting public rights-of-way, used by any type vehicle, whether moving or at rest for the purpose of (including but not limited to) driving, parking, loading, unloading, or storage.

B. **Terms Applicable to Wireless Telecommunication Structures**

Antenna. Any exterior transmitting or receiving device mounted on a tower, building or structure and used in communications that radiate or capture electromagnetic waves, digital signals, analog signals, radio frequencies (excluding radar signals), wireless telecommunications signals or other communication signals.

Antenna Support Structure. Any building or other structure other than a Tower which can be used for location of Wireless Telecommunications Facilities.

Co-location. The use of a wireless telecommunications facility by more than one wireless telecommunications provider.

Engineer, Radio Frequency. An engineer who possesses the additional qualifications of holding a FCC

General Radiotelephone Operator License and who has successfully completed training in electromagnetic field theory and antenna theory.

Equipment Shelter. The structure in which the electronic receiving and relay equipment for a Wireless Telecommunications Facility is housed.

FAA. The Federal Aviation Administration and any legally appointed, designated or elected agent or successor.

FCC. The Federal Communications Commission and any legally appointed, designated or elected agent or successor.

Height or Above Ground Level. When with respect to Chapter 1105.13, the distance measured from the finished grade at the base of the tower/structure to the highest point on the tower or other structure, including the base pad and any antenna.

Monopole. A support structure constructed of a single, self-supporting hollow metal tube securely anchored to a foundation.

Open Space. An area substantially open to the sky which may be on the same lot with a building. The area may include, along with the natural environmental features, water areas, swimming pools and tennis courts, any other recreational facilities that the Planning and Zoning Board deems permissive. Streets, parking areas, structures for habitation and the like shall not be included.

Tower. Any structure that is designed and constructed primarily for the purpose of supporting one or more antennas for telephone, radio and similar communication purposes, including self-supporting lattice towers, guyed towers, or monopole towers. The term includes radio and television transmission towers, microwave towers, common-carrier towers, wireless telecommunications towers, alternative tower structures, and the like. The term includes the structure and any support thereto.

Towers, Pre-existing and Pre-existing Antennas. Any tower or antenna for which a building permit or special use permit has been properly issued prior to the effective date of this chapter, including permitted towers or antennas that have not yet been constructed so long as such approval is current and not expired.

Viewshed. The area surrounding a Wireless Telecommunications Facility or Antenna Support Structure,

within which the Facility or Structure is visible from street level.

Wireless Telecommunications Facilities. Any cables, wires, lines, wave guides, antennas and any other equipment or facilities associated with the transmission or reception of communications as authorized by the FCC which a Person seeks to locate or has installed upon a Tower or Antenna Support Structure. However, the term Wireless Telecommunications Facilities shall not include: (1) Any satellite earth station antenna two meters in diameter or less which are located in an area zoned industrial or commercial; (2) Any satellite earth station antenna one meter or less in diameter, regardless of zoning category; (3) Antennas used by amateur radio operators are excluded from this definition.

REYNOLDSBURG ZONING CODE

REYNOLDSBURG, OH

2024 2026

STAFF REPORT
REYNOLDSBURG CITY COUNCIL

DATE: December 15, 2025

RE: An Ordinance Authorizing the Mayor to Enter into a Contract with Compton Construction for Design and Construction Services

APPROVALS:

Joe Begeny
Stephen Cicak
Chris Shook
Mollie Prasher

EMERGENCY:

REASON FOR EMERGENCY:

STAFF REPORT:

An Ordinance Authorizing the Mayor to Enter into a Contract with Compton Construction for Design and Construction Services

WHEREAS, it has been determined that additional office space for current/additional staff to accommodate both the private and public sector, given the City's overall success and growth throughout the past several years, is needed; and

WHEREAS, the City hired OHM Advisors to conduct a space planning study (attached) document, which identified two areas for conversion (upstairs conference room into office space, and the redesign of Council Chambers to include a new conference room) to accommodate the City's needs, and

WHEREAS, the cost for the design and construction of these improvements is $500,396.29; and

WHEREAS, the City solicited for proposals in both the Daily Reporter and Bid Express for this project on August 20, 2025, and

WHEREAS, on September 11, 2025, the City received one responsive bid from Compton

Construction.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF REYNOLDSBURG, OHIO:

SECTION 1. That the Mayor be and is hereby authorized to enter into a contract with Compton Construction for design and construction of additional office space and a large conference room for a cost of $550,435.92 (includes a contingency amount of $50,039.63).

SECTION 2. That an amount of $550,435.92 be appropriated from the unappropriated General Fund (110) to account number 110.448.5339 Miscellaneous Infrastructure.

SECTION 3. That this Resolution will be effective thirty days following approval of Council and the signature of the Mayor.

COMPTON CONSTRUCTION

CONSTRUCTION PROPOSAL

CITY OF REYNOLDSBURG - CITY HALL MASTER PLAN RENOVATIONS
7232 EAST MAIN STREET, REYNOLDSBURG, OHIO 43068

Reynoldsburg
OHIO • 1839



CONTENTS

CONTENTS

INTRODUCTION & PROFESSIONAL QUALIFICATIONS 3
Includes list of similar projects

PROPOSED PROJECT TIMELINE 4

FEE PROPOSAL 5

EXCLUSIONS & INCLUSIONS..... 6-8

DETAILED BID 9-11

PARTNER REFERENCES 12

INTRODUCTION & PROFESSIONAL QUALIFICATIONS

THANK YOU FOR THE OPPORTUNITY!

Compton Construction is excited for the opportunity to once again collaborate with the City of Reynoldsburg on the proposed renovation at City Hall, 7232 East Main Street. We have a long-standing relationship with the City of Reynoldsburg having recently completed the reception desk improvement project. Compton Construction remains a committed partner dedicated to delivering a successful project for all stakeholders.

Our team has completed hundreds successful, on-time and within budget, renovations around the Columbus metropolitan area both as a General Contract and Design-Build partner. Overall project sizes ranging from $50,000 to $1,000,000. Some of these projects include:

- Digital Data Technologies
- iHeart Media Office Downsize
- The Women's Fund of Central Ohio
- Youth Advocate Services
- Legends Tenant and Landlord Build-outs
- Sheakley
- Lower Lights Improvements

Compton Construction has distinguished itself since 2012 as a "go-to" partner helping clients to achieve their goals. Compton Construction, LLC, an Ohio incorporated and licensed entity, operates out of its offices at 691 Parsons Ave., Columbus, OH 43206. Compton's critical knowledge of construction and design processes allows us to position ourselves as the foremost expert in building, leaving room for an unparallel and proactive build process from the comprehensiveness of our bid through final completion of construction.


Compton Construction leans into the core values of an "all-in" mindset, craftsmanship, solution seeking, joy, community, and transparency. Each of these values are apparent in our approach to the work, communications, the consumer end-product, and relationships we develop through the construction process.

We look forward to working with the City of Reynoldsburg again and are excited to deliver another successful project at City Hall.

COMPTON CONSTRUCTION

CTI TENANT IMPROVEMENT SCHEDULE
12.13.24

ID	Task Name	Duration	Start	Finish
1	**City Hall Master Plan Renovations**	**90 days**	**Mon 9/29/25**	**Fri 1/30/26**
2	**Design Process**	**35 days**	**Mon 9/29/25**	**Fri 11/14/25**
3	Engage MEPs	5 days	Mon 9/29/25	Fri 10/3/25
4	Design Process	20 days	Mon 10/6/25	Fri 10/31/25
5	Permitting	10 days	Mon 11/3/25	Fri 11/14/25
6	Competitive Bid/Final Contract Adjustm	10 days	Mon 11/3/25	Fri 11/14/25
7	**Submittal and Procurement**	**35 days**	**Mon 11/3/25**	**Fri 12/19/25**
8	Electrical Equipment & Fixtures Submittals	5 days	Mon 11/3/25	Fri 11/7/25
9	Doors and Hardware Submittals	5 days	Mon 11/3/25	Fri 11/7/25
10	HVAC Equipment & Materials Submittals	5 days	Mon 11/3/25	Fri 11/7/25
11	Electrical Fixture Procurement	15 days	Mon 11/10/25	Fri 11/28/25
12	Glass, Doors and Hardware Procurement	30 days	Mon 11/10/25	Fri 12/19/25
13	Electric Gear Procurement	30 days	Mon 11/10/25	Fri 12/19/25
14	HVAC Equipment Procurement	10 days	Mon 11/10/25	Fri 11/21/25
15	Fire Alarm Drawings	5 days	Mon 11/3/25	Fri 11/7/25
16	Fire Suppression Drawings	5 days	Mon 11/3/25	Fri 11/7/25
17	Fire Alarm Permit	10 days	Mon 11/10/25	Fri 11/21/25
18	Fire Suppression Permit	10 days	Mon 11/10/25	Fri 11/21/25
19	**Construction**	**55 days**	**Mon 11/17/25**	**Fri 1/30/26**
20	Mobilization	5 days	Mon 11/17/25	Fri 11/21/25
21	Demolition	7 days	Mon 11/17/25	Tue 11/25/25
22	Rough Framing	7 days	Mon 11/17/25	Tue 11/25/25
23	Rough Electric	7 days	Wed 11/26/25	Thu 12/4/25
24	Rough Blocking	2 days	Mon 12/15/25	Tue 12/16/25
25	Rough Fire Alarm	3 days	Wed 11/26/25	Fri 11/28/25
26	MEP Rough Inspections	1 day	Fri 12/5/25	Fri 12/5/25
27	Framing Rough Inspection	1 day	Mon 12/8/25	Mon 12/8/25
28	Hang Drywall	3 days	Tue 12/9/25	Thu 12/11/25
29	Drywall Finish	5 days	Fri 12/12/25	Thu 12/18/25
30	Prime & Paint	5 days	Fri 12/19/25	Thu 12/25/25
31	Install/Repair Ceiling Grid	2 days	Fri 12/26/25	Mon 12/29/25
32	Above Ceiling Electric	5 days	Tue 12/30/25	Mon 1/5/26
33	Electrical Panel Install	3 days	Mon 12/22/25	Wed 12/24/25
34	Above Ceiling Fire Suppression	3 days	Tue 12/30/25	Thu 1/1/26
35	HVAC Diffuser Relocation	5 days	Tue 12/30/25	Mon 1/5/26
36	MEP Above Ceiling Inspections	1 day	Tue 1/6/26	Tue 1/6/26
37	Framing Above Ceiling Inspection	1 day	Wed 1/7/26	Wed 1/7/26
38	Install Flooring	5 days	Mon 1/19/26	Fri 1/23/26
39	Install Storefront, Doors and Hardware	7 days	Thu 1/8/26	Fri 1/16/26
40	Reinstall Seats	3 days	Mon 1/26/26	Wed 1/28/26
41	Final Paint	5 days	Mon 1/19/26	Fri 1/23/26
42	Electrical Devicing	3 days	Mon 1/19/26	Wed 1/21/26
43	Fire Alarm Devicing	3 days	Mon 1/19/26	Wed 1/21/26
44	MEP Final Inspections	2 days	Thu 1/22/26	Fri 1/23/26
45	Final Occupancy Inspection	1 day	Mon 1/26/26	Mon 1/26/26
46	Final Punchout	3 days	Tue 1/27/26	Thu 1/29/26
47	Final Clean	1 day	Fri 1/30/26	Fri 1/30/26
48	Substantial Completion	1 day	Fri 1/30/26	Fri 1/30/26



Project: Construction Schedule
Date: Thu 9/25/25

Task · Split · Milestone · Summary · Project Summary · Inactive Task · Inactive Milestone · Inactive Summary · Manual Task · Duration-only · Manual Summary Rollup · Manual Summary · Start-only · Finish-only · External Tasks · External Milestone · Deadline · Progress · Manual Progress

FEE PROPOSAL

RENOVATION COST SUMMARY

COST/SF | $192.46

GENERAL CONDITIONS & REQUIREMENTS	$91,985.90	21%
EXISTING CONDITIONS - DEMO	$24,910.00	6%
CONCRETE	$12,312.00	3%
MASONRY	$3,640.00	1%
METALS	$17,000.00	4%
DOORS & WINDOWS	$82,342.50	18%
FINISHES	$78,936.00	18%
FURNISHINGS	$6,300.00	1%
FIRE SUPPRESSION	$15,250.00	3%
HVAC	$48,750.00	11%
ELECTRICAL	$41,206.00	9%
COMMUNICATIONS	$8,540.00	2%
FIRE ALARM	$15,610.00	3%
OVERHEAD & PROFIT @ 12%	$53,396.29	

BASE BID TOTAL **$500,396.29**

EXCLUSIONS & INCLUSIONS

01-GENERAL CONDITIONS & REQUIREMENTS

- Includes all expenses as noted within the RFP, including all addenda
- Provide project appropriate project management
- Includes on-site Superintendent personnel for normal working hours
- Includes all General Requirements for project

02-EXISTING CONDITIONS

- Demolition of walls, ceilings, applied finishes, and fixtures
- Provide dumpsters on site for duration of project

03-CONCRETE

- New concrete to create level floor for new conference space

08-DOORS & WINDOWS

- New storefront - excludes all blinds
- New doors and hardware

09-FINISHES

- New walls - metal studs, drywall, and insulation
- Painting hollow metal frames and doors included
- New ACT and grid - specification TBD
- Flooring - TBD

21-FIRE SUPPRESSION

- Provide drawings and permit for sprinkler system
- Rework system according to new layout

23-HVAC

- Develop HVAC schematic plan and drawings
- Provide and install HVAC as detailed

26-ELECTRICAL

- Develop electrical schematic plan and drawings
- Provide and install electric as detailed

GENERAL ASSUMPTIONS & CLARIFICATIONS

- Permitting & Zoning Costs are by Others and not included in this proposal.
- Work to take place during the normal working hours of 7am-5pm.
- After-hours or weekend work is not included unless specifically noted.
- No hazardous material or environmental testing included. Removal, remediation, or abatement is expressly excluded.
- No work is included for areas outside the defined scope unless explicitly stated.
- Any unforeseen conditions (e.g., structural deficiencies, concealed utilities, asbestos) will be handled via change order.
- Additional requirements through correction letters, on-site inspection directives, and other means are excluded and will be delt with as a change order to the project. This proposal is based on the RFP as advertised on August 20th, 2025 and addenda.
- Pricing includes design prices for MEPs to develop own engineered drawings.
- Anywhere this scope and the budget are in conflict, scope clarification will be clarified in writing prior to execution and final contract.
- The construction schedule is based on a continuous, unimpeded sequence of work and is based on preliminary information as the full design scope and construction set is not yet determined. It is understood that pricing is based on contractor assumptions for known scope of work. Final selections and design may impact overall cost and is expected to be addressed via change order.
- It is assumed that Owner/Client will be contracting directly with Architect, or Structural Engineer, who will create the complete set of construction documents in collaboration with the MEPs and Contractor. Contractor will not have privity of contract with Architect or its partners.
- Assume project will be published Ohio prevailing wage rates.

COMPTON CONSTRUCTION
691 Parsons Avenue, Columbus, OH 43206

Proposal

Name: **City Hall Master Plan Renovations** Date: **25/Sep/2025**

Project Folder: **25BC** Address: **7232 E Main St, Reynoldsburg, OH 43068** Version: **BID**

Project Number: Owner: **City Of Reynoldsburg** Square Feet: **2,600**

Description of Work: **Office Renovation**

Code	Item Description	Group	Type	Description	Measure	Units		Unit Cost		Cost		
1-000	**GENERAL CONDITIONS**											
1-041	Project Management	01	L	Project Manager (Construction)	HR	220.00	$	121.15	$	26,653.00		
1-042	Project Superintendent	01	L	Superintendent	HR	300.00	$	103.50	$	31,050.00		
1-044	Project Estimating	01	L	Pre-construction Services	HR	80.00	$	94.18	$	7,534.40		
1-045	Project Administrative	01	L	Prevailing Wage Management	HR	150.00	$	85.29	$	12,793.50		
1-049	Insurance	01	O	Insurance	LS	1.00	$	450.00	$	450.00		
1-065	Permit Fees - Building	01	O	Bonding/Insurance - Excluded	LS	0.00	$	-	$	-		
1-070	Printing	01	O	Printing	LS	4.00	$	95.00	$	380.00		
1-521	Field Office Expense	01	O	Small Tools, Safety Materials, On Site Office Exp	LS	1.00	$	2,500.00	$	2,500.00		
1-521	Field Office Expense	01	O	Rental Equipment	LS	1.00	$	3,200.00	$	3,200.00		
1-710	Final Cleaning	01	S	First and Second Floor Final Clean	SF	2600.00	$	0.75	$	1,950.00		
1-741	General Construction Labor	02	S	General Construction Labor, Existing Conditions Protection, General Requirements	HR	25.00	$	127.00	$	3,175.00		
1-970	Project Technology	01	O	Project Technology	LS	1.00	$	800.00	$	800.00		
								TOTAL	$	91,985.90	$	**91,985.90**
2-000	**EXISTING CONDITIONS**											
2-041	Site Demolition	02	S	Demo of existing storefront, flooring, new door openings, hard lid and seating (to be relocated) and 2nd Floor Scope	LS	1.00	$	22,230.00	$	22,230.00		
2-200	Dumpsters	02	S	Construction Dumpsters	EA	4.00	$	500.00	$	2,000.00		
								TOTAL	$	24,910.00	$	**24,910.00**
3-000	**CONCRETE**											
3-306	Slab On Grade 4"	03	S	New Slab and Concrete Stoop	SF	486.00	$	17.00	$	8,262.00		
3-800	Concrete Cutting Sub	03	S	Concrete Demo	SF	450.00	$	9.00	$	4,050.00		
								TOTAL	$	12,312.00	$	**12,312.00**
4-000	**MASONRY**											
4-100	Masonry Sub	04	S	Demo and Repair around New Door Opening	LS	1.00	$	3,640.00	$	3,640.00		
								TOTAL	$	3,640.00	$	**3,640.00**
5-000	**METALS**											
5-120	Structural Steel	05	S	Steel Columns (2) Allowance	LS	1.00	$	11,000.00	$	11,000.00		
5-520	Steel Railings	05	S	Handrails	LS	1.00	$	6,000.00	$	6,000.00		
								TOTAL	$	17,000.00	$	**17,000.00**
6-000	**WOOD & PLASTICS**											
								TOTAL	$	-	$	-
7-000	**THERMAL & MOISTURE PROTECTION**											

691 Parsons Avenue, Columbus, OH 43206

Name: **City Hall Master Plan Renovations** Date: **25/Sep/2025**

Project Folder: **25BC** Address: **7232 E Main St, Reynoldsburg, OH 43068** Version: **BID**

Project Number: Owner: **City Of Reynoldsburg** Square Feet: **2,600**

Description of Work: **Office Renovation**

Code	Item Description	Group	Type	Description	Measure	Units		Unit Cost		Cost		
								TOTAL	$	-	$	-
8-000	**DOORS & WINDOWS**											
8-140	Wood Doors & Frames	08	S	Furnish and install new solid core wood doors, frame and hardware	EA	6.00	$	2,805.00	$	16,830.00		
8-400	Storefront Systems Sub	08	S	New sliding glass system Allowance	LS	1.00	$	42,500.00	$	42,500.00		
8-410	Aluminum Storefront	08	S	New Single Storefront doors	EA	5.00	$	4,250.00	$	21,250.00		
8-810	Glass Glazing	08	S	Privacy Film Allowance	SF	235.00	$	7.50	$	1,762.50		
								TOTAL	$	82,342.50	$	**82,342.50**
9-000	**FINISHES**											
9-200	Metal Studs & Drywall Sub	09	S	Frame, Insulate, Drywall Package 1st and 2nd Floor	LS	1.00	$	39,200.00	$	39,200.00		
9-510	Acoustical Ceilings	09	S	New ACT, Hard Lid and Patching	LS	1.00	$	11,480.00	$	11,480.00		
9-600	Flooring Sub	09	S	Rubber cove base Upstairs and Risers/Treads	LS	1.00	$	2,100.00	$	2,100.00		
9-680	Carpet	09	S	New Carpet Tile and Base	SF	450.00	$	16.00	$	10,080.00		
9-840	Acoustic Treatments	09	S	Acoustinc Sound Panels	SF	27.00	$	45.00	$	1,701.00		
9-910	Surface Prep	09	S	Patch and Repair Flooring Allowance	LS	1.00	$	2,500.00	$	2,500.00		
9-912	Interior Painting	09	S	Interior Paint	SF	1800.00	$	3.75	$	10,125.00		
9-970	Closeout/Punch List	LS	S	Closeout/Punch List	LS	1.00	$	1,750.00	$	1,750.00		
								TOTAL	$	78,936.00	$	**78,936.00**
10-000	**SPECIALTIES**											
								TOTAL	$	-	$	-
11-000	**EQUIPMENT**											
								TOTAL	$	-	$	-
12-000	**FURNISHINGS**											
12-100	Furnishings Sub	12	S	Labor for chair reinstall	LS	1.00	$	6,300.00	$	6,300.00		
								TOTAL	$	6,300.00	$	**6,300.00**
13-000	**SPECIAL CONSTRUCTION**											
								TOTAL	$	-	$	-
14-000	**CONVEYING SYSTEMS**											
								TOTAL	$	-	$	-
21-000	**FIRE SUPPRESSION**											
21-100	Fire Suppression Sub	21	S	Fire Suppression - drawings and install/modifications	LS	1.00	$	15,250.00	$	15,250.00		
								TOTAL	$	15,250.00	$	**15,250.00**
22-000	**PLUMBING**											
								TOTAL	$	-	$	-
23-000	**HVAC**											
23-100	HVAC Sub	23	S	New supply/returns and duct runs, permit and inspections, drawings	LS	2600.00	$	12.50	$	48,750.00		
								TOTAL	$	48,750.00	$	**48,750.00**
26-000	**ELECTRICAL**											
26-100	Electrical Sub	26	S	Allowance for new receptacles and power plan	LS	1.00	$	18,750.00	$	18,750.00		

691 Parsons Avenue, Columbus, OH 43206

Name: **City Hall Master Plan Renovations** Date: **25/Sep/2025**

Project Folder: **25BC** Address: **7232 E Main St, Reynoldsburg, OH 43068** Version: **BID**

Project Number: Owner: **City Of Reynoldsburg** Square Feet: **2,600**

Description of Work: **Office Renovation**

Code	Item Description	Group	Type	Description	Measure	Units		Unit Cost		Cost		
26-240	Service Panels	26	S	New Panel/Upgrade Service Contingency	EA	1.00	$	9,100.00	$	9,100.00		
26-510	Interior Lighting	26	S	Allowance for wall mounted light in closet	LS	1.00	$	420.00	$	420.00		
26-510	Interior Lighting	26	S	Furnish and install new Lighting Package	LS	1.00	$	12,936.00	$	12,936.00		
								TOTAL	$	41,206.00	$	41,206.00
27-000	**COMMUNICATIONS**											
27-410	AV Systems	27	S	LV Allowance - Data and Wire Pull	LS	1.00	$	3,500.00	$	3,500.00		
27-510	AV Communication Systems	27	S	AV Allowance for Cameras and Conf Room	LS	1.00	$	5,040.00	$	5,040.00		
								TOTAL	$	8,540.00	$	8,540.00
28-000	**ELECTRONIC SAFETY & SECURITY**											
28-300	Fire Alarm Sub	28	S	Fire Alarm - drawings and install/modifications	LS	1.00	$	15,610.00	$	15,610.00		
								TOTAL	$	15,610.00	$	15,610.00
31-000	**EARTHWORK**											
								TOTAL	$	-	$	-
32-000	**EXTERIOR IMPROVEMENTS**											
								TOTAL	$	-	$	-
33-000	**UTILITIES**											
								TOTAL	$	-	$	-
								Subtotal		$	446,782.40	
								OH&P	12%	$	53,613.89	
								Estimate Total		$	500,396.29	
								Cost/SF		$	192.46	

PARTNER REFERENCES

INDUSTRY REFERENCES

Walter Eguez - Tortilla Street Food - weguezv@gmail.com
Recent Projects:

- Tortilla Home Office
- Don Vito
- Tortilla Park and Building B Build-out

Chad Underwood - Modo Yoga - chad@modoyogacolumbus.com
Recent Projects:

- Modo Yoga Tenant Build-Out

Mark Robinson - Standardized Brewing - mark@standardizedbrewing.com
Recent Projects:

- Standardized Brewing Build-out

THANK YOU


On behalf of Compton Construction, I would like to thank you for the opportunity to bid your project!

It would be a privilege to complete the renovations at City Hall for the City of Reynoldsburg, and look forwarding to continuing our relationship.


Blake Compton | Founder

GOOD PEOPLE, DOING GOOD WORK,
FOR GOOD PEOPLE


3/26/2025 5:12:54 PM



4 ELEVATION - COUNCIL CHAMBERS
1/4" = 1'-0"




3 FIRST FLOOR RCP
1/8" = 1'-0" AREA OF WORK 900 SQ.FT.



2 FIRST FLOOR PLAN
1/8" = 1'-0" AREA OF WORK 2466 SQ.FT.

N



1 FIRST FLOOR DEMOLITION PLAN
1/8" = 1'-0" AREA OF WORK 740 SQ.FT.

SHEET KEYNOTES - DEMO. PLAN

01	SAW CUT AND REMOVE CONCRETE COMPLETELY IN AREA SHOWN. SEE PROPOSED PLAN FOR EXTENT OF EXCAVATION AND REWORK.
02	REMOVE INTERIOR STOREFRONT WINDOWS AND DOORS COMPLETELY.
03	REMOVE PORTION OF UNDULATING GYP. BOARD CEILING AS REQUIRED FOR NEW CONSTRUCTION.
04	REMOVE PORTION OF EXISTING WALL AS REQUIRED FOR NEW DOOR OPENING.
05	REMOVE FLOOR MOUNTED SEATING THROUGHOUT THE COUNCIL CHAMBERS AND SALVAGE QUANTITY REQUIRED FOR REINSTALLATION PER CONFIGURATION IN PROPOSED PLAN.
06	REMOVE BENCHES AND SALVAGE FOR RELOCATION SEE PROPOSED PLAN
07	REMOVE EXISTING STAIRS COMPLETELY
08	AREA NOT IN CONTRACT, PROTECT THROUGHOUT THE DURATION OF CONSTRUCTION
10	REMOVE EXISTING FLOORING AND BASE THROUGHOUT THE CHAMBER, TYPICAL. PREPARE SURFACE TO RECEIVE NEW FLOORING AND BASE

SHEET KEYNOTES - NEW PLAN

11	KNEE WALL CONSTRUCTED WITH STRUCTURAL METAL STUDS @ 16" O.C., PROVIDE ABUSE RESISTANT GYPSUM BOARD WITH SOLID WOOD CAP TO MATCH FINISH AND PROFILE OF EXISTING RAILING, TYPICAL. REINFORCE KNEE WALL WITH CLARK DEITRICH PONY WALL HEAVY SYSTEM @ 48" O.C. MAX.
12	PROVIDE NEW 4" CONCRETE SLAB ON GRADE WITH TURNED DOWN SLAB EDGE, DOWEL NEW SLAB INTO EXISTING @ 12" O.C., PATCH AND REPAIR VAPOR BARRIER AS REQUIRED WITH 10 MIL(MIN.) VAPOR BARRIER, TYP.
13	INSTALL RELOCATED SEATING IN NEW LOCATION AS SHOWN.
14	PROVIDE NEW 3'-0" x 7'-0" SOLID CORE WOOD DOOR WITH FULL GLASS LIGHT AND PRIVACY FILM. STAINED TO MATCH BUILDING STANDARD
15	PROVIDE NEW 3'-0" x 7'-0" ALL GLASS DOOR WITH INTEGRAL PANIC HARDWARE (BLUMCRAFT PA100 SERIES OR SIMILAR), OVERHEAD CONCEALED CLOSER AND RECESED FLOOR PIVOT
16	PROVIDE NEW 3'-0 X 7'-0" DOOR WITH SIDELITE. STOREFRONT TO BE 6" KAWNEER TRIFAB 600 SYSTEM FRONT GLAZED WITH INSULATED TEMPERED GLAZING WITH SANDBLASTED 3RD SURFACE.
17	PATCH AND REPAIR FLOORING AT LOCATION OF BENCH REMOVAL TO MATCH EXISTING PATTERNS AND STYLE.
18	CR LAURENCE P1 GLASS RAILING SYSTEM
19	KAWNEER 500 SERIES NON-INSULATED STOREFRONT SYSTEM CENTER GLAZED. PROVIDE WINDOW FILM AS INDICATED ON INTERIOR ELEVATIONS.
20	SOLAR INOVATIONS - FOLDING WALL (G2 NON THERMAL INFOLD). PROVIDE PRIVACY FILM AS INDICATED ON INTERIOR ELEVATIONS.
21	NEW HSS 6X6 COLUMN TO SUPPORT NEW BEAM ABOVE. SEE SECTION FOR ADDTIONAL INFORMATION.
22	PROVIDE NEW FLOORING AND BASE.CARPET TILE ALLOWANCE $16 PER SQ.FT. + INSTALLATION
23	REPLACE ALL EXISTING FLOORING AND BASE. NEW CARPET TILE ALLOWANCE $16 PER SQ.FT. + INSTALLATION.
24	JOHNSONITE TARKETT VINYL STAIR TREADS AND RISERS (SAFE T-RIB) WITH GRIP TAPE
25	ALL PARTITIONS TO BE TYPE 'B' UNLES NOTED OTHERWISE
26	TYPE 'B' PARTITION WITH 6" STUDS, THIS AREA ONLY
27	PAINTED STEEL FLOOR MOUNTED RAILING
28	POWER AND DATA FOR NEW TELEVISION WITH VIDEO CONFERENCING SYSTEM AND A/V TIED TO COUNCIL CHAMBERS
29	PATCH, REPAIR, AND REPAIR WALLS AND CEILINGS AROUND SCOPE OF WORK TO LIKE-NEW CONDITION

SHEET KEYNOTES - RCP

31	INSTALL NEW CEILING IN THE CONFERENCE ROOM ONLY
32	REPAIR AND PATCH CEILING AS NEEDED TO MATCH EXISTING CONDITION
33	NO WORK TO BE DONE IN THIS AREA. PROTECT DURING CONSTRUCTION

DEMOLITION PLAN LEGEND

GRAPHIC INDICATION (RE: A-001 SYMBOLS LEGEND)

- EXISTING TO REMAIN
- EXISTING DOOR AND FRAME ASSEMBLY TO BE REMOVED.
- EXISTING TO BE REMOVED
- EXISTING DOOR AND FRAME ASSEMBLY TO BE REMOVED AND SALVAGED FOR FUTURE WORK; AS INDICATED ON PLANS. RE: A-601 DOOR SCHEDULE
- NOT IN SCOPE

NEW PLAN LEGEND

GRAPHIC INDICATION (RE: A-001 SYMBOLS LEGEND)

- AREA OF WORK
- EXISTING TO REMAIN
- NOT IN SCOPE
- NEW SLAB
- NEW PARTITION

REFLECTED CEILING PLAN LEGEND

CEILING TYPES

- CA-1 / X' - X" — CEILING TYPE / CEILING ELEVATION
- **CA-2** 2X4 ACOUSTICAL LAY-IN CEILING TILE
- **CW-1** ARMSTRONG FORMATIONS - STAGGERED CLOUD WOOD PLANK
- **CG-2** GYPSUM BOARD PT-_
- NOT IN SCOPE

LIGHT FIXTURES

(REFER TO ELECTRICAL DRAWINGS)

- SURFACE / CEILING MOUNT
- RECESSED MOUNT
- LINEAR LED LIGHTING
- INTERIOR EMERGENCY WALL PACK
- EXIT SIGN (WALL) (CEILING)
- A/V SPEAKER SYSTEM

LIGHT FIXTURES

(REFER TO MECHANICAL DRAWINGS)

- RECTANGULAR CEILING DIFFUSER / GRILLE
- LINEAR DIFFUSER

OHM
ARCHITECTS ENGINEERS PLANNERS
OHM-ADVISORS.COM

PRELIMINARY - NOT FOR CONSTRUCTION

ISSUED FOR: SCHEMATIC DESIGN 20250221


PROJECT NUMBER 0012-24-0070
PM PM
CITY OF REYNOLDSBURG
CITY HALL MASTER PLAN
7232 E Main St, Reynoldsburg, OH 43068
FIRST FLOOR PLAN

A-101


COPYRIGHT 2025 OHM ALL DRAWINGS AND WRITTEN MATERIALS APPEARING HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF OHM AND THE SAME MAY NOT BE DUPLICATED, DISTRIBUTED, OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF OHM

Autodesk Docs://0012-24-0070 Reynoldsburg CH Master Plan/0012240070_A_ReynoldsburgCH_MP_2023_CEN.rvt


3/26/2025 5:12:55 PM




6 SECTION - FOLDING DOOR
1/2" = 1'-0"




5 SECTION - FOLDING DOOR
1/2" = 1'-0"




TYPE 'B6'
FULL HEIGHT PARTITION TO DECK OR EXISTING CEILING




TYPE 'B3'
FULL HEIGHT PARTITION TO DECK OR EXISTING CEILING




TYPE 'A3'
PARTITION TO 6" ABOVE FINISHED CEILING




7 SECTION
3/4" = 1'-0"



4 STOREFRONT ELEVATION
3/8" = 1'-0"




3 SECTION - STOREFRONT
1/2" = 1'-0"



NOTE:
SPACING: PROVIDE HANDRAIL MOUNT/ SADDLE @ 48" O.C. MAXIMUM ALONG LENGTH OF HANDRAIL. PROVIDE MOUNT WITHOUT PLATE OR ANCHOR @ STEEL GUARDRAIL POSTS WHERE HANDRAIL IS NOTED.

2 WALL MOUNTED RAILING
3" = 1'-0"



1 SECTION - RAMP
1/2" = 1'-0"

OHM
ARCHITECTS ENGINEERS PLANNERS
OHM-ADVISORS.COM

PRELIMINARY - NOT FOR CONSTRUCTION

ISSUED FOR: SCHEMATIC DESIGN 2025/02/21

PROJECT NUMBER 0012-24-0070
PM PM

CITY OF REYNOLDSBURG
CITY HALL MASTER PLAN
7232 E Main St. Reynoldsburg, OH 43068

DETAILS

A-102

COPYRIGHT 2025 OHM ALL DRAWINGS AND WRITTEN MATERIALS APPEARING HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF OHM AND THE SAME MAY NOT BE DUPLICATED, DISTRIBUTED, OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF OHM

Autodesk Docs://0012-24-0070 Reynoldsburg CH Master Plan/0012240070_A_ReynoldsburgCH_MP_2023_CEN.rvt

3/26/2025 5:12:56 PM

SHEET KEYNOTES - 2ND FLOOR DEMO

01	REMOVE EXISTING DOOR AND FRAME
02	REMOVE PORTION OF EXISTING WALL AND PATCH AS NEEDED TO MATCH EXISTING CONDITION
03	EXISTING FLOORING TO REMAIN. PROTECT DURING CONSTRUCTION. APPLY RAM BOARD AND SELFADHEREIG PROTECTIVE PLASTIC SYSTEM THROUGH OUT THE AREA OF WORK FOR DURATION OF CONSTRUCTION TO PROTECT EXISTING FLOORING

SHEET KEYNOTES - 2ND FLOOR NEW...

11	EXISTING FLOORING TO REMAIN, ADD NEW CONSTRUCTION ON TOP OF IT
12	ALL PARITIONS TO BE TYPE 'B' UNLESS NOTED OTHERWISE
13	FLOORING TRANSITION STRIP
14	FURNITURE BY THE OWNER
15	3070 SOLID CORE WOOD DOOR (TYP)

SHEET KEYNOTES - 2ND FLOOR RCP

31	NEW CEILING GRID AND ACOUSTICAL TILES
32	INSTALL WALL MOUNTED LIGHT
33	PAINTED GYP. BOARD BULKHEAD 2" BELOW ADJACENT LOWEST CEILING

REFLECTED CEILING PLAN LEGEND

CEILING TYPES

CA-1 — CEILING TYPE
X' - X" — CEILING ELEVATION

CA-2 2X4 ACOUSTICAL LAY-IN CEILING TILE

CW-1 ARMSTRONG FORMATIONS - STAGGERED CLOUD WOOD PLANK

CG-2 GYPSUM BOARD PT-_

NOT IN SCOPE

LIGHT FIXTURES

(REFER TO ELECTRICAL DRAWINGS)

- SURFACE / CEILING MOUNT
- RECESSED MOUNT
- LINEAR LED LIGHTING
- INTERIOR EMERGENCY WALL PACK
- EXIT SIGN (WALL) (CEILING)
- A/V SPEAKER SYSTEM

LIGHT FIXTURES

(REFER TO MECHANICAL DRAWINGS)

- RECTANGULAR CEILING DIFFUSER / GRILLE
- LINEAR DIFFUSER

NEW PLAN LEGEND


GRAPHIC INDICATION (RE: A-001 SYMBOLS LEGEND)

- AREA OF WORK
- EXISTING TO REMAIN
- NOT IN SCOPE
- NEW SLAB
- NEW PARTITION


DEMOLITION PLAN LEGEND

GRAPHIC INDICATION (RE: A-001 SYMBOLS LEGEND)


- EXISTING TO REMAIN
- EXISTING DOOR AND FRAME ASSEMBLY TO BE REMOVED.
- EXISTING TO BE REMOVED
- EXISTING DOOR AND FRAME ASSEMBLY TO BE REMOVED AND SALVAGED FOR FUTURE WORK; AS INDICATED ON PLANS. RE: A-601 DOOR SCHEDULE
- NOT IN SCOPE



3 SECOND FLOOR RCP
1/8" = 1'-0" AREA OF WORK 620 SQ.FT.



2 SECOND FLOOR PLAN
1/8" = 1'-0" AREA OF WORK 620 SQ.FT.



1 SECOND FLOOR DEMO PLAN
1/8" = 1'-0"

OHM
ARCHITECTS ENGINEERS PLANNERS
OHM-ADVISORS.COM

PRELIMINARY - NOT FOR CONSTRUCTION

ISSUED FOR: SCHEMATIC DESIGN 20250221

PROJECT NUMBER 0012-24-0070
PM
PM

CITY OF REYNOLDSBURG
CITY HALL MASTER PLAN
7232 E Main St, Reynoldsburg, OH 43068
SECOND FLOOR PLAN

A-103

COPYRIGHT 2025 OHM ALL DRAWINGS AND WRITTEN MATERIALS APPEARING HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF OHM AND THE SAME MAY NOT BE DUPLICATED, DISTRIBUTED, OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF OHM

Autodesk Docs://0012-24-0070 Reynoldsburg CH Master Plan/0012240070_A_ReynoldsburgCH_MP_2023_CEN.rvt